

ITEM 538
RIGHT OF WAY MARKERS

538.1. Description. Install cast-in-place concrete right of way markers.

538.2. Materials. Provide Class A concrete in accordance with Item 421, "Hydraulic Cement Concrete," and reinforcing steel in accordance with Item 440, "Reinforcing Steel." The Department will furnish bronze disks.

538.3. Construction. Cast and finish right of way markers in accordance with Item 420, "Concrete Structures," and details shown on the plans. Install right of way markers at designated points to the required horizontal and vertical locations. Center the bronze disk within 1/2 in. of the location shown. Reposition any marker that is outside this tolerance.

Unless otherwise shown on the plans, the Department will provide a survey crew working under the direction of a registered professional land surveyor, licensed to practice in Texas, to make the final alignment checks on each right of way marker installed and to place the right of way location punch mark on the bronze disk. Do not disturb or destroy the original points before installing right of way markers with bronze disks or before placing punch marks.

538.4. Measurement. This Item will be measured by each marker.

538.5. Payment. The work performed and materials furnished in accordance with this Item and measured as provided under "Measurement" will be paid for at the unit price bid for "Right of Way Markers." This price includes materials, labor (including work of the registered professional land surveyor when required by the plans), tools, equipment, and incidentals. Removal and disposal of existing right of way markers will not be paid for directly but is subsidiary to pertinent Items.