Texas Department of Transportation

BOOK 2 - TECHNICAL PROVISIONS

FOR

IH 35E MANAGED LANES

Design-Build Project

~~September 20~~October 19, 2012

Table of Contents

1 GENERAL 1

1.1 Project Scope 1

1.2 Work Facility Description 1

1.3 Project Requirements 10

1.4 Maintenance Work Requirements 10

2 PROJECT MANAGEMENT 1

2.1 Administrative Requirements 2

2.1.1 Project Schedule 2

2.1.2 Document Management 11

2.2 Quality Management Plan 15

2.2.1 General Requirements 15

2.2.2 Quality Terminology 16

2.2.3 Quality Management Organization 16

2.2.4 Quality Policy 16

2.2.5 Inspection and Testing 16

2.2.6 Responsibility and Authority of Developer Staff 17

2.2.7 Design Quality Management Plan 18

2.2.8 Construction Quality Management Plan 25

2.2.9 Maintenance Management Plan 29

2.3 Comprehensive Environmental Protection Program 29

2.4 Public Information and Communications Plan 29

2.5 Safety Plan 29

2.6 TxDOT-Developer Communications Plan 29

2.7 Right of Way Acquisition Plan 30

2.8 Risk Management Plan 30

2.9 Affected Third Parties Plan 30

2.10 Emergency Management Plan 30

2.11 TxDOT Offices, Equipment 31

2.11.1 Computers and Equipment 31

2.11.2 Core Office 33

2.11.3 Field Offices 37

3 PUBLIC INFORMATION AND COMMUNICATIONS 1
3.1 General Requirements 1
3.2 Administrative Requirements 1
3.2.1 Public Information and Communications Plan 1
3.2.2 Public Information Coordinator 4
3.2.3 Public Information Office 4
3.2.4 Customer Groups 5
3.2.5 Public Meetings 5
3.2.6 Meeting Summaries 6
3.2.7 Emergency Event Communications 7
3.2.8 Disseminating Public Information 7
4 ENVIRONMENTAL 1
4.1 General Requirements 1
4.2 Environmental Approvals 1
4.2.1 New Environmental Approvals and Amended TxDOT-Provided Approvals 1
4.2.2 Responsibilities Regarding Environmental Studies 2
4.2.3 TxDOT Review and Approval of Developer Submissions 2
4.2.4 TxDOT-Provided Approvals 2
4.3 Comprehensive Environmental Protection Program (CEPP) 2
4.3.1 Environmental Management System (EMS) 3
4.3.2 Environmental Compliance and Mitigation Plan (ECMP) 4
4.3.3 Environmental Protection Training Plan (EPTP) 10
4.3.4 EPTP Participation 12
4.3.5 Hazardous Materials Management Plan (HMMP) 12
4.3.6 Communication Plan (CP) 13
4.3.7 Construction Monitoring Plan (CMP) 14
4.3.8 Recycling Plan 15
4.4 Environmental Personnel 15
4.4.1 Environmental Compliance Manager (ECM) 15
4.4.2 Environmental Training Staff 16
4.4.3 Environmental Compliance Inspectors (ECI) 16
4.4.4 Cultural Resource Management Personnel 16
4.4.5 Natural Resource Biologist 17

4.4.6 Water Quality Specialist 17
4.4.7 Hazardous Materials Manager 17
4.5 Property Access 17
4.6 Dust Control 18
4.7 Asbestos Containing Material (ACM) 18
4.8 Lead Based Paint 18
5 THIRD PARTY AGREEMENTS 1
5.1 General Requirements 1
5.2 Traffic Signals 1
5.2.1 Red Light Cameras 1
5.3 Roadway Illumination 1
5.4 Other Affected Third Parties 1
6 UTILITY ADJUSTMENTS 1
6.1 General Requirements 1
6.1.1 When Utility Adjustment is Required 1
6.1.2 Certain Components of the Utility Adjustment Work 4
6.1.3 Agreements Between Developer and Utility Owners 4
6.1.4 Recordkeeping 5
6.2 Administrative Requirements 6
6.2.1 Standards 6
6.2.2 Communications 6
6.2.3 Utility Adjustment Team 6
6.2.4 Real Property Matters 7
6.3 Design 8
6.3.1 Developer's Responsibility for Utility Identification 8
6.3.2 Technical Criteria and Performance Standards 9
6.3.3 Utility Adjustment Concept Plans 9
6.3.4 Utility Adjustment Plans 9
6.4 Construction 12
6.4.1 Reserved 12
6.4.2 General Construction Criteria 12
6.4.3 Inspection of Utility Owner Construction 12
6.4.4 Scheduling Utility Adjustment Work 12

6.4.5 Standard of Care Regarding Utilities 13
6.4.6 Emergency Procedures 13
6.4.7 Utility Adjustment Field Modifications 13
6.4.8 Switch Over to New Facilities 13
6.4.9 Record Drawings 14
6.4.10 Maintenance of Utility Service 14
6.4.11 Traffic Control 14
6.5 Deliverables 14
6.5.1 Maximum Number of Submittals 14
6.5.2 Developer's Utility Tracking Report 15
6.5.3 Utility Assembly Submittals 15
6.5.4 FHWA Alternate Procedure 16
7 RIGHT-OF-WAY (ROW) 1
7.1 General Requirements 1
7.2 Administrative Requirements 1
7.2.1 Standards 1
7.2.2 Software Requirements 2
7.2.3 ROW Acquisition Plan 2
7.2.4 Schedule and Review Procedures 2
7.2.5 Developer's Project ROW Scope of Services 3
7.2.6 Acquisition Process Summary 4
7.2.7 ROW Personnel Qualifications 4
7.2.8 Developer Conflict of Interest 6
7.2.9 Meetings 6
7.2.10 Documentation and Reporting 6
7.2.11 Responsibilities of Developer 7
7.2.12 Responsibilities of TxDOT 8
7.2.13 TxDOT Project Monitor/Reviewer 9
7.2.14 Responsibilities of the Office of the Attorney General 9
7.3 Pre-Acquisition Activities 9
7.3.1 Project ROW Surveying and Mapping 9
7.3.2 Additional Reporting Requirements 14
7.3.3 Title Services 14

7.3.4 Introduction to Property Owners 15
7.3.5 Appraisals 15
7.3.6 Project ROW Acquisition Package Approval 18
7.4 Acquisition Activities 19
7.4.1 ROW Negotiations 19
7.4.2 Relocation Assistance 21
7.4.3 Closing Services 23
7.4.4 Condemnation Support 24
7.4.5 Clearance/Demolition of Project ROW 26
7.4.6 Property Fence 27
7.5 Early ROW Acquisition 28
8 GEOTECHNICAL 1
8.1 General Requirements 1
8.2 Design Requirements 1
8.2.1 Subsurface Geotechnical Investigation by Developer 1
8.2.2 Rehabilitation of Existing Pavements 11
8.3 Construction Requirements 12
8.3.1 Pavement Materials Requirements 12
8.3.2 Construction Verification 14
9 LAND SURVEYING 1
9.1 General Requirements 1
9.2 Administrative Requirements 1
9.2.1 Standards 1
9.2.2 Right-of-Entry 1
9.2.3 Survey by TxDOT 1
9.3 Design Requirements 1
9.3.1 Units 1
9.3.2 Survey Control Requirements 1
9.3.3 Conventional Method (Horizontal & Vertical) 2
9.3.4 Right of Way Surveys 4
9.3.5 Survey Records and Reports 5
9.4 Construction Requirements 5
9.4.1 Units 5

9.4.2 Construction Surveys 5
9.5 Deliverables 5
9.5.1 Survey Records 5
9.5.2 Final ROW Surveying and Mapping 5
9.5.3 ROW Monuments 5
9.5.4 Record Drawings and Documentation 6
10 GRADING 1
10.1 General Requirements 1
10.2 Preparation within Project Limits 1
10.3 Slopes and Topsoil 1
10.4 Sodding 2
11 ROADWAYS 1
11.1 General Requirements 1
11.2 Design Requirements 1
11.2.1 Control of Access 1
11.2.2 Roadway Design Requirements 1
11.2.3 Superelevation 2
11.2.4 Roadway Design Deviations 2
11.2.5 Miscellaneous Roadway Design Requirements 6
11.3 Minimum Requirements for Declaration Areas 7
12 DRAINAGE 1
12.1 General Requirements 1
12.2 Administrative Requirements 1
12.2.1 Data Collection 1
12.2.2 Coordination with Other Agencies and Local Governmental Entities 1
12.3 Design Requirements 2
12.4 Surface Hydrology 4
12.4.1 Design Frequencies 4
12.4.2 Storm Sewer Systems 6
12.4.3 Miscellaneous Drainage Design Requirements 8
12.4.4 Stormwater Storage Facilities 9
12.4.5 Hydraulic Structures 9
12.5 Drainage Design Report 12

12.6 Construction Requirements 12
13 STRUCTURES **1**
13.1 General Requirements 1
13.2 Design Requirements 1
13.2.1 Design Parameters 1
13.2.2 Bridge Design Loads and Load Ratings 3
13.2.3 Bridge Decks and Superstructures 4
13.2.4 Bridge Foundations 5
13.2.5 Bridge Railing and Barriers 5
13.2.6 Retaining Walls 5
13.2.7 Noise/Sound Walls 6
13.2.8 Bridge Class Drainage Structures 6
13.2.9 Sign, Illumination, and Traffic Signal Supports 7
13.2.10 Rehabilitation of Structures to be, Widened, Extended, or Reused 7
13.3 Construction Requirements 8
13.3.1 Concrete Finishes 8
13.3.2 Structure Metals 9
13.3.3 Steel finishes 9
13.3.4 Steel Erection 9
14 RAIL **1**
14.1 General Requirements 1
14.2 Projects Impacting Railroad ROW 1
14.3 Railroad Agreements 1
14.4 Railroad Design Standards 2
14.4.1 Design Criteria 3
14.5 Administrative Requirements 3
14.5.1 Project Work Affecting Railroad Operations 3
14.5.2 Railroad Agreement 3
14.5.3 Agreement for Construction, Maintenance and Use of Right of Way 3
14.5.4 Operation Safety 4
14.5.5 Railroad Right of Entry Agreement 4
14.5.6 Developer Right of Entry Agreement 4
14.5.7 Insurance Requirements 5

14.6 Construction Requirements 5
14.6.1 Flagging 5
14.6.2 Safety Certification 5
14.6.3 Rail Corridor 5
15 AESTHETICS AND LANDSCAPING 1
15.1 General Requirements 1
15.2 Administrative Requirements 1
15.2.1 Aesthetics Concepts 1
15.2.2 Aesthetics and Landscaping Plan 2
15.2.3 Personnel 3
15.3 Design Requirements 3
15.3.1 Aesthetics Principles and Strategies 3
15.3.2 Walls 4
15.3.3 Bridges and Other Structures 4
15.3.4 Trees, Shrubs, and Other Plant Materials 4
15.3.5 Riprap 5
15.3.6 Lighting 5
15.3.7 Color Pallet 5
15.4 Construction Requirements 5
15.5 Aesthetic Enhancements 5
16 SIGNING, DELINEATION, PAVEMENT MARKING, SIGNALIZATION, AND LIGHTING 1
16.1 General Requirements 1
16.2 Administrative Requirements 1
16.2.1 Meetings 1
16.3 Design Requirements 1
16.3.1 Final Design 2
16.3.2 Signing and Delineation 2
16.3.3 Project Signs – Outside the Project ROW 3
16.3.4 Advance Toll Information Signs 3
16.3.5 Third-Party Signs 3
16.3.6 Sign Support Structures 3
16.3.7 Pavement Marking 3
16.3.8 Signalization 4

16.3.9 Lighting 6
16.3.10 Visual Quality 7
16.4 Construction Requirements 8
16.4.1 Permanent Signing and Delineation 8
16.4.2 Permanent Pavement marking 9
16.4.3 Permanent Signalization 10
16.4.4 Permanent Lighting 10
17 INTELLIGENT TRANSPORTATION SYSTEMS 1
17.1 General Requirements 1
17.2 Design Requirements 2
17.2.1 ITS Communications Requirements 3
17.2.2 Conduit 4
17.2.3 CCTV Cameras 4
17.2.4 Vehicle Detection 8
17.2.5 Dynamic Message Signs (DMS) 9
17.2.6 Lane Control Signals (LCS) 10
17.2.7 Single-Line DMS (SDMS) 10
17.2.8 Communication Cabinets 10
17.2.9 Satellite Buildings 11
17.2.10 Travel Time Sensors 11
17.2.11 Center-to-Center Interface 11
17.2.12 Access Control System (ACS) 11
17.3 Construction Requirements 12
17.3.1 General 12
17.3.2 Salvaging Existing Items 12
17.3.3 Existing ITS Relocation 13
17.4 Testing 13
17.4.1 General 13
17.4.2 End-to-End Testing 13
18 TRAFFIC CONTROL 1
18.1 General Requirements 1
18.2 Administrative Requirements 1
18.2.1 Traffic Management Plan 1

18.3 Design Requirements 2
18.3.1 Traffic Control Plans 2
18.3.2 Restricted Hours 18
18.4 Construction Requirements 19
18.4.1 Developer Responsibility 19
18.4.2 Access 19
18.4.3 Detours 19
18.4.4 Local Approvals 19
18.4.5 Pavement Markings 19
18.4.6 Reinstatement of Utility Cuts 19
18.4.7 Hauling Equipment 19
18.4.8 Final Clean-Up 20
18.4.9 Stockpiles 20
19 MAINTENANCE 1
19.1 General Requirements 1
19.1.1 General Maintenance Obligations 1
19.1.2 Developer's Obligation to Remedy and Repair 133
19.2 Maintenance Management Plan (MMP) 133
19.2.1 Municipal Maintenance Agreements for Existing Facility During Work 134
19.2.2 Accident Reduction Program 134
20 BICYCLE AND PEDESTRIAN FACILITIES 1
20.1 General Requirements 1
20.2 Administrative Requirements 1
20.3 Design Requirements 1
20.3.1 Bicycle Facilities 1
20.3.2 Pedestrian Facilities 1
21 TOLLING 1
21.1 General Requirements 1
21.2 Administrative Requirements 1
21.3 Design Requirements 1
21.3.1 ETCS Infrastructure Requirements 1
21.3.2 ETCS Functional Requirements 1
21.3.3 ETCS Performance Requirements 2

21.4 Construction Requirements 2

LIST OF ATTACHMENTS

Attachment 2-1 – Project Management Plan Contents

Attachment 2-2 – Work Breakdown Structure Requirements

Attachment 2-3 - Organizational Structure for Cost Reporting

Attachment 2-4 - I2MS Test Form Fields

Attachment 4-1 - Special Specification 1122 Temporary Erosion, Sedimentation, and Environmental Controls

Attachment 4-2 - Form 2118 Construction Storm Water Pollution Prevention Plan Field Inspection and Maintenance Report

Attachment 4-3 - Form 2448 Construction Stage Gate Checklist (CSGC)

Attachment 4-4 – Section 4(f) Mitigation Master Plan

Attachment 4-5 – Environmental Permits, Issues, and Commitments (EPIC)

Attachment 6-1 – Utility Forms

Attachment 8-1 –ESALs and Traffic Data

Attachment 11-1 – Roadway Design Criteria

Attachment 12-1 – Drainage Report for Major Stream Crossings Guidelines

Attachment 17-1 - Tolling and ITS Exhibits

Attachment 21-1 - Toll Systems Responsibility Matrix

Attachment 21-2 - Plaza Pavement Details

1 GENERAL

1.1 Project Scope

The IH 35E Managed Lanes Project has been developed in cooperation with local and regional stakeholders to relieve traffic congestion along the IH 35E corridor from IH 635 to US 380. Developer will be responsible for (1) design and construction of the Project and, at TxDOT's sole option, (2) maintenance of the Project for increments of 5 years, but not to exceed 15 years. The Project is the first of a multi-phased program that will be implemented through a series of projects in order to achieve the Ultimate Project as envisioned in the IH 35E North, Middle and South Environmental Assessments. The work generally consists of the construction of managed toll lanes, the addition of general purpose lanes, the addition of collector distributor roads between PGBT and SH 121, and the construction of a new southbound bridge over Lake Lewisville.

The Work will include, but is not limited to:

- Design and construction of roadway, drainage, structures, landscaping, signing, lighting and traffic signals along IH 35E general purpose lane, managed toll lanes, frontage roads, and crossing streets.
- Design and installation of Intelligent Transportation Systems (ITS).

Developer shall manage, plan, execute, and control all aspects of the development Work. Developer shall coordinate its activities with Governmental Entities and other Persons that are directly or indirectly impacted by the development Work. In addition, Developer shall document and report all development Work in accordance with the Contract Documents.

Developer shall be responsible for the remaining right of way acquisition services at the time of contract execution or as otherwise specified by TxDOT. Developer shall be responsible for coordinating with TxDOT's existing contractors on the Project. The purchase price of the associated right of way parcels, with the exception of Developer-Designated ROW, will not be the responsibility of the Developer.

Developer shall cause all Utility Adjustments necessary to accommodate construction, operation, maintenance and/or use of the Project in both its initial configuration and, in the areas where the Ultimate Project is specified in Section 1.2 of the Technical Provisions, in its Ultimate Project. TxDOT will assist Developer in the Utility Adjustment process, to the extent described in the Contract Documents. Some Utility Adjustments may be performed by the Utility Owner with its own forces and/or contractors and consultants (i.e., Owner-Managed); all others shall be performed by Developer with its own forces and/or Subcontractors and consultants (subject to any approval rights required by the Utility Owner for those working on its facilities) (i.e., Developer-Managed). The allocation of responsibility for the Utility Adjustment Work between Developer and the Utility Owners shall be specified in the Utility Agreements.

1.2 Work Facility Description

The Scope of Work in the Technical Provisions Section 1.2 will be revised to include the scope package and options that are included in the successful Proposal.

The Project consists of general improvements along the IH 35E corridor from IH 635 to US 380. Unless otherwise specified below, the Work listed shall meet all the requirements of the Technical Provisions and shall be constructed generally consistent with the Draft Interim Schematic. Certain elements of the Ultimate Project shall be implemented in this Project Scope. These areas where the Ultimate Project shall be implemented are shown in Figure 1-1. All other areas are described as interim.

Figure 1-1: IH 35E Managed Lanes Project Package 1



Ultimate Areas

A further description of the areas where the Ultimate Project shall be implemented is as follows:

- 4th Street, including new bridges over the frontage roads, from Station 10+00 to Station 15+09.
- West Main Street, including new bridges over the frontage roads, from Station 10+00 to Station 15+07.
- Belt Line Road, including multi-level interchange and railroad re-alignment, from Station 99+00 to Station 127+00.
- IH 35E general purpose and managed lanes at Belt Line Road intersection from Station 741+65 to Station 762+35 and associated ramps.
- Dickerson Parkway, including interchange, from Station 10+00 to Station 60+81.
- Direct connector ramps on the north side of the interchange between IH 35E and SH 121, except as necessary to tie horizontally and vertically into the Project, or interim, edge of pavement.
- The Ultimate Project bridge over Lake Lewisville and associated roadway approaches from Station 1302+00 to Station 1515+15 to a width that accommodates four southbound general purpose lanes, two southbound frontage road lanes, two reversible managed lanes, and an eight-foot-wide shared use path alongside and barrier separated from the frontage roads.
- FM 407, including interchange, from Station 100+00 to Station 112+99.
- IH 35E general purpose and managed lanes bridges over FM 407 from Station 1310+21 to Station 1314+19 and associated ramps.
- Garden Ridge Boulevard, including interchange, from Station 100+82 to Station 112+50, excluding turnarounds.
- Country Lane / South Denton Drive, including interchange, from Station 101+75 to Station 110+14 excluding turnarounds.
- IH 35E general purpose and managed lanes bridge over Country Lane / South Denton Drive from Station 1467+13 to Station 1470+91 and associated ramps.
- Turbeville Road, including interchange, from Station 100+00 to Station 112+74.
- IH 35E general purpose and managed lanes bridge and IH 35E northbound frontage road bridge over Turbeville Road from Station 1507+63 to Station 1510+05 and associated ramps.
- Corinth Parkway, including interchange, from Station 10+89 to Station 21+45.
- IH 35E general purpose and managed lanes bridge over Corinth Parkway from Station 1637+93 to Station 1641+34 and associated ramps.
- Post Oak Drive, including interchange and new bridge over IH 35E, from Station 10+96 to Station 20+69.
- North Texas Boulevard, including new bridge over IH 35E, from Station 11+00 to Station 23+42. Ultimate improvements at this location shall also include the connecting street from North Texas Boulevard to Underwood Street and IH 35E general purpose lanes from Station 1984+00 to Station 1997+00.

General Project Description

A general description of the proposed improvements is as follows:

Base Scope

- Design and construct two reversible managed lanes plus exit/entrance ramps generally consistent with the Draft Interim Schematic from Pike Street to Post Oak Road, approximately from station 630+00 to 1704+00. Minor changes to the exit/entrance ramps may occur during final design, but in no way shall affect the traffic and or revenue projected for the Project. South of station 630+00, design and construct connections to the proposed managed lanes system to be built by others south of IH 635. The IH 635 northbound and southbound managed lane ramps shall be coordinated with proposed design for the IH 635 LBJ Project and generally consistent with the Draft Interim Schematic. At the northern terminus of the managed lanes, the two reversible lanes shall be reduced to one reversible lane north of Post Oak Road, approximately station 1704+00, and shall terminate north of Loop 288, approximately station 1835+00, and transition to the general purpose lanes generally consistent with the Draft Interim Schematic.

  Managed lanes construction shall be generally located along the center of the general purpose lanes. The managed lanes shall be separated from the general purpose lanes by concrete traffic barrier and access control systems to prevent entering or exiting the managed lanes into opposing traffic.

- Reconfigure and/or widen where applicable general purpose lanes to accommodate one additional general purpose lane in each direction from the IH 635 interchange northward to US 380, except for between Station 885+00 ~~to~~and Station 967+50 where three general purpose lanes shall be maintained in each direction in the area of the collector distributor system. Full depth widening of the existing pavement shall be performed as needed to accommodate the general purpose and managed lanes.

- Retain and rehabilitate, per the pavement rehabilitation plan described in Section 8, existing general purpose lane capacity, generally described as three lanes in each direction from IH 635, approximately Station 586+00, to Corinth Parkway, approximately Station 1639+62, transition to two lanes in each direction from Corinth Parkway to US 380, approximately station 2120+00, plus auxiliary lanes and exit/entrance ramps.

- Design and construct frontage roads as necessary to accommodate new interchange construction, managed lanes and general purpose lanes.

- Design and construct full deck replacement for existing bridges at the following locations:
  - IH35 NBML over Bonnie Brae
  - IH35 SBML over Bonnie Brae
  - IH35 NBML over Mayhill/State School Road
  - IH35 SBML over Mayhill/State School Road
  - IH35 NBML over Sandy Lake Road
  - IH35 SBML over Sandy Lake Road
  - IH35 NBML over US77

- Rehabilitate or replace as necessary bridge beams/girders and substructures to support the new bridge deck load in combination with live load specified in Section 13.2.2.

- Adjust signing at the Harry Hines Boulevard interchange per Section 16.3 of the Technical Provisions. Maintain facilities and traffic control per Sections 18 and 19 of the Technical Provisions. Harry Hines Boulevard interchange shall remain in place. Design and construct bridge at IH 35E from Station 597+63 to Station 599+68 allowing northbound IH 35E general purpose lanes and managed lanes to pass over Harry Hines Boulevard generally consistent with the Draft Interim Schematic.
- Adjust signal timing and signing at the Valley View Lane interchange per Section 16.3 of the Technical Provisions. Maintain facilities and traffic control per Sections 18 and 19 of the Technical Provisions. Valley View Lane interchange shall remain in place.
- Adjust signal timing and signing at the Valwood Parkway interchange per Section 16.3 of the Technical Provisions. Maintain facilities and traffic control per Sections 18 and 19 of the Technical Provisions. Valwood Parkway interchange shall remain in place.
- ~~Perform minor rehabilitation of the Crosby Drive interchange. Adjust radii at frontage road to accommodate truck turning movements.~~Adjust signal timing and signing at the Crosby Drive interchange per Section 16.3 of the Technical Provisions. Maintain facilities and traffic control per Sections 18 and 19 of the Technical Provisions. Crosby Drive interchange shall remain in place.
- Design and construct 4th Street interchange from Station 10+00 to Station 15+09 generally consistent with the Draft Interim Schematic. Elevate 4th Street at the frontage roads allowing the frontage road lanes to pass underneath 4th Street.
- Design and construct West Main Street interchange from Station 10+00 to Station 15+07 generally consistent with the Draft Interim Schematic. Elevate West Main Street at the frontage roads allowing the frontage road lanes to pass underneath West Main Street.
- Design and construct Belt Line Road interchange from Station 99+00 to Station 127+00 and IH 35E from 730+00 to 780+00 generally consistent with the Draft Interim Schematic. Design and construct associated ramp improvements and realignment of the existing railroad tracks. New interchange shall consist of three levels and shall remove all at-grade railroad crossings with Belt Line Road being relocated to the lowest level, IH 35E relocated to the highest level and the railroad crossing relocated to the middle level. This interchange shall be constructed in accordance with the Ultimate Project as shown in the environmental assessment. Belt Line Road improvements shall include construction of the Broadway Street intersection improvements and new bridge over Belt Line Road.
- IH 35E bridge beginning at Station 741+65 and ending at Station 762+35 and connecting frontage roads shall accommodate Elk Street at Station 760+23 to be designed and constructed by others.
- Perform minor rehabilitation of the Century Drive intersection. Adjust radii at frontage road to accommodate truck turning movements.
- Adjust signing at the Luna Road interchange per Section 16.3 of the Technical Provisions. Maintain facilities and traffic control per Sections 13.2, 18, and 19 of the Technical Provisions. Luna Road interchange shall remain in place.
- Adjust signal timing and signing at the Whitlock Lane / Sandy Lake Road interchange per Section 16.3 of the Technical Provisions. Maintain facilities and traffic control per Sections 18 and 19 of the Technical Provisions. Whitlock Lane / Sandy Lake Road interchange shall remain in place.
- Design and construct the Dickerson Parkway interchange from Station 10+00 to Station 60+81 generally consistent with the Draft Interim Schematic. Dickerson Parkway shall overpass IH 35E and adjacent frontage roads.

- Design and construct a collector-distributor system from Dickerson Parkway, approximately station 857+00, to south of Round Grove Road, approximately station 1009+00, consisting of one to three lanes in each direction generally between the frontage roads and general purpose lanes and connecting PGBT and SH 121 generally consistent with the Draft Interim Schematic. At the southern and northern terminus, the collector distributor system shall be provided as an auxiliary lane to the general purpose lanes generally consistent with the Draft Interim Schematic. Ingress/egress points to the collector-distributor systems at its southern limits will be accessible via the ramps leading to the PGBT direct connector ramps at Dickerson Parkway. Ingress / egress points to the collector-distributor systems at its northern limits will be accessible via the ramps leading to the SH 121 direct connector ramps near Round Grove Road.
- Adjust ~~signal timing and~~ signing at the Frankford Road interchange per Section 16.3 of the Technical Provisions. Maintain facilities and traffic control per Sections 13.2, 18, and 19 of the Technical Provisions. Frankford Road interchange shall remain in place.
- Design and construct four direct connector ramps on the north side of the interchange between IH 35E and SH 121 in the Ultimate Project location, except as necessary to tie horizontally and vertically into the Project, or interim, edge of pavement as shown in the Draft Interim Schematic: One ramp connecting westbound SH 121 to northbound IH 35E, one from eastbound SH 121 to northbound IH 35E, one from southbound IH 35E to eastbound SH 121 and one from southbound IH 35E to westbound SH 121.
- Design and construct the Round Grove Road interchange from Station 106+91 to Station 108+82 generally consistent with the Draft Interim Schematic. Round Grove Road bridge shall be lengthened to accommodate the Project.
- Design and construct the Corporate Drive interchange from Station 105+97 to Station 107+82 generally consistent with the Draft Interim Schematic. Corporate Drive bridge shall be lengthened to accommodate the Project.
- Adjust signal timing and signing at the SH 121 Business interchange per Section 16.3 of the Technical Provisions. Maintain facilities and traffic control per Sections 18 and 19 of the Technical Provisions. SH 121 Business interchange shall remain in place.
- Design and construct the Fox Avenue interchange from Station 103+67 to Station 111+57 generally consistent with the Draft Interim Schematic. Fox Avenue bridge shall be replaced as needed to accommodate the Project.
- Design and construct the FM1171 / Main Street interchange from Station 105+26 to Station 107+26 generally consistent with the Draft Interim Schematic. FM 1171 bridge shall be replaced as needed to accommodate the Project.
- Adjust signal timing and signing at the Valley Ridge Road interchange per Section 16.3 of the Technical Provisions. Maintain facilities and traffic control per Sections 13.2, 18, and 19 of the Technical Provisions. Valley Ridge Road interchange shall remain in place.
- Design and construct retaining wall system along the western abutment of the existing KCS Railroad bridge crossing at Station 1270+00 to accommodate two southbound frontage road lanes generally consistent with the Draft Interim Schematic.
- Construct the FM 407 / Lake Park Road interchange from Station 100+00 to Station 112+99 per the design shown in the 100% signed and sealed plans, specifications, and aesthetic requirements as provided in the Reference Information Documents to convert the existing interchange from an

underpass to an overpass. Lower FM 407 to grade and construct bridge at IH 35E allowing IH 35E general purpose lanes and managed lanes to pass over FM 407. FM 407 design and construction shall accommodate the Utility Adjustments for the following Utilities as provided in the Reference Information Documents: Brazos Electric (U13765) and Oncor Electric Transmission (U13815 and U13816).

- Perform minor rehabilitation of the Bogard Lane intersection. Adjust radii at frontage road to accommodate truck turning movements.
- Design and construct the Garden Ridge Boulevard interchange from Station 100+82 to Station 112+50 generally consistent with the Draft Interim Schematic in order to convert the interchange from an underpass to an overpass. Lower Garden Ridge Boulevard to grade allowing IH 35E general purpose lanes and managed lanes to pass over Garden Ridge Boulevard.
- Design and construct Highland Village intersection from Station 10+00 to Station 106+00 generally consistent with the Draft Interim Schematic.
- Design and construct the Copperas Branch Park Road generally consistent with the Parks Mitigation Master Plan.
- Design and construct a portion of the Ultimate Project bridge over Lake Lewisville and associated roadway approaches from Station 1302+00 to Station 1515+15 generally consistent with the Draft Interim Schematic to accommodate four southbound general purpose lanes, two southbound frontage road lanes barrier separated from the general purpose lanes, two reversible managed lanes, and an eight-foot-wide shared use path which is barrier separated from the frontage roads.
- Re-purpose, and rehabilitate the existing bridge over Lake Lewisville generally consistent with the Draft Interim Schematic to accommodate four northbound general purpose lanes, two frontage road lanes barrier separated from the general purpose lanes, and a fourteen-foot-wide shared use path which is barrier separated from the frontage roads.
- Design, construct, widen or rehabilitate existing pavement as necessary to accommodate two northbound frontage roads from Eagle Point Road, Station 1352+00, Denton Drive/Country Lane, and Station 1470+00 generally consistent with the Draft Interim Schematic.
- Design and construct Country Lane / Denton Drive interchange from Station 101+75 to Station 110+15 generally consistent with the Draft Interim Schematic. Construct bridge at IH 35E allowing IH 35E general purpose lanes and managed lanes to pass over Country Lane / Denton Drive.
- Design and construct Turbeville Road/Hundley Drive interchange from Station 100+00 to Station 112+74 generally consistent with the Draft Interim Schematic.
- Perform minor rehabilitation of the FM 2181 / Swisher Road interchange. Adjust radii at frontage road to accommodate truck turning movements.
- Perform minor rehabilitation of the Quail Run intersection. Adjust radii at frontage road to accommodate truck turning movements.
- Adjust signal timing and signing at the Meadow Oaks / Dobbs Lane intersection per Section 16.3 of the Technical Provisions. Maintain facilities and traffic control per Sections 18 and 19 of the Technical Provisions. Meadow Oaks / Dobbs Lane intersection shall remain in place.
- Design and construct Corinth Parkway interchange from Station 10+89 to Station 21+45 to convert the existing interchange from an underpass to an overpass as needed to accommodate the Ultimate

Project. Lower Corinth Parkway to grade and construct bridge at IH 35E allowing IH 35E general purpose lanes and managed lanes to pass over Corinth Parkway.

- Design and construct Post Oak Drive interchange, including new bridge over IH 35E, from Station 10+96 to Station 20+68 generally consistent with the Draft Interim Schematic and as needed to accommodate the Ultimate Project.
- Adjust signal timing and signing at the Mayhill Road interchange per Section 16.3 of the Technical Provisions. Maintain facilities and traffic control per Sections 18 and 19 of the Technical Provisions. Mayhill Road interchange shall remain in place.
- Adjust signal timing and signing at the Loop 288 interchange per Section 16.3 of the Technical Provisions. Maintain facilities and traffic control per Sections 18 and 19 of the Technical Provisions. Loop 288 interchange shall remain in place.
- Adjust signal timing and signing at the Pennsylvania Drive / San Jacinto Boulevard intersection per Section 16.3 of the Technical Provisions. Maintain facilities and traffic control per Sections 18 and 19 of the Technical Provisions. Pennsylvania Drive / San Jacinto Boulevard intersection shall remain in place.
- Adjust signal timing and signing at the Teasley Drive / FM 2181 interchange per Section 16.3 of the Technical Provisions. Maintain facilities and traffic control per Sections 18 and 19 of the Technical Provisions. Teasley Drive / FM 2181 interchange shall remain in place.
- Adjust signal timing and signing at the Fort Worth Drive interchange per Section 16.3 of the Technical Provisions. Maintain facilities and traffic control per Sections 18 and 19 of the Technical Provisions. Fort Worth Drive interchange shall remain in place.
- Adjust signal timing and signing at the McCormick / Avenue A interchange per Section 16.3 of the Technical Provisions. Maintain facilities and traffic control per Sections 18 and 19 of the Technical Provisions. McCormick / Avenue A interchange shall remain in place.
- Design and construct bridge at IH 35E from Station 1969+82 to Station 1971+60 allowing IH 35E general purpose lanes and managed lanes to pass over McCormick / Avenue A generally consistent with the Draft Interim Schematic.
- Design and construct North Texas Boulevard interchange, including new bridge over IH 35E, from Station 10+99 to Station 23+42 generally consistent with the Draft Interim Schematic and as needed to accommodate the Ultimate Project. Improvements at this location shall also include the connecting street from North Texas Boulevard to Underwood Street and IH 35E general purpose lanes from Station 1984+00 to Station 1997+00.
- Perform minor rehabilitation of the Collier Street / Knight Street intersection. Adjust radii at frontage road to accommodate truck turning movements.
- Perform minor rehabilitation of the Avenue C intersection. Adjust radii at frontage road to accommodate truck turning movements.
- Adjust signal timing and signing at the Bonnie Brae interchange per Section 16.3 of the Technical Provisions. Maintain facilities and traffic control per Sections 18 and 19 of the Technical Provisions. Bonnie Brae interchange shall remain in place.

- Adjust signal timing and signing at the Oak Street interchange per Section 16.3 of the Technical Provisions. Maintain facilities and traffic control per Sections 18 and 19 of the Technical Provisions. Oak Street interchange shall remain in place.
- Adjust signal timing and signing at the US 380 interchange per Section 16.3 of the Technical Provisions. Maintain facilities and traffic control per Sections 18 and 19 of the Technical Provisions. US 380 interchange shall remain in place.
- Rehabilitate existing bridges that are to be reused or widened.
- Maintain managed lanes, general purpose lanes, frontage roads, bridges and other drainage structures and other facility appurtenances within the Project right of way and transition areas during the construction period until substantial completion.
- The Project does not include design and construction of the University of North Texas (UNT) pedestrian overpass which will be performed by others under a separate contract. Final plans are provided in the Reference Information Documents.
- Bridges and bridge class structures identified as "Bridges not in Project" in the IH 35E Bridge Condition Summary, as provided in the Reference Information Documents, shall not be included in the scope of this Project.

Options Scope

- Not applicable

1.3 Project Requirements

Developer shall design and construct the Project in compliance with requirements in TxDOT's *Standard Specifications for Construction and Maintenance of Highways, Streets, and Bridges (2004 or latest edition)*. The Developer's design of the Project shall accommodate the Ultimate Project in future phases. Developer shall construct the Ultimate Project in the areas where the Ultimate Project is specified in Section 1.2 of the Technical Provisions. In all other areas, it is understood that due to future horizontal and vertical profile shifts it may not be reasonable or feasible to accommodate the Ultimate Project during this Project. These areas are described as interim. The Developer's design shall provide for a feasible transition from the Project Scope to the Ultimate Project unless otherwise in accordance with the Contract Documents. Prior to construction of the Project Scope, Developer shall provide to TxDOT a schematic level design showing the transition from the Project Scope to the Ultimate Project. Such design shall include a draft sequence of construction plan, a preliminary traffic control plan, horizontal and vertical alignments, wall locations, cross-sections, and bridge layouts in accordance with TxDOT's Project Development Process Manual, Chapter 2, Section 4 - Preliminary Schematics, paragraph 2360 – Develop Typical Sections. For providing this schematic level design that shows the transition plan, Developer is not required to perform or prepare for any public involvement activities, prepare minute orders, coordinate with railroad companies, government entities or third parties, or give consideration to landscape and aesthetic requirements.

Requirements for any portion of the Work are not limited to any individual section of these Technical Provisions and may be addressed within more than one section. Developer shall review and follow all requirements related to the Work as described in all sections of the Technical Provisions.

Certain TxDOT standards, manuals, and other documents are referenced as requirements in the Technical Provisions. If any such standards, manuals, or documents are expressly required in the Technical Provisions, then all work associated with the commitments, statements, requirements and guidelines included in these documents shall be included in the Project. All provisions and guidelines of TxDOT standards and other referenced documents, including figures and tables, shall be interpreted as mandatory, and words such as "should," "may," "could," "can," and "will" shall mean "shall" unless the context requires otherwise, as determined in the sole discretion of TxDOT. The Developer shall disregard qualifying words such as "usually," "normally," and "generally." In addition, references to TxDOT's preferred practices and policies shall be construed to be mandatory requirements unless the context requires otherwise, as determined in the sole discretion of TxDOT. It shall be in TxDOT's sole discretion to determine when the context does not require a provision to be mandatory.

References to mainline, mainlane, and ML throughout these Technical Provisions shall include general purpose lanes and managed lanes.

1.4 Maintenance Work Requirements

Developer shall maintain all Elements within the Project right of way limits in accordance with Section 19.

Developer shall ensure that the existing Elements meet the requirements of Section 19.

Developer is not responsible for maintenance of roadways beyond the longitudinal limit of the Work determined by the end of transitions from the Project to existing roadways.

2 PROJECT MANAGEMENT

Developer shall establish and maintain an organization that effectively manages all of the Work. This project management effort shall be defined by and follow the Project Management Plan (PMP), which is a collection of several plans describing the Work as set forth in Table 2-1 below. The Project Management Plan is an umbrella document that describes Developer's managerial approach, strategy, and quality procedures to design and build the Project and achieve all requirements of the Contract Documents. Each part of the PMP shall include details of external auditing procedures.

Table 2-1: Project Management Plan Components

Chapter Title	Section of Book 2 That Defines the Chapter Requirements
Project Administration	Section 2
Quality Management Plan • **Design Quality Management** • **Construction Quality Management** • **Maintenance Management**	Sections 2 and 19
Comprehensive Environmental Protection Program	Section 4
Public Information and Communications Plan • **Public** • **Developer Entities** • **Local Government and Stakeholders** • **TxDOT**	Section 3
Safety Plan	Section 2
TxDOT – Developer Communications Plan	Section 2
Right of Way Acquisition Plan	Section 7
Risk Management Plan	Section 2
Affected Third Parties Plan	Section 5
Emergency Management Plan	Section 2

A listing of documents to be included in the Project Management Plan is contained in Attachment 2-1, Project Management Plan Contents, which also indicates when each document must be submitted to TxDOT.

TxDOT shall audit and monitor the activities described in the management plans to assess Developer performance. All commitments and requirements contained in the PMP shall be verifiable in accordance with ISO quality and audit standards.

2.1 Administrative Requirements

2.1.1 Project Schedule

2.1.1.1 General Requirements

The Project Schedule shall define the timeframe for completion of the Project and achievement of milestones, and be used to monitor progress and denote changes that occur during design, construction, and maintenance, as well as serving to determine the amount due to Developer for a progress payment, if applicable. Before the commencement of any Schedule Activity, Developer shall submit a Project Baseline Schedule in accordance with the Work Breakdown Structure. The planning, design, construction, and completion of the Work shall be undertaken and completed in accordance with the most recent Project Schedule approved by TxDOT.

2.1.1.2 Required Submittals

2.1.1.2.1 Project Baseline Schedule

Developer shall use the Preliminary Project Baseline Schedule (PBS-1) submitted with the Proposal as a foundation to prepare a Project Baseline Schedule and shall submit a draft of the Project Baseline Schedule to TxDOT for review and approval. Approval of the Project Baseline Schedule (PBS-2) shall be a condition of NTP2. Developer shall submit the draft PBS-2 to TxDOT 90 days in advance of the anticipated NTP2 date. TxDOT will review the Project Baseline Schedule within 30 days of submission. In the event that TxDOT does not accept the Project Baseline Schedule, Developer shall revise and resubmit it with changes clearly identified. TxDOT will review each resubmission of the Project Baseline Schedule within 30 days of resubmission. Developer shall submit a single hardcopy of the Project Baseline Schedule on full-size (24" x 36") color plot sheets, along with an electronic version of the schedule in its native format for each submittal. Developer shall be responsible for updating scheduling software to maintain compatibility with then-current TxDOT-supported scheduling software. Compatible shall mean that the Developer-provided electronic file version of the Project Baseline Schedule may be loaded or imported by TxDOT using TxDOT's scheduling software with no modifications, preparation, or adjustments. All scheduling software settings within the scheduling/leveling dialog box shall remain "default" unless otherwise approved by TxDOT.

The Project Baseline Schedule will be developed in stages beginning with the PBS-1. At each stage of PBS development, a new version will be created with more details added. PBS-2 shall be progressed and updated monthly until PBS-3 is approved. PBS-3 shall be submitted sufficiently in advance to obtain approval within ninety (90) days after the Agreement Effective Date. The approved PBS-3 shall be progressed and updated monthly until a subsequent version (PBS-3+) is approved.

PBS-3 and all subsequent schedule revisions (PBS-3+) shall be submitted sufficiently in advance to obtain approval prior to performance of any utility relocation or construction activities changed in the revised baseline.

Developer shall submit to TxDOT a Revised Project Baseline Schedule within fourteen (14) Days after each Change Order or each Directive Letter is executed. All approved Change Orders shall be incorporated into the originally planned execution of the Work. TxDOT shall confirm in writing the approval of each Revised Project Baseline Schedule. The approved Project Baseline Schedule or current

approved Revised Project Baseline Schedule shall remain in force until a subsequent Revised Project Baseline Schedule is approved by TxDOT.

The Project Baseline Schedule shall include a separate narrative report which describes, in general fashion, Developer's proposed methods of operation for designing and constructing the major portions of the Work required by the Contract Documents. The schedule narrative shall describe the general sequence of design and construction, the proposed Critical Path of the Project, and all Completion Deadline.

The Project Baseline Schedule shall include all major Work activities required under the Contract Documents, in sufficient detail to monitor and evaluate design and construction progress, from commencement of the Work to Final Acceptance of the Work. The Project Baseline Schedule shall also include activities for property acquisition, Utility Adjustments, permit acquisitions and maintenance during construction, and interfaces with other projects, localities, municipalities, and other Governmental Entities. For each major activity, Developer shall indicate the duration (in Days) required to perform the activity and the anticipated beginning and completion date of each activity. In addition, the Project Baseline Schedule shall indicate the sequence of performing each major activity and the logical dependencies and inter-relationships among the activities.

The Project Baseline Schedule shall be organized consistent with the Work Breakdown Structure (WBS), the minimum requirements of which are included as Attachment 2-2, Work Breakdown Structure Requirements, and shall be cost and resource loaded in accordance with Table 2-2. Each Schedule Activity shall be mapped to one and only one of the WBS elements. Developer shall further develop and detail the WBS in accordance with its specific Schedule Activities and retaining the ability to summarize to at least the same level as shown in the base. Developer may add additional activities to the levels presented in Attachment 2-2 with TxDOT's written approval.

Table 2-2: Schedule Level-of-Detail Requirements

Discipline	Detail	PBS-1	PBS-2	PBS-3+
Right of Way Acquisition	WBS Level	4	All levels	All levels
	Cost Loading	No	No	No
	Resource Loading	No	No	No
	Maximum duration of Schedule Activity	No maximum	20 Days[1]	20 Days[1]
Preconstruction Submittals & Permitting	WBS Level	4	All levels	All levels
	Cost Loading	No	No	No
	Resource Loading	No	No	No
	Maximum duration of Schedule Activity	No maximum	20 Days[1]	20 Days[1]
Utility Coordination	WBS Level	4	All levels	All levels
	Cost Loading	No	No	No
	Resource Loading	No	No	No

	Maximum duration of Schedule Activity	No maximum	20 Days[1]	20 Days[1]
Design	WBS Level	4	All levels	All levels
	Cost Loading	No	No	No
	Resource Loading	No	No	No
	Maximum duration of Schedule Activity	No maximum	20 Days[1]	20 Days[1]
Utility Relocation	WBS Level	5	5	All levels
	Cost Loading	Yes	Yes	Yes
	Resource Loading	No	No	Yes
	Maximum duration of Schedule Activity	No maximum	No maximum	20 Days[1]
Construction	WBS Level	4	4	All levels
	Cost Loading	No	Yes	Yes
	Resource Loading	No	No	Yes
	Maximum duration of Schedule Activity	No maximum	No maximum	20 Days[1]
Operations and Maintenance During Construction	WBS Level	4	4	All levels
	Cost Loading	No	Yes	Yes
	Resource Loading	No	No	Yes
	Maximum duration of Schedule Activity	No maximum	No maximum	20 Days[1]

[1]Or as otherwise approved by TxDOT.

At a minimum, all resource loading shall detail the number of crews and crew type. Prior to the inclusion of any crew in any Project Baseline Schedule, Developer shall provide, for approval by TxDOT, the composition and production rate for each crew type.

The Project Baseline Schedule shall divide the Work into activities with appropriate logic ties to show the Developer's overall approach to the planning, scheduling, and execution of the Work. All Work shall be divided into reasonable sections; design level activities shall be divided at a maximum by roadway purpose (i.e. NBFR, SBFR, SBGPL, NBGPL, ML, XR, etc.). Construction level activities shall be divided, at a maximum, by work areas between intersecting streets and by roadway purpose and shall be represented by Schedule Activities. The duration and logical relationships of the Schedule Activities (or summaries at phase level) shall be based on the actual duration and relationships anticipated. Developer shall not use calendar dates or constraints to logically begin or complete any Schedule Activity unless such calendar dates or constraints are shown in the Technical Provisions or other Contract Documents.

Developer shall use standard and consistent Schedule Activity identification numbers, textual descriptions, and codes in all Project Baseline Schedule submittals in a manner acceptable to TxDOT. Each Project Baseline Schedule submittal shall be clearly identified. Resubmissions of a Project Baseline Schedule shall use the same revision number as the original submission individually identified by a sequential appended letter (A, B, C, etc.) as an identification of a revised version.

Developer shall allocate the total Price throughout the Schedule Activities in the Project Baseline Schedule. Such allocation shall accurately reflect Developer's cost for each Schedule Activity and shall not artificially inflate, imbalance, or front-load line items. The price of each Schedule Activity shall be all-inclusive and shall include all direct and indirect costs, overhead, risks, and profit. Cost information shall be included with Developer's first monthly Project Status Schedule Update.

Each milestone shall be separately identified, conform to the scheduling requirements set forth in the Contract Documents, and be assigned a "finish no later than" constraint date.

No unspecified milestones, constraints, Float suppression techniques, or use of Schedule Activity durations, logic ties, and/or sequences deemed unreasonable by TxDOT, shall be used in the Project Baseline Schedule. Each Project Baseline Schedule submittal shall clearly and individually define the progression of the Work within the applicable time frame by using separate Schedule Activities. The critical path shall be highlighted in red on all schedules to distinguish critical Schedule Activities from other Schedule Activities and Float shown for all Schedule Activities.

Float shall not be considered as time for the exclusive use of or benefit of either TxDOT or Developer but shall be considered as a jointly owned, expiring resource available to the Project and shall not be used to the financial detriment of either party. Any method utilized to sequester Float calculations will be prohibited without prior approval of TxDOT. Any schedule, including the Project Baseline Schedule and all updates thereto, showing an early completion date shall show the time between the scheduled completion date and the applicable Completion Deadline as "Project Float."

The Project Baseline Schedule shall be used by the Parties for planning the progress of the Works. Approved logic changes and approved changes to the Agreement shall be incorporated into the Project Baseline Schedule.

The materials, labor, or equipment quantity that the Schedule Activity value will be based on shall be indicated as a resource and only those resources actually available to the Developer shall be included. Labor-loading of activities may be based upon total number of workers, but at a minimum total number of crews. Major construction equipment to be used by Developer and Subcontractors at all tiers in prosecuting Work shall be assigned to applicable activities. The quantity shall represent the estimated effort in-place for the Schedule Activity value.

Developer shall develop the WBS with clearly identifiable linkage to the Schedule of Values and Developer-designed Schedule Activities and phases represented in the Project Baseline Schedule. The Schedule Activity for each Work Element shall indicate the duration, timing, and logical relationship to other Work Elements, including to Schedule Activities other than the parent Schedule Activity of the particular Work Element. Schedule Activities shall be broken down minimally to Work Elements (for example, bridges shall be broken down into foundations, substructure, superstructure, and decks.) All Work shall be broken down to similar manageable Work Elements. For mobilization Schedule Activities or Work Elements, Developer shall provide a list of Work items that are included in each Schedule Activity or Work Element.

The Project Baseline Schedule shall include a listing of all submittals as called out in the Contract Documents. Submittal activity durations shall include specific durations for TxDOT review and/or

approval of Developer's submittals as called out elsewhere in the Agreement and these Technical Provisions.

With the exception of activities relating to Environmental Approvals by Governmental Entities, each activity depicting Developer's operations shall have duration of not more than twenty (20) Days, and not less than one (1) Day, except as otherwise approved by TxDOT. All activities shown in the schedule, with the exception of the first and last activities shall have a minimum of one predecessor and a minimum of one successor activity.

The Project title and data date shall be displayed on all schedules, charts, and diagrams. A legend shall be provided on all schedules, charts, and diagrams which indicate the various symbols used and their meanings. Electronic versions shall likewise be uniquely identifiable by filename.

2.1.1.2.2 Project Status Schedule Updates

Beginning with the first full month after NTP2, Developer shall submit Project Status Schedule Updates to TxDOT within 7 calendar days after month end. The Project Status Schedule Updates shall be submitted monthly, as part of the monthly Progress Report and payment request, if applicable, until Final Acceptance of the Work.

The Project Status Schedule Updates shall accurately reflect the current status of the Project including all activities completed as of the effective date of the current PBS, recovery schedules, schedule revisions due to approved Change Orders, Developer's detailed schedule for completing the Work, and all information and reporting required for the Project Schedule. At a minimum, the monthly Project Status Schedule Update(s) shall include the following current Work data:

- Detailed resource-loaded schedule of activities that clearly identify the Critical Path
- If applicable, progress for the current payment request period for all Project activities
- Actual start and finish dates of Work, physical percent complete, and Days remaining for Work in progress
- Work as a result of a Directive Letter

The data date for use in calculating the Project Status Schedule Update shall be the first day of the following month. The Project Status Schedule Update shall accurately reflect updated progress as of the effective date of the updated PBS, forecast finish for in-progress Schedule Activities, and reforecast early dates and late dates for remaining Schedule Activities and shall indicate the overall physically complete percent of the Project. If any actual dates are changed or corrected in any following month, a narrative must be included providing explanation of the change.

Time-scaled network diagrams shall be submitted, on at least a monthly basis, on sheets no larger than 22" X 34", using a scale that yields readable plots. The network diagrams shall be organized consistent with the Project WBS. Project activities shall be linked by logic ties and shown on their early dates. The Critical Path shall be highlighted and Float, where applicable, shown for all Project activities.

The monthly Project Status Schedule Update(s) shall include additional, separate, filtered lists of Project activities and work elements included in the Project Schedule to create the following reports:

a) Coordinating with and accomplishing Work associated with Utilities,

b) Bar chart schedule sorted by segment or section indicating the physical status of all activities as of date of the update,

c) Graphical report which compares Developer's progress to planned progress by segment or section, and major payment item/WBS,

d) Design document submittals for the forthcoming period,

e) Tabular report listing all activities with ten (10) days or less Float,

f) Sixty-day (60) look ahead report on all TxDOT and Governmental Approvals required,

g) Ninety-day (90) look ahead bar chart schedule sorted by WBS and activity early start dates,

h) Monthly expenditure projections and cash expenditure curves by WBS,

i) Critical items graphical report for each Critical Path sorted by activity early start date, and

j) Time-scaled critical path network plot indicating the status of all activities as of the date of the update.

The reports shall be accompanied by a narrative progress report describing the status of the Project in detail including progress made that period; plans for the forthcoming period; all potential delays and problems; their estimated effect on the Project Schedule and overall completion, and whether ahead of or behind schedule.

TxDOT will review the monthly Project Status Schedule Update(s) for consistency with Developer's WBS and the current approved Project Schedule and for conformance with the Contract Documents. Developer shall correct any deficiencies and resubmit its monthly Project Status Schedule Update(s) with the payment request. TxDOT will notify Developer of corrections required within ten (10) Business Days of receipt of the Project Status Schedule Update(s).

TxDOT will use these updates to manage its activities to be responsive to Developer's Project Schedule, to analyze monthly progress payments to Developer, and to measure Developer's performance with respect to its plan for accomplishing the Work.

Developer shall submit a single hard copy of the Project Status Schedule Update in full-size color plot sheets, along with an electronic version of the schedule in its native format. Software settings shall not be changed or modified, for any schedule submissions, without prior TxDOT Approval. No changes in activity durations, calendar assignments, logic ties, or constraints will be allowed in the Project Status Schedule Update without the written approval of TxDOT.

2.1.1.2.3 Schedule of Values

Concurrent with the Project Baseline Schedule, the Developer shall submit to TxDOT a complete Schedule of Values for all Payment Activities as described below for TxDOT's approval. TxDOT approval of the Schedule of Values shall be a condition of NTP2. In addition, no payment by TxDOT will be made until the Schedule of Values is approved by TxDOT.

The following pertains to presentation of the Schedule of Values:

a) The Payment Activities shall be organized and grouped according to the approved WBS with subtotals for each WBS item at each WBS Level. There can be one or more Payment Activities for each of the lowest (terminal) WBS elements in the WBS. For example, earthwork (WBS Level VI) could have one Payment Activity or multiple Payment Activities that roll up costs to the WBS Level VI element.

b) The Schedule of Values shall contain for each Payment Activity from the Project Baseline Schedule, the activity unique identification number, the activity description, the quantity, the applicable unit, unit price, and scheduled value.

c) The Developer's project management, administration, design, contingencies, and any allowance for inflation, profit and financing, as well as indirect site costs such as site cleanup and maintenance; temporary roads and access; off-site access roads; and security shall be prorated through all Payment Activities so that the sum of all the Schedule of Values line items equals the Total Project Construction Cost.

If it becomes necessary to add, combine, eliminate, or modify any Payment Activities due to changes in the Work, a revised Schedule of Values as derived from a revised Project Baseline Schedule, shall be submitted fourteen (14) days after the respective Change Order is executed for acceptance by TxDOT.

2.1.1.2.4 Progress Report

Each month, beginning with the first full month after NTP2, the Developer shall submit to TxDOT the Progress Report. The Developer shall submit the Progress Report by close of business within seven (7) days following prior month's end. An electronic and printed copy of the entire Progress Report shall be submitted to TxDOT.

The Progress Report shall contain a narrative which shall include the following items:

a) Describe progress for each section and the Project as a whole, including all phases of Work. Identify start date and completion dates on major areas of Work. Group the information based on the WBS.

b) Summarize QA/QC findings.

c) List any Change Orders that were identified or executed during the period from the submission of the previous month's progress report to the submission of the current progress report. Include their status.

d) Identify Schedule Activities planned for the upcoming period.

e) Identify problems and issues that arose during the period from the submission of the previous month's progress report to the submission of the current progress report and issues that remain to be resolved.

f) Summarize resolution of problems/issues raised in previous progress reports or resolved during the period from the submission of the previous month's progress report to the submission of the current progress report.

g) Identify Critical Path issues and proposed resolution.

h) Provide a report on the Completion Deadlines showing the schedule dates for the immediate prior month and current month. A narrative is required to explain why the dates have changed for variances greater than thirty (30) days.

i) Provide monthly expenditure projection curves for the total Project.

j) Identify requested and/or required TxDOT actions for the next month.

k) Provide digital progress photographs that accurately depict Project progress as outlined in the progress report narrative.

The Project Status Schedule Update shall be provided as part of the Progress Report using the following print outs:

a) Gantt chart sorted by Work areas indicating the physical status of all Schedule Activities as of the date of the update and comparing the Developer's progress to planned progress;

b) Gantt chart showing all critical Schedule Activities, sorted by early start dates;

c) Ninety-day (90) look ahead Gantt chart showing all upcoming Submittals from the Developer and approvals required by TxDOT or Governmental Entities;

d) Ninety-day (90) look ahead Gantt chart grouped by WBS and sorted by early start dates; and

e) Gantt chart that clearly identifies the longest path sorted by early start dates.

If any Progress Payment is to be submitted, it shall accompany the monthly Progress Report.

If requested by TxDOT, the Developer shall make all corrections to the monthly Progress Report and resubmit. If the Developer does not agree with TxDOT's comments, the Developer shall provide written notice of disagreement within seven (7) Days from the receipt of the comments.

2.1.1.2.5 As-Built Schedule

Upon completion of the Punch List, the Developer will submit the Project Status Schedule Update identified as the "as-built schedule". The "as-built schedule" shall reflect the exact manner in which the Work up to each Final Acceptance and described by the Contract Documents was actually performed (including start and completion dates, Schedule Activities, actual durations, sequences, and logic). The "as-built schedule" shall be signed and certified by the Developer's Project Manager and the Developer's scheduler as being a true record of when the Work was actually performed. The "as-built schedule" that TxDOT determines is both correct and complete is a requirement for each Final Acceptance.

2.1.1.3 Revisions

If it becomes necessary to add, combine, eliminate, or modify Payment or Schedule Activities to reflect modifications to the Work, such changes shall be made through a Change Order that has been provided by TxDOT, and therefore reflected in the Project Schedule. Revisions to the Project Schedule and consequent realignment of funds between Payment Activities may be requested by the Developer through a Change Request.

2.1.1.4 Time Impact Analysis

Developer shall submit to TxDOT a written time impact analysis (TIA) in each of the following situations:

a. As part of a PCO Notice based on a delay as set forth in Contract Documents.

b. If any changes in a schedule update impact the Critical Path, such that they create an extension of the Substantial Completion Date beyond the Substantial Completion Deadline.

c. If the Developer has claim for delay. Developer shall submit a separate TIA for each delay event.

TxDOT may request, at any time, a TIA demonstrating impact or potential impact to the schedule resulting from claimed delays or Change Orders which are being negotiated between TxDOT and Developer. If TxDOT requests a TIA, Developer shall submit the requested TIA within 15 Days of receiving the request. TxDOT will return the TIA to Developer as approved or not approved with comments to be incorporated for resubmission within 7 days of receipt by Developer. The submittal process shall be repeated until receiving TxDOT approval of the submittal.

Submission of a TIA does not relieve Developer of complying with all contractual requirements regarding notification and documentation of potential Change Orders and Change Orders.

Each TIA submitted by Developer shall consist of the following steps or elements:

a. Establish the status of the Project before the impact by using the most recent schedule update that has the closest data date prior to the event for TIA, or as adjusted by mutual agreement.

b. Identify the impact event, estimate duration of the impact, determine appropriate logic, and insert the impact activity or fragnet of activities into the schedule. Progress the schedule.

c. Demonstrate any resulting affects from the impact through layouts generated from the scheduling software. Filter activities to show added or modified activities and activities impacted from changes. Note any other changes made to the schedule including modifications to the calendars or constraints.

d. If the current Project Status Schedule Update is revised subsequent to submittal of a time impact analysis but prior to its acceptance, Developer shall promptly indicate, in writing to TxDOT, the need for any modification to its time impact analysis.

Developer shall submit the following with each TIA Submittal:

a. A narrative report which:

- Identifies the schedule update(s) used for analysis.
- Describes the procedures used to analyze schedule impacts including:
  - Additions, deletions, or modification to activities and or fragnets
  - Modifications to the calendars or constraints
  - Modifications to relationships
- Describes the impact or potential impact by comparing Work prior to the impact and Work affected or predicted to be affected after the impact.
- Describe mitigation efforts taken to date.
- Describe potential resolutions to mitigate or avoid impact.

b. Schedule layouts in PDF file format. Filter activities to clearly show impacted activities and affects to the Critical Path. Multiple layouts may be required to adequately demonstrate the impact to the Critical Path. At a minimum, provide a layout demonstrating associated activities prior to the impact and a layout demonstrating associated activities after the impact is inserted and the schedule is progressed.

c. One electronic copy in native software of the impacted PBS

d. Other information or documentation pertinent to the analysis.

Incorporation of TIA activities into the current schedule update submittal requires TxDOT approval.

2.1.1.5 Recovery Schedule

If at any time, the Work on any Critical Path item is delayed for a period which exceeds the greater of either thirty (30) days in the aggregate or that number of days in the aggregate equal to 5% of the days remaining until a Completion Deadline (including delays to which Developer may be entitled to a time extension under Section 13), then Developer, upon TxDOT's request, shall prepare and submit to TxDOT for review and approval with the next Project Status Schedule Update a Recovery Schedule demonstrating Developer's proposed plan to regain lost schedule progress and to achieve the original contractual milestones in accordance with this Agreement, including Substantial Completion by the Substantial Completion Deadline and Final Acceptance by the Final Acceptance Deadline.

If the recovery schedule is required hereunder, the Developer shall have no right to receive settlement of a payment request until such time as the Developer has prepared and TxDOT has accepted such recover schedule.

2.1.2 Document Management

All electronic information submitted to TxDOT shall be searchable and legible.

2.1.2.1 Document Storage and Retrieval Requirements

Developer shall establish and maintain an Electronic Document Management System (EDMS) to store, catalog, and retrieve all Contract Documents using the applicable control section job (CSJ) numbers. Unless otherwise directed by TxDOT, record retention shall comply with the requirements of the *Texas State Records Retention Schedule*, and shall be provided to TxDOT at the time of the expiration or earlier termination of the Agreement.

Maintenance records shall utilize the same format as TxDOT utilizes for its statewide asset inventory and condition assessments and shall be capable of being integrated into TxDOT's maintenance management systems.

Construction quality acceptance test results shall be automatically transmitted to TxDOT's I2MS system using TxDOT's extensible markup language (XML) web service. A sample is shown in Attachment 2-4, I2MS Test Form Fields. Developer shall coordinate with TxDOT to obtain the most current version prior to commencing construction quality acceptance testing. The responsible technician and his/her supervisor shall sign the daily test reports and the results of the daily tests shall be provided to TxDOT within 48-hours after test completion.

In the provision of a document management system, the Developer shall:

a) Use data systems, standards and procedures compatible with those employed by TxDOT and implement any new operating practices required as a result of TxDOT's amendments to any such systems, standards and procedures.

b) Provide a secure location for any interface as may be provided by TxDOT, such that only authorized users have access and that it is protected from loss, theft, damage, unauthorized or malicious use.

c) Employ appropriate standards and procedures, and train Developer personnel to operate any TxDOT data management system which TxDOT may require in connection with the Project.

d) Provide a mechanism for the electronic transfer of meta data along with the associated portable document format (PDF) images for uploading into an EDMS employed by TxDOT.

To allow for disaster recovery, the Developer shall back-up all Project-related documents on a nightly basis and store all Project-related documents in a secure off-site area on a weekly basis.

Developer shall provide TxDOT at Developer's expense, sufficient access to Developer's document control database as deemed necessary by TxDOT.

2.1.2.2 Design Visualization

Developer shall provide three-dimensional design files to TxDOT for use during the design and construction process.

2.1.2.2.1 Services to be Provided by TxDOT

The type of available data may vary dependent on the level of project development. Typical types of data the TxDOT will provide to the Developer if available are:

1. Data that TxDOT has on file concerning the project, if available. Examples include as-built plans, field notes, etc.)
2. Electronic data of topography, roadway alignments and edge lines, pavement markings, criteria files, cross sections, and Digital Terrain Models TxDOT or their consultant contractor have concerning the project.
3. Drawings, sketches, renderings or photographs of special design elements such as, sidewalk paving materials, crosswalk details, landscaping, and any architectural treatments, if available.
4. Elevation data that may be needed in some areas where the terrain changes abruptly and special design features are required, such as retaining walls or elevated structures.

2.1.2.2.2 Services to be Provided by the Developer

Developer shall provide accurate three-dimensional models that depict the Project. Completed models will represent realism and aesthetic attributes of the existing conditions and the proposed Project. The Developer will add roadway design details to the model that are not normally provided at the stage of schematic design and verify that the schematic design complies with design guidelines presented in the TxDOT Roadway Design Manual, Texas MUTCD, and the AASHTO Green Book.

The design visualization models shall show existing and proposed design conditions either separately or combined in the same display. Based on specific project requirements the final design visualization deliverables may include photo-matched renderings, rendered plan view layouts, and animated sequences. Developer shall provide a three dimensional CADD model of the completed project and any work product generated during the modeling process such as site photographs, textures, material assignments, and additional terrain information. All CADD data should be in electronic format and native to TxDOT's CADD architecture using Bentley Systems, Inc. MicroStation to provide complete compatibility between the contractor and TxDOT. The current CADD architecture and standards can be viewed at http://www.txdot.gov/business/contractors_consultants/v8.htm.

The Developer shall collect, review, and evaluate all of the available existing data pertaining to the Project and prepare the design visualization models to reflect current design requirements. The data will include MicroStation design files, GEOPAK geometry files, existing terrain models, and digital ortho photography. The Developer shall field verify the existing and proposed condition of design visualization models for dimensional accuracy and realism.

2.1.2.2.3 Design Visualization Services - Photo Simulations and Exhibits

The Developer shall provide photo simulations of no more than seven (7) locations to be determined by TxDOT.

The Developer shall coordinate the location of the photographs. The Developer shall take two existing condition photographs at each of the seven (7) locations. These photographs will serve as the basis for the photo-simulations.

The Developer shall provide two (2) mounted "before" images and two (2) mounted "after" static 3D photo matched images of proposed design elements at each of the seven (7) locations..

The computer model shall accurately depict the geometric design of the proposed improvements at each of the seven (7) locations that would cover the limits of the existing condition photographs. Engineering judgment will be used for definition of slope, retaining wall, bridge abutment placement, and other physical features that may not be readily apparent from the design schematic. The computer model is intended to be used by TxDOT for public information purposes.

All CADD work and resulting data will duplicate TxDOT's existing CADD architecture to ensure total compatibility. This data shall be delivered in native format using Bentley Systems, Inc. MicroStation and GEOPAK or match present versions in use by TxDOT. Specific TxDOT data/configuration for GEOPAK and geometric design will be used. Resulting animations for design visualization purposes do not have to be native MicroStation, but do need to be capable of viewing on any device with minimal support or effort by the end user. The current CADD architecture and standards can be viewed at http://www.txdot.gov/business/contractors_consultants/v8.htm.

Developer shall provide the following:

- Project Management
  - Coordinate with the TxDOT and interested parties on development of content, sequences and text placement.
- Project Set-Up / CADD Data Conversion
  - The Developer shall provide 3D roadway and ramp centerlines, striping, typical sections, planimetrics, base digital ortho aerial photography, and 3D contour data for the proposed roadway design.
  - Planimetric creation for additional corridor buildings.
- Modeling and Animation
  - The Developer shall model 3D.
  - Landscape creation (existing features).
  - Modeling of notable buildings around major interchanges.
  - Modeling of proposed grading along the roadway
- Texture Development
  - Color aerial photography field digital photography (building textures around major interchanges)
- Location Development
  - Still camera development and photo location matching
- Deliverables
  - Final Imagery Editing Development
    - Provide three (3) scheduled deliveries: 60% draft, 95% draft and final delivery
    - Provide the final delivery in three (3) digital formats: JPG, TIF, and PDF
    - Provide the final delivery on two (2) foam-core mounted before images and two (2) foam-core mounted after images limited in size to 11" x 14" for each of the seven (7) locations.

2.1.2.2.4 Design Visualization Services - 3-D Computer Model

The Developer shall prepare a topographically accurate 3D computer model of no more than ten (10) locations.

The Developer shall also produce a set of rendered orthographic plots of the entire project boundary at a scale of 1" = 100'.

The computer model will accurately depict the geometric design of the proposed improvements at each of the ten (10) locations and associated interchanges. Engineering judgment will be used for definition of slope, retaining wall, bridge abutment placement, and other physical features that may not be readily apparent from the design schematic. The computer model will also incorporate existing features in the corridor out to a distance of approximately 500-feet either side of the roadway centerline, but up to 750 feet as needed.

The Developer shall provide still-shot 3D views from various perspectives, and full-motion animated sequences recorded to DVD. The content of the stills and animated sequences is to be determined collaboratively with the TxDOT.

All CADD work and resulting data shall duplicate TxDOT's existing CADD architecture to ensure total compatibility. This data shall be delivered in native format using Bentley Systems, Inc. MicroStation and GEOPAK or match present versions in use by TxDOT. Specific TxDOT data/configuration for GEOPAK and geometric design shall be used. Resulting animations for design visualization purposes do not have to be native MicroStation, but do need to be capable of viewing on any device with minimal support or effort by the end user. The current CADD architecture and standards can be viewed at http://www.txdot.gov/business/contractors_consultants/v8.htm.

Developer shall provide the following:

- Project Management
  - Provide three scheduled deliveries: 60% draft, 95% draft, and final delivery.
  - Coordinate with the TxDOT and interested parties (up to two meetings) on development of content, sequences and text placement.
- Modeling and Animation
  - The Developer shall model 3D topography based on provided CADD data/standards
  - Generic creation of surrounding neighborhoods
  - Landscape creation (existing features)
  - Modeling of notable buildings around major interchanges
  - Modeling of proposed grading along the roadway.
- Texture Development
  - Color aerial photography
  - Field digital photography (building textures around major interchanges)
  - Surrounding vegetation
- Animation
  - Camera development (i.e. interchange overviews, "helicopter view" flight of modeled roadway, and various stills)
  - Passively animated traffic
- Editing/Compositing

- Compositing final footage
- Format preparation for DVD

- DVD Authoring
  - Interactive menu development
  - Graphic design of packaging and menus
  - Master DVD creation
- Orthographic Plots
  - Creation of orthographic cameras for high resolution plots of the entire project area.

2.2 Quality Management Plan

Developer shall submit a comprehensive Quality Management Plan to TxDOT for approval that is consistent with and expands upon the preliminary Quality Management Plan submitted with the Proposal. The Quality Management Plan shall comply with ISO standards for quality systems, quality plans and quality audits. Developer may elect to obtain formal ISO 9001 certification, but will not be required to do so.

2.2.1 General Requirements

Developer shall develop, implement, and maintain the Quality Management Plan for the Term. The Quality Management Plan shall describe the system, policies, and procedures that ensure the Work meets the requirements of the Contract Documents and provides documented evidence of same.

The complete Quality Management Plan shall incorporate the following features:

a) Developer shall make all quality records immediately available to TxDOT for review. Developer shall provide TxDOT with a copy of any and/or all quality records when requested.

b) The Quality Management Plan shall encompass all Work performed by Developer and Subcontractors of all tiers.

c) Developer shall submit to TxDOT the results of all internal audits within seven (7) Days of their completion**.**

d) Developer shall promptly submit to TxDOT non-conformance reports both upon issuance and resolution.

The Quality Management Plan shall contain detailed procedures for Developer's quality control and quality assurance activities. Developer's quality process shall incorporate planned and systematic verifications and audits undertaken by an independent party. Developer shall conduct all quality control, quality assurance, performance verification, and design overlay and coordination among design disciplines, all in accordance with the Quality Management Plan and the requirements of the Contract Documents.

Inspections, reviews, and testing shall only be performed by personnel with appropriate training and qualifications, for each appropriate item of Work (items produced on and off the Project site) using appropriate equipment that is accurately calibrated and maintained in good operating condition at an AASHTO (AASHTO R18-10, *Establishing and Implementing a Quality System for Construction Materials Testing Laboratories*) accredited facility, or at a facility with comparable accreditation (e.g., ISO 17025, *General Requirements for the Competence of Testing and Calibration Laboratories*).

2.2.2 Quality Terminology

Quality terminology, unless defined or modified elsewhere in the Contract Documents, shall have the meaning defined in ISO 9001. Terms used in ISO 9001 shall have the meanings defined below:

a) Organization: Developer's organization, including any Affiliates and Subcontractors.

b) Customers: the Users of the roadways, TxDOT, Customer Groups, and key stakeholders that have an adjacent property interest or connecting roadway.

c) Product: the Work.

2.2.3 Quality Management Organization

Developer shall regularly maintain the Quality Management Plan to contain current versions of the following information:

a) The organizational chart that identifies all quality management personnel, their roles, authorities and line reporting relationships.

b) Description of the roles and responsibilities of all quality management personnel and those who have the authority to stop Work.

c) Identification of testing agencies, including information on each agency's capability to provide the specific services required for the Work, certifications held, equipment, and location of laboratories for products produced both on and off the Project site.

d) Resumes for all quality management personnel.

2.2.4 Quality Policy

The Quality Management Plan shall contain a complete description of the quality policies and objectives that Developer will implement throughout its organization. The policy shall demonstrate Developer senior management's commitment to implement and continually improve the quality management system for the Work.

2.2.5 Inspection and Testing

The Quality Management Plan shall contain detailed descriptions of the inspection and test plans, including the timing, quantities represented and frequency of testing, that Developer will use to meet quality control and quality assurance requirements of the Work

Developer shall revise its Quality Management Plan when its own quality management organization detects a systemic or fundamental non-conformance in the work performed or in the manner the Work is inspected or tested, or when TxDOT advises Developer of such a problem.

2.2.5.1 TxDOT Construction Notices

On a weekly basis, Developer shall provide TxDOT with a rolling three-week inspection notice. The inspection notification shall include the fabrication schedule and planned construction activities for items where TxDOT is performing the fabrication inspection.

2.2.5.2 Reporting, Recordkeeping, and Documentation

Developer shall develop and maintain inspection and testing records that include, but are not limited to:

a) Quality control inspection reports and process control material sampling/testing results and control charts shall be submitted to TxDOT within twenty-four (24) hours following the inspection or test.

b) The Construction Quality Acceptance Firm (CQAF) shall maintain, electronically, a daily log of all inspections performed for both Developer and Subcontractor operations in a format acceptable to TxDOT and transmitted to TxDOT daily. The daily inspection reports shall identify inspections conducted, results of inspections, location and nature of defects found, causes for rejection, and remedial or corrective actions taken or proposed. The responsible technician and supervisor shall sign the daily inspection reports. The results of the daily inspections shall be provided to TxDOT in an electronic format within twenty-four (24) hours after the work shift.

c) The CQAF shall be responsible for establishing an electronic system for recording all material test results. The responsible technician and his/her supervisor shall sign the daily test reports. The results of the daily test shall be provided within one (1) Day of test completion.

d) The CQAF's inspection and materials quality program shall electronically deliver the laboratory and field test results to TxDOT in the database format provided in Attachment 2-2. This electronic reporting is intended to allow the Developer and TxDOT to make timely and accurate decisions on workmanship and material quality issues.

2.2.5.3 Laboratory Requirements

Developer shall perform testing in accordance with, but not limited to:

a) Quality acceptance tests shall be conducted by the CQAF's testing laboratory identified in the CQMP that complies with the requirements of the AASHTO Accreditation Program (AAP) or other appropriate accreditation acceptable to TxDOT for the pertinent test. A copy of AAP accreditation certificate(s) shall be transmitted to TxDOT upon their receipt by the testing laboratory.

b) Equipment in all laboratories shall be certified prior to commencing any construction activities and shall retain the certification by AASHTO, or TxDOT as applicable for the duration of the Work.

2.2.5.4 Supply Source and Material Quality

Quality of all materials shall conform to requirements contained in the Contract Documents and to any requirements of affected Utility Owners. The CQAF shall provide plant inspection and aggregate sampling and testing at concrete and asphalt plants. Manufacturers' test reports may supplement, but not replace, the QA inspections, sampling, testing and certification provisions.

2.2.6 Responsibility and Authority of Developer Staff

Personnel assigned to perform inspection, testing, or monitoring of characteristics for acceptance shall not be those personnel performing or directly supervising the Work being accepted.

Developer's Quality Manager and quality assurance staff shall have no responsibilities in the production of the Work. Quality control staff shall only have responsibilities in the production of the Work and shall remain independent of the quality assurance staff.

The Quality Manager shall prepare a monthly report of the quality inspections and tests performed, results of such inspections and tests, and occurrences and resolution of non-conformance discoveries. Developer shall submit the monthly reports to TxDOT for review.

Developer's Quality Manager, quality assurance manager, and quality control manager(s) shall have the authority to stop Work for quality-related issues.

2.2.7 Design Quality Management Plan

Developer shall prepare and submit to TxDOT for review and approval a Design Quality Management Plan (DQMP) that describes its policies, procedures, and staffing to manage design quality in accordance with the requirements of this Section 2.2.7.

2.2.7.1 Released for Construction Documents

Developer shall submit to TxDOT all Released for Construction Documents in accordance with the submittal requirements of the Design Quality Management Plan. Developer's Released for Construction Documents shall comply with the requirements of the Contract Documents, and shall be detailed, complete, constructible, and shall allow verification of the design criteria and compliance with Contract Documents.

Not later than two (2) Business Days after Developer has completed design of any particular Released for Construction Document, Developer shall submit the signed and sealed document to TxDOT.

The Developer shall prepare and provide all Project related Submittals and documents using English units of measure.

The Developer shall furnish all Submittals by electronic copy in accordance with Section 2.1.2. Unless otherwise stated in the Contract Documents, the Developer shall provide to TxDOT four paper copies and a single electronic copy of each Submittal. Each Submittal shall have the signature of an authorized representative of the Developer, unless otherwise expressly stated for a particular Submittal. The electronic copy shall be in a suitable format (e.g. PDF) or in the format in which the Work was originally created unless stated otherwise in the Contract Documents.

The Developer shall include with each Submittal a transmittal cover sheet in a form acceptable to TxDOT.

The minimum sheet size for the Submittals shall be 8.5 inches by 11 inches. The maximum sheet size shall be 36 inches by 120 inches. Every page in a Submittal shall be numbered in sequence.

Each Submittal shall be full and complete and shall be assigned a unique, sequential number, clearly noted on the transmittal cover sheet. Original Submittal shall be assigned a unique numeric Submittal number. Revised Submittals shall bear an alphanumeric designation which consists of the unique Submittal number assigned to the original Submittal followed by a letter of the alphabet to represent that it is a subsequent Submittal of the original.

Any changes made on a revised Submittal, other than those made or requested by TxDOT, shall be identified and noted on the revised Submittal.

Design deliverables shall include a title block, consistent with the standard Project drawing format established as part of the Quality Management Plan, with the following information:

a) Date of issuance and including all prior revision dates.

b) Contract title and number.

c) The names of the Developer and applicable Affiliates.

d) Stage of development.

e) Reference to applicable Technical Documents and amendments.

f) If required, review and acceptance or approval from a Governmental Entity, prior to submission to TxDOT.

g) Review stamp.

h) Action block space – All deliverables shall include a sufficient blank space in which the Developer may list required actions to be taken.

i) When calculations accompany drawings in a Submittal, cross-references from the body of the calculations to the individual drawing to which the pages of the calculations pertain.

j) Organization of the CAD drawings and associated documents in a logical manner, having a uniform and consistent appearance, and clearly depicting the intention of the design.

2.2.7.2 Record Drawings and Documentation

Within ninety (90) Days of Final Acceptance of all or part of the Project, Developer shall submit to TxDOT a complete set of Record Drawings in hard copy and native electronic format for the portion of the Project actually opened to traffic. The Record Drawings and documentation shall be an organized, complete record of Plans and supporting calculations and details that accurately represent what Developer constructed.

Developer shall ensure that the Record Drawings reflect the actual condition of the constructed Work. Developer shall submit to TxDOT the electronic files used to prepare the Record Drawings and documentation.

2.2.7.3 DQMP General Requirements

The DQMP shall describe and include the following general requirements:

a) The quality control and quality review procedures for Professional Services products shall be organized by discipline (such as structural, civil, utilities). These procedures shall specify measures to ensure that appropriate quality requirements are specified and included in the Professional Services product and to control deviations from such requirements.

b) Specific quality control and quality review procedures, including all required forms and checklists, shall be specified for preparing, verifying and checking all Professional Services products to ensure that they are independently checked and back-checked in accordance with generally accepted engineering practices in the State of Texas and the requirements of the Contract Documents. The checking of structural design shall include a set of independent calculations performed by the Developer's Design Firm for all structural elements.

c) The designer and checker shall be clearly identified on the face of all Final Design Documents. The DQMP shall also include specific procedures for verifying the Professional Services product along with any computer programs being used for such purposes. Design Documents shall be stamped, signed and dated by the engineer in responsible charge for that item, element, or phase of the Work.

d) Procedures shall be described for coordinating Professional Services performed by different individuals or firms working in the same area, in adjacent areas, or on related tasks to ensure that conflicts, omissions or misalignments do not occur between drawings or between the drawings and the specifications. This shall also include the coordination of the review, approval, release, distribution and revision of documents involving such parties.

e) Procedures shall: (1) ensure that Developer personnel are familiar with all the provisions of the Contract Documents concerning their respective responsibilities; (2) provide for the education, training and certification, as appropriate, of personnel performing activities affecting or assessing the quality of the Work to assure that such personnel achieve and maintain reasonable proficiency;

and (3) ensure that the Work is performed according to the DQMP, generally accepted engineering practices in the State of Texas and the Contract Documents.

f) Procedures shall be established for meeting documentation requirements; the filing of design criteria, reports and notes, calculations, plans, specifications, schematics, and supporting materials needed during the Final Design; and the specific responsibilities of personnel to satisfy these requirements. All Design Documents shall be maintained, organized and indexed by Developer and copies made available to TxDOT upon request.

g) Procedures and schedules for the PSQCM to perform audits of the Design Firm's quality control procedures under the DQMP.

2.2.7.4 Personnel and Staffing

Professional Services Quality Control Manager - Developer shall assign a Professional Services Quality Control Manager (PSQCM) who shall be responsible for management of quality control program for the design, environmental, ROW, Utilities, and survey. The PSQCM shall not be involved with direct scheduling or production activities and shall report directly to Developer's management team. The PSQCM shall see that the methods and procedures contained in the approved DQMP are implemented and followed by Developer design staff in the performance of the Work. The PSQCM shall be a Registered Professional Engineer.

Personnel in Responsible Charge - Developer shall designate (by name) the personnel in responsible charge for each item, element, or phase of the Work. The personnel in responsible charge shall possess the necessary registrations in the State of Texas and shall be personally responsible for directly supervising the Work and will stamp, sign, and date the Professional Services product for a given item, element, or phase of the Work as applicable.

Reviewing Professional Services - The Developer personnel performing the quality control check of the Professional Services shall not be directly involved with the original development of the item, element, or phase being checked.

2.2.7.5 Professional Services Submittal Review Process

Developer shall conduct a series of working meetings with its Professional Services staff, the internal quality control of Developer staff and TxDOT to establish workflow processes and procedures to be utilized during the design review process that are consistent with the Contract Documents. The working meetings are also to develop an understanding on general design concepts such as geometrics, aesthetics, drainage, traffic control, and structures.

Developer and TxDOT shall collaborate and mutually agree upon (i) a list of proposed sections (i.e., Station x+xx to Station y+yy) for the Work; (ii) Professional Services packaging and content (such as drainage, individual structures, roadway, traffic sequencing, and others); (iii) a list of mandatory submittals; and (iv) a proposed submittal schedule. The Professional Services reviews shall be evenly scheduled over the duration of the Professional Services phase of the Work. Sections and packages shall be logically organized into manageable pieces and shall contain sufficient information and details to confirm Developer intent and to validate conditions. Developer shall obtain TxDOT's written approval of the sections, packages and contents, the schedule, and the methodology prior to making the first submittal.

The PSQCM shall chair the submittal reviews with TxDOT and Developer shall maintain formal documentation of these meetings for TxDOT's audit.

The purpose of the submittal reviews is for TxDOT to review Professional Services products for general compliance with Project requirements, sound engineering practice, applicable Law, the Governmental Approvals, and the Contract Documents. All submittals are subject to review and comment by persons designated in the Technical Provisions.

If the Developer and TxDOT cannot come to an agreement on the list of mandatory submittals, the following list shall be provided at minimum:

- Corridor Structure Type Study and Report submittals
- Preliminary Bridge Layout submittals
- Preliminary Design submittal
- Final Design Submittal
- Any deliverables described in the Technical Provisions
- Exhibits Supporting railroad agreements
- Design Exceptions and Design Waiver Requests

2.2.7.5.1 Final Design Submittal

The Final Design Submittal shall be submitted to TxDOT for general review and the PSQCM shall provide certification of compliance. Construction packages for individual Work items, elements, or phases shall be organized such that the final document package can be assembled in a manner similar to the standard construction documentation typically provided to TxDOT for conventional project letting, as mutually agreed upon by Developer and TxDOT.

When Developer has completed the Final Design Submittal for an item, element, or phase and wishes to obtain TxDOT's concurrence of such a design, the PSQCM shall certify that:

a) The design meets all applicable requirements of the Contract Documents, applicable Law and the Governmental Approvals.

b) The design has been checked in accordance with Developer's approved DQMP.

c) The item or element is ready for construction.

d) Developer has obtained all required ROW, Governmental Approvals, and Utility Owner approvals.

The Final Design Submittal shall be complete Design Documents incorporating all of the design submittal review comments. All documentation, including copies of TxDOT's approval of deviations for design standards and/or Design Exceptions shall be provided with the Final Design Submittal.

Prior to certifying the above items, elements, or phases, and upon review and comment of the Final Design Submittal by the TxDOT, PSQCM shall schedule a formal review with TxDOT.

2.2.7.5.2 Formal Review

PSQCM will conduct a formal review presentation to TxDOT at a location acceptable to TxDOT. The formal review presentation will be held following the TxDOT's review and comment of the mandatory submittals.

At least five (5) Business Days prior to the applicable formal review presentation dates, Developer will assemble and submit drawings or other documents to TxDOT for information and review.

Draft minutes of formal review presentations shall be submitted to TxDOT by PSQCM within five (5) Business Days after completion of each review.

2.2.7.6 Resubmittal Process

Resubmittals of any design submittal may be required if deemed necessary by TxDOT or any Governmental Entities with jurisdiction over the Project. Each resubmittal must address all comments received from a prior submittal in a manner satisfactory to the commenting party. Submittals shall be resubmitted as many times as necessary to address comments from TxDOT or any Governmental Entity with jurisdiction over the Project.

If TxDOT had requested additional information during the final formal review, PSQCM will conduct an additional formal review of the resubmitted items, elements, or phases. A copy of all correspondence relating to each submittal made to any Governmental Entity with jurisdiction over the Project shall be concurrently provided to TxDOT.

2.2.7.7 Certification of Compliance

PSQCM shall verify that Developer obtained approval from applicable Governmental Entities and Utility Owners prior to the issuance of a "Certification of Compliance" designation of the Design Documents by the PSQCM. Following issuance of a "Certification of Compliance" by the PSQCM, TxDOT shall review and provide written concurrence.

After Developer has incorporated the Final Design Submittal and/or the resubmittal of formal review comments into its design and all concerns and questions have been resolved to the satisfaction of TxDOT, Developer shall provide Final Design package to TxDOT. Developer as part of its Final Design package shall include all:

a) Design drawings

b) Design calculations

c) Design reports

d) Specifications

e) Electronic files

f) Documentation required for all Final ROW

g) Governmental Approvals

h) Utility Owner approvals

TxDOT's concurrence with the PSQCM's certification of compliance will not constitute approval of the design or subsequent construction, nor relieve Developer of its responsibility to meet the requirements

hereof. Irrespective of whether TxDOT provides Developer with the authority to begin construction on items, elements, or phases of the Work prior to completion of the design for the entire Project, Developer shall bear the responsibility to assure that construction meets the requirements of the Contract Documents, applicable Law and Governmental Approvals.

Construction on any item, element or phase covered by the PSQCM's certification of compliance of said item, element, or phase shall only progress to the extent covered by the Design Documents included in that statement except for the Work performed in accordance with Section 2.2.7.9 (Early Start of Construction). Prior to progressing further with construction of a certified package, Developer shall complete the next item, element or phase of design or complete the Final Design, and obtain TxDOT's concurrence, except for the Work performed in accordance with Section 2.2.7.9. Any items, elements or phases of design, subsequent to the certification of compliance from PSQCM, shall be checked and certified by the PSQCM in the same manner indicated above.

If TxDOT determines that the Final Design Documents do not meet the requirements of the Contract Documents, applicable Law and/or the Governmental Approvals, TxDOT will notify Developer in writing of any specific deficiencies in the Final Design Documents. Developer shall correct such deficiencies; modify the Final Design Documents; and, if necessary, modify construction upon receipt of TxDOT's comments.

If there is evidence that the DQMP procedures are not adequate, as evidenced by TxDOT's oversight reviews or problems during construction, TxDOT may, at its sole discretion, withhold payment for design and construction until sufficient DQPM procedures are in place. If construction is in progress, TxDOT may suspend ongoing Work represented by the deficient design and require correction of design and/or construction defects.

Developer shall provide quantity estimates for Work covered by Final Design Documents. The quantity estimates shall be in units consistent with the quality acceptance and quality review sampling and testing requirements in the DQMP.

2.2.7.8 Design Changes

Developer or TxDOT may initiate design changes. Design changes may occur either on items, elements, or phases undergoing construction or after Final Design. In order to process these types of changes, Developer shall submit, when the problem or change occurs, a Request for Information (RFI) for TxDOT's approval.

All design changes submitted under the RFI procedure shall undergo the same DQMP checks as the original design.

The designer responsible for the original design shall approve design changes during construction, or design changes to Final Design Documents in writing. If the original designer is no longer available, then after notification to the original designer, an experienced Registered Professional Engineer shall provide documentation of design changes. All plans, final submittals, specifications, calculations, and reports for design changes shall be stamped, signed and dated by a Registered Professional Engineer. In all cases, the PSQCM shall certify in writing that the design change has been:

a) Designed in accordance with the requirements of the Contract Documents, applicable Law and the Governmental Approvals,

b) Checked in accordance with Developer's approved DQMP, and

c) Prepared consistently with other elements of the original design.

Developer shall request and schedule interim and final RFI formal design review(s) by TxDOT for all design changes made during construction or to the Final Design Plans. All changes made through the RFI process shall be documented in the As-Built drawings.

2.2.7.9 Early Start of Construction

The following will set forth the circumstances under which certain items, elements, or phases of the Work may be packaged by Developer to initiate an Early Start of Construction prior to obtaining TxDOT's concurrence of the Final Design for the item, element or phase. The "Early Start of Construction" requirements shall apply to any Work that is performed by Developer prior to receiving TxDOT's written concurrence with the PSQCM's certification of compliance of the Final Design Submittal for the Work. All such Work is performed at the sole risk of Developer. TxDOT does not consider any items as satisfying the DQMP requirements until the PSQCM has issued a certification of compliance and TxDOT has issued a written concurrence therewith.

TxDOT, at its sole discretion, may defer Early Start of Construction for any portions of the Work as requested by Developer.

Any Work constructed by Developer prior to receiving TxDOT's concurrence of the Final Design Submittal for the Work, and later determined to be unacceptable by TxDOT in its sole discretion, shall be revised, removed, or otherwise reconfigured to the satisfaction of TxDOT at Developer's sole cost and expense and without any consideration given to an extension of the Completion Deadline.

TxDOT and Developer shall agree on procedures for Early Start of Construction, which procedures shall, among other things, include a process for distributing construction documents signed and sealed by a Registered Professional Engineer to TxDOT and Developer's field staff. In order for Developer to proceed with early phases of construction of a portion of the Work, specific pertinent items of the design shall have been previously reviewed by TxDOT and comments from TxDOT shall have been transmitted to the Developer. For example, Early Start of Construction may be rough grading of a specific portion of the Project, for which specific pertinent items of the design may include:

a) Horizontal and vertical drainage system

b) Typical sections

c) Related elements of the drainage system

d) Related elements of the Traffic Control Plan specifically applicable during the term of the Early Start of Construction scope

e) Subsurface geotechnical investigations and recommendations

f) Slope stability analysis and recommendations

g) Preliminary structure general plans (if a structure is within the element or portion of the nonstructural Work)

h) Settlement monitoring program

i) Construction specifications

An Early Start of Construction shall be at the sole and complete risk of Developer, and does not release Developer from any of the requirements described in Section 2.2.7 (Design Quality Management Plan). If, as a result of the review process, construction modification or changes to already completed Work elements performed under the Early Start of Construction are required, Developer shall make any and all construction modifications to already completed construction activities at its sole cost and expense without any entitlement to time extensions or adjustments in the Price.

2.2.8 Construction Quality Management Plan

Developer shall construct the Work in accordance with the Released for Construction Documents, following a reasonable timeframe for TxDOT review and comment, together with the relevant requirements and specifications of the Contract Documents.

Developer's Construction Quality Management Plan (CQMP) shall contain detailed procedures for the Developer's quality control and quality assurance activities for construction activities. The CQMP shall be consistent with the applicable procedures contained in the current TxDOT *Contract Administration Handbook for Construction* and establish a clear distinction between quality control and quality acceptance activities and persons performing them. At a minimum, the CQMP shall specify:

a) Methods and procedures that clearly define the distinction/authority/responsibility for the administration of Developer's CQMP.

b) That Developer, Supplier, and Subcontractors designate an individual on each crew to be responsible for performing daily field inspections of their own Work and for preparing a daily QC report to document the inspection performed.

c) The review and approval of all Portland cement concrete and hot mix asphaltic concrete mix designs by a CQAF Registered Professional Engineer.

d) Methods and procedures to be utilized by Developer to obtain active participation of the work force in quality control operations to achieve a quality Project; reporting forms to be used by the responsible quality control personnel shall be included.

e) A construction quality control organization and staffing plan. The period of time that the quality control staff member will be present on the site shall be shown, resumes of the Key Personnel shall be included, and the experience/knowledge/skill levels of the quality control support staff shall be stated.

f) CQAF organizational and staffing plans. The period of time that the quality acceptance staff member will be present on the site shall be shown; resumes of key staff members shall be included; and the required minimum knowledge, technical skills, and experience level of the personnel related to the various inspection functions, such as grading, drainage, pile-driving, and structures inspections that will occur on the Work shall be stated. The administrative/clerical support staff for maintenance and management of records/documents pertinent to quality acceptance for the QCP activities shall be identified.

g) Procedures for inspecting, checking, and documenting the Work. Inspection, examinations, and measurements shall be performed for each operation of the Work to assure quality.

h) Procedures to ensure that all activities affecting the quality of the Work are accomplished under controlled conditions using appropriate equipment for the task being performed.

i) Procedures to ensure that the education, training, and certification of personnel performing CQMP activities are achieved and maintained and that all Work is performed in accordance with the approved designs, plans, and specifications.

j) Procedures to ensure that critical elements of the Work are not started or continued without inspection and testing by the quality acceptance personnel on site. Inspection or hold points shall be identified and communicated to the CQAF, Construction Quality Control Manager (CQCM), and TxDOT. Procedures to proceed beyond inspection points shall be developed.

k) Description of specific procedures to ensure that all Work conforms to the requirements of the Contract Documents, Governmental Approvals and applicable Law, and the Design Documents, as well as that all materials, equipment, and elements of the Work will perform satisfactorily for the purpose intended.

l) Documents specify that all activities undertaken by or on behalf of Developer affecting the quality of the Work shall be prescribed and accomplished by documented instructions, procedures, and appropriate drawings. Such instructions, procedures, and drawings shall include quantitative and qualitative criteria to be used to determine compliance.

m) Measures to ensure that purchased materials, equipment, and services conform to the Contract Documents, Governmental Approvals, applicable Laws, Rules, and the Design Documents. These measures shall be consistent with Good Industry Practice and shall include provisions for source evaluation and selection, objective evidence of quality furnished by Subcontractors and Suppliers, inspection at the manufacture or vendor source, and examination of products upon delivery.

n) Procedures for identification and control of materials, equipment, and elements of the Work. These procedures shall be consistent with the Good Industry Practice to ensure that identification of the item is maintained by appropriate means, either on the item or on records traceable to the item, as necessary, throughout fabrication, erection, installation, and use of the item.

o) Procedures to ensure that materials, equipment or elements of the Work that do not conform to requirements of the Contract Documents, the Governmental Approvals, applicable Law or the Design Documents are not used or installed. These procedures shall include identification, documentation, segregation, disposition and notification to TxDOT and, if appropriate, Governmental Entities and other affected third parties as well as procedures for TxDOT to review Nonconforming Work.

p) Procedures for processing a RFI to resolve discrepancies and/or questions in the plans and specifications so that all changes are documented and approved by Developer's design engineers and TxDOT.

q) Procedures to indicate, by the use of markings such as stamps, tags, labels, routing cards, or other suitable means, the status of inspections, and tests performed upon individual items of the Work.

r) A program for inspection for each operation of all Work examinations, measurement, and test of materials or elements of the Work to assure quality.

s) A program for coordination of all inspection and testing with the inspections and tests of Governmental Entities and Utility Owners.

t) A program to ensure performance of all testing required to demonstrate that all materials, equipment and elements of the Work will perform satisfactorily for the purpose intended and meet the standards specified in the Contract Documents. It shall specify written test procedures which include provision for ensuring that all prerequisites for the given test have been met and

that adequate test instrumentation is available and used. The CQMP shall require test results be documented and evaluated to ensure that test requirements have been satisfied. The CQMP shall also demonstrate how the CQAF will track its testing frequencies to ensure compliance with the Contract Documents.

u) Procedures for reviewing and approving acceptance test results, categorizing test results in a manner acceptable to TxDOT, transmitting acceptance test results to TxDOT in a format acceptable to TxDOT for use in fulfilling its statistical validation requirements, and working collaboratively with TxDOT to resolve statistical non-validation between CQAF and TxDOT test results.

v) Measures to ensure that tools, gauges, instruments, and other measuring and testing devices used in activities affecting quality are properly maintained, controlled, calibrated, certified, and adjusted at specified periods to maintain accuracy within industry standards.

w) Procedures to control the handling, storage, shipping, cleaning and preservation of materials and equipment to prevent damage or deterioration.

x) Procedures to ensure that conditions adverse to quality, such as failures, malfunctions, deficiencies, defective material and equipment, deviations and other Nonconforming Work are promptly identified and corrected. The procedures shall ensure that the cause of the condition is determined and corrective action taken to preclude repetition. The identification of the significant condition adverse to quality, the cause of the condition and the corrective action taken shall be documented and reported to TxDOT in writing and to appropriate levels of Developer's management to ensure corrective action is promptly taken.

y) A comprehensive system of planned and periodic audits of Developer's CQMP to determine adherence to and the effectiveness of the CQMP. CQAF personnel shall perform the audits in accordance with the written procedures or checklists. Audit results shall be documented, reviewed, and acted upon by Developer. Follow-up action, including re-audit of deficient areas following corrective action shall be taken where indicated.

z) Measures to control the receipt and issuance of documents such as instructions, procedures, training manuals, and drawings, including changes thereto, which prescribe activities affecting quality. These measures shall ensure that approved documents, including authorized changes thereto, are reviewed for adequacy and approved for release by authorized personnel of Developer and are distributed to and used at the location where the prescribed activity is performed. Changes to documents shall be reviewed and approved by the same organizations that performed the original review and approval unless TxDOT consents in writing to another responsible organization.

aa) The requirements and methods for controlling documents. Developer's document control system shall be compatible with TxDOT's.

bb) Procedures and personnel to be used to assure that specified instrumentation is installed and monitored in accordance with applicable specification.

cc) The form and distribution of certificates of compliance.

dd) Procedures for quality acceptance in the CQMP with respect to checking and verifying the accuracy and adequacy of construction stakes, lines, and grades established by Developer.

2.2.8.1 Personnel and Staffing

2.2.8.1.1 Construction Quality Control Manager (CQCM)

Developer shall assign an on-site Construction Quality Control Manager (CQCM) who shall be responsible for management of the quality aspect of the CQMP. The CQCM shall not be involved with scheduling or production activities, and shall report directly to Developer's management team. The CQCM shall see that the methods and procedures contained in approved CQMP are implemented and followed by Developer and Subcontractors in the performance of the Work. The CQCM shall be a Registered Professional Engineer.

2.2.8.1.2 Construction Quality Control Staff

Developer's and Subcontractors' construction work force are all considered to be members of Developer's quality control staff as each and every one is responsible for the quality of the Work. Personnel performing QC inspection shall ensure quality of workmanship and QC sampling/testing shall ensure that materials meet the required specifications prior to acceptance testing performed by the CQAF. Personnel responsible for performing quality control inspection shall be knowledgeable and receive training to perform their quality control duties. Personnel performing quality control sampling/testing shall be knowledgeable in the testing methods and procedures and do not need to be certified or direct employees of the Developer, but cannot be employees of the CQAF.

2.2.8.1.3 Construction Quality Acceptance Manager (CQAM)

Developer's CQAF shall assign an on-site Construction Quality Acceptance Manager (CQAM) who shall be responsible for management of the quality acceptance aspect of the CQMP. The CQAM shall be a Registered Professional Engineer and shall be an employee of the CQAF. The CQAM shall report jointly to Developer's management team and TxDOT. The CQAM shall not report to any person or party directly responsible for design or construction production.

The CQAM shall review, approve, authorize, examine, interpret, and confirm any methods or procedures requiring the "Engineers' review, approval, authorization, examination, interpretation, confirmation, etc." which are contained in the TxDOT Standards.

2.2.8.1.4 Construction Quality Acceptance Staff

A quality acceptance inspection and material sampling/testing staff shall be provided under the direction of the CQAM to perform inspection and material sampling/testing of all Work performed and materials incorporated into the Project by any member of Developer's group. If approved in writing in advance by TxDOT, qualified individuals who are employees of or retained by manufacturers, vendors, or Suppliers may inspect certain portions of Work.

The quality acceptance inspection and testing staff shall be employees of the CQAF and shall have been trained in the applicable inspection and material sampling and testing procedures. The quality acceptance staff shall be experienced in highway inspection and material testing. The training and experience of the quality acceptance staff shall be commensurate with the scope, complexity, and nature of the activity to be controlled and tested. Qualifications shall include appropriate TxDOT or State Highway Agency certification for testing and inspection as well as nationally recognized certifications such as ACI certification in applicable inspection or testing activities. Construction quality acceptance staff shall report to the CQAM.

The quality acceptance staff shall provide oversight and perform audits of the quality control inspection and material sampling/testing operation.

The quality acceptance inspection staff shall check compliance of all material, equipment, construction, installations, and operations. Construction activities requiring continuous field quality acceptance inspection or sampling and testing, in the sole discretion of TxDOT, shall proceed only in the presence of assigned QA personnel. The CQMP shall identify those activities.

2.2.8.1.5 Construction Quality Acceptance Staff Levels

The size of the quality acceptance staff shall reflect the volume of quality acceptance activities necessary for the Work in progress and shall be maintained in accordance with the approved CQMP. The CQAF staff will perform quality acceptance oversight, inspection, and testing services typically performed by TxDOT on traditional projects, with the exception of monitoring testing.

The construction quality acceptance staffing requirements shall be updated as necessary throughout the Term of Work to reflect changes in the actual construction schedule. Developer shall ensure that adequate construction quality acceptance staff is available and that CQMP activities are undertaken in a manner consistent with the Project Schedule and in a manner that will enable Developer to achieve the Substantial Completion and Final Acceptance deadlines.

Should TxDOT determine that Developer is not complying with CQMP because of lack of staff, TxDOT shall have the right, without penalty or cost, including time extensions or delay damages, to restrict Work efforts until appropriate levels of staffing consistent with the CQMP and satisfactory to TxDOT are obtained or TxDOT may contract with a separate firm to perform these services and withhold payment to Developer for such services.

2.2.9 Maintenance Management Plan

Section 19 (Maintenance) includes requirements for maintenance management.

2.3 Comprehensive Environmental Protection Program

Section 4 (Environmental) includes requirements for environmental management.

2.4 Public Information and Communications Plan

Section 3 (Public Information and Communications) includes requirements for public information and communications.

2.5 Safety Plan

Developer shall be responsible for the safety of its personnel and of the general public affected by the Project.

Developer shall submit to TxDOT for approval a comprehensive Safety Plan ("Safety Plan") that is consistent with and expands upon the preliminary Safety Plan submitted with the Proposal. The Safety Plan shall fully describe Developer's policies, plans, training programs, Work Site controls, and Incident response plans to ensure the health and safety of personnel involved in the Project and the general public affected by the Project during the Term of the Agreement.

Developer's Safety Plan shall address procedures for immediately notifying TxDOT of all Incidents arising out of or in connection with the performance of the Work, whether on or adjacent to the Project.

2.6 TxDOT-Developer Communications Plan

Developer shall submit, to TxDOT for approval, a TxDOT–Developer Communications Plan that is consistent with and expands upon the preliminary communications plan submitted with the Proposal.

Developer shall maintain and update the TxDOT – Developer Communications Plan throughout the Term.

The TxDOT – Developer Communications Plan shall describe the procedures for communication of Project information between Developer's organization and TxDOT.

The TxDOT – Developer Communications Plan shall describe how Developer's organization will respond to unexpected requests for information, communicate changes, or revisions to necessary Developer personnel, and notify affected stakeholders before and after changes are made to the Contract Documents.

2.7 Right of Way Acquisition Plan

Section 7 (Right of Way) includes requirements for right of way acquisition management.

The Acquisition Survey Document Package shall be reviewed by an independent Registered Professional Land Surveyor (RPLS) for consistency and compliance with all applicable laws, standards, and requirements. The boundary location and the survey methods remain the responsibility of Developer, and are not part of this review process. The reviewing surveyor shall review the survey document package and return his comments to Developer in a timely manner. Developer shall revise and correct the documents in accordance with the reviewing surveyor's comments in a timely manner. TxDOT will not accept the Acquisition Survey Document Package as complete until the reviewing surveyor has signed and sealed the compliance certificate (see Reference Information Documents).

2.8 Risk Management Plan

The Risk Management Plan shall describe the approach to identification, management, mitigation, and allocation of Project-specific risks, including a risk matrix which shall identify the following at a minimum:

(a) Significant risk categories during the design and construction of the Project.
(b) The potential consequences of the identified risks.
(c) The probable likelihood of risks.
(d) Proposed procedures and tools to conduct a risk sensitivity analysis.
(e) Risk-mitigation strategies to eliminate or reduce specific risks.

2.9 Affected Third Parties Plan

Section 5 (Third Party Agreements) includes requirements for the Affected Third Parties Plan.

2.10 Emergency Management Plan

The Emergency Management Plan (EMP) will cover procedures for Force Majeure events and vehicle accidents that may disrupt construction or damage facilities. The EMP will describe the Developer's plan for responding to the following emergency situations:

(a) Severe weather incidents such as tornados, hail storms, snow storms, and flooding.
(b) Power failures that may affect traffic signals and lighting.
(c) Vehicular accidents that may damage facilities or interfere with traffic flow.
(d) Hazardous materials spills including flammable liquids.
(e) Vandalism including graffiti.

The plan will describe how the developer will coordinate with local law enforcement agencies and emergency personnel to respond to emergency situations. The plan will describe how the developer will notify the public about the emergency situation.

2.11 TxDOT Offices, Equipment

Except where noted elsewhere in the Contract Documents, Developer and TxDOT shall collocate for the term of the Agreement to facilitate Project coordination and daily communication. The definition of "collocate" for this Agreement is office space meeting the conditions of this Technical Provision that are near each other along or adjacent to the Project within one mile of the Project ROW or as otherwise approved by TxDOT.

Developer shall provide TxDOT office space (i.e., available for occupancy) within sixty (60) Days of issuance of Notice-to-Proceed 1 (NTP1). The location, condition, and amenities of the office space for TxDOT are subject to TxDOT's prior written approval. The office space requirements for the core office and the field offices are provided below.

2.11.1 Computers and Equipment

The Developer shall provide, install, and maintain the following computers, peripherals, and software for the TxDOT office spaces:

- One computer with two flat panel monitors including all necessary peripherals for each personnel office area and the reception area in core and field office. Fifteen of these computers shall be laptops with docking stations.
- Desktop computers specifications and operating systems shall generally be same as those used by technical staff on Developer's team.
- Laptops specifications and operating systems shall generally be same as those used by the management staff on Developer's team.
- Necessary software and licenses required to perform TxDOT functions for the Project, including Microsoft Office Professional, Microsoft Outlook or Novell GroupWise, Microstation, Geopak, applicable drainage software, and Adobe Acrobat.
  Software version currently employed:
  - Microsoft Office 2010
  - Novell GroupWise v.8
  - Microstation v8i v.2
  - GeoPakSS2
  - Adobe Acrobat X Pro
- Software and licenses shall be compatible with all other Microsoft software products.
- (3) GPS Cameras (to include compass / GPS module, 4GB SD card, camera bag, additional battery, USB cable, neck strap, rechargeable lithium-ion battery, battery charger, instruction manuals and warranty card)
- (1) Digital Video Cameras
- (3) iPad with Wi-Fi + 3G 64GB along with 3G service (latest version available) and protective case
- (3) iPhone 4S along with service (or latest version available) and protective case

- High Speed Office Internet access that is wired separately from phone service
- Peripherals shall include at minimum, monitor stand, docking station for laptop computers, mouse, keyboard, extra battery for laptop computers, and a carry bag for laptop computers. The computers, monitors, and peripherals shall be at least equal to the ones used by the Developer's staff.

The Developer shall provide, install, and maintain the following telephones, servers, copiers and fax equipment, internet service and premise wiring for the TxDOT office space:

- At least one touch-tone telephone, for each personal office area, each with a status indicator, access to all outside lines, and conference-call capability; and including speakers for the telephones in the enclosed offices rooms.
- At least one touch-tone conference telephone with satellite microphones for each conference room, each with a status indicator, caller id, access to all outside lines, and conference-call capability.
- Hardware and software shall be compatible with that of Good Industry Practice and of the Developer's system interface.
- Full-scale color plotter capable of handling 36 inch roll plots, 36x24 inch plots and 18x12 plots (core office only).
- One high-speed laser computer printer capable of handling 11x17 prints.
- One high-speed color printer capable of handling 11x17 prints.
- One high-speed color photocopy machine capable of handling 11x17 prints.
- One facsimile transmission machine.
- One color scanner capable of handling 11x17 prints.
- All office supplies including copier paper, toners, pens, pencils, notepads, and other miscellaneous office supplies.
- Complete voice/data communications cabling system, which includes but is not limited to the EMT conduit, bridle rings, pull boxes, category 5e UTP cable, category 5e "RJ-45" UTP receptacles, category 3 "RJ-11" UTP receptacles, receptacle boxes, cover plates, and multimode fiber optic cable. All cable shall be routed, terminated, labeled, and tested. Voice and data circuits shall be installed in conjunction with ISD and TxDOT Department of Information Resources staff.

All equipment shall be replaced and updated at least once every three years or when the Developer upgrades, whichever comes first. A multipurpose piece of equipment capable of meeting multiple parts of the requirements above shall be considered to meet the requirements.

Developer shall certify and state supplied components as functional before installation and shall bear all responsibility for replacement of parts at work commencement.

Developer shall prepare, test, plan, and submit before installation, test installed system and supply test results, and shall conform to all industry standard testing procedures

Developer shall terminate all category 5e UTP cable in 66M150 punch down blocks for voice cabling and shall terminate all category 5e UTP data cable in data patch panels within the wiring closet.

Each drop shall contain two data ports with RJ45 connectors and two voice ports with RJ11 connectors.

Developer shall provide all materials, as needed and required, to complete the installation of the cable plant which shall include all cable, connectors, patch panels, equipment rack(s) , patch cables, face plates, punch down blocks, fiber optic cable and other miscellaneous materials.

2.11.2 Core Office

Developer shall provide all space, facilities, and support Elements necessary to design, construct, and maintain the TxDOT core office in accordance with the Contract Documents. Developer shall provide office space, not to exceed 12,000 square feet, for TxDOT's design and Project management staff including, the General Engineering Consultant and other contract employees. If it is necessary to locate any of these Elements of the Work off-site or outside of this office, Developer shall obtain TxDOT's prior written consent.

Developer shall provide a preliminary TxDOT facility area layout plan to TxDOT no later than seven (7) Days after NTP1. TxDOT shall promptly review and comment on required modifications to the layout within ten (10) days. Developer shall submit a final facility layout plan within ten (10) Days of receipt of TxDOT comments.

Developer shall have the TxDOT facility area available for move-in no later than sixty (60) days after NTP1.

2.11.2.1TxDOT Facility Area and Items Provided by Developer

Developer shall provide separate office space for the exclusive use of TxDOT's Design and Project management staff in the TxDOT facility area as specified herein and subject to TxDOT's prior written approval. This office space shall be located within the same building or complex as Developer's office staff. TxDOT shall be reasonable regarding re-use of existing space within Developer's current office facility, providing the space is contiguous and workable in TxDOT's sole discretion.

2.11.2.2Office Condition

The offices shall be in good and serviceable condition, at least of the same quality as those of Developer's counter-part office space and available for occupancy as specified herein. Both Parties shall participate in a facility condition survey prior to and at the completion of occupancy. TxDOT shall return possession of Developer-provided TxDOT facility area to Developer in essentially the same condition as when TxDOT occupied the facilities, except for reasonable wear and tear and except for alterations, or loss or damage caused by any member of Developer-Related Entity.

2.11.2.3Loss or Damage

If office spaces, related facilities, fixtures, or equipment specified in Section 2.11.1 are destroyed, damaged or stolen during the Work, in the TxDOT facility area, except as a direct result of willful misconduct of TxDOT or its personnel, Developer shall, at its cost and within ten (10) Business Days after the occurrence of such destruction or damage, repair those items to their original condition or replace them. However, in the case of lost, damaged, or stolen office equipment (e.g., computers, fax

machines, copy machines, printers, and telephones) necessary for normal office operations, replacement shall occur within two (2) Business Days. If loss or damage is caused as a direct result of willful misconduct of TxDOT or its personnel, Developer shall replace the facilities noted herein within the timeframes specified herein, and TxDOT shall reimburse Developer for actual, reasonable and documented costs incurred.

2.11.2.4 Office Facilities and Equipment

For the TxDOT facility area it provides, Developer shall:

a) General. Secure facility space, obtain all permits, install and pay for all utility services, and maintain the facilities as part of the Work.

b) Access and Security. Provide separate TxDOT entrance/exit(s) from building, which shall be secured with electronic door lock(s) plus a deadbolt lock. Developer shall provide security badge card access with locking doors running on time zone/holiday schedules for entry doors as well as other designated areas (e.g., server room, document storage, offices). Developer shall provide software for maintaining access to these areas, which shall be owned and/or maintained by TxDOT's design and Project management staff.

c) Lighting and Electricity. Include with all interior spaces overhead lighting meeting OSHA, building, and electrical and energy code requirements for similar office space (provide nominal 30 foot candles of light at 30 inches above finish floor). Each office space shall have at least four duplex receptacles, with minimum circuit capacity of twenty (20) amperes.

d) Janitorial, Trash and Recycling Services. Provide daily janitorial service (except Saturdays, Sundays and Holidays) and maintain trash and recycling containers and trash and recycling pickup service for the building and site areas beyond the TxDOT facility area. This shall include, but not be limited to, sweeping and mopping floors, cleaning restrooms and break room, emptying wastebaskets, and periodic dusting. This service shall be paid for by Developer. Developer shall pay for and procure janitorial services for the TxDOT facility area.

e) Exterior Maintenance. Maintain the exterior areas of office spaces, including access to parking areas.

f) Accessibility and Licensing. Meet all access requirements of the Texas Accessibility Standards, the Americans with Disabilities Act Accessibility Guidelines, as amended (42 USC §§12101, et seq.), and the applicable building code. Facility design plans shall be submitted to the Texas Department of Licensing and Regulation (TDLR) for review and approval as required by Section 16, Chapter 68 of the Texas Administration Code.

g) Restrooms, Break Room, and Entry Space. Provide access to women's and men's restrooms, break room space and building entry space, these spaces may be shared with Developer's office space/staff. These spaces and all TxDOT spaces shall have access 24 hours per day, 7 days per week, 365 days per year (24/7/365). In lieu of access to a common break room, Developer may provide a 200 SF break room/kitchen within the TxDOT space, with refrigerator with freezer compartment, ice machine, sink including waste disposer, microwave, and dishwasher. If the building does not have a general building vending area then the break room shall have vending machines and a standalone ice machine. The Developer shall provide coffee, tea, condiments, and bottled water, generally, the same as the Developers

staff. Break room/kitchen shall have storage closet (25 sq. ft.) and cabinets with drawers and counter tops. In the event that access to restrooms cannot be accessed from a common building entry/lobby, Developer may provide separate restrooms for the TxDOT facility area. In the event it is necessary to locate a separate break room and/or restrooms within the TxDOT facility area, the TxDOT space allocation may be required to be increased to accommodate these spaces.

h) HVAC. Provide electrical, heating, ventilation, and air conditioning (HVAC) systems capable of maintaining temperatures between 65 and 75 degrees Fahrenheit in all spaces, 24 hours per day, 7 days per week, 365 days per year (24/7/365), through the year. Server room shall have dedicated air conditioning/cooling system capable of maintaining temperatures between 65 and 70 degrees Fahrenheit, and 15% relative humidity.

i) Code Requirements. Meet all applicable building and fire code requirements.

j) Disposal and Removal. Be responsible for disposal or removal of all Developer-provided facilities and any facility and/or site restoration Work as required.

2.11.2.5Space Requirements

Although actual spaces may vary slightly, the following nominal size requirements shall apply, and the typical TxDOT facility area shall include the following Elements:

a) Offices. Enclosed offices for TxDOT's management staff (nominal 150 square feet each) 15 total (5 with keyed door hardware).

b) Cubicles. Cubicle area spaces for administration staff (nominal 100 square feet each) 15 total; (power supply and data and communication lines to cubicles may be provided through power pole drops).

c) Conference Rooms. Three conference rooms (enclosed) 2 at nominal 12'x 20' (240 SF), one at nominal 12'x 30' (360 SF) and one assembly room (enclosed) at nominal 32'x45' (1575 SF) All shall have dimmable lighting, minimum 60-inch flat panel monitor with VGA/HDMI accessibility in conferences rooms, a minimum 120-inch diagonal projected image 1024 by 768 resolution in assembly room; each conference room shall have one chair for every 24 SF of conference room space and a conference table of sufficient size for each chair.

d) Reception Area. Receptionist space with waiting area with seating for 8 visitors (nominal 200 SF); other furniture to be determined jointly by developer and TxDOT.

e) Work Room. Work room (nominal 150 SF) with 30-inch high plastic laminate wall-mounted counters (15 lineal feet of counter). Work room shall be located near the center of the facility, and in close proximity to the receptionist space.

f) Storage and Filing. One (1) lockable space for storage and filing, nominal 15'x20' (300 SF).

g) Server Room. One computer server room (100 SF) that has limited access and is locked via security card access. Server room shall be accessible via hallway entry not sharing any walls with the exterior of the building, and have no windows, a non-static floor covering, a standard 7'-19" rack and at least three dedicated 20-amp power circuits and one 30-amp circuit. All patch panels (phone and data) shall be

located within the designated server room. Temperature shall be maintained with a dedicated air conditioning/cooling system as defined above.

h) Parking Area. Parking area for at least forty (40) vehicles (30 staff/10 visitors) that is reasonably level (all-weather surface and all-weather access). A portion of the available parking area must accommodate an 8' vehicle height.

i) Exterior Lighting. Sufficient exterior security lighting that is automatically activated at low light levels to maintain two (2) foot-candles of lighting within the building and parking areas of the site.

j) Corridors. Corridors within the TxDOT facility shall have a nominal width of 54 inches.

2.11.2.6Miscellaneous Requirements and Features

The following shall be provided as noted:

a) Flooring. Carpeted flooring (nonstatic in server room).

b) Entry Access. Entry to TxDOT areas by electronic door hardware card access (not keyed), with U.P.S. on locks (fail closed).

c) Electrical Outlets. Each office and conference room shall have two (2 data, 1 com Cat 5E) outlets per room, and one (2 data, 1 com Cat 5E) outlet per cubicle, as well as outlets at designated printer, fax and copier locations and any and all shared areas (i.e., workroom, storage room, etc.). All data/voice outlets shall be installed next to power outlets.

d) HVAC. 24/7/365 HVAC as previously described.

e) Window Coverings. Horizontal mini-blinds (no drapes) for each exterior window.

f) Power Circuits. Provide dedicated electrical power circuits for copiers, and minimum of 6 duplex receptacles with three dedicated 20-amp circuits and one 30-amp circuit for the server room.

g) Fire Extinguishers. Developer shall provide fire extinguishers, per fire code and fire marshal with jurisdiction.

h) Insurance. Insurance (obtained and provided by Developer) covering the use of the Project office by Developer and TxDOT, in accordance with the terms of the underlying property use agreement with the property owner, but in no event shall the insurance be less than that required by the Agreement.

i) Vending Area. Developer shall provide access to general building vending area.

j) Utilities. Initial installation and monthly expense of all utilities paid by Developer except long distance telephone service.

k) Emergency Contacts. 24-hour emergency contact to Developer.

l) Furniture. Developer-provided allowance of $50,000 in the Price for furniture, which shall be obtained by Developer at the direction of TxDOT, and billed through Developer. At the end of the Project, Developer shall have ownership of the furniture and shall be entitled to the full salvage value of the furniture, with the right to retain or otherwise dispose of the furniture at its sole discretion, without any further accounting to TxDOT.

m) Cable Television. Provide basic cable television connections or service to public information office.

2.11.2.7Items Not Required

The following items are not required:

a) Outside storage.

b) Electronic security system (other than electronic door access hardware).

2.11.3 Field Offices

Developer shall provide field office space for the exclusive use of TxDOT's field construction staff for the Project as specified herein.

Subject to TxDOT's prior written approval, Developer shall provide separate facilities for TxDOT's resident engineer staff located within the same complex as Developer's field office. Should Developer elect to construct the Work using field offices other than the one specified, corresponding facilities shall be provided for TxDOT's exclusive use and shall be at least of the same quality as Developer's counterpart management and field staff. Should Developer elect to combine the field office with the design and management office, the combined facility shall be within reasonable proximity to the Project and subject to TxDOT's prior written approval.

Developer shall provide the field staff facilities at least ten (10) Business Days prior to starting any Work activity involving staff that shall occupy the field staff facilities.

2.11.3.1Office Condition

The field office(s) shall be in good and serviceable condition, at least of the same quality as those of Developer's counterpart management and field staff, respectively and available for occupancy as specified herein. Both Parties shall participate in a facility condition survey prior to and at the completion of occupancy. TxDOT shall return possession of Developer-provided facilities to Developer in essentially the same condition as when TxDOT occupied the facilities, except for reasonable wear and tear and except for alterations, loss, or damage caused by any member of Developer-Related Entity.

2.11.3.2Loss or Damage

If office space(s) or related facilities are destroyed, damaged or stolen during the Work, except as a direct result of willful misconduct of TxDOT or its personnel, Developer shall, at its cost and within ten (10) Business Days after the occurrence of such destruction or damage, replace those items that it had provided or repair them to their original condition; however, in the case of lost, damaged, or stolen office equipment (e.g., computers, fax machines, copy machines, printers, etc.) necessary for normal office operations, replacement shall occur within two (2) Business Days. If loss or damage is caused as a direct result of willful misconduct of TxDOT or its personnel, Developer shall replace the facilities noted herein within the timeframes specified herein, except that TxDOT shall reimburse Developer for actual, reasonable, and documented costs incurred.

2.11.3.3Office Facilities and Equipment

For the facilities it provides, Developer shall:

a) General. Secure sites, obtain all site permits, install and pay for all utility services, and maintain the facilities as part of the Work.

b) Access and Security. Provide separate buildings or trailers for TxDOT staff that include at least two entrances/exits, providing an 8' x 10' (minimum) covered area, from each building or trailer. Each entrance/exit shall be secured with a door lock plus a deadbolt lock.

c) Lighting and Electricity. Include with all interior spaces overhead lighting meeting the requirements of the Occupational Safety and Health Administration (OSHA) and of building and electrical codes for office space. Each office space shall have at least two duplex receptacles. The minimum circuit capacity shall be twenty (20) amperes.

d) Janitorial and Trash Service. Provide daily janitorial service (except Saturdays, Sundays and Holidays) and maintain trash containers and trash pickup service. This shall include, but not be limited to, sweeping and mopping floors, cleaning the toilet, and lavatory and emptying wastebaskets.

e) Exterior Maintenance. Maintain the exterior areas of office spaces, including access to parking areas.

f) Accessibility. Meet all access requirements of the Americans with Disabilities Act, as amended (42 USC §§12101, et seq.).

g) Utility Service. Provide potable water, sewer service, and electricity to the office facility.

h) HVAC. Provide heating, ventilation, and air conditioning (HVAC) systems capable of maintaining temperatures between 65 and 70 degrees Fahrenheit in all spaces through the year.

i) Code Requirements. Meet all local building and fire code requirements.

j) Disposal and Removal. Be responsible for disposal or removal of all Developer-provided facilities and any site restoration Work as required.

2.11.3.4Space Requirements

Although actual space requirements shall depend upon Work schedule and geographic locations of the field offices, a typical field office should include the following Elements:

a) Offices. Enclosed offices for TxDOT's construction representative, TxDOT-designated construction manager and three other TxDOT or contract employees (150 square feet each).

b) Offices/Cubicles. Offices or cubicles for up to ten (10) field engineer/inspection/ administration staff (100 square feet each).

c) Conference Rooms. Conference rooms (enclosed) (200 square feet) and access to another conference room (350 square feet). d) Storage and Filing. Two (2) lockable spaces for storage and filing at each field office (a combined space of 150 square feet).

e) Surveying Equipment Storage. Clean inside storage space for surveying equipment (80 square feet).

f) Tool Shed. Shed for small tools and equipment (outside) (150 square feet).

g) Site Amenities. A well-graded site for the office with access road, parking area, and security fence with lockable drive-in gates sufficient to enclose the office and parking area.

h) Staff Parking Area. A parking area for at least fifteen (15) vehicles that is reasonably level (all-weather surface and all-weather access) within the boundaries of a security fence.

i) Visitor Parking Area. An all-weather level surface outside the security fence to accommodate visitor parking (all-weather surface and all-weather access-minimum of 2,000 square feet).

j) Security. A 24-hour security service or silent watchmen-type security system.

k) Exterior Lighting. Sufficient exterior security lighting that is automatically activated at low light levels to maintain two (2) foot-candles of lighting within the fenced field office site.

l) Window Security. Security bars on all windows.

m) Laboratory Facility. A completed facility suitable to accommodate a functioning portable lab (approximately 2500 square feet).

n) Cultural Resources Storage. Sufficient space and covered facilities for any archeological or paleontological recovery operations (approximately 2,000 square feet).

o) Kitchen/Break Room. Each field office shall contain a 200 sq. ft. kitchen with storage closet (25 sq. ft.), cabinets with drawers and counter tops.

p) Restrooms. Two restrooms including toilets and sinks.

q) First Aid Facilities. Emergency first aid facilities.

2.11.3.5Items Not Required

The following items are not required:

a) Laboratory Testing Equipment.

3 PUBLIC INFORMATION AND COMMUNICATIONS

3.1 General Requirements

Developer shall coordinate all public information communication plans with ongoing TxDOT public information activities to ensure that a consistent message is being distributed to the Customer Groups. Copies of all materials to be presented to the public or the media shall be provided to TxDOT at least three (3) Business Days prior to dissemination.

3.2 Administrative Requirements

3.2.1 Public Information and Communications Plan

Developer shall submit to TxDOT for approval a comprehensive Public Information and Communications Plan (PICP) within 30 days of NTP 1, based upon the preliminary public information and communications plan submitted with Developer's Proposal, which informs, educates, and engages the Customer Groups throughout every stage of the Project. Developer shall obtain TxDOT approval as a condition precedent of NTP 2. The PICP shall identify specific outreach or engagement activities, the frequency of those activities, what modes of communication will be used and what process Developer will use in order to measure the effectiveness of the PICP. Submittal shall be in both hardcopy form and electronic format compatible with TxDOT software. TxDOT approval of the PICP shall be a condition of issuing NTP2.

In preparing this plan, Developer shall identify the Customer Groups and develop specific plans to respond to their concerns and needs in all respects regarding the Project. After incorporation of comments from TxDOT on the PICP, Developer shall implement the various activities and initiatives contained therein. Developer shall continually maintain the plan to ensure delivery of high-quality, well executed communications throughout the Term of the Agreement.

The PICP shall be flexible to capture the full magnitude of yet-to-be-determined impacts from Project activities such as design, construction, and maintenance, and the public's reaction to these and other impacts. Together with the TxDOT's designated point of contact for the local public information office, the Developer shall periodically review the PICP on a basis not less than annually to forecast, plan and coordinate updates in the plan, and strategies needed to effectively accomplish the stated goals and objectives. The PICP shall also be resilient to successfully implement the outlined strategies, given the ever-changing desire for depth, breadth, and frequency of information by a variety of important Customer Groups such as the media, elected officials, and the general public.

The PICP shall include a general timeline listing public information activities for the Project over the entire Term of the Agreement. This timeline shall be used as an initial guide and shall be updated by Developer as the Project is implemented but no less than on a yearly basis.

TxDOT may audit Developer's performance of the activities set forth in the PICP. Developer shall make appropriate changes to the PICP as required to meet the findings of any audit or review and to suit the changing goals and needs of the Project. Developer shall cooperate with TxDOT to amend the PICP as required to suit circumstances as yet unknown, including public reaction to the impacts, real or perceived, from the Work and the depth, breadth and frequency of information necessitated by Customer Groups. Developer shall document the efforts and results of the PICP in measurable terms to clearly indicate compliance.

Developer shall provide sufficient qualified staffing to effectively implement the PICP.

In developing the PICP, Developer shall make appropriate provisions to achieve the following goals:

a) Gain and maintain support and/or informed consent from Customer Groups, building on existing community partnerships and communication networks.

b) Provide Customer Groups with regular opportunities for input early and often throughout the development process

c) Demonstrate to Customer Groups that the Project will be developed pursuant to a well-executed program.

d) Notify Customer Groups in advance of key Project ROW acquisition, construction and maintenance activities and communicate the potential impacts of these activities.

e) Provide public information which facilitates alternative trip planning during construction.

f) Address the Project-specific concerns of Customer Groups, including but not limited to interests in Emergency Services vehicle access, business owner and patron driveway access, delivery access, adjacent neighborhood access, changes to bicycle and pedestrian access and neighborhood traffic patterns, changes to mobility access associated with the *Americans with Disabilities Act* (ADA), construction noise and lighting, and ongoing noise issues.

To achieve these goals, Developer shall use, but not be limited to, the following implementation strategies:

Customer Groups

a) Develop a forum to coordinate on-going dialogue among Customer Groups, TxDOT, and Developer.

b) Prepare and distribute Project-related materials in a user friendly format to inform Customer Groups through appropriate means such as: meetings, interviews, media kits, news releases, telephone correspondence, newsletters, brochures, e-mail, text messaging service, social media, mobile phone apps, hotlines, Highway Conditions Reports (HCRs), dynamic message boards, Web alerts, public opinion polls/surveys, videos, display booths, presentations, public access information kiosks, and special events.

c) Organize and manage meetings and communications with key elected officials, the general public, representatives of civic organizations, businesses, and special interest groups along the Project corridor (individually or in groups) for the purpose of building rapport and gaining feedback with Customer Groups. Meetings can be held on an ad hoc basis or, as appropriate, on a regular basis as established in consultation with TxDOT.

d) TxDOT has convened a Project specific advisory committee, the Traffic Management Committee, which is comprised of stakeholders along the corridor, to set priorities for the overall traffic operations and safety throughout the corridor during construction. Developer shall continue to coordinate with the TxDOT appointed TTI mobility coordinator and organize and manage quarterly meetings and coordination, or more frequently as directed by TxDOT and/or TTI, with the Traffic Management Committee throughout during design and construction of the Project.

e) Respond to invitations and seek opportunities to attend meetings, conferences, and other events at which Project information can be exchanged with Customer Groups.

f) Notify Customer Groups in advance of key Project ROW acquisition, construction, operations and maintenance activities, and communicate the potential impacts of these activities.

g) Develop, disseminate and display timely, high-quality, innovative, user-friendly, accurate and appropriate community information concerning the Project, including exhibits showing slope

grading, drainage, bridge structures, retaining walls, sound walls, Project ROW acquisition, and aesthetic characteristics.

h) Develop and manage a public relations campaign and communication strategy to convey key messages, branding, and pertinent information about the Project.

i) At appropriate times and stages and as requested by TxDOT or key stakeholders, coordinate tours of the Project.

j) Comply with the requirements of the *Guidelines for Analysis and Abatement of Roadway Traffic Noise*.

k) Develop materials and make arrangements for English as a Second Language groups when it can be reasonably anticipated that material will be presented to English as a Second Language Customer Groups.

l) Communicate impacts and Ultimate Project design for accommodation of pedestrians and bicyclists throughout the Project, particularly at the Lewisville Lake Bridge and adjacent Copperas Branch Park.

m) Coordinate with other projects along the Interstate 35/35E corridor statewide to recognize impacts to through-travelers who may be affected by multiple major closures in different regions of the state.

n) Conduct tabletop exercises with stakeholders and government agencies to help prepare for potential emergency situations during construction phase.

o) Compile database of all customer group contacts and make readily available to TxDOT in an easily accessible format.

Media

a) Build on existing TxDOT media resources and/or create and develop advertising messages, including graphics, logos, and slogans.

b) Place Project-related messages in the appropriate media.

c) Develop and distribute public service announcements, paid advertising, news reports, and other communication materials as appropriate.

d) Manage media relations with key transportation and business reporters and prepare and distribute news releases and media kits.

e) Develop and implement communications plans that anticipate and attempt to minimize traffic impacts of public, special and seasonal events adjacent to the corridor that may draw large crowds through the Project limits.

f) Monitor local, state, and national media coverage for accuracy and to gauge local opinion. Coordinate with TxDOT regarding response to inaccurate information as soon as possible in the same media.

g) Document and provide Project-specific media clips to the entire Project team

Environmental

The PICP shall detail the communication hierarchy for information distribution related to compliance with the Comprehensive Environmental Protection Program, as described in Section 4 (Environmental).

The PICP shall include names and contact information, including emergency contact information, and the preferred methods of routine, and emergency communication distribution.

Developer shall assign audit and quality assurance responsibilities to a member of his quality assurance team. The Public Information Coordinator shall not perform those duties because of the potential conflict of interest.

3.2.2 Public Information Coordinator

Developer shall provide a Public Information Coordinator to lead Developer's responsibility for public involvement activities on a day-to-day basis throughout the Term of the Agreement. The Public Information Coordinator shall have a minimum of four years of relevant experience on projects of similar type and scope, and the ability to competently perform the following:

a) Serve as the primary point of contact between Developer and Customer Groups and act as clearinghouse for the receipt of and response to written or verbal comments or complaints regarding the Project.

b) Lead the production, implementation, audit, quality control/quality assurance, and update of the PICP.

c) Coordinate and supervise day-to-day activities of Developer's personnel in performing the activities described in the PICP.

d) Facilitate communication among Developer, TxDOT personnel (including TxDOT's public information officers), and Customer Groups.

e) Interact with Customer Groups and represent the interests of the Project at associated meetings and other formal and informal events.

f) Develop a "first-hand feel" for Customer Groups' concerns and reactions regarding the Project and public information program and incorporate that knowledge into improving the PICP.

g) Liaise with the person assigned to coordinate the initial response to any Incident or Emergency and any Governmental Entity that may have jurisdiction in the Emergency.

h) Liaise with the appropriate staff and customer groups as appropriate to outline the impacts and benefits of the Project in relation to parks and pedestrian/bicyclist access.

i) Create and manage a Customer Group database. Allow TxDOT access to database as needed.

3.2.3 Public Information Office

Developer shall maintain a public information office for the Term of the Agreement. The hours of operation for this office shall be as outlined below. This office shall serve as the primary business location for the Public Information Coordinator and shall be conveniently located to the Project site. The public information office shall facilitate the exchange of information between Developer and the public and provide a centralized location for residents and other Customer Groups to obtain information on the Project, including Project maps and Plans, fact sheets, alternative routes, lane closures, construction updates, community impacts, and commute options.

The public information office shall have readily available two conference rooms capable of hosting Customer Group meetings. The rooms shall be ADA-compliant, convenient to and accessible by Customer Groups and appropriately supplied with electrical outlets, tables and chairs, and other basic equipment to meet meeting requirements. One of these rooms shall accommodate at least 50 persons and another shall accommodate at least 15 persons.

During major construction, the minimum hours of operation of the public information office shall be as follows.

Monday-Friday	8 a.m. – 5 p.m. and by appointment
Saturday	By appointment
Sunday	Closed

Developer shall extend hours of operation to appropriately service Customer Groups.

Developer shall provide reasonable access to the Project site to give TxDOT-approved Customer Groups the opportunity to view the construction.

In addition to the services listed above, Developer shall provide a 24-hour telephone hotline manned during normal business hours of the public information office with a recorded message describing Emergency procedures after hours. Developer shall respond to voicemail messages left after hours within 24 hours of receiving the voicemail message.

3.2.4 Customer Groups

The Public Information Coordinator shall actively engage, inform, and seek appropriate support from Customer Groups for the Project throughout every stage of the Project. Customer Groups shall include the following:

a) Media

b) Local, State, and Federal Governmental Entities including regulatory and law enforcement agencies

c) General public residing or working within the general vicinity of the Project or traveling within or across the limits of the Project

d) Business owners within or adjacent to the Project corridor

e) Utilities, railroads, transportation authorities, and providers (such as local airports, transit operators, toll authorities, and other highway concessionaires) affected by the Project

f) Neighborhood associations, community groups, and other organizations with special interest in the Project

g) Major traffic generators that could be affected by closures or construction (such as universities and major employers) and sponsors/coordinators of major regional special events such as Super Bowls.

3.2.5 Public Meetings

Developer shall organize and manage public meetings with the Customer Groups during design and construction activities and will serve as the clearinghouse for invitations to attend meetings and other events.

The frequency of public meetings shall be addressed in Developer's PICP and will increase or decrease as needs arise to better inform and engage the Customer Groups. Developer shall propose a schedule of public meetings to TxDOT and then conduct the public meetings that, at a minimum, shall address Project construction and maintenance.

To maximize public participation, public meetings shall be advertised with sufficient advance notice in the appropriate media outlets, such as the *Texas Register*, local newspapers, and television and radio

stations, or via media advisories and media releases as appropriate. Developer shall be solely responsible for meeting advertisement except that the *Texas Register* advertising, when appropriate, shall be routed through TxDOT's Public Information Office.

During such meetings, Developer shall inform the participants of the Project's progress and discuss key issues as they emerge. Developer shall provide timely and useful information regarding subjects of interest to the Customer Groups, including:

a) Design and construction issues affecting adjacent residential areas, frontage roads, local streets, and utilities, including such issues as Project ROW definition, Project ROW acquisition process, grading, drainage, access, lighting, aesthetics and noise, and retaining walls

b) Street and roadway detour design and implementation

c) Scheduling and duration of Work, including hours of construction

d) Haul routes

e) Methods to minimize noise and dust

f) Environmental mitigation measures, including noise wall meetings.

g) Other environmental issues

h) Tolling plans and ingress and egress points to the managed lanes

i) Developer shall conduct a ROW open house at the direction of TxDOT and invite all affected and potentially affected property owners.

Developer shall notify TxDOT a minimum of 48 hours in advance of any meetings with the public. TxDOT reserves the right to attend any such meetings. When requested by TxDOT, Developer shall participate in and provide support for any meetings with the Customer Groups called and conducted by TxDOT. When TxDOT decides to conduct such meetings, Developer shall share, in a readily manipulative form, all necessary information regarding potential Customer Groups at TxDOT's request. Developer shall bear all costs associated with the meetings organized and managed by Developer.

3.2.6 Meeting Summaries

For all meetings with the Customer Groups which Developer conducts or directly participates in, Developer shall prepare meeting summaries within five (5) Business Days after the conclusion of such meetings. At a minimum, Developer shall include the following items in the meeting summary:

a) A complete list of attendees (including their affiliations, telephone numbers, and e-mail addresses)

b) Documentation of the exhibits, presentations and/or handouts available at the meeting

c) Documentation of the issues discussed and any associated solutions

d) Description of remaining open issues and action items (including the person(s) responsible for follow-up and target date for resolution)

For any formal public meetings or open houses at which a court reporter is required, Developer shall also include detailed verbal transcripts in the summary. Developer shall submit draft versions of all meeting summaries to TxDOT for review before distributing final versions to the meeting attendees and appropriate Customer Groups.

Meeting summaries shall be submitted to TxDOT in readily accessible form (e-mail, Project intranet site, or file sharing site) within the five (5) Business Days required.

3.2.7 Emergency Event Communications

For all Emergency events, such as major vehicle collisions, ice/snow conditions, and Hazardous Material spills, the Public Information Coordinator shall take timely and appropriate action to inform TxDOT and appropriate Customer Groups of all pertinent details. The Public Information Coordinator shall provide these details through the use of appropriate tools to ensure effective communication. These tools include, but are not limited to: dynamic message signs (DMS), TxDOT's Highway Conditions Report, TxDOT Dallas District Office Highway Advisory Report, email/Web/text alerts, telephone notification, facsimiles, and media releases/interviews, as appropriate. The Public Information Coordinator shall continue to provide updated information, as available and on a timely basis, until the Emergency no longer exists.

In the event of an unforeseen Emergency, timely notification shall mean as soon as practicable, but in no event longer than within one hour of the occurrence. The definition of an unforeseen Emergency shall follow TxDOT's general guidelines requiring emergency notification when delays for motorists in traffic extend beyond two (2) hours. If advanced warning is available for an Emergency event such as ice/snow, timely notification shall mean as soon as practicable, but in no event longer than within one hour of the time the information is available. In both situations, the Public Information Coordinator shall continue to provide updated information, as available and on a timely basis, until the Emergency no longer exists.

3.2.7.1 Lane Closures

Subject to the lane closure restrictions set forth in Section 18 (Traffic Control), Developer shall provide TxDOT and appropriate Customer Groups a minimum of two weeks advance notice for lane closures and/or traffic switches planned to be in effect longer than 24 hours, or all full highway closures in effect during any portion of the period from 6 a.m. to 8 p.m., regardless of duration, and a minimum of 48 hours advance notice for lane closures other than full closures that are planned to be in effect less than 24 hours, using all appropriate tools as needed. The Public Information Coordinator shall input all lane closures (or an event that results in lane closures) into the TxDOT Highway Conditions Report.

For planned lane closures and Emergency event lane closures, as appropriate, Developer shall coordinate lane closures that may affect crossing TxDOT facilities with appropriate TxDOT district and area offices, as needed, to ensure that no conflicts occur. Developer shall provide advance notification of all lane closure notices to the appropriate TxDOT district and area office. TxDOT will provide appropriate contacts and information upon request. Developer shall also monitor other projects along the I-35/I-35E corridor for major closures that could affect statewide travelers. Developer shall provide notification to TxDOT and coordinate with those projects to ensure appropriate levels of statewide mobility.

3.2.8 Disseminating Public Information

Developer shall prepare and distribute materials regarding Project-related subjects, using all appropriate methods, including, but not limited to: meetings, news releases, telephone correspondence, newsletters, emails, text messages, mobile phone applications, hotlines, Highway Conditions Report, dynamic message signs, Web alerts, maps, displays, renderings, presentations, brochures, pamphlets, highway advisory radio, and video news releases. Copies of draft public information materials shall be submitted to TxDOT. TxDOT shall have a period of seven (7) days to review and comment in advance of final editing. Copies of all final materials shall be provided to TxDOT at least three days prior to dissemination.

Developer shall create a public Web site to convey Project-related information, including, but not limited to:

a) Contact information
b) Project maps
c) Frequently asked questions (FAQs)
d) Current Project activities addressing design, construction, and maintenance
e) Timing of street and ramp closures and openings
f) Real-time traffic information, including speeds of traffic along the corridor and major incidents
g) Live traffic camera feeds
h) Recommended route alternatives during closures
i) Newsletter and meeting materials
j) Meetings and special events announcements and calendar
k) Links to TxDOT Highway Conditions Reports
l) Links to other related sites as deemed appropriate by TxDOT
m) Information on TxTags, TollTags and a toll calculator
n) Job opportunities
o) Subcontractor information
p) Comment form
q) Mailing list request form
r) Historical archive of photos taken during construction
s) Renderings or video animations of the Ultimate Project, as appropriate
t) Published materials in Spanish or other languages as needs warrant, as well as TxDOT advised translated materials
u) Link to www.my35.org website

The Web site shall also contain other general Project-related information that enhances the engagement or education of the general public. Developer shall regularly review and update information on this public Web site throughout the Term of the Agreement to provide current and appropriate information and the Web site shall provide for question and feedback opportunities for public communication. Developer shall develop and implement a plan to make the Customer Groups aware of the Project Web site.

All written materials produced for Customer Groups shall follow the TxDOT *Style Guide* and/or other appropriate spelling/writing guidelines.

Developer, working collaboratively with TxDOT, shall assess the need for multi-lingual communications and, where appropriate, furnish Project-related materials in Spanish or other demographic adaptations.

Developer shall track all incoming comments and inquiries and requests for information related to the Project. The following information shall be collected with each contact, and a summary of all contacts without contact information shall be reported to TxDOT on a monthly basis:

- Name of individual
- Address (not required)
- Phone number
- E-mail address
- Subject matter
- Specific comment, question or request
- Date of comment, question or request
- Response given

4 ENVIRONMENTAL

4.1 General Requirements

The Developer shall deliver the environmental commitments required by the Contract Documents and all applicable federal and state Laws and regulations. The Developer shall develop, operate, and maintain a Comprehensive Environmental Protection Program (CEPP) for the Work to ensure environmental compliance with all applicable Environmental Laws and commitments. The Program shall obligate the Developer to protect the environment and document the measures taken during the performance of the Work to avoid and minimize impacts on the environment from the design, construction, maintenance, operation, and rehabilitation activities of the Project.

The Program shall be designed to incorporate all features and guidelines of ISO 14001. The Program shall effectively demonstrate in detail the Developer's knowledge of all applicable Project-specific Environmental Approvals, issues, and commitments and applicable Environmental Laws as set forth in these Technical Provisions, and shall describe the processes that will be followed during the course of the Work to comply with those Environmental Approvals, issues, and commitments and Laws, as well as the documentation required to validate compliance. All monitoring and reporting activities shall be concise, consistent throughout the Term of the Agreement as applicable to the activities being performed, and in accordance with the requirements set forth in the Environmental Laws. The program shall also effectively describe the quality control and assurance measures that the Developer will implement to verify the compliance of the program with all applicable Environmental Laws.

The program shall establish and implement environmental permits, issues, and commitments consistent with the Environmental Approvals. The program shall establish a goal of zero environmental violations during the performance of all Work activities. However, should violations occur, the program shall set forth detailed processes for rectifying such violations in an appropriate and timely manner.

The Developer shall cause Work to comply with Environmental Approvals and compliance requirements for any additional actions throughout the Term of the Agreement. The Developer shall monitor and document Work activities so that documents providing evidence for compliance are available to TxDOT for inspection at any time.

The costs of all field laboratory and consulting work, including but not limited to Phases II to III environmental site assessments, related to Hazardous Materials will be considered part of the Hazardous Materials Allowance. In no event shall any Phase I Hazardous Materials investigation cost be included in the Hazardous Materials Allowance.

4.2 Environmental Approvals

4.2.1 New Environmental Approvals and Amended TxDOT-Provided Approvals

TxDOT-Provided Approvals are based on the Ultimate Project and approved environmental document(s) and the Draft Interim Schematic. Such approvals may require re-evaluation, amendment, supplement, or additional studies/reports as the Work progresses or in order to accommodate actions not identified in the Environmental Approvals or covered specifically by environmental documents, permits, and existing resource and regulatory agency coordination. Changes to the Draft Interim Schematic or incorporation of Additional Properties into the Project shall require the validity of existing Environmental Approvals to be reassessed and may require new Environmental Approvals.

The Developer shall be responsible for coordination with Governmental Entities necessary to obtain new Environmental Approvals or amendments to the TxDOT-Provided Approvals except where TxDOT has agreements with Governmental Entities to perform such coordination.

The Developer shall be responsible for ensuring compliance with the conditions and schedules set forth in amendments to any TxDOT-Provided Approvals or new Environmental Approvals. TxDOT may, in its discretion, provide assistance in securing new Environmental Approvals or amendments to TxDOT-Provided Approvals.

4.2.2 Responsibilities Regarding Environmental Studies

Developer shall be responsible for conducting additional and/or continuing environmental studies based on the TxDOT Provided Approvals in Exhibit 4 of the Development Agreement and Developer provided schematic design.

Developer shall be responsible for conducting environmental studies and re-evaluations caused by actions not identified in the Environmental Approvals, actions not covered specifically by existing resource and regulatory agency coordination, or incorporation of Additional Properties into the Project. The Developer shall be responsible for all coordination of environmental studies with appropriate Governmental Entities, except where TxDOT has agreements with Governmental Entities to perform such coordination.

4.2.3 TxDOT Review and Approval of Developer Submissions

TxDOT reserves the right to review, comment on, require revisions to, and reject for resubmission documentation submitted for environmental compliance or Environmental Approvals. Documentation shall conform to current TxDOT submission standards and the requirements of all applicable Governmental Entities, laws, and regulations. TxDOT shall return approved documentation to the Developer for submittal to the appropriate Governmental Entity in cases where the Developer performs coordination. TxDOT, acting reasonably, shall approve those submissions for which TxDOT signature or other approval is required. Documentation not meeting current submission standards or requirements of Governmental Entities will be returned to the Developer, and shall be revised by the Developer to meet standards or requirements.

4.2.4 TxDOT-Provided Approvals

The TxDOT-Provided Approvals are provided in Exhibit 4 of the Development Agreement.

~~All mitigation~~The requirements ~~and environmental commitments~~ set forth in ~~the FONSI documents for each Project segment are included in the Project and~~Exhibit 4 of the Development Agreement shall be the responsibility of the Developer unless specifically stated otherwise. Furthermore, the Developer shall comply with any and all permit requirements.

4.3 Comprehensive Environmental Protection Program (CEPP)

As part of the PMP, the Developer shall develop and implement a CEPP, applicable throughout the Term of the Agreement to establish the approach, requirements and procedures to be employed to protect the environment. The CEPP shall be developed in the form of a comprehensive environmental management system incorporating all features and guidelines outlined in ISO 14001. All component parts shall reflect

in order of priority: impact avoidance, minimization and as last resort mitigation. The CEPP shall satisfy applicable FHWA, TxDOT and resource and regulatory agency requirements, including those detailed as commitments in any Environmental Approvals. The CEPP shall be updated to comply with any changes to the environmental commitments resulting from changes to the Metropolitan Transportation Plan (MTP) as maintained and approved by the North Central Texas Council of Governments (NCTCOG).

The CEPP shall be the overarching system by which the Developer shall cause environmental commitments made during the Environmental Approval and permitting processes, and other environmental requirements to be carried forward and reflected, as appropriate, in the design and implemented throughout the Work. The Developer shall utilize the CEPP to track on-going issues, identify environmental compliances, non-compliances and identify actions required/taken to correct any such non-compliances.

At a minimum, the CEPP shall include the following component parts:

a) Environmental Management System (EMS)

b) Environmental Compliance and Mitigation Plan (ECMP)

c) Environmental Protection Training Plan (EPTP)

d) Hazardous Materials Management Plan (HMMP)

e) Communication Plan (CP)

f) Construction Monitoring Plan (CMP)

g) Recycling Plan (RP)

h) Environmental team resumes

The dates by which component parts comprising the CEPP are to be submitted for TxDOT approval are set forth throughout these Technical Provisions. Amendments and updates to the CEPP as necessary to address changing conditions and environmental requirements shall be in accordance with the procedures for amendments to the PMP.

4.3.1 Environmental Management System (EMS)

The EMS shall be the overarching system by which the Developer shall cause environmental commitments made during the Environmental Approval and permitting processes, and other environmental requirements to be carried forward and reflected, as appropriate, in the design and implemented throughout the Work. The Developer shall utilize the EMS to track on-going issues, identify environmental compliances, non-compliances and identify actions required/taken to correct any such non-compliance.

The EMS shall establish a schedule for periodic CEPP review to ensure it is up to date. The EMS shall provide a means to track the reviews and results. At a minimum, the EMS shall require documents in the following list to be on file at the Site and available at any time for TxDOT review:

a) CEPP component parts;

b) Weekly Environmental Monitoring Reports;

c) Investigative Work Plans, Site Investigation Reports, and remedial action plans as necessary for hazardous material discovery/remediation;

d) Jurisdictional Determinations and appropriate Section 404 Permit Application. Once permits are obtained, changes to the design or temporary construction impacts may require modifications;

e) Mitigation or resource monitoring reports, as required by resource-specific mitigation plans;

f) Designs for wetland and floodplain mitigation;

g) TPDES Construction General Permit (TXR150000), Notice of Intent (NOI);

h) TPDES Construction General Permit (TXR150000), Notice of Termination (NOT) for Work completed;

i) Storm Water Pollution Prevention Plan (SW3P) and amendments, as required to reflect Project development and staging, including off-site plans, controls and reporting from borrow sites, waste sites, and plant location sites;

j) Completed Permit applications and permits as issued;

k) Pre-Construction Inspection Report;

l) Training Documentation;

m) Developer's final traffic noise analysis, if different than that included in the TxDOT-Provided Approvals;

n) Attachment 4-1, Temporary Erosion, Sedimentation, and Environmental Controls;

o) Attachment 4-2, Construction Storm Water Pollution Prevention Plan Field Inspection and Maintenance Report (Form 2118);

p) Attachment 4-3, Construction Stage Gate Checklist (CSGC) (Form 2448); and

q) Attachment 4-5, Environmental Permits, Issues, and Commitments (EPIC) Sheets.

4.3.2 Environmental Compliance and Mitigation Plan (ECMP)

The ECMP shall document and fully detail compliance strategies and procedures to be employed to cause Work performance in accordance with requirements of applicable Environmental Laws and Environmental Approvals. This plan shall establish and/or document schedules, protocols, and methodologies to be used in accomplishing Work, with an emphasis on monitoring, reporting, corrective actions and adaptive management. The plan shall include a Compliance Action Plan (CAP). The CAP shall consist of a decision making matrix which will define the triggers for initiating or re-initiating environmental compliance actions for construction and maintenance activities including construction noise mitigation measures and the triggers for initiating mitigation measures. For each trigger, the CAP shall identify the appropriate type or level of environmental study or other compliance action necessary to ensure the ongoing validity of Project Environmental Approvals and commitments. In addition, the ECMP shall detail any mitigation required by Environmental Approvals and the Developer's approach to satisfying mitigation requirements, including mitigation requirements identified after completion of the ECMP.

The ECMP shall include the following components:

- **Environmental Permits, Issues, and Commitments (EPIC) Sheets**

The Developer shall develop and maintain EPIC construction plan sheets. Applicable permits and environmental commitments shall be identified on EPIC sheets and updated throughout the construction period to identify on-Site conditions.

The State shall ensure that EPIC sheets shall include the Environmental Commitments required to ensure that any discharge from the Project site into a sanitary sewer system complies with appropriate codes and standards of the sanitary sewer owner.

- **Clean Water Act - Sections 404 and 401: Waters and Wetlands of the United States**

The Developer shall document how they will comply with the terms and conditions for Section 404 permit(s) issued to TxDOT by the U.S. Army Corps of Engineers (USACE) and associated Section 401 State Water Quality Certification(s) as administered by the TCEQ (Texas Commission on Environmental Quality) as well as any additional Section 404 permits and 401 certifications issued to the Developer during the life of the Project. The documentation at a minimum shall include:

a) Process for training personnel to recognize Waters of the U.S. that fall under the jurisdiction of the USACE;

b) Process for communicating the terms and conditions of all USACE 404 permits and TCEQ 401 certifications and other permits as necessary;

c) Procedures for carrying out any required mitigation; and

d) Procedures for handling off-right-of-way Project Specific Locations (PSL) as required by all Section 404 permit(s) issued to either TxDOT or the Developer by the USACE.

In addition to Section 404/401 requirements, the South Segment is within the Trinity River Corridor Development Regulatory Zone and a Corridor Development Certificate (CDC) shall be provided by the Developer. Additionally, for the Middle Segment, BMPs must be designed to ensure that runoff from the first flush of storm water off the Lewisville Lake bridge would be treated properly. USACE review/approval of the BMPs associated with Lewisville Lake will be required. USACE requirements that shall be met by the Developer include, but not limited to, "no net loss of valley storage" at Lewisville Lake.

- **Clean Water Act - Sections 402: Texas Pollutant Discharge Elimination System (TPDES)**

The Developer shall document how they will comply with Section 402 of the CWA. The documentation shall include that the Developer has day-to-day operational control over activities necessary to ensure compliance with the Storm Water Pollution Prevention Plan (SW3P) and Attachment 4-1, Temporary Erosion, Sedimentation, and Environmental Controls and has the sole responsibility for any potential non-compliance issue. The documentation shall also include that the Developer is responsible for submitting a NOI to TCEQ. The documentation at a minimum shall include:

a) Process for training personnel on the requirements and conditions of the Texas Construction General Permits for Storm Water Discharges from Construction Sites (CGP),

b) Procedures for incorporating additional properties outside the original NEPA approved schematic and any off- right-of-way PSL within one linear mile of the Project limits to comply with the CGP and the Project's SW3P,

c) Procedures for handling non-compliance issues,

d) Escalation procedures for SW3P items.

e) Attachment 4-2 - Form 2118 Construction Storm Water Pollution Prevention Plan Field Inspection and Maintenance Report

f) Attachment 4-3 - Form 2448 Construction Stage Gate Checklist (CSGC)

- **State Listed Species and Unregulated Habitat**

Developer shall document how they will address state listed species and unregulated habitat. The documentation shall be in agreement with all Memorandum of Understandings (MOU) and Memorandum of Agreements (MOA) TxDOT has with the Texas Parks and Wildlife Department (TPWD) including the requirement for coordination with TPWD to be conducted by TxDOT. The documentation at a minimum shall include:

a) Process for communicating any commitments regarding state listed species and unregulated habitat; and

b) Procedures for complying with any commitments as detailed in Attachment 4-5, EPIC Sheets.

- **Endangered Species Act (ESA), Fish and Wildlife Coordination Act (FWCA), and Migratory Bird Treaty Act (MBTA)**

Developer shall document how they shall comply with the ESA, FWCA, and MBTA. The documentation shall reflect that coordination with U.S. Fish and Wildlife Service (USFWS) shall be conducted by TxDOT. The documentation at a minimum shall include:

a) Process for training personnel on the requirements of the ESA and FWCA;

b) Process for communicating any commitments regarding ESA and FWCA; and

c) Procedures for complying with any commitments including mitigation as detailed in Attachment 4-5, EPIC Sheets.

- **Traffic Noise**

The Developer shall document how they will address traffic noise mitigation. The documentation at a minimum shall include:

a) Process for carrying out traffic noise mitigation measures as identified and discussed in the approved NEPA document schematic and any supplemental noise studies completed by TxDOT or Developer;

b) Process for carrying out traffic noise mitigation measures determined throughout the life of the Project; and

c) Process to handle changes that may occur to proposed permanent traffic noise mitigation in the approved NEPA document and schematic.

To fulfill the commitments of the previously mentioned TxDOT-Provided approvals the Developer shall be responsible for implementing all traffic noise mitigation measures to minimize construction impacts of

the Work as prescribed in TxDOT-Provided approvals and subsequent TxDOT-Provided approvals secured by the Developer. The Developer acknowledges that TxDOT-Provided approvals and proposed permanent traffic noise mitigation is proposed based on the Draft Interim Schematic and schematic ROW; consequently the proposed permanent traffic noise mitigation may require amending by the Developer as the Work progresses due to Developer changes in the Draft Interim Schematic. Such amendments shall be submitted to TxDOT for review and approval.

The Developer shall provide traffic noise abatement at the locations listed in the table below. TxDOT has applied for Environmental Approval for these sound wall locations and will provide the Environmental Approval when it becomes available.

NOISE WALL NO.*	SEGMENT	SIDE	STATION FROM	WALL OFFSET (FT)	WALL HEIGHT (FT)	STATION TO	WALL OFFSET (FT)	WALL HEIGHT (FT)
2A	Middle	RT	1158+19	149	10	1159+27	150	10
2B	Middle	RT	1160+08	149	10	1169+59	150	10
5A	Middle	LT	1348+50	107	14	1354+80	107	14
5B	Middle	LT	1353+76	187	10	1357+69	189	10
5C	Middle	LT	1357+10	145	10	1372+95	82	10
5D	Middle	LT	1380+66	79	12	1400+60	79	12
5E	Middle	LT	1400+32	152	12	1409+33	148	12
6A	Middle	LT	1446+13	148	12	1454+19	152	12
6B	Middle	LT	1454+19	79	12	1473+80	79	12
NW5	North	RT	1995+66	146	12	2004+74	147	12

**Corresponds to the EA wall number.*

Developer shall perform any necessary structural engineering associated with the wall, in accordance with the Technical Provisions. Developer shall conduct the Traffic Noise workshop associated with the walls listed above in accordance with TxDOT *Guidelines for Analysis and Abatement of Highway Traffic Noise.*

The noise walls shall be designed and constructed to allow for future relocation. This shall include removable panels that can be easily relocated by others in a future phase as TxDOT transitions the corridor to the Ultimate Project. The phrase easily relocated, as used in this paragraph, shall be interpreted to mean that the effort needed to remove and relocate the noise wall panels may be performed

by personnel and equipment commonly used on highway construction projects in a manner that will not inherently cause damage to the noise wall panel.

Developer shall be responsible for public notification and involvement per TxDOT *Guidelines for Analysis and Abatement of Highway Traffic Noise* and in accordance with Section 3 of the Technical Provisions. Developer shall allow fifteen (15) Days for adjacent affected property comments after each noise workshop. Developer shall perform all of the duties contained in this document, when required, including, but not limited to:

- Traffic Noise workshop;
- Property owner notification;
- Survey/ballot; and
- Final design

Developer shall be responsible for all coordination with adjacent property owners and Governmental Entities necessary to obtain all such amendments to TxDOT-Provided Approvals and for ensuring compliance with the conditions and schedules set forth in the amendment of any TxDOT-Provided Approvals.

As stated in the Middle Segment, USACE guidelines require noise generating activities to be coordinated with USACE staff to determine the allowable actions from 10 p.m. to 6 a.m.

- **Water Well Impacts and Requirements**

Developer shall document how they will address wells (such as municipal, domestic, irrigation, oil and gas, or monitoring and observations wells) encountered during the life of the Project. The documentation shall include that the Developer is responsible for plugging and abandoning all wells in accordance with Item 103, Disposal of Wells, from TxDOT Standard Specifications for Construction and Maintenance of Highways, Streets, and Bridges, as well as the developer is responsible for any required remediation efforts. The documentation at a minimum shall include:

a) Process for training personnel on recognition of wells,

b) Procedures for handling wells,

c) Procedures for handling contamination of a well that results from the Developer's work. Procedures shall include a requirement to notify TxDOT and with TxDOT's concurrence notify appropriate regulatory agency within 24 hours of the discovery.

- **Cultural Resource Studies**

Developer shall be responsible for ensuring compliance with cultural resource Laws on the Project through the Term of the Agreement. TxDOT shall perform consultation for the Project according to current procedures for implementing Section 106 of the National Historic Preservation Act, and the Antiquities Code of Texas.

Subsequent to issuance of NTP1, Developer shall be responsible for performing any necessary cultural resource surveys, evaluations, testing, and mitigation in those areas outside the footprint of the Project ROW shown on the schematics as defined in the original NEPA Approval and within the area of potential effects. The Developer shall coordinate all necessary Antiquities Permits through TxDOT. Antiquities

Permits shall be obtained from the Texas Historical Commission (THC) for archeological surveys, testing, monitoring, and data recovery.

Developer shall document efforts to avoid impacts to cultural resources that are listed on or determined to meet the eligibility criteria for listing to the National Register of Historic Places (NRHP) as specified in 36 CFR 60.4, or that are designated or determined to meet the criteria for designation as State Archeological Landmarks as specified in 13 TAC 26.8.

If evidence of a possible historic property or archeological deposits are encountered during the course of the Work, the Developer shall immediately cease Work in the immediate area and contact TxDOT to initiate post-review/accidental discovery procedures under the provisions of the Programmatic Agreement (PA) among TxDOT, State Historic Preservation Officer (SHPO), FHWA, and Advisory Council on Historic Preservation (ACHP) as well as the MOU between TxDOT and the THC. The Developer shall undertake appropriate measures to protect the site from further intrusion to the extent feasible until an appropriate evaluation of the site can be made by a qualified representative. Work shall not be resumed in the area until the Developer receives notification and approval from TxDOT.

- **Other Mitigation/Requirements for Middle Segment**

Section 4(f)

Impacts to Section 4(f) properties within the Middle Segment EA (USACE Property, Highland Lakes Park, and Arrowhead Park) and associated mitigation are being further developed in the form of a Master Plan. The Developer shall be responsible for mitigation of all elements as shown and described in Attachment 4-4. Developer shall complete construction of elements 2.o, 2.p, 2.q, 2.r, and 2.v (Copperas Branch Park East) as shown on Attachment 4-4 within 365 days of NTP2. Developer shall coordinate implementation of all mitigation measures shown and described in Attachment 4-4 with TxDOT, USACE, and the appropriate entities.

As described in TxDOT-Provided Approvals, specifically Chapter V. of the Final EA, Developer shall also be responsible for on-site mitigation and/or a fee payment for impacts to natural resources on USACE Property. Per the Final EA, typical compensatory mitigation for the anticipated loss of vegetation/habitat in accordance with the level of detail known at the time the Section 4(f) was approved was calculated as presented in Appendix G, Exhibit 5 of the Final EA. Developer shall be responsible for the compensatory mitigation required by USACE and for any revisions required to determine a final compensatory mitigation cost, including on-site and/or fee payment or any other requirements deemed necessary to satisfy USACE requirements for impacts to natural resources. Since the Section 4(f) was approved, additional mitigation for loss of park revenue and amenities in the form of an in-lieu fee payment has been agreed to and will be the responsibility of TxDOT. The Developer shall be responsible for any modifications or additional requirements related to in-lieu fee payments above and beyond this agreement. TxDOT is preparing the environmental documents and permits required to address this change.

Multiple Use Agreement

A Multiple Use Agreement shall be obtained by the Developer to allow for parking under the IH 35E bridge over Lewisville Lake in accordance with 23 CFR 710.405 and FHWA Airspace Guidelines.

Coordination with TxDOT and the Office of General Counsel is required prior to the start of construction to obtain the Agreement.

Construction License

The Developer shall obtain a construction license for activity outside of the approved easement for the proposed improvements on USACE fee simple property, exclusive of the flowage easement (537 ft). Any activity occurring on USACE property outside of the approved easement would be part of the construction license and is the responsibility of the Developer to obtain through coordination with USACE.

- **Public Involvement**

Developer shall document how they will comply with all public involvement requirements, including public involvement requirements specifically related to cultural resources. The documentation shall comply with all applicable requirements including, but not limited to, 43 TAC §2 Subchapter E4, Section 106 of the National Historic Preservation Act (36 CFR 800), Chapter 26 of the Texas Parks and Wildlife Code, the Civil Rights Act of 1964, and the Civil Rights Restoration Act of 1987. The documentation shall include that the Developer is responsible for conducting all public involvement requirements for the life of the Project except where TxDOT has agreements with Governmental Entities to perform public involvement requirements. The documentation at a minimum shall include:

a) Process for handling public involvements requirements; and

b) Procedures for documenting public involvement.

- **Standard Operating Procedures**

Developer shall develop standard operating procedures for the following activities and include them in the ECMP:

a) Controlling dust during construction;

b) Mitigating vibration during construction;

c) Mitigating light intrusion on adjacent properties; and

d) Complying with Section 404 regulations and the Section 404 permits for the Project.

4.3.3 Environmental Protection Training Plan (EPTP)

The Developer shall develop and implement an EPTP that shall meet the minimum requirements set forth herein. The EPTP shall include methods and procedures documented in the ECMP to:

a) Educate every worker to:

- Recognize the overall importance of environmental issues to constructing, operating and maintaining a successful Project.
- Appreciate the various environmental sensitivities of the Project.

b) Train every worker to:

- Recognize environmentally sensitive resources that may be encountered during the Work.
- Avoid or take appropriate action to minimize environmental impacts from the Work.

- Know the required actions, practices, and procedures regarding regulated resources.
- Understand protocols for meeting environmental commitments for post-review discoveries.

c) Foster the Developer's management and supervisory personnel's attitude of commitment to the Project's environmental quality.

d) Convey to all workers, the Developer's management commitment to the Project's environmental quality.

e) Convey to all workers, TxDOT's and the Developer's commitment to zero tolerance for violations.

4.3.3.1 EPTP Scope and Content

The goal of the EPTP is to educate Project personnel about the following:

a) Overall importance of environmental protection to the Project

b) Compliance responsibility and Governmental Entity authority including background and environmental issues regulatory overview.

c) Overview of the Developer's environmental commitments and responsibilities at the Project level.

d) Worker responsibilities.

e) Wetlands identification.

f) Environmental Approvals terms and conditions including an overview of the provisions of the ESA, Migratory Bird Treaty Act, and Stormwater Pollution Prevention Program (SW3P).

g) Best Management Practices (BMPs) for environmental compliance, including pollution prevention, erosion, sedimentation, post construction controls, and dust control measures to maintain water and air quality.

h) Required mitigation measures.

i) Procedures and precautions in the event of spills of or discovery of Hazardous Materials or unknown chemicals or contamination.

j) Procedures and precautions in the event human skeletal remains or other archeological or paleontological resources are discovered.

k) Procedures regarding the relocation of historical markers (i.e. Texas Historic Commission Subject Markers, DAR OSR Markers, Texas Centennial Markers, Texas Highway Department Markers, and local/county markers).

l) Groundwater protection requirements.

m) CWA regulations and surface water protection requirements.

n) Overview of noise and residential impact reduction procedures.

o) Air quality requirements.

p) Penalties and/or fines for violations of and noncompliance with Environmental Approvals and Environmental Laws, including termination of employment.

Developer shall submit to TxDOT for review and approval course outlines containing learning objectives designed to achieve stated goals and suggested staff attendance for all anticipated training requirements through the Term of the Agreement. Course outlines shall be submitted within ninety (90) Days after NTP1.

4.3.4 EPTP Participation

Developer shall require all non-administrative employees to participate in the EPTP and shall keep accurate records documenting attendance, as well as materials presented.

4.3.4.1 EPTP Schedule

Developer shall include activities for implementation of the EPTP in the Project Schedule. The length of training sessions and their frequency shall be sufficient to achieve the goals set forth above. Periodic training sessions at key times (e.g., prior to construction or major maintenance in sensitive areas or construction timing restrictions to protect threatened and/or endangered species) shall be used to update workers on specific restrictions, conditions, concerns, and/or requirements.

4.3.5 Hazardous Materials Management Plan (HMMP)

Developer shall prepare a HMMP for the safe handling, storage, treatment and/or disposal of Hazardous Materials, whether encountered at or brought onto the Project site by the Developer, encountered or brought onto the Project site by a third party, or otherwise, during the Term of the Agreement. A Limited Phase I Environmental Site Assessment Report was provided in the Reference Information Documents that lists the known hazardous material sites. The Developer shall submit the final HMMP to TxDOT for review and approval in its good faith discretion within sixty (60) Days of NTP1; approval of the Plan by TxDOT shall be a condition of commencement of Construction Work.

The HMMP shall include procedures compliant with all applicable Environmental Laws and include, at a minimum:

a) For all chemicals to be used on the Project, the Developer shall keep and update Material Safety Data Sheets (MSDS), per Occupational Safety and Health Administration (OSHA) requirements, for the Term of the Agreement;

b) Designated individuals responsible for implementation of the plan;

c) Procedures for identifying and documenting potential contaminated sites which might impact Project development;

d) Procedures for mitigation of known contaminated sites anticipated to impact construction;

e) Procedures for mitigation of unanticipated contaminated sites encountered during construction;

f) Procedures for mitigation of contamination during the operation and maintenance of the Project;

g) Procedures for developing a detailed Spill Response Plan for the Term of the Project;

h) Process for training personnel for responding to and mitigating Incidents involving contamination or waste;

i) Provisions for appropriate storage and disposal of all waste encountered or disposed of on the Project for the Term;

j) Provision for a Hazardous Materials training module as an Element of the EPTP component of the CEPP;

k) Procedures for preparing an Investigative Work Plan (IWP) and Site Investigative Report (SIR) in the event that Hazardous Materials are discovered during construction; operations or maintenance activities; and

l) Identification and contact information for designated responsible individuals.

The HMMP shall include provisions for making all on-Site workers aware of and able to recognize the potential Hazardous Materials to which they may be exposed, limiting Subcontractors and other Site workers' exposure to Hazardous Materials and providing all necessary personal protection equipment to protect workers from exposure. The HMMP shall require Developer to provide any non-Developer personnel who visit the Project with the appropriate personal protection equipment.

The HMMP shall require that all personnel of Developer-Related Entities handling Hazardous Materials be trained and certified at least to the minimum requirements established under the current guidelines of OSHA 1910.120 (HAZWOPER Training).

Further, the HMMP shall include procedures for ensuring that all applicable certifications, licenses, authorizations and Governmental Approvals for Developer personnel handling Hazardous Materials are current and valid through the duration of the Work.

4.3.5.1 Investigative Work Plans (IWP) and Site Investigation Reports (SIR)

If Hazardous Materials are encountered within any of the Project ROW or Additional Properties used as Developer's staging area, field office site, plant sites, borrow site, or stockpile location, Developer shall prepare an Investigative Work Plan (IWP) that addresses the methods, techniques, and analytical testing requirements to adequately characterize the extent of the contaminated media (soil and/or groundwater) potentially impacting the Project. Developer shall locate and assess the likely source of contamination.

A Registered Professional Engineer and other qualified professionals, as needed, shall prepare the IWP and other necessary reports in accordance with applicable, relevant or appropriate Laws and guidance.

Upon satisfactorily completing the investigative work, Developer shall summarize the findings within a SIR and make recommendations regarding potential response actions necessary for Project development. Developer shall take Hazardous Materials contamination into account during all subsequent phases of Project development, including Additional Properties negotiation and acquisition, property management, design, and construction.

The SIR shall address the characterization of the impacted area; sampling efforts and findings; opportunities to avoid the contamination by adjusting the design; level of response action warranted if the contamination cannot be avoided; feasibility of initiating response actions prior to construction; pursuit of cost-reimbursement from responsible parties; the need for completing response actions concurrent with construction and nature of any special specifications and provisions necessary for incorporation into the Project.

Developer may initiate a preventative or corrective action after TxDOT review and approval of the Site Investigation Report from appropriate Federal or State agencies.

4.3.6 Communication Plan (CP)

The developer shall develop a CP which describes in detail the communication hierarchy for information distribution related to the compliance with the CEPP. The CP will include names and contact information, including emergency contact information, and the preferred methods of routine, and emergency communication distribution.

4.3.7 Construction Monitoring Plan (CMP)

The CMP shall identify times, locations, and other conditions where monitoring of construction activities are to be performed to maintain and cause compliance with Environmental Laws, Environmental Approvals, and the Contract Documents. The CMP shall establish and/or document schedules, protocols and methodologies to be used for monitoring Work with an emphasis on timely reporting, corrective actions and adaptive management. The CMP shall establish reporting procedures, identify reporting requirements and establish controls for report distribution and records retention. All Environmental Monitoring Reports shall be made available for review by TxDOT at TxDOT's request. Should any non-compliance or violation be observed that represents an imminent danger to human health or the environment, the CMP shall include procedures to cause immediate notification of TxDOT.

Prior to NTP2, Developer and TxDOT shall jointly inspect existing facilities, structures, and environmentally sensitive areas in the vicinity of the Site but not included as part of the Work. Developer shall provide a minimum 2-week advance notice to TxDOT of this joint inspection. The inspection shall document the pre-construction condition of vegetation, streets, sidewalks, landscaping, residential and commercial property, creeks, storm drainage and infrastructure. The purpose of the inspection is to provide a point of reference from which TxDOT can determine if any facility, structure and environmentally sensitive area damaged during the Work is restored to its pre-construction condition. Developer shall document the inspection with a report that shall include photographs, sketches, maps, and narratives clearly depicting the pre-construction Site condition.

All photographs shall be archival quality and shall be accompanied by a caption describing the date; time of day; location and direction in photograph was taken. If the photograph shows existing damage, the damage must be clearly shown and noted in the caption. All sketches and maps must be no larger than 11"x17". All photographs must be 4"x6".

The post award inspection shall inspect the municipal separate storm sewer system located within and adjacent to the Site. During the inspection, Developer shall note the following:

a) Storm drains, culverts, swales, and other components of the municipal separate storm sewer system that Developer verified as free of floatable trash, silt, debris, and functioning as originally intended.

b) Storm drains or culverts that do not function or appear not to function as originally intended.

c) Siltation of culverts, concrete swales, and other components of the municipal separate storm sewer system.

d) The presence of construction on adjacent, up-gradient, or down-gradient properties. If construction on other properties is noted, Developer shall photographically document the general condition of these properties and their compliance with storm water regulations.

e) Pre-existing off-site tracking from the Site or surrounding properties.

f) Potential pre-existing contamination (i.e., any areas of soil discoloration or distressed vegetation).

g) Any other pre-existing condition that, by its nature, could be construed as a violation of the TPDES General Construction Permit.

Following construction of the Project, Developer shall conduct a yearly inspection to monitor and repair any of the above mentioned deficiencies in the storm water system.

4.3.8 Recycling Plan

The recycling plan shall document and fully detail the Developer's commitment to recycling, waste minimization and use of "green products" during all aspects of Work. The recycling plan shall document the Developer's recycling initiatives as well as methods and procedures for maximizing the use of recycled materials in all aspects of the Work. If recyclable materials shall be used in lieu of TxDOT approved construction and maintenance materials, the Developer shall follow the TxDOT Material Specification DMS 11000.

4.4 Environmental Personnel

Developer, acting through the Environmental Compliance Manager (ECM), shall designate an Environmental Team (ET), as detailed in this section, to prevent, minimize, and/or correct any violation of or noncompliance with Environmental Approvals. The ET shall include Environmental Training Staff, Environmental Compliance Inspectors (ECIs), Cultural Resources Management Personnel, Natural Resource Biologist, Water Quality Specialist, and Hazardous Materials Manager. All of the ET shall be deemed other principal personnel.

In the CEPP, Developer shall establish a detailed approach, procedures and methods for:

a) Staffing and availability of ECM and all ET personnel.

b) ET staff response times during the Work.

4.4.1 Environmental Compliance Manager (ECM)

Developer shall designate a full-time ECM for the Work. The ECM shall report and coordinate all issues directly with TxDOT and the Developer's Project Manager. In the event the ECM, in consultation with Developer's Project Manager and TxDOT, is unable to reach satisfactory resolution of environmental issues, the ECM shall provide written notification to the Developer and TxDOT outlining the concerns, actions taken in attempt to correct the concerns, and provide a recommendation as to the suggested course of action.

The ECM shall direct the work of the ET and shall monitor, document, and report the current status of environmental compliance for the Work. The ECM shall report immediately to TxDOT and the Developer any violation or non-compliance and shall include with any such report, the appropriate recommendations for corrective action including stoppage of Work.

The ECM shall coordinate with TxDOT, the Developer, and appropriate Governmental Entities. The ECM shall submit all necessary environmental documentation and monitoring reports to the appropriate Governmental Entities and when applicable, through TxDOT, to the extent necessary to maintain compliance with applicable Environmental Approvals.

Developer shall not have the ability to relieve the ECM of his or her duty without the written consent of TxDOT. Should Developer desire to replace ECM, Developer shall submit to TxDOT the resume of a replacement candidate. The replacement candidate shall be available fulltime within thirty (30) Days

after delivery of TxDOT's written acceptance. In the absence of the Environmental Compliance Manager, Developer's Hazardous Materials Manager shall act as an interim Environmental Compliance Manager.

The ECM candidate shall have at least five years of experience successfully managing environmental compliance of urban freeway construction. The qualifying experience used to evaluate an ECM candidate must include the following experience:

a) Developing and managing a SW3P;

b) Developing and managing a hazardous substance and petroleum products management plan;

c) Implementing environmental mitigation plans;

d) Providing environmental and personal protection training; and

e) Monitoring compliance with Section 404 Permit conditions.

The Environmental Compliance Manager's qualifying experience must demonstrate the Manager is familiar with:

a) The scope and terminology of ASTM E 1527-05, *Standard Practice for Environmental Site Assessments: Phase I Environmental Site Assessment Process*,

b) Provisions of the TPDES Construction General Permit (TXR 150000), and

c) Requirements of Section 404 and permit provisions.

4.4.2 Environmental Training Staff

Under the direction of the ECM, the environmental training staff shall develop, schedule and conduct environmental awareness and environmental compliance training for the Developer's personnel. All training shall be in accordance with the requirements set forth in Section 4.2.3. Environmental Training Staff members shall have at least one year of experience providing environmental compliance inspection for freeway construction.

4.4.3 Environmental Compliance Inspectors (ECI)

The ECIs shall conduct on-Site environmental monitoring, prepare documentation, and report to the ECM daily all violations, compliance, and noncompliance with Environmental Approvals.

The ECI shall report immediately to the ECM any violation or non-compliance and shall include with any such reports, the appropriate recommendations for corrective action, including, but not limited to stoppage of Work.

The ECIs shall have at least one year operational control experience of SW3P activities.

4.4.4 Cultural Resource Management Personnel

The ECM shall designate personnel to provide expertise in the event that a need arises to comply with cultural resource laws.

The Cultural Resource Management Personnel shall meet the certification requirements of TxDOT Work Category, 2.8.1, "Surveys, Research and Documentation of Historic Buildings, Structures, and Objects," 2.9.1, "Historic Architecture," 2.10.1, "Archeological Surveys, Documentation, Excavations, Testing Reports and Data Recovery Plans," and 2.11.1, "Historical and Archival Research" as applicable.

4.4.5 Natural Resource Biologist

The ECM shall designate a Natural Resource Biologist to provide expertise in monitoring impacts on wildlife and the natural environment during the course of the Work.

The Natural Resource Biologist shall meet the certification requirement of TxDOT Work Category 2.6.1, "Protected Species Determination (Habitat)" and 2.6.3, "Biological Surveys".

4.4.6 Water Quality Specialist

The ECM shall designate a Water Quality Specialist to provide expertise in permitting delineation, stormwater pollution prevention, and the protection of jurisdictional waters during the course of the Work.

The Water Quality Specialist shall have verifiable experience implementing SW3P and be able to demonstrate a working knowledge of the TPDES and MS4 permit requirements applicable to the Project.

The Water Quality Specialist shall meet the certification requirements of TxDOT Work Category 2.4.1, "Nationwide Permit" and TxDOT Work Category 2.3.1, "Wetland Delineation".

4.4.7 Hazardous Materials Manager

The ECM shall designate a Hazardous Materials Manager to provide expertise in the safe handling of Hazardous Materials required to perform the Work and those that may be discovered/impacted during the duration of the Agreement. The Hazardous Materials Manager shall conduct appropriate activities such as the following:

a) Schedule and/or conduct training for the Developer's employees.

b) Verify all employee certifications prior to and required for any handling of Hazardous Materials.

c) Maintain records of all incidents involving Hazardous Materials and notify the ECM, TxDOT and appropriate authorities in writing of any such incidents.

The Hazardous Materials Manager shall be a qualified professional with 40-hour HAZWOPER certification and at least five years of experience in similar projects in the following areas:

a) Experienced in developing IWPs, SIRs, and remedial action plans or equivalent reports necessary and acceptable to the TCEQ in material discovery and remediation efforts of Hazardous Materials.

b) Experienced in TCEQ guidance for the investigation and remediation of Hazardous Materials under the TCEQ Voluntary Cleanup Program and Texas Risk Reduction Program Rules.

The Hazardous Materials Manager shall meet the certification requirements of TxDOT Work Category 2.13.1, "Hazardous Materials Initial Site Assessment."

4.5 Property Access

To fulfill the obligation of the TxDOT-Provided Approvals to maintain current access during and after construction, Developer shall make reasonable efforts to minimize the inconvenience to vehicles, bicycles and pedestrians during the Term of Agreement. The Developer shall maintain access to adjacent properties during construction and ensure that visibility of businesses is maintained.

4.6 Dust Control

Developer shall institute dust control measures to minimize air quality impacts. The measures shall be adjusted as necessary based on construction traffic, forecasted wind speeds, and persistent dry weather conditions.

4.7 Asbestos Containing Material (ACM)

Developer shall identify, inspect, notify, amend notifications as necessary, pay notification fees and abate asbestos found on any structure, including but not limited to bridges and buildings, in accordance with appropriate or relevant regulations or guidance.

Asbestos containing materials (ACM) and lead based paint (LBP) testing shall be performed on the existing bridge structures. ACM and LBP testing shall be performed on building structures to be removed dependent upon the age of the individual structure. Developer shall notify the Department of State Health and Human Services (DSHS) of the bridge demolition 15-working days prior to the scheduled demolition.

4.8 Lead Based Paint

Developer shall identify, inspect, notify, amend notifications as necessary, pay notification fees, and abate lead based paint found on any structure, including but not limited to bridges and buildings, in accordance with appropriate or relevant regulations or guidance.

5 THIRD PARTY AGREEMENTS

5.1 General Requirements

TxDOT has existing agreements with local Governmental Entities along the Project corridor that define the requirements for construction, maintenance, and operation of traffic signals, illumination, and roadway maintenance. These agreements specify the local Governmental Entities responsibilities and TxDOT's responsibilities with respect to the requirements and are provided in the Reference Information Documents.

Developer shall perform all TxDOT responsibilities and duties as defined in the current and future agreements. Developer shall provide TxDOT and Governmental Entities all information necessary for it to fulfill TxDOT's responsibilities under these agreements.

Current and subsequent agreements require TxDOT to reimburse the local Governmental Entity for their role in operating and/or maintaining certain facilities, Developer shall reimburse TxDOT the said costs. Developer shall make payment to TxDOT within thirty (30) days from receipt of TxDOT's request for payment.

5.2 Traffic Signals

New construction or modifications to the existing traffic signals are defined in Section 16 (Signing, Delineation, Pavement Marking, Signalization, and Lighting).

5.2.1 Red Light Cameras

TxDOT shall have the sole discretion to approve any red light cameras within the corridor. Developer shall forward any red light cameras installation requests directly to TxDOT.

5.3 Roadway Illumination

Some local Governmental Entities may request continuous illumination along the frontage roads within the Project limits in addition to the lighting required in Section 16. Should this occur, additional agreements between TxDOT and the Governmental Entity will be required. Developer shall coordinate with and provide reasonable accommodations to the third party to carry out the installation, operations and maintenance obligations as specified in such agreements.

For sections of continuous lighting specified by these additional agreements, safety lighting shall be included as a component of the overall system, and responsibilities for said safety lighting shall be as specified in the terms of the additional agreement.

New construction or modifications to the existing illumination are defined in Section 16 (Signing, Delineation, Pavement Marking, Signalization, and Lighting).

5.4 Other Affected Third Parties

When Work interfaces with other third party facilities, Developer is responsible for coordinating the Work with all third parties potentially affected by the Work. Developer shall prepare a plan, the Affected Third Parties Plan, which describes how the Developer will mitigate the impact of the Work upon

potentially impacted third parties, for TxDOT's review prior to initiating discussions with potentially impacted third parties.

When the Work interfaces with other construction projects within, connecting to, or along the corridor, Developer shall coordinate the Work with the other projects to ensure that the proposed design, construction, and schedules for the Project and other projects are not in conflict. A description of how Developer will coordinate with other construction projects shall be included in the Affected Third Parties Plan.

6 UTILITY ADJUSTMENTS

6.1 General Requirements

A number of existing Utilities are located within or in the vicinity of the Project ROW, some pursuant to statutory rights and some pursuant to property rights. Certain of those existing Utilities will need to be relocated or otherwise adjusted in order to accommodate the Project. This Section 6 establishes procedures and requirements for Utility Adjustments including such processes as coordination with Utility Owners, administration of the engineering, construction and other activities necessary for Utility Adjustments, and required documentation. This Section 6 references certain TxDOT forms for Developer's use in Utility Adjustments. Copies of those forms are included in Attachment 6.1, Utility Forms. Except as otherwise provided in this Section 6 or directed by TxDOT, whenever a TxDOT form is provided, Developer shall prepare all forms of the same type using the TxDOT form and is required to notify TxDOT of all changes to the forms for TxDOT's approval prior to execution by the Utility Owner.

Developer shall cause all Utility Adjustments necessary to accommodate construction, operation, maintenance and/or use of the Project in both its initial configuration and in its Ultimate Project configuration. TxDOT will assist Developer in the Utility Adjustment process, to the extent described in the Contract Documents. Some Utility Adjustments may be performed by the Utility Owner with its own forces and/or contractors and consultants (i.e., Owner-Managed); all others shall be performed by Developer with its own forces and/or Subcontractors and consultants (subject to any approval rights required by the Utility Owner for those working on its facilities) (i.e., Developer-Managed). The allocation of responsibility for the Utility Adjustment Work between Developer and the Utility Owners shall be specified in the Utility Agreements as described in Section 6.1.3.

Developer's obligations regarding reimbursement to Utility Owners for eligible costs of Utility Adjustment Work, and Developer's obligations regarding the accommodation of Utilities from and after NTP 2, are set forth in Section 6.8.6 and Section 6.8.1.1 of the Agreement.

TxDOT is currently performing certain Utility Adjustments for Brazos Electric and Oncor Electric near the IH 35E/FM 407 interchange. The Approved Utility Agreements are provided in the RID, including proposed Utility relocation plans. These three Utility Adjustments as shown in the RID are not part of the Agreement to the extent that the work associated with these Utility Agreements will be performed by others and the estimated costs shall not be included in the Contract Price. It is assumed that these three Utility Adjustments will occur prior to NTP2, however, should this not occur, Developer shall make all necessary adjustments to the Project Schedule to accommodate these Utility Adjustments. Developer shall incorporate the proposed Utility relocation plans into the design of the Project. Once these Utility Adjustments are complete, Developer shall verify the location of these Utilities and make any necessary adjustments to the design of the Project as needed.

This Section 6 does not address Utility services to the Project. Utility services to the Project shall be the subject of separate agreements between Developer and Utility Owners.

6.1.1 When Utility Adjustment is Required

A Utility Adjustment may be necessary to accommodate the Project for either or both of the following reasons: (a) a physical conflict between the Project and the Utility, and/or (b) an incompatibility between the Project and the Utility based on the requirements in Section 6.2.1 (Standards), even though there may be no physical conflict. The physical limits of all Utility Adjustments shall extend as necessary to functionally replace the existing Utility, whether inside or outside of the Project ROW. Section 6.2.4.2

(Acquisition of Replacement Utility Property Interests) contains provisions that address the acquisition of easements for Utilities to be installed outside of the Project ROW.

~~Utilities may remain in their existing locations within the Project ROW if (a) the requirements of Section 6.2.1 (Standards) are met, and (b) the existing location will not adversely affect the construction, operation, safety, maintenance and/or use of the Project and Utility. The Utility Owner must agree to its facilities remaining in its existing location.~~

In areas where ROW is acquired, utilities shall be relocated to be compliant with the Ultimate Project and in accordance with the Utility Accommodation Rules (UAR~~.~~).

~~Immediately adjacent to ROW parcels that are acquired in this Project, the Developer shall transition the utilities back to the interim utility location that is within existing ROW and shall be compliant with the UAR.~~

~~In areas where ROW is not purchased and in areas described as interim in Section 1.2 of the Technical Provisions, utilities in conflict with the proposed construction (such as widening of frontage roads) shall be relocated in compliance with the UAR.~~

~~In areas where ROW is not purchased and in areas described as interim in Section 1.2 of the Technical Provisions, and the utility is not in conflict with the proposed construction, no adjustments are required unless the interim construction creates utility clear zone or other safety violations.~~ Utility facilities located within areas described as interim in Section 1.2 of the Technical Provisions and in table labeled 6-1 may be eligible to remain or be protected in place with the Utility Owners concurrence. The developer is required to submit sufficient information to TxDOT to determine if the Utilities described in Table 6-1 meet UAR requirements and may be eligible to remain or protect in place. Existing utilities that cross the ROW and are located on an existing compensable property interest may be allowed to occupy the existing compensable property interest and cross at less than 90 degrees, up to 30 degrees, measured from the highway centerline station. The crossing may not bisect or cross through any connecting roadway intersection or other major highway design feature and must meet the requirements of the UAR, other than the 90 degree reference above.

Table 6-1

Line Type	Approximate Location	
	From	To
Overhead Power	590+00	-
Fiber Optic	646+00	-
24" Water	664+50	-
Overhead Power (large)	673+00	680+00
Fiber Optic	691+15	-
Fiber Optic	692+00	-
24" San. Sewer	761+10	-
24" San. Sewer	761+90	-
24" Water	795+50	-
Fiber Optic	813+90	-
54" Water	816+75	-
96" Water	824+90	-
2 - 72" Water	825+25	-
60" Water	826+00	-

2 - Overhead Power (large)	848+00	852+00
66" San. Sewer (RCB)	867+70	_
Overhead Power (large)	899+50	_
Overhead Power (large)	901+00	_
Overhead Power (large)	902+20	_
Fiber Optic	906+05	_
Overhead Power (large)	918+00	_
Overhead Power (large)	919+60	_
Fiber Optic	1027+75	_
Fiber Optic	1028+25	_
Overhead Power	1031+00	_
Fiber Optic	1042+60	_
Fiber Optic	1043+50	_
Overhead Power (large)	1124+25	_
24" Water	1132+75	_
Fiber Optic	1206+25	_
Overhead Power (large)	1219+00	1234+00
Fiber Optic	1263+25	_
Fiber Optic	1279+25	_
Fiber Optic	1280+25	_
Fiber Optic	1280+40	_
Overhead Power (large)	1285+00	_
Overhead Power (large)	1286+00	_
Fiber Optic	1495+20	_
10" San. Sewer (Force Main)	1539+00	_
Fiber Optic	1539+10	_
Fiber Optic	1540+10	_
18" San. Sewer (Force Main)	1542+40	_
Fiber Optic	1609+00	_
Fiber Optic	1715+15	_
Overhead Power (large)	1716+50	_
24" San. Sewer	1735+10	_
21" San. Sewer	1735+40	_
Fiber Optic	1774+50	_
30" Water	1835+75	_
Fiber Optic	1947+10	_
20" Water	1948+10	_
Fiber Optic	1948+50	_
Fiber Optic	1950+95	_
Fiber Optic	2008+50	_
Fiber Optic	2058+20	_

6.1.2 Certain Components of the Utility Adjustment Work

6.1.2.1 Coordination

Developer shall communicate, cooperate, and coordinate with TxDOT, the Utility Owners and potentially affected third parties, as necessary for performance of the Utility Adjustment Work. Developer shall be responsible for preparing (unless prepared by the Utility Owner) and securing execution (by Developer and the Utility Owner) of all necessary Utility Agreements.

All Utility Agreements must be approved by TxDOT prior to any utility adjustment construction related activity.

6.1.2.2 Betterments

Replacements for existing Utilities shall be designed and constructed to provide service at least equal to that offered by the existing Utilities, unless the Utility Owner specifies a lesser replacement. Utility Enhancements are not included in the Work; however, any Betterment work furnished or performed by Developer as part of a Utility Adjustment shall be deemed added to the Work, on the date the Utility Agreement providing for same becomes fully effective. Developer shall perform all coordination necessary for Betterments.

6.1.2.3 Protection in Place

Developer shall be responsible for Protection in Place of all Utilities impacted by the Project as necessary for their continued safe operation and structural integrity and to otherwise satisfy the requirements described in Section 6.2.1 (Standards). The Utility Owner must agree to all Protection in Place work that pertains to Utility Owner's facilities.

6.1.2.4 Abandonment and Removal

Developer shall make all arrangements and perform all work necessary to complete each abandonment or removal (and disposal) of a Utility in accordance with the requirements listed in Section 6.2.1 (Standards), including obtaining Governmental Approvals and consent from the affected Utility Owner and any affected landowner(s), or shall confirm that the Utility Owner has completed these tasks. Abandonment of Utilities in place shall require approval by TxDOT.

6.1.2.5 Service Lines and Utility Appurtenances

Whenever required to accommodate construction, operation, maintenance and/or use of the Project, Developer shall cause Service Line Adjustments and Utility Appurtenance Adjustments. The Service Lines shall have a definitive point of termination such as a meter or point of sale. On completion of these, Developer shall cause full reinstatement of the roadway, including reconstruction of curb, gutter, sidewalks, and landscaping, whether the Utility Adjustment Work is performed by the Utility Owner or by Developer.

6.1.3 Agreements Between Developer and Utility Owners

Except as otherwise stated in this Section 6 or in the Agreement, each Utility Adjustment shall be specifically addressed in a Project Utility Adjustment Agreement (PUAA) or in a Utility Adjustment Agreement Amendment (UAAA), as described elsewhere in this Section 6. Developer is responsible for preparing, negotiating (to the extent allowed by this Section 6), and obtaining execution by the Utility Owners, of all Utility Agreements, (including preparing all necessary exhibits and information about the Project, such as reports, Plans and surveys). A Utility Agreement is not required for any Utility Adjustment consisting solely of Protection in Place in the Utility's original location within the Project ROW, unless the Utility Owner is being reimbursed for costs incurred by it on account of such Protection

in Place. If no reimbursement is required to the Utility Owner, a Utility Joint Use Acknowledgement and set of plans detailing UAR compliance is required pertaining to the Protection in Place work.

6.1.3.1 Project Utility Adjustment Agreements (PUAA)

Developer shall enter into one or more PUAAs with each affected Utility Owner to define the design, material, construction, inspection, and acceptance standards and procedures necessary to complete Utility Adjustments, as well as to define Developer's and the Utility Owner's respective responsibilities for Utility Adjustment costs and Utility Adjustment activities such as material procurement, construction, inspection, and acceptance. A PUAA may address more than one Utility Adjustment for the same Utility Owner. Additional Utility Adjustments may be added to an existing PUAA by a Utility Adjustment Agreement Amendment (UAAA).

Developer shall prepare each PUAA using the standard form of TxDOT Project Utility Adjustment Agreement (Owner-Managed) or TxDOT Project Utility Adjustment Agreement (Developer-Managed), Attachment 6-1, Utility Forms. Developer shall not modify the standard forms except by approval of TxDOT.

Promptly following issuance of NTP1, Developer shall begin negotiations with each affected Utility Owner to reach agreement on one or more PUAAs. Developer shall finalize the necessary PUAAs with each affected Utility Owner within a reasonable time period after issuance of NTP1. Developer shall include any proposed changes to a standard form (other than filling in blanks specific to a particular Utility Owner) in a Utility Owner-specific addendum. Each PUAA (including the Utility Adjustment Plans attached thereto) shall be subject to TxDOT review and approval as part of a Utility Assembly.

Language modification to a PUAA shall be approved by TxDOT prior to the submission of a Utility Assembly.

6.1.3.2 Utility Adjustment Agreement Amendments

Except where Utility Adjustment Field Modifications are permitted pursuant to Section 6.4.7 (Utility Adjustment Field Modifications), modification of an executed PUAA or any component thereof, after it has been approved by TxDOT as part of a Utility Assembly, shall be stated in a Utility Adjustment Agreement Amendment (UAAA). A UAAA may be used only when the allocation of responsibility for the Utility Adjustment Work covered by that UAAA is the same as in the underlying Utility Agreement; otherwise, an additional PUAA will be required.

Each UAAA (including any Utility Adjustment Plans attached thereto) shall be subject to TxDOT's approval as part of a Supplemental Utility Assembly. Except as otherwise directed by TxDOT or provided in an applicable Utility Agreement, Developer shall prepare all UAAAs using the standard form included in Attachment 6-1, Utility Forms. Developer shall not modify the standard forms except by approval of TxDOT. Developer shall include any proposed changes to a standard form (other than filling in the blanks specific to a particular Utility Owner) in a Utility Owner specific addendum.

Language modification to a UAA shall be approved by TxDOT prior to the submission of the UAAA.

6.1.4 Recordkeeping

Developer shall maintain construction and inspection records in order to ascertain that Utility Adjustment Work is accomplished in accordance with the terms and in the manner proposed on the approved Utility Adjustment Plans and otherwise as required by the Contract Documents and the applicable Utility Agreement(s).

6.2 Administrative Requirements

6.2.1 Standards

All Utility Adjustment Work shall comply with all applicable Laws, Codes, Regulations and Technical Provisions of the Development Agreement, including the Utility Adjustment Standards, the TxDOT *Utility Manual*, Section 6.8 of the Agreement, and the requirements specified in this Section 6.

6.2.2 Communications

6.2.2.1 Communication with Utility Owners

Developer is responsible for holding meetings and otherwise communicating with each Utility Owner as necessary to timely accomplish the Utility Adjustments in compliance with the Contract Documents. TxDOT shall be notified of all meetings and will participate in these meetings if requested by the Utility Owner or Developer or otherwise as TxDOT deems appropriate.

Before distribution of any mass mailings to Utility Owners, Developer shall submit to TxDOT, 21 Days in advance of distribution, for its review and comment the form, content, and addressees of any such mass mailings. For purposes of this Section 6, the term "mass mailing" means correspondence that is sent to 50 percent or more of Utility Owners within a three-week time period, and contains substantially the same content with respect to each Utility Owner.

6.2.2.2 Meetings

At least three Business Days in advance of each scheduled meeting, Developer shall provide notice and an agenda for the meeting separately to TxDOT and, if necessary, to the appropriate Utility Owner. Developer shall prepare minutes of all meetings and shall keep copies of all correspondence.

Developer shall prepare meeting minutes within five Business Days after the conclusion of such meetings. At a minimum, Developer shall include the following items in the meeting minutes:

- A complete list of attendees (including their affiliations, telephone numbers, and e-mail addresses)
- Documentation of the issues discussed and any associated solutions
- Description of remaining open issues and action items (including the person(s) responsible for follow-up and target date for resolution)

Developer shall submit draft versions of all meeting minutes to TxDOT for review before distributing final versions to the meeting attendees and appropriate Customer Groups.

6.2.3 Utility Adjustment Team

Developer shall provide a Utility Adjustment team with appropriate qualifications and experience for the Utility Adjustment Work. Developer shall provide the names and contact details, titles, job roles, and specific experience of the team members in the PMP. Specifically, Developer shall provide a Utility Manager (UM) and a Utility Design Coordinator (UDC) and a Developer Utility Coordinator (DUC) as described herein.

The UM's primary work responsibility shall be the performance of all Developer's obligations with respect to Utility Adjustments. The Utility Manager shall have a bachelor's degree, and have at least four years of relevant experience in coordinating and solving complex utility adjustments on highway improvement projects. The Utility Manager should be authorized by the Developer to approve all financial and technical modifications associated with Utility Adjustments, and modifications to the Utility Agreement.

The UDC shall be a Registered Professional Engineer. The UDC shall be responsible for coordinating the Utility Adjustment design with the overall highway design features during the planning, design, and construction phases of the Work.

The DUC shall hold a bachelor's degree and have at least five years of relevant experience in ROW and Utility coordination activities involving large transportation projects. The DUC will be responsible for tracking and following the Developer's activities and communicating the progress to the Developer. The DUC will assist with developing good working relationships with the Utility Owners and assisting the Developer in all utility coordination matters.

6.2.4 Real Property Matters

Developer shall provide the services described below in connection with existing and future occupancy of property by Utilities.

6.2.4.1 Documentation of Existing Utility Property Interests -- Affidavits

For each Existing Utility Property Interest within the Project ROW claimed by any Utility Owner, Developer shall include an Affidavit of Property Interest in the applicable Utility Assembly, with documentation of the Existing Utility Property Interest (e.g., an easement deed) attached. Any such claim shall be subject to TxDOT's review as part of a Utility Assembly approval. Except as otherwise directed by TxDOT, Developer shall prepare all Affidavits of Property Interest using the standard forms included in Attachment 6-1, Utility Forms.

6.2.4.2 Acquisition of Replacement Utility Property Interests

Each Utility Owner will be responsible for acquiring any Replacement Utility Property Interests that are necessary for its Utility Adjustments. Developer shall have the following responsibilities for each acquisition:

1. Developer shall coordinate with, and provide the necessary information to each Utility Owner as necessary for the Utility Owner to acquire any Replacement Utility Property Interests required for its Utility Adjustments.
2. If any of Developer-Related Entities assists a Utility Owner in acquiring a Replacement Utility Property Interest, such assistance shall be by separate contract outside of the Work, and Developer shall ensure that the following requirements are met:
   a) The files and records must be kept separate and apart from all acquisition files and records for the Project ROW.
   b) The items used in acquisition of Replacement Utility Property Interests (e.g., appraisals, written evaluations and owner contact reports) must be separate from the purchase of the Project ROW.
   c) Any Developer-Related Entity personnel negotiating the acquisition of Replacement Utility Property Interests must be different from those negotiating the acquisition of Project ROW.

Developer is not responsible for Utility Owner condemnation proceedings.

6.2.4.3 Relinquishment of Existing Utility Property Interests

Developer shall cause the affected Utility Owner to relinquish each Existing Utility Property Interest within the Project ROW, unless the existing Utility occupying such interest is either (i) remaining in its original location or (ii) being reinstalled in a new location still subject to such interest.

6.2.4.4 Quitclaim Deeds

Except as otherwise directed by TxDOT, Developer shall prepare a Quitclaim Deed for each relinquishment of an Existing Utility Property Interest using TxDOT's standard form included in Attachment 6-1, Utility Forms. Each Quitclaim Deed shall be subject to TxDOT's review as part of a Utility Assembly approval as described below.

Developer understands and expects that a Utility Owner will not relinquish any Existing Utility Property Interest until after the Utility Adjustment has been accepted by the Utility Owner in its new location. Accordingly, instead of an executed Quitclaim Deed, the Utility Assembly for such a Utility Adjustment shall include a letter signed by the Utility Owner's authorized representative confirming that the interest will be quitclaimed upon completion of the Utility Adjustment, and a copy of the unsigned Quitclaim Deed. In these cases, Developer shall obtain the executed Quitclaim Deed within 90 Days of completion of the Utility Adjustment or unless otherwise approved by TxDOT in writing. The Quitclaim Deed must be approved by TxDOT prior to recording.

6.2.4.5 Utility Joint Use Acknowledgements

Developer shall prepare a Utility Joint Use Acknowledgment (UJUA) for:

1. Each Utility proposed to be relocated within the Project ROW
2. Each Utility proposed to remain in its existing location within the Project ROW
3. Any Existing Utility Property Interest located within the Project ROW that is not required to be relinquished pursuant to Section 6.2.4.3 (Relinquishment of Existing Utility Property Interests), and is not addressed in the foregoing clause (a) or clause (b)

Developer shall prepare all Utility Joint Use Acknowledgments using TxDOT's standard form included in Attachment 6-1, Utility Forms. Developer also shall prepare all required documentation to be included with each Utility Joint Use Acknowledgment.

Developer shall arrange for the Utility Owner to execute each Utility Joint Use Acknowledgment. Each Utility Joint Use Acknowledgment (executed by the Utility Owner) shall be subject to TxDOT's approval as part of a Utility Assembly.

6.2.4.6 Documentation Requirements

Developer shall prepare, negotiate (to the extent permitted by this Section 6.2.4 (Real Property Matters), and obtain execution by the Utility Owner of (and record in the appropriate jurisdiction, if applicable) all agreements and deeds described in this Section 6.2.4, including all necessary exhibits and information concerning the Project (e.g., reports, Plans, and surveys). Each agreement or deed shall identify the subject Utility(ies) by the applicable Utility Assembly Number, and shall also identify any real property interests by parcel number or highway station number, or by other identification acceptable to TxDOT.

6.3 Design

6.3.1 Developer's Responsibility for Utility Identification

Developer bears sole responsibility for ascertaining, at its own expense, all pertinent details of Utilities located within the Project ROW or otherwise affected by the Project, whether located on private property or within an existing public ROW, and including all Service Lines.

Developer shall prepare and submit to TxDOT, no later than 90 days after NTP2 or 30 days before the first assembly package is submitted, a Utility Strip Map showing the information obtained and/or

confirmed pursuant to this Section 6.3.1. Developer's Utility Strip Map shall show in plan view all Utilities within the Project ROW or otherwise impacted by the Project, in each case detailing the type of Utility facility (communication, gas, oil, water, etc.) size, material and the Utility Owner's name and contact information. The scale of the Utility Strip Map shall be 1"=100'. Developer shall update the information provided in the Utility Strip Map with SUE data and shall submit the same to TxDOT in accordance with the PMP.

6.3.2 Technical Criteria and Performance Standards

All design plans for Utility Adjustment Work, whether furnished by Developer or by the Utility Owner, shall be consistent and compatible with the following:

a) The applicable requirements of the Contract Documents, including Section 6.2.1 (Standards)
b) The Project as initially designed
c) Any Utilities remaining in, or being installed in, the same vicinity
d) All applicable Governmental Approvals
e) Private approvals of any third parties necessary for such work

6.3.3 Utility Adjustment Concept Plans

Developer shall prepare a proposed conceptual Utility design (a Utility Adjustment Concept Plan) for the Project (or proposed Utility Adjustment Concept Plans for various segments of the Project), as appropriate), showing the approximate location of each existing Utility, the existing Utilities to remain proposed location of each Utility and Developer's Utility Adjustment recommendations.

In accordance with the PMP, Developer shall submit the proposed Utility Adjustment Concept Plans(s) to TxDOT for its review. The Utility Adjustment Concept Plan(s) shall be submitted in both tabular and plan formats. The plan(s) shall be color-coded and shall utilize a scale that clearly depicts all of the required information. Developer shall coordinate with the affected Utility Owners as necessary to obtain their respective concurrence with the Utility Adjustment Concept Plan(s) as initially submitted to TxDOT and with any subsequent revisions. The Utility Adjustment Concept Plan is a working document. Developer must update the Utility Adjustment Concept Plan as the Work progresses.

6.3.4 Utility Adjustment Plans

Utility Adjustment Plans, whether furnished by Developer or by the Utility Owner, shall be signed and sealed by a Registered Professional Engineer (PE) per governmental regulations and industry practice.

6.3.4.1 Plans Prepared by Developer

Where Developer and the Utility Owner have agreed that Developer will furnish a Utility Adjustment design, Developer shall prepare and obtain the Utility Owner's approval of plans, specifications, and cost estimates for the Utility Adjustment (collectively, "Utility Adjustment Plans") by having an authorized representative of the Utility Owner sign the plans as "reviewed and approved for construction." The Utility Adjustment Plans (as approved by the Utility Owner) shall be attached to the applicable Utility Agreement, which Developer shall include in the appropriate Utility Assembly for TxDOT's approval.

Unless otherwise specified in the applicable Utility Agreement(s), all changes to Utility Adjustment Plans previously approved by the Utility Owner (excluding estimates, if the Utility Owner is not responsible for any costs) shall require written Utility Owner approval. Developer shall transmit any TxDOT comments to the Utility Owner, and shall coordinate any modification, re-approval by the Utility Owner and re-submittal to TxDOT as necessary to obtain TxDOT's approval.

6.3.4.2 Plans Prepared by the Utility Owner

For all Utility Adjustment Plans to be furnished by a Utility Owner, Developer shall coordinate with the Utility Owner as necessary to confirm compliance with the applicable requirements as referenced in Section 6.2.1. Those Utility Adjustment Plans shall be attached to the applicable Utility Agreement, which Developer shall include in the appropriate Utility Assembly for TxDOT's approval. Developer shall transmit any TxDOT comments to the Utility Owner, and shall coordinate any modification, review by Developer and re-submittal to TxDOT as necessary to obtain TxDOT's approval.

6.3.4.3 Design Documents

Each proposed Utility Adjustment shall be shown in the Design Documents, regardless of whether the Utility Adjustment Plans are prepared by Developer or by the Utility Owner.

6.3.4.4 Certain Requirements for Underground Utilities

Casing as specified in the ~~Utility Accommodation Rules (UAR)~~UAR shall be used for all underground Utilities crossing the Project ROW. However, high-pressure gas and liquid petroleum pipelines may be allowed to cross the Project ROW without steel casing as long as the requirements of the ~~Utility Accommodation Rules~~UAR are met. All high-pressure gas pipelines within the Project ROW shall comply with a design factor "F" = 0.6 or less as required by the class location of the pipeline. The Utility Owner is required to submit or approve the Barlows calculation(s) in writing to be included in the Utility Assembly.

6.3.4.5 Utility Assemblies

Each Utility Adjustment in addition to each Utility remaining in place in the Project ROW and not requiring any Protection in Place or other Utility Adjustment shall be addressed in a Utility Assembly prepared by Developer and submitted to TxDOT for its review and comment, and for TxDOT's approval of any items for which this Section 6 requires TxDOT's approval. Temporary Adjustments that are installed within the Project ROW must also be included with an assembly for TxDOT's prior approval unless TxDOT waives or allows other approval methods concerning Temporary Adjustments. Each Utility Adjustment shall be addressed in a full Utility Assembly, unless it is appropriate for a Supplemental Utility Assembly or Abbreviated Utility Assembly, as described below. Developer shall coordinate with the Utility Owner to prepare all components of each Utility Assembly. Completion of the review and comment process for the applicable Utility Assembly, as well as issuance of any required TxDOT approvals, shall be required before the start of construction for the affected Utility Adjustment Work.

Provisions governing the procedure for and timing of Utility Assembly submittals are in Section 6.5 (Deliverables).

All Utility Adjustments covered by the same initial PUAA can be addressed in a single full Utility Assembly.

Each set of the required Utility Assembly shall include the following:

a) A transmittal memo recommending approval and detailing any unique characteristics or information pertaining to the adjustment.

b) A completed Utility Assembly Checklist.

c) A TxDOT approved Utility Adjustment Agreement.

d) Plans which:

1. Show the existing and proposed Utility facilities,
2. Show existing and proposed grades for all utility crossings,
3. Show the existing and Project ROW lines along with the Control of access denial line,
4. Show an offset distance from the Project ROW line to all longitudinal Utilities within the Project ROW.
5. Present sufficient information to enable TxDOT to verify compliance with the UAR requirements for each Utility located within the Project ROW, including highway design features.
6. Are folded to 8.5" x 11" size unless waived by TxDOT.

e) Estimate(s) from the Utility Owner (and also from Developer, where Developer is furnishing design and/or performing construction), which estimates shall, without limitation, detail material type and quantity (material quantities detailed on the estimates must correlate to the materials shown on the plans described in (d) above. The estimate must list the estimated amount of reimbursement to the Utility Owner, taking into consideration the betterment credit calculation, salvage credit and any applicable eligibility ratio.

f) A proposed Utility Joint Use Acknowledgement

g) Statement of Work form, if applicable

h) Affidavit(s) of Property Interest form (With property interest instrument of conveyance attached), if applicable; and

j) A ROW map showing the existing and proposed utility facilities identified on a plan view. This ROW map will only be required to be included with TxDOT's copy of the Utility Assembly.

k) All utility no conflict sign off forms.

Utility Adjustment Amendment Agreements (UAAA). For each UAAA, Developer shall prepare an additional Utility Assembly for the relevant initial PUAA (an Assembly), covering all Utility Adjustments addressed in the UAAA. The UAAA Assembly shall contain a transmittal memo, Utility Assembly Checklist, proposed UAAA cost estimate, a proposed UAAA which has been executed by the Utility Owner and Developer (one original in each of the two original Supplemental Utility Assemblies), including all required attachments, and applicable revisions to the Utility Adjustment Plans, as well as Utility Joint Use Acknowledgement(s) and Affidavit(s) of Property Interest, if applicable. The transmittal memo shall briefly describe the desired amendment and explain why the amendment is necessary including an estimated construction start date and duration. Each of the foregoing items shall comply with the requirements for same described in Attachment 6.2, Utility Assembly and Tracking Report Requirements.

Abbreviated Utility Assemblies. Developer shall prepare an Abbreviated Utility Assembly for each Utility proposed to remain at its original location within the Project ROW that is not required to be addressed in a PUAA or UAAA, unless an Adjustment is required pursuant to Section 6.1.1. If Developer is reimbursing the Utility Owner any of its costs, a PUAA or UAAA is required. Each Abbreviated Utility Assembly shall contain a transmittal memo recommending that the subject Utility(ies) remain in place, a completed Utility Assembly Checklist, a certification from the Utility Owner approving leaving the Utility(ies) in place, as well as Utility Joint Use Acknowledgement(s) and Affidavit(s) of Property

Interest, if applicable. Each of the foregoing items shall comply with the requirements for same described in Attachment 6-1, Utility Forms.

6.4 Construction

6.4.1 Reserved

6.4.2 General Construction Criteria

All Utility Adjustment construction performed by Developer shall conform to the requirements listed below. In addition, Developer is responsible for verifying that all Utility Adjustment construction performed by each Utility Owner conforms to the requirements described below. In case of nonconformance, Developer shall cause the Utility Owner (and/or its contractors, as applicable) to complete all necessary corrective work or to otherwise take such steps as are necessary to conform to these requirements.

a) All criteria identified in Section 6.3.2 (Technical Criteria and Performance Standards)

b) The Utility Adjustment Plans included in the Utility Agreement approved by TxDOT (other than Utility Adjustment Field Modifications complying with Section 6.4.7 (Utility Adjustment Field Modifications)

c) All Project safety and environmental requirements

d) All pre-construction meeting requirements

e) The ROW acquisition schedule described in Section 7 (ROW)

f) Utilities standards provided in the Utility Agreement

6.4.3 Inspection of Utility Owner Construction

Developer shall set forth procedures in the PMP for inspection of all Utility Adjustment Work performed by Utility Owners (and/or their contractors) to verify compliance with the applicable requirements described in Section 6.4.2 (General Construction Criteria). Developer is responsible for Quality Control and Quality Assurance for all Work performed by the Utility Owners and/or their contractors.

6.4.4 Scheduling Utility Adjustment Work

The Utility Adjustment Work (other than construction) may begin at any time following issuance of NTP1. Refer to Section 4.4.2 of the Development Agreement for the conditions to commencement of Utility Adjustment construction work by Developer. Developer shall not arrange for any Utility Owner to begin any demolition, removal, or other construction work for any Utility Adjustment until all of the following conditions are satisfied:

a) The Utility Adjustment is covered by an executed Utility Agreement (and any conditions to commencement of such activities that are included in the Utility Agreement have been satisfied);

b) Pre-construction meeting, in accordance with Section 6.2.2.2, shall be required after execution of the Utility Agreement and prior to commencement of any construction activities, unless otherwise approved by TxDOT.

c) Availability and access to affected Replacement Utility Property Interests have been obtained by the Utility Owner (and provided to Developer, if applicable);

d) If any part of the Utility Adjustment construction work that will affect the Project ROW, availability and access to that portion of the Project ROW has been obtained in accordance with the applicable requirements of the Contract Documents.

e) If applicable, the Alternate Procedure List has been approved by FHWA, and either (a) the affected Utility is on the approved Alternate Procedure List, as supplemented, or (b) the Utility Owner is on the approved Alternate Procedure List, as supplemented.

f) The review and comment process has been completed and required approvals have been obtained for the Utility Assembly covering the Utility Adjustment.

g) All Governmental Approvals necessary for the Utility Adjustment construction have been obtained, and any pre-construction requirements contained in those Governmental Approvals have been satisfied.

h) All other conditions to that Work stated in the Contract Documents have been satisfied.

6.4.5 Standard of Care Regarding Utilities

Developer shall carefully and skillfully carry out all Work impacting Utilities and shall mark, support, secure, exercise care, and otherwise act to avoid damage to Utilities. At the completion of the Work, the condition of all Utilities shall be at least as safe and permanent as before.

6.4.6 Emergency Procedures

Developer shall provide Emergency procedures with respect to Utility Adjustment Work in the PMP. Developer shall obtain Emergency contact information from, and establish Emergency procedures with each Utility Owner in the event of rupture, break, or damage to Utility Owner's Utility facilities.

6.4.7 Utility Adjustment Field Modifications

Developer shall establish a procedure to be followed if a Utility Adjustment Field Modification is proposed by either Developer or a Utility Owner, after the Utility Assembly (which includes the Utility Adjustment Plans) has been approved. The procedure shall contain, at minimum, the following processes:

a) The Utility Owner's review and approval of a Utility Adjustment Field Modification proposed by Developer, or Developer's review and approval of a Utility Adjustment Field Modification proposed by the Utility Owner. The UAFM shall have approval prior to commencement of construction. All revisions shall be signed and sealed by a PE and formally submitted to TxDOT for review and approval;

b) Transmittal of Utility Adjustment Field Modifications to the appropriate construction field personnel;

c) Inclusion of any Utility Adjustment Field Modifications in the Record Drawings for the Project.

Developer shall cause the procedure to be followed for all Utility Adjustment Field Modifications, whether the construction is performed by Developer or by the Utility Owner.

6.4.8 Switch Over to New Facilities

After a newly Adjusted Utility has been accepted by the Utility Owner and is otherwise ready to be placed in service, Developer shall coordinate with the Utility Owner regarding the procedure and timing for placing the newly Adjusted Utility into service and terminating service at the Utility being replaced.

6.4.9 Record Drawings

Developer shall provide Record Drawings to each Utility Owner for its Adjusted Utilities, in accordance with the applicable Utility Agreement(s).

Developer shall provide Record Drawings to TxDOT (regardless of whether design and/or construction of the subject Utilities was furnished or performed by Developer or by the Utility Owner). These drawings shall show the location of, and label as such, all abandoned Utilities, shall show and label all other Utilities, whether remaining in place or relocated, located within the Project ROW or otherwise impacted by the Project, and shall otherwise comply with Section 2 (Project Management). Developer shall provide the Record Drawings for each Adjustment to TxDOT not later than 90 Days after Utility Owner acceptance as defined in the Utility Agreement, the Adjustment or before such earlier deadline as is specified elsewhere in the Contract Documents.

6.4.10 Maintenance of Utility Service

All Utilities shall remain fully operational during all phases of construction, except as specifically allowed and approved in writing by the Utility Owner. Developer shall schedule Utility Adjustment Work in order to minimize any interruption of service, while at the same time meeting the Project Schedule and taking into consideration seasonal demands. Each Utility Adjustment or remain in place location must allow for adequate access to the Utility facility that is agreed to by the Utility Owner.

6.4.11 Traffic Control

Developer shall be responsible for the Traffic Management Plan. The Traffic Management Plan shall cover, all traffic control made necessary by for Utility Adjustment Work, whether performed by Developer or by the Utility Owner. Traffic control for Adjustments shall be coordinated with, and subject to approval by, the local agency(ies) with jurisdiction. Traffic control shall comply with the guidelines of the TMUTCD and of Section 18 (Traffic Control).

6.5 Deliverables

Developer shall time all submittals described in this section to meet the Project Schedule, taking into account the maximum number of submittals set forth in this Section 6.5 or, if not stated therein, then as stated in Section 3.1 of the Development Agreement. All deliverables shall conform to the standards required in the Project Management Plan.

6.5.1 Maximum Number of Submittals

Developer shall coordinate all Submittals required pursuant to this Section 6.5, so as not to overburden TxDOT's staff and consultants. In each calendar week, Developer shall not submit more than:

a) Two Utility Assemblies (excluding Supplemental or Abbreviated Utility Assemblies); and

b) Two of any documentation constituting any of the following:

- A modified or additional item submitted in response to TxDOT comments on a particular Utility Assembly
- A Quitclaim Deed
- Any other type of relinquishment document; and

c) Two Supplemental Utility Assemblies; and

d) Two Utility Adjustment Agreements, Amendment Assemblies.

Where the number of Submittals exceeds these limits, the Submittals shall be considered excess and TxDOT may defer its review of any such excess Submittals to a subsequent calendar week (or weeks), as necessary.

6.5.2 Developer's Utility Tracking Report

Developer shall maintain a Utility Tracking Report in tabular form, listing all Utilities located within the Project ROW or otherwise potentially affected by the Project. Developer shall submit the Utility Tracking Report to TxDOT on a monthly basis in the format described below unless otherwise approved by TxDOT. The Utility Tracking Report shall, at a minimum, contain the following information for each utility:

a) The name of the Utility Owner and a unique tracking number starting with the prefix "Highway U-" followed by a four digit number starting with 500- to be assigned by the Developer;

b) Utility size and type;

c) Location of the Utility based upon station and offset;

d) The proposed method of treatment;

e) State whether the adjustment will be Owner or Developer Managed;

f) Dates on which the PUAA/UAAA was executed by TxDOT, Utility Owner, Developer;

g) Dates on which the UJUA was executed by the Utility Owner and TxDOT;

h) The Utility Owner's existing right of occupancy of the right of way for each Utility (e.g. UJUA, permit, easement or combination);

i) Whether any Replacement Utility Property Interest will be necessary;

j) Estimated cost approved in the PUAA or UAAA;

k) Amounts and dates of payments made by the Developer to the Utility Owner, listing in each case the type of payment (final, partial or lump sum);

l) Scheduled start and completion date for construction of each adjustment;

m) Percent complete of construction;

n) Whether any betterment is included in the adjustment

The Utility Tracking Report shall also include a separate section for Replacement Utility Property Interest including each necessary Replacement Utility Property Interest with the names of property owners or parcel number(s), Utility Assembly Numbers, status of the acquisition, acquisition cost, and other information as necessary. Developer shall maintain this section of the Utility Tracking Report and submit to TxDOT in the same manner as all other portions of the Utility Tracking Report.

6.5.3 Utility Assembly Submittals

The following procedure shall govern submittal and review of each Utility Assembly, including Supplemental and Abbreviated Utility Assemblies:

a) Before submitting a Utility Assembly to TxDOT, Developer shall:

- Verify that each subject Utility (or the Utility Owner) is on the approved Alternate Procedure List, if applicable;

- Submit the complete Utility Assembly to the quality control/quality assurance entity designated by Developer in accordance with the PMP; and
- Resolve all comments made by the quality control/quality assurance entity, coordinating with the Utility Owner as appropriate.

b) Developer shall submit to TxDOT three identical and complete originals of each Utility Assembly, each of which shall be bound and labeled "Developer Copy," "TxDOT Copy," or "Utility Owner Copy," as appropriate. The "TxDOT Copy" shall be color coded and shall include the Project ROW map with the existing and proposed Utility facilities identified on a plan view. These submittals shall be for TxDOT's review and comment, except for any components of the Utility Assembly for which TxDOT's approval is required by this Section 6.5.

TxDOT will review the Utility Assembly for compliance with the requirements of this Section 6.5.3, and within ten (10) Business Days will return the Utility Assembly to Developer with the appropriate notations pursuant to Section 3.1.5 of the Development Agreement to reflect its responses. Developer shall transmit any TxDOT comments to the Utility Owner, and shall coordinate any modification, review and approval by the Utility Owner and re-submittal to TxDOT, as necessary to resolve all TxDOT comments and/or obtain TxDOT's approval, as applicable. Upon (a) TxDOT's approval of any Utility Assembly components for which TxDOT's approval is required, and (b) completion of the review and comment process for all other Utility Assembly components, TxDOT will sign three originals of any approved UJUA and of any other components of the Utility Assembly for which this Section 6 requires TxDOT's signature.

6.5.4 FHWA Alternate Procedure

The Developer will develop the Alternate Procedure List that includes the utility owner's name, approximate station numbers and estimated cost. TxDOT will then submit to the FHWA the Alternate Procedure List in order to obtain FHWA authorization for federal reimbursement Promptly upon determining that any additional Utility Owner not referenced on the Alternative Procedure List is impacted by the Project, Developer shall submit to TxDOT all documentation as referenced above in order to update the Alternative Procedure List.

TxDOT will forward the approved Alternate Procedure List (and any amendments thereto) to Developer, promptly upon receipt of same from the FHWA.

7 RIGHT-OF-WAY (ROW)

7.1 General Requirements

Developer's obligations in respect of the acquisition of Project ROW are set forth in Section 6.1 of the Development Agreement.

This Section 7 sets forth the ROW activities assigned to Developer, including pre-acquisition and acquisition activities, and designates which ROW activities TxDOT will conduct. This section also sets forth the requirements applicable to the Work assigned to Developer related to the acquisition of Project ROW. Developer shall provide all services necessary to acquire title to the Project ROW, in form and substance acceptable to TxDOT, in the name of the State; relocation of displaces; and clearance/demolition of the improvements from the Project ROW, as more fully described in the following sub-sections.

Except as otherwise set forth in the Agreement, Developer's Project ROW staff and/or Subcontractors will function as independent contractors while acquiring Project ROW, and not as an agent, representative, or employee of TxDOT.

If Developer obtains a Property Agreement to facilitate design, construction or maintenance in relation to the Project, Developer shall provide a copy of the agreement to TxDOT.

7.2 Administrative Requirements

7.2.1 Standards

Project ROW shall be acquired in accordance with State and federal Law and the practices, guidelines, procedures, and methods contained in the following as it pertains to Right of Way:

a) TxDOT *Right of Way Manual* Collection (available online at http://onlinemanuals.txdot.gov/manuals)

b) TxDOT *Access Management Manual* (available online at http://onlinemanuals.txdot.gov/manuals)

c) TxDOT *Survey Manual*

d) TxDOT *Appraisal and Review Manual*

Pursuant to the applicable federal regulations, Developer shall (i) acquire ROW parcels for the Project on behalf of the State, but without the direct participation of TxDOT, subject to TxDOT's rights of review, approval, and audit; (ii) certify acceptance of the TxDOT *Right of Way Manual*; (iii) provide adequate access to all occupied properties; (iv) maintain Utility service to occupied properties until relocation is complete; and (v) not permit open burning within 1000 feet of an occupied dwelling.

Developer shall maintain a complete and current set of the TxDOT *Right of Way Manual* Collection, Volumes 1 through 8 (available online at http://onlinemanuals.txdot.gov/manuals), TxDOT *Access Management Manual*, TxDOT *Appraisal and Review Manual*, and a current approved Project ROW map for public use. Any TxDOT forms referenced in this section shall be found in the TxDOT *Right of Way Manual* Collection or will be provided by TxDOT.

All Project ROW activities must be completed and documented in compliance with all applicable Laws, including the Uniform Act, and the rules and regulations implementing the Uniform Act.

7.2.2 Software Requirements

Developer shall employ software that is fully compatible with the software in use by TxDOT, or fully transferable to TxDOT's systems. Developer must supply and maintain a web-based, parcel-by-parcel database that incorporates the fields and information required by TxDOT's approved ROW tracking system: ROWIS. Developer must maintain and participate in any other required ROW tracking system required by the Contract Documents or otherwise agreed to by the parties. The database shall be fully accessible to Persons authorized by TxDOT.

7.2.3 ROW Acquisition Plan

Developer shall prepare a ROW Acquisition Plan in accordance with the requirements of this Section 7 and Section 2 (Project Management). The ROW Acquisition Plan shall set forth Developer's organization including names, titles and qualifications of Key Personnel, and other Project ROW personnel, integration of the Project ROW schedule into the Project Schedule, interface between design and Project ROW activities, documentation and reporting, quality control procedures and quality review standards.

The ROW Acquisition Plan shall contain, as a minimum, the following:

a) The name of TxDOT approved title company(ies) to be used for title services

b) The name and qualifications of the proposed ROW Acquisition Manager (ROW AM)

c) The resumes and qualifications for appraisers, appraisal reviewers, land planners, relocation agents, negotiators, real estate attorneys, eminent domain specialist and ROW personnel who shall have the minimum qualifications and experience specified in Section 7.2.7

The ROW Acquisition Plan shall establish the specific means by which Developer will:

a) Provide sufficient personnel to achieve, in accordance with the Project Schedule, the goals and milestones established for Project ROW acquisition, relocation assistance, appraisals and appraisal review, and clearance/demolition of the improvements from the Project ROW.
b) Provide administrative support.
c) Provide for Spanish, visually impaired, or hearing impaired translation, as necessary.
d) Provide documentation and reports.
e) Produce and distribute acquisition and relocation brochures as approved by TxDOT.
f) Establish, implement, and maintain quality control procedures and quality review standards for the acquisition for Project ROW.
g) Prevent fraud, waste, and mismanagement.

Developer shall update the ROW Acquisition Plan regularly, at least quarterly, in accordance with the Contract Documents.

7.2.4 Schedule and Review Procedures

The Project Schedule shall indicate the date to begin the acquisition of the Project ROW and the anticipated completion date of acquisition activities for each parcel. TxDOT shall be advised of all Additional Properties and temporary rights or interests in real property to be acquired by Developer. In developing the Project Schedule, Developer will give priority to the acquisition of parcels that have significant impact on the Project Schedule and/or affect the Critical Path as so indicated. The monthly status reports required by Section 2.1.1 shall provide updated projections for the acquisition date of each parcel.

In developing the Project Schedule, Developer shall incorporate adequate time periods for TxDOT review and approval of Acquisition Packages. TxDOT intends to review the completed Acquisition Packages as expeditiously as possible; however, for the purposes of the Project Schedule, Developer shall assume that the reviews performed by TxDOT will require ten (10) Business Days for Acquisition Packages that Developer submits as final and complete in accordance with Section 7.3.6 (Project ROW Acquisition Package Approval), up to a maximum of twenty-five (25) Acquisition Packages. Any Submittals that would require TxDOT to review more than twenty-five (25) Acquisition Packages within any given ten (10) Business Day period shall be considered excess, and TxDOT may defer its review of any such Acquisition Packages to a subsequent ten (10) Business Day period (or periods as necessary). TxDOT will notify Developer of its election to defer any excess Acquisition Packages within ten (10) Business Days after receipt. The balance of Acquisition Packages in excess of twenty-five (25) will be rolled over to the next ten (10) Business Day period and added to the Acquisition Package Submittals made by Developer in that period. When Developer submits more than ten (10) Acquisition Packages at any given time, Developer shall indicate the priority of review.

If TxDOT notifies Developer that any submitted Acquisition Package has a deficiency, Developer shall correct such deficiency and resubmit the package to TxDOT. Resubmissions shall be treated as a new Acquisition Package as described above. An Acquisition Package shall be deficient, as determined by TxDOT, if any of its components fails to meet any of the criteria established by this section for such component, or contains any material errors or omissions. Schedule delays resulting from inadequate or incomplete submissions of Acquisition Packages shall be the responsibility of Developer and will not be eligible for treatment as a Change Order.

TxDOT reserves the right to undertake additional review on Acquisition Packages that contain or identify facts or issues of an unusual nature or which do not clearly fit within TxDOT standards and will notify Developer in writing that the review period will be extended by an additional ten Business Days before rendering a decision to Developer.

Developer may request TxDOT to do a preliminary review of the survey and appraisal before the complete Acquisition Package is submitted. TxDOT shall review the preliminary submission of the survey and appraisal and notify Developer of any deficiencies within ten Business Days after TxDOT's receipt of such preliminary submission.

7.2.5 Developer's Project ROW Scope of Services

Developer shall complete all administrative activities and prepare all documentation sufficient for Developer to acquire the Project ROW. Developer shall obtain TxDOT's review and prior written approval of all Project ROW maps and surveys, appraisals, legal descriptions, acquisition documentation, purchase price, requests to acquire Project ROW, condemnation-related activities, and funding/closing procedures. TxDOT will (i) approve and return the Project ROW acquisition documentation, (ii) provide review comments for incorporation by Developer in accordance with Section 7.2.4 (Schedule and Review Procedures), or (iii) in the case of an Acquisition Package that is deficient, notify Developer of the deficiency(ies) to be corrected by Developer in accordance with Section 7.2.4 (Schedule and Review Procedures). Except as otherwise authorized by applicable State and federal policy and regulations for early acquisition and approved by TxDOT, Developer shall not proceed with acquisition of the Project ROW until the NEPA Approval is issued, public involvement procedures have been completed, and ROW maps and legal descriptions for the applicable constructible segment as established by the logical termini of the Project have been prepared and approved by TxDOT. TxDOT will provide a separate release for each approved segment. Further, Developer shall not commence any negotiations with

landowners nor will TxDOT begin eminent domain procedures until the specific Acquisition Package for that particular parcel is approved by TxDOT.

If Developer and the landowner cannot negotiate an agreed-upon purchase price, acceptable to TxDOT, TxDOT will commence acquisition of the property through eminent domain procedures. Developer shall not be permitted to commence any condemnation action through the statutory "Declaration of Taking" procedure without the express written consent of TxDOT. Consent may be withheld in TxDOT's sole and absolute discretion.

Developer shall not begin construction on any parcel of real estate unless property rights for the parcel have been conveyed and recorded in favor of TxDOT, possession has been obtained through eminent domain or any other method as provided for in Section 7.2.1 (Standards), or a Possession and Use Agreement has been validly executed and delivered by all necessary parties in accordance with Section 7.4.1 (Project ROW Negotiations).

7.2.6 Acquisition Process Summary

Developer's major activities with respect to the acquisition of the Project ROW include:

a) Project ROW surveying and mapping

b) Project ROW budget estimates and updates

c) Title services

d) Appraisal services

e) Appraisal review

f) Negotiations

g) Closing services

h) Relocation assistance

i) Condemnation support services

j) Clearance and demolition of Project ROW

k) Environmental due diligence

l) Documentation and document control

m) Progress reports

n) Project ROW administration and management

o) Project ROW quality management

p) Letter from Developer's design engineer certifying that the required Project ROW acquisition is necessary and that any proposed alternatives are not feasible or are cost prohibitive

q) Obtaining rights of entry, as necessary

7.2.7 ROW Personnel Qualifications

Developer's ROW Acquisition Manager shall have at least five years experience managing the acquisition of transportation ROW projects for a condemning authority, be licensed as a real estate salesman or broker pursuant to the *Texas Real Estate License Act* or rules established by the Texas Real Estate Commission, be familiar with appraisal and appraisal report review pursuant to the Uniform

Standards of Professional Appraisal Practice (USPAP), and be familiar with the Uniform Act and applicable Laws of the State of Texas.

Quality Control Specialist(s) – Developer shall designate a specific person(s) responsible for internal quality control and quality assurance. This individual will review all Developer deliverables associated with survey, title, appraisal, acquisition, relocation and eminent domain prior to the deliverable being delivered to TxDOT for review.

Appraiser and Appraisal Reviewer – Each appraiser and appraisal reviewers shall be licensed and certified in the State of Texas and shall have a minimum of five years experience in appraising real property for eminent domain purposes, including partial taking appraisal, partial taking appraisal review and expert witness testimony. He or she must also have been actively and continuously engaged for at least three years immediately preceding his or her selection for this Project in appraisal work primarily in ~~Harris~~Dallas and ~~Montgomery~~Denton Counties, or as approved by TxDOT. The appraisers and the appraisal reviewers shall have separate and distinct duties, and appraisers must be employed by different firms from the appraisal reviewers. Each appraiser shall be required to submit three samples of previous appraisal work prepared for eminent domain purposes. All appraisers preparing and signing appraisals must be approved by TxDOT before performing any appraisals on the Project. If required by TxDOT, the appraiser will be required to demonstrate his/her skills at expert witness testimony.

Land Planner - Each land planner shall have a minimum of five years experience in land planning including experience with expert witness testimony in eminent domain proceedings. He or she must also have been actively and continuously engaged for at least three years immediately preceding his or her selection for this Project in land planning work primarily in ~~Harris~~Dallas and ~~Montgomery~~Denton Counties or as approved by TxDOT. Developer shall provide a minimum of two land planners to assist appraisers and complete land plans.

Relocation Agent - Each relocation agent shall have a minimum of three years experience in relocation assistance for ROW projects pursuant to the Uniform Act. A relocation agent's responsibilities shall include the following: Determination of eligibility of all displacees, contacting all displacees and informing them of their benefits, maintaining a file of all documentation concerning the relocation of the displacees, and extending all relocation assistance advisory services.

Negotiator - Each ROW negotiator shall be licensed either as a real estate sales person or broker pursuant to the *Texas Real Estate License Act* or rules established by the Texas Real Estate Commission, and shall be familiar with appraisal and appraisal report review pursuant to the USPAP. The negotiator shall have a minimum of three years experience in right of way negotiations. The ROW negotiator's responsibilities shall include the following: contact with property owners on the Project to discuss the acquisition of property needed for the Project, maintaining complete and accurate files of all transactions and contacts with the property owners and/or their representatives, and actively working toward a joint resolution to acquire the property with the property owner.

Eminent Domain Specialist – Each eminent domain specialist shall have a minimum of 3 years experience with TxDOT procedures and policies as related to acquisition of property through the use of eminent domain. The eminent domain specialist must be well versed in all activities necessary with the acquisition of parcels through the TxDOT Eminent Domain process. This includes correctly completing all TxDOT forms including the ROW-E-49, filing the eminent domain forms, coordinating the hearing with all appropriate parties and ensuring that the Award of Special Commissioners is deposited into the registry of the Court and all notices sent to the appropriate parties.

Real Estate Attorney - Each real estate attorney shall be licensed by the State of Texas and shall have at least five years experience in title review and curative matters. The real estate attorney's responsibilities shall include coordinating and clearing all title issues, and compliance assistance with State and federal acquisition requirements for the properties acquired for the Project.

ROW personnel shall have at least three years experience in title review and curative matters. ROW personnel's responsibilities shall include, but not be limited to the following: maintain complete and accurate files of all transactions and contacts with the property owners and/or their representatives, coordinate and clear all title issues and assist at closing for properties acquired for the Project.

7.2.8 Developer Conflict of Interest

If at any time, Developer or to the best of Developer's knowledge, any Developer-Related Entity directly or indirectly (i) acquires or has previously acquired any interest in real property likely to be parcels of the Project ROW or the remainders of any such parcels; (ii) loans or has previously loaned money to any interest holder in any real property likely to be a Project ROW parcel and accepts as security for such loan the parcel, or the remainder of any such parcel that is not a whole acquisition, or (iii) purchases or has previously purchased from an existing mortgagee the mortgage instrument that secures an existing loan against real property likely to be a Project ROW parcel, or the remainder of any such parcel, Developer shall promptly disclose the same to TxDOT. In the case of acquisitions, loans or mortgage purchases that occurred prior to the execution of the Agreement, such disclosure shall be made within ten days after execution of the Agreement.

In the event that Developer, or any subsidiary or parent company of Developer, acquires a real property interest, whether title or mortgage, in parcels of the Project ROW, the real property interest acquired or a release of mortgage as the case may be, shall be conveyed to the State of Texas without the necessity of eminent domain.

Developer shall not acquire or permit the acquisition by Developer or any Developer-Related Entity of any real property interest in a Project ROW parcel, whether in fee title or mortgage, for the purpose of avoiding compliance with the Laws, practices, guidelines, procedures and methods described in Section 7.2.1 (Standards).

7.2.9 Meetings

Developer shall attend meetings as requested by TxDOT. At such meetings Developer shall provide exhibits, take minutes, and distribute the minutes to all attendees for review and comment. Minutes will not be finalized until all attendees agree on content. Meeting minutes shall be provided to TxDOT within five (5) Business Days from the date of the meeting. TxDOT will respond within five (5) Business Days or at the next occurrence of the meeting. Proposed agendas shall be provided three (3) Business Days prior to the meeting.

7.2.10 Documentation and Reporting

Developer shall provide TxDOT with all specific reports and supporting documentation for review and approval during the acquisition process. All correspondence with TxDOT and property owners relating to acquisition of real property shall include a heading with the following information (at a minimum):

a) County

b) Control Section Job (CSJ) number

c) Right-of-Way Control Section Job (RCSJ) Number

d) Highway Designation

e) Project limits

f) Parcel number

g) Name of record owner(s)

In administering and managing its Project ROW activities, Developer shall:

a) Maintain parcel records on file of all aspects of the acquisition process in accordance with TxDOT requirements and applicable Law. Each parcel file shall include all documents required by the Contract Documents, the FHWA, and/or TxDOT.

b) Provide monthly summaries for the cost of Project ROW acquisition and related relocation assistance including amounts authorized and amounts paid on a parcel-by-parcel basis and budget forecasting on an overall Project basis as requested by TxDOT.

c) Maintain and electronically transmit to TxDOT, in a format acceptable to TxDOT, monthly status reports including appraisal, acquisition and relocation status of all parcels and activities related to Project ROW, acquisition and disposition of Additional Properties and acquisition and disposition of temporary easements or other property interests, and provide weekly (or as requested) updates to TxDOT.

d) Evaluate and report to TxDOT, Subcontractor status and performance on a monthly basis or more frequently as requested.

e) Prepare and submit electronically to TxDOT, on a monthly basis, a spreadsheet that contains Project ROW specific data required in order to complete the fields in TxDOT's ROWIS tracking software program or as directed by TxDOT.

f) Input and update parcel status in TxDOT approved web-based tracking system or as directed by TxDOT.

7.2.11 Responsibilities of Developer

As set forth in Section 6.2 of the Development Agreement and as more fully described in this section, Developer shall be responsible for the costs of all services and preparation of all documentation for all Project ROW acquisition, easement acquisition, permitting and related relocation assistance for the Project. The Work related to Project ROW acquisition includes mapping, surveying, environmental assessment, testing and remediation, appraisal, appraisal review, negotiation, acquisition, procurement of title insurance, clearing of title, closing of acquisitions, condemnation support including expert witnesses required by TxDOT and/or the Attorney General's Office for all condemnation proceedings through special commissioner's hearings. The Developer shall also be responsible for all exhibits, transcripts, and photos associated with condemnation services and proceedings required by the Attorney General's Office through special commissioner's hearings, jury trials, appeals, relocation assistance, and clearance/demolition of improvements, as required.

Developer shall not contact the Attorney General's Office or an Assistant Attorney General handling a specific parcel that has been filed for eminent domain action or is in the process of settlement unless authorized by TxDOT.

Developer acknowledges that Developer has incorporated the value of saleable improvements into the Project ROW costs shown in the Base Case Financial Model and any Base Case Financial Model Updates, and Developer shall concurrently, with conveyance of the real property interest to the State of Texas, and without the necessity of further documentation executed by the State, obtain the rights to said

saleable improvements. Developer shall not be entitled to a credit for any improvements retained by a property owner. Upon conveyance of the real property interest to the State of Texas, Developer shall comply with all applicable Laws with respect to relocation assistance and demolition.

Developer shall also be responsible for the costs of acquisition and documentation for the acquisition of any temporary right or interest in real property not necessary for the Project but that Developer deems advisable to acquire for work space, contractor lay-down areas, material storage areas, borrow sites, or any other convenience of Developer. Except as otherwise authorized by Law for temporary areas necessary for construction of the Project, TxDOT shall not be obligated to exercise its power of eminent domain in connection with Developer's acquisition of any such temporary right or interest, and TxDOT shall have no obligations or responsibilities with respect to the acquisition, maintenance or disposition of such temporary rights or interests.

Developer shall be responsible for processing and distributing all payments of: agreed purchase prices or court awards and judgments; special commissioner's awards; relocation assistance payments; all legal, administrative, and incidental expenses of, or related to, Project ROW (including the purchase price of Project ROW for drainage and other required easements); and temporary easements or other interests in real property acquired for the Project.

Developer is responsible for the payment of all closing costs associated with the purchase of Project ROW in accordance with the Uniform Act and TxDOT policies.

Developers cost shall include all costs not paid for by TxDOT.

7.2.12 Responsibilities of TxDOT

TxDOT will have the following responsibilities in connection with acquisition of Project ROW:

a) Except as otherwise set forth in this Section 7, provide final approval for all Acquisition Packages, relocation assistance payments, administrative settlement requests, negotiated settlement requests, court settlement requests, payments, and other approvals required by the Contract Documents, by the State, or by applicable Law within ten (10) Business Days after receipt of complete Acquisition Packages from Developer.

b) After receiving a complete condemnation packet from Developer in accordance with Section 7.4.4, TxDOT will submit a minute order request on the agenda of the next scheduled Texas Transportation Commission meeting; provided the completed condemnation package is submitted before the Commission's required deadline for eminent domain minute order requests.

c) TxDOT shall endeavor to reasonably accommodate a written request from Developer for early submission to the agenda of the Texas Transportation Commission. TxDOT will coordinate with the Office of the Attorney General to provide legal counsel to prepare and deliver to TxDOT the condemnation petition within twenty (20) Business Days after the Attorney General's receipt of the condemnation packet, including Commission minute order approval. TxDOT will deliver the condemnation petition to Developer within ten (10) Business Days after receipt of the condemnation petition from the Office of the Attorney General.

d) TxDOT will provide all coordination services between Developer and the Office of the Attorney General for prosecution of jury trials.

e) TxDOT will provide a ROW Administrator to serve as first point of contact for all Project ROW issues as set forth in 23 CFR § 710.313(d).

f) TxDOT will pay for payments to property owners and payments to displacees for relocation assistance.

7.2.13 TxDOT Project Monitor/Reviewer

In addition to its review and approval authority as expressly set forth in other provisions of this Section 7, TxDOT may, at its sole discretion, audit and/or monitor the ROW activities and services performed by Developer. TxDOT may contract with independent consultants to assist it in fulfilling the audit/monitoring function provided that the audit authority is not delegated. In addition to any of the matters specifically required to be provided by Developer to TxDOT pursuant to the foregoing sections, Developer shall provide information to TxDOT as requested to assist in its review and assessment of the progress, timeliness, adequacy, or sufficiency of Developer's Project ROW activities.

7.2.14 Responsibilities of the Office of the Attorney General

The Office of the Attorney General, with the assistance of Developer and coordination of TxDOT, shall be responsible for implementing all necessary legal actions for acquiring and obtaining possession of the Project ROW (and any necessary temporary construction easements approved by TxDOT for acquisition by condemnation) through the eminent domain process and eviction process. The responsibilities of the Office of the Attorney General will include:

a) Represent TxDOT as the State's Attorney of Record

b) Preparation of complete petitions for condemnation with the appropriate court for a cause number to be assigned

c) Coordination with TxDOT on all legal matters concerning acquisition processes, including negotiated settlements

d) Analysis of recommended parcel values and/or appraisal issues

e) Additional legal advice and opinions as needed by TxDOT

f) Special commissioners' hearings

g) Jury trials including determination of expert witnesses and all appeals

h) Preparation, obtaining, and filing of all necessary legal documentation for eviction of property owners or tenants.

7.3 Pre-Acquisition Activities

7.3.1 Project ROW Surveying and Mapping

Developer shall perform all Project ROW surveying and mapping and shall prepare all Project ROW documents in accordance with applicable TxDOT Standards, including the TxDOT *Right of Way Manual*, the TxDOT *Survey Manual*, and the TxDOT *GPS User's Manual*. Developer shall refer to the current *Manual of Practice* by the Texas Society of Professional Land Surveyors and the *US National Map and Accuracy Standards*. Developer shall refer to Section 9 (Land Surveying) for additional survey requirements.

The Project ROW map shall be prepared by Developer and submitted to TxDOT for review and approval. The Project ROW map may be prepared in separate constructible segments established by the logical termini of the Project. TxDOT shall have fifteen (15) Business Days for review of each submitted ROW map, each containing up to a maximum of 25 parcels. Any submittals that would require TxDOT to review more than 25 parcels within any given fifteen (15) Business Day period shall be considered

excess, and TxDOT may defer its review of any such excess parcels to a subsequent fifteen (15) Business Day period (or periods as necessary).

Developer shall assemble an Acquisition Survey Document Package and deliver to TxDOT upon request of preliminary and/or final review. The Acquisition Survey Document Package shall include:

a) Three half size right of way maps on paper, Scale 1"= 100' (11"X 17").

b) One separate set of Originals signed and sealed by RPLS, legal descriptions and parcel sketch, traverse closure sheets and a copy of the parent track deeds and subdivision plat if tract is a platted lot.

c) Create CD with DGN Master File, Map Sheets, Excel Point List and Raw Data File and/or Field Notes and scanned copies of the instruments of record or other pertinent documents.

d) One full size right of way map on paper, Scale 1" = 50' (22"x34").

e) One set of folders for each parcel, Parts 1 & 2, etc., would be considered one folder. With one (copy signed and sealed) legal description, sketch, closure sheet, parent tract deed and subdivision plat if tract is a platted lot (and bi-section if applicable) secured inside on the right side.

f) Three copies (signed and sealed) of each legal and sketch.

Developer shall prepare all Project ROW surveying and mapping in accordance with the following supplemental specifications:

a) Developer shall assemble an Acquisition Survey Document Package. The Acquisition Survey Document Package shall include the Project ROW map, a parcel (metes and bounds) description, and a parcel plat, with a closure report for each of these three items for each of the parcels to be acquired. The latter three items shall be on standard 8½" x 11" bond paper. The Project ROW map sheets shall be on 22" x 34" paper. Each final submission to TxDOT shall include two sets of each document, unless otherwise directed. Each map sheet and document page shall have an "as of" date near the lower right hand corner. The parcel plat and parcel description for a given parcel should show identical "as of" dates.

b) The ROW map sheet and plat shall show all areas of denied access for the parcel according to the current TxDOT *Access Control Management Manual*.

c) The point of beginning (POB) shall be located on the proposed Project ROW line and shown in all documents with its centerline (survey baseline) station and offset or as reviewed and approved by TxDOT.

d) The point of commencing (POC), where applicable, shall be a well-defined monument or monument of record, and shall be tied to the POB by measured bearing and distance. The POC shall not be located on any proposed Project ROW line, or existing Project ROW line within the proposed Project ROW.

e) The centerline (survey baseline) station and offset shall be shown on the Project ROW map sheets for all significant points along the Project ROW line such as point of curvature (PC), point of tangency (PT), point of intersection (PI), point of compound curvature (PCC), and point of reverse curvature (PRC), and for property line intersections (PLI) with the Project ROW line, and for any other monumentation points on the Project ROW line.

f) The centerline (survey baseline) station and offset shall be shown in the parcel description and parcel plat at the beginning and ending, being the points with the lowest station and the highest station, of each parcel along the proposed Project ROW line.

g) Project ROW map sheets shall include all curve data, with the station and coordinates of the PI, and the stations at each end (PC, PT, PRC, PCC), for every centerline (survey baseline) curve on that map sheet.

h) Any existing ROW lines being incorporated into the proposed Project ROW, including intersecting rights of way, shall be surveyed and monumented (if not previously monumented).

i) All Project ROW maps (and on the title sheet) and all parcel descriptions (at the end of the description) shall include a notation that identifies the State Plane Coordinate System and UTM zones, datum (NAD83) (1993 adj), or as shown on the current ROW maps, and the Project grid-to-surface coordinate adjustment factor or refer to Primary Project Controls provided by TxDOT (refer to Section 9.3).

j) A Project ROW map title sheet with signature blocks shall be produced for each portion of the Project. Developer shall sign the Project ROW map.

k) All Project ROW maps shall include a control sheet (or sheets), to show the primary survey control points with their location relative to the Project.

l) The parcel description and parcel plat documents shall all be referenced as parts of the exhibit recorded with the deed, so the pages shall be numbered accordingly. For example, if the parcel description is two pages, the parcel plat is one page, and then the first page of the parcel description is denoted "Page 1 of 3", the parcel plat is denoted "Page 3 of 3".

m) Improvements within 100 feet outside of all proposed Project ROW shall be depicted on the Project ROW map sheets. All improvements should be current as of the date of the on-the-ground property survey.

n) All visible improvements (buildings and structures) within 50 feet outside of the proposed Project ROW line shall be located by an "on-the-ground" survey and documented on the Project ROW map sheets and the parcel plats by measured offset distance from the proposed Project ROW line. Clearly indicate which distances are surveyed on–the-ground.

o) Calculated points shall be shown by a symbol on the drawing, with their relationship to the found reference points.

p) All property, city, county, abstract, section, and survey lines shall be indicated appropriately. A map legend should clearly define the line styles and symbols used.

q) Upon final submittal from Developer of the Project ROW documents to TxDOT, Developer shall cause the surveyor to mark on the ground, using permanent and stable monuments as defined in Section 663.17 of the General Rules of Procedures and Practices of the Texas Board of Professional Land Surveying (TBPLS), all significant points along the Project ROW line, as described above, and all property line intersections with the Project ROW line. TxDOT requires these monuments to be a 5/8-inch iron rod, driven just below surface level, capped by a TxDOT-labeled aluminum cap (rod-and-cap monument).

r) Prior to acceptance of the ROW maps and surveys by TxDOT, Developer shall cause a TxDOT Type II monument to be set at all significant points on the Project ROW line and at intersections

with existing Project ROW lines, replacing monuments as described above (construct according to TxDOT specifications), unless otherwise directed by TxDOT.

s) Developer shall cause a TxDOT Type II monument to be set at all significant points on the Project ROW line and at intersections with existing Project ROW lines, replacing monuments as described above, unless directed by TxDOT. Project ROW line intersections with property lines shall remain monumented by a 5/8-inch iron rod with a TxDOT aluminum cap (rod-and –cap monument).To reference all significant points along the centerline (survey baseline), Developer shall set a rod-and-cap monument; and upon completion of the Project ROW acquisition or as directed by TxDOT, Developer shall replace it with a TxDOT Type II monument, on the final Project ROW lines, perpendicularly left and right of each significant centerline point, regardless of the relative orientation of the final Project ROW line.

t) For any required revisions, Developer shall resubmit to TxDOT all documents pertaining to the parcel to reflect the most recent revision date, and shall add a notation on the appropriate documents to state briefly the reason for the revision.

u) Documents shall contain deed references (survey name, abstract number, volume and page or document number, grantee, and area) for all existing public right of way encountered within the Project limits. If there is no recorded information found, a note shall state "Based upon our research, there appears to be no recorded vesting deed for the public right of way as shown hereon".

v) The documents produced by the surveyor are the property of TxDOT, and release of any document shall be subject to TxDOT's prior written approval.

w) Developer shall cause the surveyor to include the denial of access line on the Project ROW map sheets and on the parcel plats, as required for controlled access facilities. Developer also shall cause the surveyor to describe the area of denied access in the parcel description and monument on the ground with a 5/8-inch iron rod with a TxDOT aluminum cap stamped "TxDOT ADL" the limits of the denial of access.

x) The Project ROW map and each parcel plat shall include a parcel information table containing the areas, expressed in square feet, of the following: 1) the parent ownership as stated in all adjoining record vesting deeds or converted from the stated record acreage in those vesting deeds; 2) the parcel to be acquired as shown on the closure report for that parcel, and; 3) the remainder tract (item 1 minus item 2). If the parcel to be acquired consists of multiple parts, the Project ROW map shall show the net remainder. The parcel information table shall also contain the areas, expressed in acres, of the parent tract, the parcel to be acquired, and the remainder. This acreage (except stated record) shall be converted from the square footage as contained in the table. A note shall be included on the Project ROW map and on each parcel plat stating: "The acreage calculated and shown hereon is converted from the square footage shown hereon, and is for informational purposes only." Parcels with area less than one acre will not require acreage units to also be shown. All parcels, including parcels acquired by TxDOT or other Governmental Entity, shall be included on the Project ROW map.

y) Within the proposed Project ROW, all property owned by a city, county, or other local public agency (LPA) in fee or easement that does not have a vesting deed shall be identified by a parcel number and included on the Project ROW map. Developer shall cause the surveyor to prepare a parcel description and parcel plat for use as an exhibit in the Project ROW acquisition (property transfer) documents.

z) Developer shall cause an independent Registered Professional Land Surveyor (RPLS) to review the Acquisition Survey Document Package for consistency as to the information delineated thereon and for compliance with all applicable Technical Provisions and survey documents. The boundary location and the survey methods remain the responsibility of Developer, and are not part of this review process. TxDOT will have no obligation to accept the Acquisition Survey Document Package as complete until the reviewing RPLS has signed and sealed the compliance certificate (compliance certificate form to be provided by TxDOT).

aa) Parcel numbering shall follow the TxDOT *ROW Manual*. Parcels are to be numbered based upon the parent tract. Developer shall revise parcel numbering due to subsequent transactions as in the following example: From a 50-acre parent tract, with a proposed Project ROW acquisition parcel identified as Parcel 14, a 5-acre tract is sold which will also require Project ROW acquisition. The result is, Parcel 14 is "Not Used", and the two new Project ROW acquisition parcels are identified as Parcel 14A and 14B. If the property containing Parcel 14B sells a portion, then 14B is "Not Used" and the new Project ROW acquisition parcels are identified as Parcel 14C and 14D, etc. Developer shall not use the letter "E" to avoid confusion with easement designations. Parcel numbering shall be sensitive to the appraisal of the required parcels.

bb) Complicated portions of a Project ROW acquisition survey can cause the Project ROW Map to be very difficult to read. TxDOT's preferred solution is to create an additional Project ROW map sheet or sheets for details, curve data, general notes, etc. The primary page would still retain the whole property inset, record ownership data, and most of the usual information. The additional sheet(s) should be clearly referenced and be numbered as the next sequential page(s). Pages numbered with a letter added (for example: 6A, 6B) are for revisions and corrections. Developer shall use the preferred solution unless TxDOT approves an alternate method.

cc) An ownership sheet or sheets, containing an index to the information for all the parcels, shall be included and located near the beginning of the Project ROW map, after the title sheet and control sheet. The ownership sheet index shall include the parcel numbers, the names of the property owners, the vesting deed recording information, the record area of the parent tract, the area of parcel(s) to be acquired, the area of the remainder(s) left and right, the beginning and ending stations of the parcel along the Project ROW line, and the sheet number in the Project ROW map where the parcel is located.

dd) At property corners where more than one monument is found, a detail shall be provided to show the measured relationship between the monuments found and the monument set or held.

ee) Developer shall purchase all materials, supplies and all items necessary for proper survey monumentation. Developer may purchase Type II monuments from TxDOT. TxDOT shall make available for pick-up by Developer Type II monuments within 75 Days after TxDOT receives from Developer a written order, specifying the number of monuments to be purchased. Payment for TxDOT-supplied monuments shall be due within 30 Days after TxDOT delivers to Developer a written invoice. Developer may use these monuments only for this Project and shall be responsible for proper storage thereof.

ff) Developer at the request of the property owner or TxDOT shall re-stake the proposed ROW with ½" iron rod and aluminum cap.

Design Certification

Developer shall provide sufficiency of design to determine the Ultimate Project configuration ROW need and produce ROW maps that delineate the proposed ROW and potential impacts to the remaining ROW. A design certification of ROW will be provided by the Developer for each parcel which confirms that the proposed ROW acquisition is adequate and necessary to construct and perform operations and maintenance on the Project and that other ROW acquisition alternatives are not feasible and/or cost prohibitive.

7.3.2 Additional Reporting Requirements

In addition to the Project ROW map, parcel description, and parcel plats, Developer shall provide the following reports and electronic files:

a) Monthly Parcel Report: Developer shall provide a report, prior to the first of the month, listing all parcel deletions, parcel additions, and parcel splits.

b) Monthly Progress Report: Developer shall provide a report of all survey activity that occurred during the previous month, including a two-week look ahead of anticipated survey activity.

c) CADD Files: Developer shall provide digital CADD files in MicroStation format which includes: property lines and/or existing ROW lines, as surveyed; proposed ROW lines; parcel numbers; resource files; level assignments; and plot files. Developer shall submit CADD files prior to submitting the first Acquisition Package, and provide updates as needed.

7.3.3 Title Services

With respect to title services, Developer shall comply with the applicable standards identified in Section 7.2.1, including the following requirements:

a) Select and contract with one or more title companies approved by TxDOT and deliver to TxDOT a five-year sales history, a preliminary title commitment or preliminary title report, and, if necessary or appropriate, copies of all underlying documents and a plot of all easements, including Existing Utility Property Interests, referenced therein for each parcel (including fee acquisitions, slope easements, other drainage and roadway ROW or easements and abandonment of utility easements) to be acquired by TxDOT for the Project. Each title report shall be dated not more than 90 Days prior to the date of submittal to TxDOT of the Acquisition Package for such parcel. Developer shall, at its own cost, review each title report to ensure that it complies with the format required by the Contract Documents. Developer shall, at its own cost, retain the services of a real estate attorney, licensed and located in the State of Texas, to be available for title support and acquisition assistance. All title reports must be in the following required format: clearly indicate which exclusions and exceptions shall be deleted upon acquisition of the subject parcel, and clearly indicate any required deliverables to the title company to clear identified exclusions and exceptions. Title reports shall be in accordance with Good Industry Practice. Developer shall notify the title company, by letter, which exceptions should be removed, including easements that (a) are appurtenant to and/or of benefit to the parcel but not included in the parcel to be acquired, and (b) are a burden on the parcel and not acceptable.

b) Review the preliminary title commitment or report to ensure that all current owners of record title are contacted and that negotiations or condemnation actions are conducted with all appropriate parties.

c) Work with the current owners of record title to each parcel or interest in a parcel or their designee and all other appropriate parties to clear any title exceptions or exclusions not acceptable to TxDOT.

d) Secure an owner's policy of title insurance in the amount of the total acquisition cost for each parcel from a title company acceptable to TxDOT for each parcel acquired, whether by deed or eminent domain judgment, insuring title as required by TxDOT. All Project ROW shall be acquired, and TxDOT's title in the Project ROW shall be insured, in fee simple absolute or easement interest as appropriate, free and clear of any and all liens and encumbrances. Developer shall pay the applicable title company for the cost of the title policies, including all endorsements thereto required by TxDOT. Title policies must be in a form and substance approved by TxDOT. Title to the Project ROW shall be insured in the name of the "State of Texas by and through the Texas Department of Transportation."

7.3.4 Introduction to Property Owners

Developer shall prepare and send out initial contact letters of introduction for both property owners and displacees. The letters shall clearly describe the Project, TxDOT's need for the owner's property, and shall include the name and telephone number of a Developer's representative. TxDOT's ROW Administrator or his/her designee will sign the letters on TxDOT letterhead. The forms for these letters shall be approved by TxDOT prior to use. Property owners or displaces unable to read or understand the notice must be given appropriate translation.

Developer shall prepare a copy of the State of Texas Landowner's Bill of Rights for each property owner and submit a copy to be included with the letter of introduction. The copy of the Bill of Rights shall be the latest version as shown on the Attorney General's website,

https://www.oag.state.tx.us/agency/Landowners_billofrights.pdf.

7.3.5 Appraisals

7.3.5.1 Appraisal Services

Developer shall provide TxDOT with fair market value appraisals prepared by appraisers meeting the minimum qualifications established herein. All appraisals shall be prepared in conformance with applicable Law (including the Uniform Act), and in accordance with professional appraisal methods and applicable TxDOT standards for all parcels to be acquired by TxDOT. Developer shall:

1. Select appraisers from TxDOT's list of approved fee appraisers and meeting the requirements specified in Section 7.2.7 (ROW Personnel Qualifications). TxDOT shall have final approval of the selection of each appraiser and appraisal reviewers submitted by Developer. Developer must identify and receive written approval of the appraiser who will be responsible for the appraisal work product and who will be signing the reports.

2. Establish personal pre-appraisal contact with each owner of record title and each occupant, and document all contacts utilizing forms provided by TxDOT.

3. If necessary, make a diligent effort to secure a written agreement between the record title owner and Developer granting TxDOT, Developer or assignees permission to enter the applicable parcel to be acquired (a "Right of Entry Agreement"). Developer may at its sole discretion and expense offer to pay reasonable compensation for any required Right of Entry Agreements. If Developer, after best efforts, is unable to secure a Right of Entry Agreement from the property owner,

Developer shall provide documentation acceptable to TxDOT indicating conversations, correspondence, and efforts used to attempt to secure the Right of Entry Agreement.

4. Contact the record title owners or their designated representatives, in writing, to offer them the opportunity to accompany the appraiser on the appraiser's inspection of the parcel, and maintain a record of all such contacts in the parcel file.

5. Cause the appraiser to prepare a complete appraisal report for each parcel to be acquired to include the whole property, the portion to be acquired, and any damage to the remainder. It shall also include all improvements on the whole property, unless otherwise directed by TxDOT. The appraisal reports shall comply with and include all matters required by this section and TxDOT ROW related manuals, and shall satisfy the requirements of the USPAP in effect at the time the appraisal is submitted. Special analyses, studies or reports, as necessary, shall be made a part of each appraisal. The appraiser must use the most current edition of the standards referenced above and continually monitor these standards to ensure the appraisals conform to the most current requirements of professional appraisal practice. All appraisals shall utilize TxDOT Form ROW-A-5 - Real Estate Appraisal Report unless otherwise authorized by the TxDOT *Right of Way Manual* or TxDOT *Appraisal and Review Manual*; however, all appraisals for condemnation proceedings shall utilize TxDOT Form ROW-A-5 - Real Estate Appraisal Report.

6. Obtain and provide TxDOT with copies of all written leases, licenses and other occupancy agreements, including outdoor advertising/sign agreements, in order to identify lessees, licensee and other occupants with potential compensable interests in each parcel and to determine the value of each such interest.

7. Perform an evaluation of all outdoor advertising signs, as required, utilizing the appropriate forms as instructed by TxDOT.

8. Cause the appraiser(s) to testify as an expert witness(es) or provide expert witness(es) approved by TxDOT in special commissioners' hearings or eminent domain proceedings through jury trial and be available for depositions, other discovery, pre-hearing or pre-trial meetings and appeals, as directed by TxDOT. Developer shall also provide administrative and/or technical support for such proceedings as requested by TxDOT.

9. Coordinate with the review appraiser regarding corrections and/or additional information that may be required for a particular appraisal.

10. Cause a report to be prepared by an environmental professional that meets ASTM E-1527-05, Standard Practice for Environmental Site Assessments: Phase 1 Environmental Site Assessment Process, or provide a report in a manner approved by TxDOT, documenting the environmental condition of each parcel, which may be based on field investigations and/or historical review, as appropriate for the particular parcel. The report shall be completed in coordination with the appraiser(s) and shall be available to the appraiser(s). A Phase I environmental site assessment or a report provided in a manner approved by TxDOT shall be performed for all properties. If it is determined that there is a potential environmental risk based on the Phase I report or other report then a Phase II investigation shall be performed. A Phase III investigation shall be performed if the Phase II report justifies it. The Phase III report must indicate the approximate cost to remediate the parcel to achieve its current use and its highest and best use. Prepare timely written notification to TxDOT of any environmental or other concerns associated with the Project ROW or Additional Properties to be acquired that could require environmental remediation or other special attention or which would cause a report to be prepared.

11. Engage the services of, and cause, a land planner to perform, or otherwise assist in the preparation of, any and all appraisals that involve a parcel with a valuation analysis indicating a highest and best use that is other than the current use of such parcel, or as directed by TxDOT for certain other appraisals. Developer shall notify TxDOT in writing of each and every instance when the highest and best use of a parcel is different and TxDOT will determine to what degree land planner services will be utilized by Developer.
12. Cause the appraiser(s) to prepare updated appraisals, as well as updated appraisal reviews, when required by TxDOT or as needed during eminent domain proceedings. An updated appraisal package shall comply with USPAP, specifically the Statement on Appraisal Standards No. 7 (SMT-7) and Advisory Opinion, AO-3. The term "Update of an Appraisal" is defined as "an extension of a complete or limited appraisal and report relied on by a client for a prior business decision." At a minimum, the updated appraisal report must include:
    - A letter of transmittal with a specific reference to the original appraisal report, any changes in market conditions, since the original appraisal, any changes in the subject property since the original appraisal, a statement of the current value or extension of the original value opinion and the listing of the current date of value.
    - An updated Page 1 from TxDOT Form ROW-A-5 – Real Estate Appraisal Report or Form ROW-A-6 – Real Estate Appraisal Report, as appropriate, with the current date of a recent inspection of the subject property and a current date of value. This form needs to have a current signature and date by both the appraiser and the reviewing appraiser in the appropriate spaces on the form.
    - Any qualifying and limiting conditions or general assumptions by the appraiser shall be clearly stated and attached.
    - A copy of the survey and legal description of the property being acquired, current photographs of the subject property, clearly showing the area being acquired, even though the original appraisal report contained photographs of the subject and the area of the acquisition. If there are significant changes to the subject property, the area being acquired, access to the remainder property, damages to the remainder(s), market conditions, the subject property's highest and best use from the previous appraisal or significant changes in the approaches to value, the property shall be reappraised using either TxDOT Form ROW-A-5 – Real Estate Appraisal Report, or, when approved by TxDOT, TxDOT Form ROW-A-6 – Real Estate Appraisal Report, depending on the report used for the original appraisal. Appraisers shall refer to Sections 6.03 and 6.04 of the TxDOT *Appraisal & Review Manual* for additional guidance. Developer shall follow these guidelines in producing updated appraisal reports and shall discuss specific updating requirements for any complex appraisals with TxDOT before beginning the assignment.
13. Prepare and deliver to TxDOT upon request, a copy of all file documents, as formally requested in discovery motions or request for production.
14. Complete and furnish, to the appraiser, TxDOT Form ROW-A-9 - Property Classification Agreement before appraisal is completed.

7.3.5.2 Appraisal Review

In connection with appraisal review, Developer shall:

1. Select review appraisers from TxDOT's list of approved fee appraisers and meeting the requirements of Section 7.2.7. The review appraiser selected must follow the appraisal guidelines and procedures found in Chapter 4 of the TxDOT *ROW Appraisal & Review Manual*.
2. Determine, in consultation with TxDOT, if additional appraisal reports or technical expert reports are required. Initiate, review, and reconcile each report required.
3. Review all appraisal reports for each parcel to determine consistency of methodology, supporting documentation related to the conclusion reached, and compliance with TxDOT standards, as defined in Section 7.3.5.1 (Appraisal Services) and this Section 7.3.5.2 (Appraisal Review), the TxDOT *ROW Appraisal & Review Manua*l, the *Uniform Appraisal Standards and Federal Land Acquisitions* and the requirements of the Appraisal Foundation's USPAP in effect at the time the appraisal is reviewed. The review appraiser must use the most current edition of the standards referenced above and continually monitor these standards to ensure the appraisals conform to the most current requirement of professional appraisal practice.
4. Inspect the subject properties and the sale properties used in direct comparison for each appraisal being reviewed.
5. Upon completion of the review outlined above, the appraiser shall certify in writing to TxDOT that all required standards have been met. This certification will occur by signing on Page 1 of each TxDOT Form ROW-A-5 (Real Estate Appraisal Report) or TxDOT Form ROW-A-6 (Real Estate Appraisal Report) in the block provided. The review appraiser will also complete TxDOT Form ROW-A-10 (Tabulation of Values) to accompany each appraisal.
6. For appraisal updates, the review appraiser shall perform a complete review of the updated appraisal, re-inspecting the subject property and the sales used, as of the current date of value. The review appraiser shall follow the procedures outlined in the TxDOT *ROW Appraisal and Review Manual*. A new TxDOT Form ROW-A-10 (Tabulation of Values) will be required for each updated appraisal ordered by Developer.
7. In accordance with providing a Quality Control Specialist(s) as stated in Section 7.2.7, ensure that appraisal consistency and quality for the entire Project is monitored for Project-wide controls and consistency.

7.3.6 Project ROW Acquisition Package Approval

Acquisition Packages submitted by Developer for TxDOT's approval shall include the following items, prepared for each parcel in accordance with the requirements of this section:

1. A cover sheet setting forth the following information for each parcel.
   - Parcel number and number of parts
   - Station number
   - CSJ number
   - Location of parcel
   - Name of owner
   - County and/or other jurisdiction
   - Extent of acquisition (partial or whole acquisition)
   - Type of conveyance (fee, easement, etc.)

2. A complete legal description of the parcel adequate to effect the desired acquisition of the parcel, signed and sealed by an RPLS. A legal description and parcel plat is required for each parcel. Control of access shall be addressed in all legal descriptions. All descriptions shall be in recordable form and shall be prepared in a form and manner acceptable to TxDOT in all respects.
3. The parcel plat, as prepared by the RPLS, and a half size (11" x 17") copy of the ROW map sheet(s) pertaining to the parcel, such plat to include control of access designations.
4. A title report, current within 90 Days, including copies of all documents identified in the exceptions listed therein and a plot of all easements identified therein. The Acquisition Package shall include Developer's analysis of each preliminary title report or title commitment to determine potential problems and proposed methods to cure title deficiencies. Developer shall perform title curative work. Developer shall provide TxDOT with copies of all curative documents.
5. A copy of the appraisal report with an effective date less than 180 Days and all supporting documentation.
6. A copy of the environmental site assessment and all amendments as described in Section 7.3.5.1 (Appraisal Services).
7. A real/personal property report detailing the items making up each parcel are classified as real estate, tenant-owned improvements or personal property. Particular attention shall be paid to items that have questionable classifications. A completed TxDOT Form ROW-A-9 (Property Classification Agreement).
8. Replacement Housing Calculations, notification of business eligibility, completed displacee interviews, all comparables used in estimating the Replacement Housing Calculations, and letter to displacee(s) explaining Replacement Housing Calculations. Calculations and replacement housing benefit package shall be prepared and reviewed by a qualified consultant, in conformance with TxDOT's standard relocation procedures and applicable to State and federal Laws.
9. The proposed initial offer letter, memorandum of agreement, deed, and any other documents, which shall be prepared by Developer as required or requested by TxDOT, on Developer's letterhead or as otherwise directed. TxDOT will provide the format for preparing these documents. Documents referred to in this section are standardized by TxDOT and modification of standardized documents shall be kept to a minimum. All changes are subject to approval by TxDOT in writing, in TxDOT's sole discretion.
10. Any other required TxDOT forms, such as record of all contacts with the property owner or any party with a compensable interest.

No Acquisition Packages will be approved if performed or submitted by appraisers or agents not previously approved by TxDOT for this Project.

Upon TxDOT's prior written approval of the Acquisition Package, Developer may proceed with the offer to the property owner.

7.4 Acquisition Activities

7.4.1 ROW Negotiations

Developer shall conduct all negotiations in accordance with the requirements of applicable Law. In conjunction with negotiations, Developer shall:

a) Within ten Business Days of TxDOT's approval of the Acquisition Package, contact each property owner or owner's designated representative, in person where practical, to present the offer and deliver an appraisal report (not more than 6 months old) and appropriate brochures. The approved appraisal shall be sent by certified mail, return receipt requested. A copy of the appraisal report for the subject property shall be provided to the property owner or authorized representative at the time of offer. All appraisal reports produced or acquired by TxDOT relating specifically to the property owner's property and prepared in the 10 years preceding the date of the offer must also be delivered to the property owner. Developer shall also maintain a file record of receipt of appraisal signed by the property owner. Developer shall also maintain follow-up contacts and secure the necessary documentation and title curative Work upon acceptance of the purchase offer.
b) At the time of offer, produce and distribute to all property owners and displacees, TxDOT-approved informational brochures, as appropriate. The ROW brochures shall be purchased by Developer and shall include language about the use of the *Declaration of Taking* procedure if Developer anticipates requesting the utilization of this procedure by TxDOT anywhere within the Project.
c) Identify lessees, licensees, occupants, or other parties with potential compensable interests including outdoor advertising sign owners, and, if appropriate, after consultation with TxDOT, negotiate with such parties for the acquisition of their compensable interests.
d) Advise the property owners, lessees, licensees, occupants, and other holders of compensable interests, as applicable, of the administrative settlement process. Confer with and transmit to TxDOT's ROW Administrator any settlement request from property owners, lessees, licensees, occupants, or other holders of any compensable interest, as applicable, including a detailed recommendation from Developer in accordance with standards, manuals and procedures as defined in Section 7.2. TxDOT shall determine whether to accept a settlement request. Delivery of the administrative settlement request and Developer's recommendation to TxDOT must occur within fifteen (15) Business Days following Developer's receipt of the administrative settlement request.
e) Developer, at its request or the request by TxDOT and/or the TxDOT Administrative Settlement Committee, may participate in the evaluation of the administrative settlement request and attend the committee meeting.
f) Developer shall provide a letter with the TxDOT Administrative Settlement Committee's response to the property owner, lessee, licensee, occupant, or other holder of a compensable interest, as applicable. Developer shall deliver all settlement responses (if within reasonable proximity of the Project) by hand within three Business Days after receipt. If this delivery method is not feasible, Developer shall mail (return receipt requested) response letters not more than three Business Days following any decision by the TxDOT Administrative Settlement Committee. If Developer selects the mailing option, Developer shall make a telephone call to the property owner to discuss the settlement offer prior to mailing the response letter. The TxDOT ROW Administrator, on an as-needed basis, will convene the TxDOT Administrative Settlement Committee.
g) Notwithstanding an unsuccessful completion of the formal administrative settlement process, Developer may, in its sole discretion, engage in ongoing negotiations with the owners of compensable interests. Developer shall develop and incorporate in its ROW Acquisition Plan a procedure for these negotiated settlements. Said negotiations may continue until such time as the Texas Transportation Commission adopts a minute order authorizing the filing of a condemnation

petition. Developer shall submit to TxDOT its recommendation of a negotiated settlement and obtain TxDOT's consent prior to acceptance of any settlement.

h) Provide timely (i.e., not more than ten Business Days after inquiry) response to the verbal or written inquiries of any property owner, lessee, licensee, occupant or other holder of a compensable interest, as applicable.

i) Prepare a separate negotiator contact report for each meeting or conversation with any person (or their appointed representative(s) supported by a written confirmation of appointment) who has a compensable interest in each parcel on TxDOT Form ROW-N-94 – Negotiator's Report. Contact reports shall also be prepared for unsuccessful attempts to contact such persons.

j) Maintain a complete parcel file for each parcel. All original documentation related to the purchase of the real property interests will be maintained (housed separately from the relocation files) in conformance with TxDOT standards, manuals, and procedures, as defined in Section 7.2. All original Project ROW documents must be retained and properly secured in Developer's Project office or as otherwise approved by TxDOT. Signed original documents shall be forwarded to TxDOT periodically or as requested by TxDOT with a transmittal form during the acquisition process; provided, however, that all remaining original documents shall be forwarded upon completion of the acquisition of Project ROW for the Project.

k) Prepare and deliver documents of conveyance (including bisection clause and access clause, if applicable) to the property owner, lessee, licensee, occupant, or other holder of any compensable interest, as applicable, and obtain their execution of the same. All signatures on documents to be recorded shall be notarized in accordance with Texas Law.

l) Pursue and obtain Possession and Use Agreements (PUA) concurrently with the parcel negotiations. The form of PUA will be provided by TxDOT and will contain provisions allowing for construction to commence while negotiations are finalized. Such agreements will be sought and negotiated by Developer strictly in accordance with the Law and only with the prior written consent of TxDOT. If Developer exercises the use of a TxDOT PUA, Developer must obtain a deed or commence action on condemnation proceedings by forwarding a condemnation packet to TxDOT for approval within six months from the date of the PUA.

m) Be open to all reasonable settlement requests (that comply with the regulations as outlined in this section) from the property owners, which are feasible and help expedite the Project ROW acquisition process. Developer acknowledges and understands that TxDOT encourages all positive and creative solutions which satisfy the property owner and promote the success of the Project.

n) Developer shall prepare and deliver a final offer letter to the property owners, lessees, licensees, occupants, or other holders of any compensable interest, as applicable, no sooner than 30 days from the date of the offer letter in accordance with Senate Bill 18. The letter shall be on Developer's letterhead and shall be signed by the ROW Acquisition Manager. The final offer letter shall allow a property owner lessee, licensee, occupant or other holder of compensable interest at least fourteen (14) Days as the consideration time period to review the final offer. Developer shall submit to TxDOT, a copy of the final offer letter within two days after delivery to the property owner.

If the offer is not accepted, Developer shall follow the procedures established for condemnation.

7.4.2 Relocation Assistance

Developer shall coordinate and perform the administrative requirements necessary to relocate any occupants from Project ROW. All Work prepared by Developer with respect to relocation assistance shall

be performed in accordance with applicable Law, including the Uniform Act and TxDOT standards, and in accordance with all provisions of this Agreement.

Developer shall maintain a relocation office (meeting ADA requirements) within reasonable proximity of the Project area as approved by TxDOT. At a minimum, the office hours of the relocation office shall be posted to meet the following timetables:

a) Monday thru Friday: 8:00 am to 5:00 pm

b) Saturday: 9:00 am and 12:00pm

c) Sunday: office may be closed

In addition to the office hours listed above, Developer shall be available to all displacees for relocation services at the convenience of the displacees.

Developer's major activities with respect to the relocation assistance of occupants from Project ROW include:

1. Prepare a Relocation Plan in accordance with the TxDOT *Right of Way Manual*, Volume 3, Chapter 8 (Relocation Program Planning and Construction).
2. Monitor relocation assistance activities.
3. Prevent fraud, waste and mismanagement.
4. Assist with all requests and be responsible for carrying out decisions made by TxDOT, the review/appeal process and judicial reviews.

Developer shall provide relocation assistance strictly in accordance with the Law, and, in particular, the Uniform Act and TxDOT standards. With respect to relocation assistance, Developer shall:

1. Provide written notice to all property owners, lessees, licensees, occupants, other holders of compensable interests, and other potential displacees regarding relocation assistance and produce and provide them with a relocation assistance brochure that has been approved by TxDOT. Developer shall perform relocation interviews, complete and maintain interview forms and discuss general eligibility requirements, programs, and services with potential displacees. Developer shall maintain a written record of all verbal contacts.
2. Give written notice of the pending acquisition to any non-eligible occupants. Any questions as to the eligibility of a potential displacee shall be directed in writing to TxDOT's ROW Administrator.
3. Contact and provide relocation assistance to those parties affected by the Project ROW acquisition and complete forms for all displacees, as required.
4. Locate, evaluate and maintain files on comparable available housing, commercial, retail, and industrial sites.
5. Calculate replacement supplement benefits.
6. Compute and submit requests for relocation rental/housing supplement to TxDOT prior to submission to relocatees. All relocation supplements shall be subject to TxDOT's written approval.
7. Perform a Decent, Safe and Sanitary (DSS) inspection for each replacement housing comparable, photograph the comparable and complete the DSS inspection form, TxDOT Form ROW-R116 (Replacement Housing Inspection).
8. Request at least two moving estimates from moving companies to effect relocation of personal property or consistent with the Uniform Act.

9. Prepare moving plan with appropriate photos, sketches and inventory of personal property to be moved.
10. Coordinate moves with displacees and moving companies in accordance with TxDOT standards and the Uniform Relocation Act.
11. Maintain relocation contact logs on a TxDOT Form ROW-R96-R (Relocation Advisory Assistance – Parcel Record).
12. Attend all closings on replacement properties, if requested by any party involved, and assure supplemental payments, if any, are properly distributed.
13. Process and compute increased interest payments on the mortgage of owner-occupied dwellings, as required.
14. Deliver to displacees a 90 Day notice of eligibility letter simultaneous with the delivery of the relocation benefits package. Deliver a 90 Day letter to displacees with the location of the comparable property used to compute the supplement.
15. Deliver a 30 Day notice to displacees and property owners upon acquisition of Project ROW.
16. Notify TxDOT's ROW Administrator office immediately if a displacee has not moved after 30 Day notice expires. Prepare a written recommendation to facilitate the displacee's move.
17. Be available for any appeals or hearings.
18. Prepare relocation payment claim submissions for all displacees and all relocation assistance benefits.
19. Verify DSS dwelling criteria on all replacement housing as selected by the displacees.
20. Secure dwellings and structures no later than ten Days after vacancy and protect the Project ROW following acquisition and relocation.
21. Maintain a complete file, separate from acquisition files, on each displacee and make available for inspection.
22. Be responsible for all relocation activities that may occur after deposit of the special commissioner's award in the courts, including instances when a parcel referred to the Attorney General's office for eminent domain also has a relocation issue.
23. Prepare all correspondence to the displacees or their representative(s) on Developer's designated relocation letterhead and have Developer's correspondence signed by the Project ROW relocation specialist.
24. Deliver to each displacee the relocation assistance payments according to the TxDOT *Right of Way Separation of Duties* chart provided.
25. Assist the Attorney General's office with eviction proceedings. Serve notice of eviction proceedings to the occupant(s) of the property who have not complied with move dates. Coordinate the eviction process with the local authorities and accompany the Sheriff's Department when the local authorities are carrying out eviction.

7.4.3 Closing Services

For purposes of closing services, Developer shall:

1. Submit a closing package to TxDOT for review a minimum of 24 hours prior to closing. The package shall include the following: a.) a reference to the disposition of any environmental matters; b) updated title commitment, no more than fifteen (15) Days prior, with notations indicating the disposition of all schedule "C" items; c) a copy of the executed warranty deed to be delivered; d) a proposed closing statement indicating disposition of all proceeds; e) a copy of any and all releases of liens; f) a copy of any miscellaneous documents and other curative matters required to be delivered at closing and g) a copy of the closing memorandum outlined in item 2 below.

2. Prepare the escrow agreement and closing documents, including a closing memorandum identifying all parties involved in the closing, and listing all documents to be executed and/or delivered in connection with the closing.
3. Attend closings; provide curative documents and exhibits as required and in conjunction with the applicable title company. Confirm that all conditions to closing are satisfied and notify TxDOT of all closing appointments.
4. Obtain an issued title policy based on the approved updated title commitment within 30 Days following closing and transmit the same to TxDOT.
5. Obtain and deliver to TxDOT one certified copy of each instrument of conveyance immediately after closing, and provide a copy of the title policy to TxDOT within five Business Days after receipt. Cause to be delivered to TxDOT a copy of the recorded deed within ten Days after the title company receives the recorded deed.

7.4.4 Condemnation Support

Developer shall provide an individual or individuals having sufficient knowledge of the design of the Project to appear as an expert witness for testimony at the special commissioners' hearing or other proceedings. This individual(s) is also responsible for preparing exhibits as requested by TxDOT or the Office of the Attorney General in support of said testimony.

Developer shall support condemnation efforts as directed by TxDOT and further delineated as follows:

1. Notify TxDOT of any potential condemnation and document the reason(s) for condemnation including recommendations for property closure.
2. Conduct all applicable eminent domain-condemnation activities in accordance with the policies and procedures as described in the TxDOT *Right of Way Manual*, Volume 4: "Eminent Domain "; in the TxDOT *ROW Appraisal and Review Manual*, Chapter 7 "Eminent Domain-State Acquisition" or as revised; and in Chapter 21, Texas Property Code and Senate Bill 18.
3. After non-response or upon receipt of a copy of the rejected final offer from a property owner or other property right holder entitled to compensation, request an updated title report from the title company issuing the original title commitment.
4. Provide to TxDOT, within ten Days following non-response or rejected certified mailing, notification thereof together with a signed and sealed parcel description and parcel plat, and a bisection clause and access clause, if necessary, with the clauses attached to a property exhibit containing the parcel description and parcel plat.
5. Use the information from the title report to join all parties having a property interest on applicable the TxDOT form. Spouses of property holders with compensable rights must also be joined.
6. Upon completion of TxDOT Form ROW-E-49 (Request for Eminent Domain Proceedings), prepare a condemnation packet containing two copies each of the following documents: the completed TxDOT form, negotiation logs, the updated title report not more than 90 Days old, appraisal receipt acknowledgment, pre-appraisal contact sheet, signed and sealed field notes, parcel sketch, bisection clause and access clause exhibits (if necessary), initial offer letter and final offer letter reflecting latest appraisal, complete minute order request form (form to be provided by TxDOT), any correspondence sent by Developer or from the owner of the compensable interest or representatives, one copy of the appraisal report not more than 180 Days old from the effective date of the appraisal report and evidence of a bona fide offer to the property owner. Submit two (2) complete condemnation packets to TxDOT's ROW Administrator for review and approval.

7. Send a copy of the complete petition to the title company and confirm with the title company that the appropriate parties were joined in the case and that no changes in title have occurred since the original litigation guaranty was issued.
8. File the petition for condemnation with the appropriate court clerk after a determination that a timely settlement is not feasible. Send a copy of the petition, by certified mail, return receipt requested, to the owner, lessee, licensee, occupant or other holder of compensable interest.
9. Coordinate and provide legal and technical support to the Attorney General's office, as required to facilitate filing the petition, assignment of a court, and setting of a hearing date.
10. Make available to TxDOT on behalf of the Attorney General's office an agent who will be expected to assist in making arrangements for conferences with witnesses prior to trial, filing the condemnation petition, informing the Attorney General's office as to the filing date of the petition and the case number assigned to the suit, and perform any other duties which will assist in the successful prosecution of the suit, including his or her attendance in court and filing necessary documents to complete all eminent domain proceedings.
11. Depending on the market conditions or if over six months have elapsed since the date of the initial offer, contact the attorney handling the case for TxDOT and confer about the advisability of preparing an updated appraisal. If it is determined that an updated or new appraisal is necessary or desirable, obtain such appraisal using the same procedures as described in Section 7.3.5.1 (Appraisal Services) above. Developer must also undertake appraisal review as described in Section 7.3.5.2 (Appraisal Review).
12. Coordinate with TxDOT on behalf of the Attorney General as to land planners and/or other expert witnesses as required by the Attorney General. Developer, at its cost, shall provide the land planner or other expert at the request of TxDOT or the Attorney General. The land planner or other expert report, if required, shall be completed and forwarded to the appraiser before the updated appraisal is completed.
13. Appear or provide for the appearance of expert witness(es) or fact witness(es) when requested by TxDOT or the Attorney General's Office. The appearances may include pre-commissioner's hearing preparations, special commissioner's hearings, and subsequent proceedings including jury trials and related proceedings.
14. Submit the updated appraisal to TxDOT and the attorney handling the case for TxDOT for review and approval, which review and approval shall occur within ten Business Days of receiving the updated appraisal. TxDOT and Developer must approve any revised offer in writing prior to an offer letter being sent. If a revised offer is approved, prepare a final offer letter, make the revised offer to the property owner or other holder of a compensable interest, as applicable, and submit a copy of the final offer letter to TxDOT for written approval.
15. Communicate with TxDOT as to the parcel status on a monthly basis and in the Project progress report or as requested by TxDOT.
16. Serve in person, a "Notice of Hearing" not later than twenty (20) Days before the date of the special commissioners' hearing or other hearings and notice requirements as directed or authorized by the court.
17. Call and send reminders letter two to three weeks in advance of any hearing to the assigned attorney, engineer, technical experts, appraiser, the commissioners, court reporter, and TxDOT's ROW Administrator concerning hearing dates.
18. Upon completion of the hearing, prepare TxDOT Form ROW-E-73 (Data Sheet – Special Commissioner's Hearing) and commissioners' time sheets. Developer shall make payment to all commissioners involved in the hearing and include payment for commissioners as part of general Project ROW services.

19. Coordinate and provide support to TxDOT's counsel and facilitate distribution of copies of award, prepare request for payment, and file notice of deposit. Developer shall coordinate with TxDOT on behalf of the Office of the Attorney General regarding expert witnesses needed to testify on behalf of the State at the special commissioners' hearing and subsequent proceedings including jury trials. At the request of the Office of the Attorney General or TxDOT, Developer shall provide and pay for all necessary expert witnesses including: engineering, land planners, real estate consultants, cost estimators, outdoor advertising sign experts and environmental consultants and Developer shall appear as expert witness or fact witness, as requested. Developer shall also make any Subccontractors available to appear as an expert witness or fact witness, as requested at the special commissioners' hearing or subsequent proceedings. The selection of all expert witnesses to be used for jury trials shall be determined by the Attorney General's Office.
20. Schedule and pay for all court reporter services, transcription costs, expert witness fees, exhibits, and exhibit workbooks as directed by TxDOT.
21. Be responsible for coordinating the pre-hearing meeting with TxDOT on behalf of the Attorney General's office and all others required for testimony or exhibit preparation. Developer shall require expert witnesses with all exhibits and documents to be present at a pre-hearing meeting.
22. Timely file and provide proper service of objections if requested by TxDOT after completion of the special commissioner's hearing and promptly provide evidence of filing and copies of all filed documents to TxDOT. Within three days after objections have been filed, Developer, at its cost, shall order transcripts of such hearing.
23. Developer shall provide an individual or individuals having sufficient knowledge of the design of the Project to appear as an expert witness for testimony at the Special Commissioner's Hearing or other proceedings. This individual(s) is also responsible for preparing exhibits as requested by TxDOT or the Office of the Attorney General in support of said testimony. Exhibits shall be left in the custody of TxDOT at the close of the hearing.

7.4.5 Clearance/Demolition of Project ROW

Prior to demolition of any improvements, Developer shall provide to TxDOT, photographs of the property and all improvements, unless the special commissioner's hearing has been completed and objections have not been filed. Developer shall also have photos of personal property and any other items of dispute in and of a quality suitable for presentation as evidence in court. Following acquisition or possession of any parcel of Project ROW, Developer shall:

1. Within ten (10) Days from acquisition of the property and improvements, secure and protect the buildings, improvements and fixtures on the Project ROW until they are disposed of or demolished. Developer shall board-up, mow, and winterize as required by TxDOT or applicable Law.
2. Coordinate with the owner and occupants to assure the clearance of personal property from the Project ROW, as applicable.
3. Provide for any insect and rodent control and initiate extermination as required to protect the adjacent properties and rid the Project ROW from infestations.
4. Secure Governmental Approvals required for demolition and environmental surveys or tests, and notify TxDOT in writing of all such activities.
5. To the extent required by Section 7.2.11 (Developer Responsibility for Costs), prepare necessary documentation for disposal of improvements, fixtures and buildings in accordance with applicable Laws and submit the same to TxDOT.
6. Provide written notification to TxDOT of any real and/or personal property remaining on the Project ROW after vacated by the occupants and not acquired as part of the acquisition.

7. Terminate all utility service(s) when appropriate.
8. Process all required forms, documents and permit applications in order to proceed with the timely demolition or removal of any and all improvements, buildings and fixtures located within the Project ROW, as applicable.
9. Demolish and/or remove all improvements.
10. Notify TxDOT upon completion of the demolition and clearance of the Project ROW, as applicable.

7.4.6 Property Fence

In connection with fences, Developer shall comply with the policies and procedures of the TxDOT *Right of Way Manual*, as well as the specifications found in the current TxDOT *Standard Specifications for Construction of Highways, Streets and Bridges*. Fencing standards for Developer-provided fencing shall conform to the overall aesthetics requirements found elsewhere in these Contract Documents and referenced standards.

7.4.6.1 Property Fencing for Public Properties

Where public facilities now exist that are in high risk areas for public use (particularly those containing parks, sport areas, schools or any highly traveled pedestrian areas), Developer shall, at a minimum, construct a 6-foot-high chain-link fence with metal posts. Developer shall use Good Industry Practice in fencing public properties to control public access to the Project.

7.4.6.2 Property Fencing for Private Properties

Developer shall instruct the appraiser to use the "Cost to Cure" format to compensate an owner of private property for a replacement fence when the Project ROW line leaves one or more unfenced remainder property(s) that were fenced before the taking. Compensation for the new fencing will be based upon the same type of fence as the property owner's existing fence.

When the property owner is paid through the appraisal process for the cost to rebuild the fence on the remainder property, Developer shall include in the memorandum of agreement or the purchase agreement for such property the following clause:

"It is further understood and agreed that the Grantor has been compensated for the construction of a new fence and shall be responsible for constructing the necessary fencing within 30 Days from the date of closing. Grantor specifically understands and agrees that the fences are the property of the Grantor and they shall be liable and responsible for any reconstruction, maintenance, or adjustment with regard to such fencing."

Developer shall make reasonable and good faith efforts to ensure that the property owners, who have been compensated for fencing of the remainder properties, erect the fence in accordance with the construction schedule.

If necessary to maintain the Project construction schedule and to control unauthorized access to the Project ROW by the public or livestock, Developer shall be responsible for providing temporary fencing in cases where the property owner refuses to fence the property within the allotted timeframe.

After the property owner's retention period has expired and if any existing fencing remains, Developer shall remove the existing fences from the newly acquired Project ROW and will be responsible for all costs associated therewith.

7.5 Early ROW Acquisition

TxDOT shall notify the Developer if certain Project ROW parcels are scheduled to be acquired by Governmental Entities prior to issuance of the NTP. The Developer will be updated regularly on the status of the acquisition process for each parcel.

After NTP, Developer shall be responsible for coordinating the scheduling of any remaining early Project ROW acquisition by other Government entities with the Project Schedule. Based on the status of each parcel, TxDOT at its sole discretion may require the Developer to complete the acquisition of certain parcels including the removal of improvements.

8 GEOTECHNICAL

8.1 General Requirements

Developer shall perform all geotechnical investigations, testing, research, and analysis necessary to effectively determine and understand the existing surface and subsurface geotechnical conditions of the Project to be used by Developer to carry out the Work. Developer shall ensure the geotechnical investigations and analyses are both thorough and complete in accordance with TxDOT and FHWA geotechnical requirements, so as to provide accurate information for the design of roadways, pavements, foundations, structures, and other facilities that result in a Project that is safe, and meets the requirements of the Contract Documents.

References to mainline pavement in this section shall include general purpose lanes and managed lanes.

8.2 Design Requirements

8.2.1 Subsurface Geotechnical Investigation by Developer

Developer shall determine the specific locations, depths, frequency, and scope of all subsurface geotechnical investigations, testing, research, and analysis Developer considers necessary to provide a safe and reliable roadway, pavement, foundation, structure, and other facilities for the Project in accordance with TxDOT and FHWA geotechnical requirements.

Developer shall prepare and amend, as needed, their Geotechnical Engineering Reports documenting the assumptions, conditions, and results of the geotechnical investigation and analysis, including the following:

a) The geology of the Project area, including soil and/or rock types, and drainage characteristics

b) Field investigations and laboratory test results used to characterize conditions. Field investigations shall include descriptions of the soil/rock, Texas Cone Penetration test results, in-situ test results, and RQD for rock. If laboratory testing is required then the results shall include moisture content, plasticity index, gradations for each major soil strata change, levels of shrink/swell potential, levels of sulfate (on-site and borrow), soil compressibility, and short-term and long-term strength tests and properties in accordance with TxDOT and ASTM geotechnical testing standards

c) A discussion of conditions and results with reference to specific locations on the Project

d) Design and construction parameters resulting from the geotechnical investigation and analysis, including parameters for the design of pavements, pipes, foundations, structures, slopes, and embankments in accordance with TxDOT and FHWA geotechnical requirements

e) Slope stability analyses for embankment and excavation, including roadway section, and retaining wall slopes including both short-term (undrained) and long-term (drained) conditions, and discussion of design measures undertaken to ensure stability and safety of all slopes. The design minimum factor of safety required for global stability of a slope shall be in accordance with the TxDOT *Geotechnical Manual*. The analysis shall consider the potential for long-term surficial slide failures common to high plasticity clays in Texas, and specific recommendations shall be provided to minimize their occurrence

f) Plan view locations of field sampling (Boring Locations Plan), boring logs and other field data, laboratory test results, calculations, and analyses that support design decisions

The report shall:

a) Ensure that adequate investigation, testing, analysis, design, mitigative measures, and construction planning are applied to assess and provide for the effects of swell pressures from expansive soil and rock materials on foundations, pipes, pavements, and earth retaining structures. They shall address all design features and facility characteristics that could affect expansive soil behavior.

b) Provide design and construction parameters derived from geotechnical investigation.

c) Assess the corrosion potential of the soil and rock materials and conditions that will be encountered, and the impacts to planned surface and subsurface facilities.

Each Geotechnical Engineering Report, upon completion and including any later supplements or amendments shall be submitted to TxDOT for review and comment.

Pavement Design

The TxDOT *Pavement Design Guide* shall be the basis for all pavement designs for the Project, and is supplemented with the requirements contained within this document as identified in the paragraphs in this section. Where there are conflicts between the requirements in these two documents, the requirements in this document shall take precedence.

The number of ESALs and/or the traffic volumes to be used in the pavement designs shall be those provided in Attachment 8-1, Pavement ESALs. Lane distribution factors for both flexible and rigid pavement designs shall be applied in accordance with the following criteria:

Table 8-1. Lane Distribution Factors

Total Number of Lanes in One Direction	Lane Distribution Factor
One or two lanes	1.0
Three lanes	0.7
Four or more lanes	0.6

Developer should expect that subgrade materials will vary throughout the Project limits. Developer shall verify that the materials encountered or imported meet the Effective Modulus of Subgrade Reaction, modulus, or other design subgrade support value as utilized for the structural section design. If the site subgrade materials have a lower value than used for the Proposal-phase pavement designs, Developer shall submit an adjusted pavement design for review and acceptance by TxDOT.

Developer shall prepare separate pavement designs, as applicable, for the following:

a) Managed Lanes, General Purpose Lanes, and frontage road lanes constructed in the Ultimate Project configuration – Developer shall design and construct Managed Lanes, General Purpose Lanes, and frontage road lanes in areas specified as the Ultimate Project in Section 1.2 consistent

with this Section 8 that will yield a design life of thirty (30) years for the type of traffic anticipated in the data provided in the Reference Information Documents and Attachment 8-1.

b) Managed Lanes in areas of existing pavement, not constructed in the Ultimate Project configuration – For areas where Managed Lanes occur on existing pavement and are not specified as the Ultimate Project in Section 1.2, Developer shall evaluate the existing pavement structure and provide a rehabilitation strategy that will ensure an additional ten (10) years of life to remain in the existing pavement for the type of traffic anticipated in the data provided in the Reference Information Documents and Attachment 8-1.

c) Managed Lanes not constructed in the Ultimate Project configuration – In areas where the existing pavement cannot meet the requirements of above, or where the existing pavement must be widened to accommodate the Managed Lanes, and in areas not specified as the Ultimate Project in Section 1.2, Developer shall design and construct a new pavement section consistent with this Section 8 that will yield a design life of twenty (20) years for the type of traffic anticipated in the data provided in the Reference Information Documents and Attachment 8-1.

d) Managed Lane gantry pavement sections - see Section 21

e) General Purpose Lanes in areas of widening and not constructed in the Ultimate Project configuration – Developer shall design and construct the pavement section for General Purpose Lanes in areas specified as interim widening in Section 1.2 consistent with this Section 8 that will:

- yield a design life of twenty (20) years for the type of traffic anticipated in the data provided in the Reference Information Documents and Attachment 8-1; or
- Match the existing pavement cross section

f) Frontage road lanes not constructed in the Ultimate Project configuration – Developer shall design and construct the pavement section for frontage road lanes in areas not specified as the Ultimate Project in Section 1.2 consistent with this Section 8 that will:

- yield a design life of twenty (20) years for the type of traffic anticipated in the data provided in the Reference Information Documents and Attachment 8-1; or
- Match the existing pavement cross section; or
- Overlay with HMAC as necessary to achieve the desired profile alignment

g) General Purpose Lanes, auxiliary lanes and exit/entrance ramps to be retained and rehabilitated – For areas not specified as the Ultimate Project in Section 1.2, Developer shall evaluate the existing pavement structure of General Purpose Lanes, auxiliary lanes and exit/entrance ramps and provide a rehabilitation strategy that ensures an additional ten (10) years of life to remain in the existing pavements for the type of traffic anticipated in the data provided in the Reference Information Documents and Attachment 8-1.

h) Cross-road pavements

i) Service driveways and parking areas

j) Temporary pavement construction areas

Pavement design report(s) shall document the assumptions, considerations, and decisions contributing to Developer's pavement designs, including the following:

a) Pavement design details by location, including structural layer materials, general specifications, and thicknesses

b) Where applicable, life-cycle cost analysis, including the periods for resurfacing, reconstruction, and other rehabilitation measures and what these activities are likely to entail

c) Relevant pavement evaluation data (structural and functional) and condition information on adjacent roads

d) Site conditions which might influence the design and performance of pavements

e) Relevant geotechnical data and drainage requirements including boring logs, laboratory soil test results, and active or passive drainage system design

f) Design criteria used in determining the pavement design(s), including traffic loads, pavement material characterization, environmental conditions, and pavement design life

g) Other considerations used in developing the pavement design(s), including subgrade preparations and stabilization procedures

Developer shall submit to following to TxDOT for review:

a) Pavement Design Reports including any later supplements or amendments

b) Verification of Proposal phase pavement thickness designs

c) Traffic Control Plans associated with subsurface geotechnical or pavement investigations

d) A list of all geotechnical and pavement design software proposed for use

e) Verification plan for effective modulus of subgrade reaction

8.2.1.1 Methodology Enhancements

Recognizing that the development of pavement design methods, products, and procedures are under continuous enhancement within the pavement community, the Developer and TxDOT understand that new methods, procedures, and products may present opportunities for improved pavement design and management during the time frame of this Agreement. Both parties mutually agree to consider the use of new design technologies provided that any such technologies and methods are agreed to by the Developer and approved by TxDOT in writing prior to final implementation.

8.2.1.2 Related Pavement Materials Specifications

Unless otherwise specified herein, pavement material requirements are defined in the most current version of the TxDOT *Standard Specifications for Construction and Maintenance of Highways, Streets, and Bridges* (hereafter referred to as the TxDOT *Standard Specifications*) and per special provisions as provided these Contract Documents. Test procedures identified herein shall be the most current version identified in the Materials Test Procedures, AASHTO or ASTM standards or equivalent guidance as approved or provided by TxDOT.

8.2.1.3 Pavement Type Selection

The following requirements shall be incorporated into the final pavement selection and design:

Mainline and Managed Lanes Pavement. In the case of rigid pavement selection, only Continuously Reinforced Concrete Pavement (CRCP) pavement is acceptable for the mainline pavement.

Shoulders. Pavement for the shoulders of all roadways shall be the same section (materials and depths) as the adjacent roadway pavement.

Toll Zone(s). Toll Zone(s) gantry areas may be exempted from required use of CRCP. The Developer shall coordinate with TxDOT for special reinforcing or pavement design, within toll zone areas. Concrete Pavement Contraction Design (CPCD) shall be selected when Glass Fiber Reinforced Polymer (GFRP) Bars are used. Final design details used on the Project shall be submitted to TxDOT for acceptance.

Ramp Pavement. Ramp pavements shall be constructed with the same section (materials and depths) as the adjacent mainline pavement.

Facility Access Parking. Facility access parking areas shall be Concrete Pavement Contraction Design (CPCD) with a minimum concrete thickness of eight (8) inches unless otherwise specified by the Owner.

Developer shall provide documentation of criteria and rationale for the construction approaches selected to widen pavement sections. Developer shall comply with TxDOT *Pavement Design Guide*, historical performance, district policy, industry guidelines, and research findings when designing the widened sections and selecting construction approaches. Construction joints along the existing and new pavement sections shall be placed as far as possible from the wheel path to improve performance. Geotextiles or stress absorbing membrane interlayer (SAMI) shall be placed over the widening joint to delay reflective cracking.

For all widened sections, including widened toward the median for Managed Lanes, the interface between the new widened pavement and the existing pavement shall provide a uniform surface of the same material type across all adjacent lanes. In areas where an existing asphalt surface is in place and widening is required, a new surface course will be required.

8.2.1.3.1 Rigid Pavement

Design Specification. Rigid pavement shall be designed in accordance with the TxDOT's *Pavement Design Guide* using the design inputs as summarized in the table below.

Table 8-2. Rigid Pavement Design Inputs

28 day Concrete Modulus of Rupture, psi	620
28 day Concrete Elastic Modulus, psi	5,000,000
Effective Modulus of Subbase/Subgrade Reaction, psi/inch	300 psi/inch max.
Serviceability Indices ▪ Initial Serviceability Index ▪ Terminal Serviceability Index	 4.5 2.5
Load Transfer Coefficient	*

Drainage Coefficient	**
Overall Standard Deviation	0.39
Reliability %	95
Design Traffic, 18 Kip Equivalent Single Axle Load (ESAL)	Attachment 8-1
* Table 8-1, *TxDOT Pavement Design Guide, Revised October 2011* ** Table 8-2, *TxDOT Pavement Design Guide, Revised October 2011*	

Effective Modulus of Subgrade Reaction. The Effective Modulus of Subgrade Reaction (k in psi/in) is to be used for design and the value to be achieved at all times during construction activities.

Potential Vertical Rise (PVR). Developer shall design the overall new subgrade and new pavement structure to have a PVR no greater than 1.0 inch as calculated in accordance with TEX-124-E from soil tests in a soil column 15 feet deep as measured from the proposed finished pavement grade. Alternatively, provide materials that result in an Effective Plasticity Index (PI) of less than 25 when calculated to a depth of 8 feet from finished pavement surface for mainline pavements, and to a depth of 7 feet from finished pavement surface for non-mainline pavements. Calculation and sampling requirements for determination of Effective PI are stated in Section 8.3.1 (Pavement Material Requirements).

8.2.1.3.2 Flexible Pavement

Design Methodology. For flexible pavement design, the Developer shall use the TxDOT online *Pavement Design Guide*. The pavement designs shall utilize either the TxDOT FPS 21 procedure or the 1993 *AASHTO Guide for the Design of Pavement Structures* and the latest version of the DARWin computer program, approved by AASHTO. All pavement thickness designs shall be checked using the Modified Texas Triaxial Class design method, and other analyses techniques necessary to prevent premature failure from rutting and fatigue.

Performance Life Requirements. The design life for the Project will be based on the following:

a) *Mainline and Ramps.* For areas in Section 8.2.1 "*Pavement Design*" of the Technical Provisions where a thirty (30) year design life is required, a design life of thirty (30) years shall be used with an initial performance period of at least fifteen (15) years.

b) *Frontage Road and Cross Roads.* For areas in Section 8.2.1 "*Pavement Design*" of the Technical Provisions where a thirty (30) year design life is required, a design life of thirty (30) years shall be used with an initial performance period of twelve (12) years when projected traffic loads are less than 1 million ESALs and fifteen (15) years for more than 1 million ESALs.

Potential Vertical Rise. Developer shall design the overall new subgrade and new pavement structure to have a PVR no greater than 1.5 inch for mainline and 1.5 inches for non-mainline pavements as calculated in accordance with Tex-124-E from soil tests in a soil column 15 feet deep as measured from

the proposed finished pavement. Alternatively, provide materials that result in an Effective Plasticity Index of less than 25 when calculated to a depth of 8 feet from finished pavement surface for mainline and to a depth of 7 feet from finished pavement surface for non-mainline pavements. Calculation and sampling requirements for determination of Effective PI are stated in Section 8.3.1 *Pavement Material Requirements*.

Design Modulus. The Developer shall establish the design modulus using laboratory resilient modulus tests conducted on representative samples of the soils supporting the pavement structures. This design modulus shall be used for either the FPS 21 or AASHTO design procedures, and shall not exceed the Effective Resilient Modulus as described below. Design moduli shall be determined for other pavement layers where the maximum value does not exceed values established from methods and criteria stated below. Design moduli determined from methods identified are irrespective of the pavement design method used, where the material is placed in the pavement structure, and depth of the layer. When it is in the interest of TxDOT to use alternative methods for determining material moduli proposed by the Developer, justification and documentation shall be provided to demonstrate that an equivalent pavement structure will be provided.

(a) Effective Resilient Modulus, (MR). Effective Resilient Modulus testing is only applicable to subgrade materials; that is, natural subgrade or materials imported as embankment and are not stabilized. Determine the MR using the AASHTO laboratory test method T307 for subgrade soil samples over the Project, or segments of the Project, with an adjustment of test results for seasonal variations, per AASHTO *Guide for the Design of Pavement Structures, 1993*. Only load sequence number 7 of 15 (4 psi confining pressure, 4 psi maximum axial stress for Type 2 materials; 10 psi confining pressure, 10 psi maximum axial stress for Type 1 materials) will be used to determine the test result.

Where multiple layers of material are present, MR shall be determined for the predominant soil within three feet in depth from the finished pavement subgrade elevation. Where rock is the predominant subgrade and MR determination is not practical, a maximum MR of 25,000 psi may be assumed.

Run tests on samples at optimum moisture content (OMC), 2% dry of OMC, and 2% wet of OMC. Optimum moisture content shall be determined by the appropriate TxDOT compaction procedure; molding shall be governed by the appropriate method for the material tested as identified in AASHTO T307.

Distribute MR values as shown in Table 8-3 for the region in which the Developer will be constructing the Project. Determine which distribution to apply by selecting the rainfall range appropriate for the Project location from Figure 8-1.

Table 8-3. Regional distribution of months used to determine Effective Resilient Modulus.

Region	Annual Rainfall Range	Moisture Content Weighting in Months		
		- 2% OMC	@ OMC	+ 2% OMC
1	0 – 12	6	4	2
2	12 – 24	4	4	4
3	24 – 36	2	5	5
4	36 – 48	2	4	6
5	48 – 56	0	3	9

(b) Unbound Base and Subbase. Only material meeting the definition of Unbound Base in Section 8.3.1 will be considered; all other unbound materials used as a pavement layer that do not meet this definition shall be considered subgrade/embankment. For materials meeting the requirements of Item 247, TxDOT *Standard Specifications,* the design modulus shall not exceed three times the Effective Resilient Modulus for the layer immediately below the unbound base or subbase layer, and shall not exceed 75,000 psi.

(c) Stabilized Base. Stabilized base materials shall meet the requirements of Stabilized Base in Section 8.3.1, or shall be considered a subgrade or subbase material that may require stabilization. The design moduli of stabilized base materials shall be established by the greater of: (a.) the ratio of stress to strain in a near-linear portion of the loading curve during UCS testing, or (b.) ten times the Effective Resilient Modulus for subgrade, whichever is greater. Refer to Table 3 for asphalt stabilized base moduli.



Figure 8-1. Rainfall graph for determining regional soil testing requirements

(d) ***Stabilized Subbase and Stabilized Subgrade.*** Materials shall meet the requirements of Subbases in Section 8.3.1 or the material shall be regarded as subgrade material and may be subject to MR measurements. Stabilized subgrade and stabilized Subbases may be incorporated as a structural layer and shall have a design modulus equal to the greater of: (a.) the ratio of stress to strain in a near linear portion of the loading curve during UCS testing, or (b.) two times the value of the Effective Resilient Modulus of the subgrade.

(e) ***Design Structural Values.*** Use Table 8-4 for structural material design values. For materials not listed, provide documented testing establishing the design value appropriate for the design procedure being used.

Table 8-4. Design Structural Values

Material Type	2004 Specification	Maximum Modulus for FPS 21	AASHTO layer coefficient (max.)
Dense-Graded Hot Mix Asphalt	Item 340 (for temporary pavement), 341 (for permanent pavement)	Combined HMA thickness: ≤8" use 500ksi > 8.0" use 650ksi	 0.44 0.45
Permeable Friction Course	Item 342	300 ksi	0.30
Performance Design Mixtures	Item 344	Combined HMA thickness: ≤ 6.0" use 650ksi 6"<T≤8" use 700ksi > 8.0" use 850ksi RBL: 350ksi	 0.45 0.46 0.47 RBL: 0.40
Stone-Matrix Asphalt	Item 346	Same as Item 344	Same as Item 344
Unbound Base	Item 247, Grade 1	*75ksi	0.14
Stabilized Base ▪ Cement ▪ Asphalt	 Items 275 and 276 Item 292	 *200ksi 350 ksi	 0.16 0.34
Stabilized Subgrade or Sub-base ▪ Hydrated Lime ▪ Cement	 Item 260 Item 275	 *30ksi *30ksi	 0.12 0.12

* Maximum design values.

Poisson's Ratio. Use 0.20 for cement stabilized or fly ash stabilized materials meeting the requirements of Items 275, 276 and 265 as defined in the most recent edition of the TxDOT *Standard Specifications*. Use 0.35 for all other materials not identified in the aforementioned Items; except for subgrade or embankment/fill materials, use 0.4.

Truck Volumes. The percentage of truck traffic as well as the annual growth percentage in truck volumes shall be those which are provided in Attachment 8-~~2~~1, Truck Volumes.

Initial ADT and 20yr projected ADT. The Initial ADT is the projected ADT when the Project is opened for public access as provided in Attachment 8-~~3~~1, Average Daily Traffic. The ADT projected to occur 20 years after the Project is opened to public access is provided in Attachment 8-~~4~~1, Projected Average Daily Traffic.

Initial Serviceability Index. The initial serviceability index for Mainline pavements on this Project shall be 4.5. Frontage road pavements shall use an initial serviceability index of 4.2.

Serviceability Index (SI) after Overlay. The SI after overlay shall be 4.0.

Terminal (Minimum Acceptable) Serviceability Index. The terminal serviceability index at the end of any performance period for this Project shall be 3.0 (mainline and frontage roads). A serviceability index of 2.5 may be used if the HMAC thickness exceeds eight inches.

Serviceability Index After a Structural Overlay (FPS design only). Where no level up course of HMA is placed prior to a single lift HMA overlay, use 4.0. Where a level up used or multiple HMA lifts, use 4.2.

Design Reliability or Confidence Level. The reliability factor shall be 95% for mainline, ramps, frontage roads and cross roads.

Maximum Period of Overlay. The maximum planning period for any overlay following the initial performance period of this Project shall not exceed fifteen (15) years. The minimum period shall be eight (8) years.

Overall Standard Deviation (AASHTO design only). Use 0.49.

8.2.2 Rehabilitation of Existing Pavements

Pavement rehabilitation includes the resurfacing and restoration work undertaken to restore serviceability, to extend the service life of existing pavements, and to achieve the performance measures identified in Section 8.2.1 of the Technical Provisions. This can include partial recycling of the existing pavement, placement of additional surface materials, or other work necessary to return existing pavements to a condition of structural or functional adequacy.

The Developer shall prepare and submit a pavement rehabilitation plan after evaluating the existing pavements to determine the adequacy of past performance, determine failure mechanisms, and determine the extent of rehabilitative effort necessary. The structural and functional characteristics shall be evaluated either by destructive or nondestructive tests and surveys as outlined in *Texas Pavement Design Manual*. Destructive testing involves coring and boring to obtain representative samples for laboratory evaluation and to observe the in situ condition of the various layers. Nondestructive tests and surveys can be performed to acquire data that can be reduced to structural properties, presence of moisture, degree of distress, friction properties, and smoothness. Based on the pavement evaluation, the Developer shall select and submit to TxDOT for approval the rehabilitation plan considering cost, existing problems, and prevention of future problems.

8.2.2.1 Flexible Pavement Rehabilitation

The flexible pavement rehabilitation shall include but is not limited to overlay, milling and overlay, or equivalent service life as determined by TxDOT of the existing asphalt pavement to mitigate the effects of per ride rutting, cracking, and other distresses as identified during the evaluation of the existing pavements; and provide for a low maintenance surface course that provides for uniformity across adjacent lanes. The required voids on mineral aggregate (VMA) and the asphalt concrete binder shall be selected based on the pavement cores collected as part of the pavement rehabilitation plan.

Hot In-place Recycling (HIPR) and Cold In-place Recycling (CIPR) shall be used to rehabilitate only AC pavements with surface distresses and texture issues with adequate support by the underlying base layers. HIPR and CIPR shall not be used for pavements with delaminations in the top 2 inches, rutted pavements, heavily patched pavements, and chip-sealed pavements. The HIPR technique shall be used to mill the top one to two inches of the existing AC layer then place back two inches of AC overlay. The CIPR shall be used to mill 4 to 6 inches of existing AC pavements. Flexible pavement hot mix overlays shall be designed in accordance with *Texas Pavement Design Manual* using FPS-19. Flexible pavement rehabilitation shall conform to Items 351 and 358 of *TxDOT Standard Specifications*.

8.2.2.2 Rigid Pavement Rehabilitation

Rigid pavements full depth repair (FDR) shall be used if the rehabilitated area is at least 6 ft long and at least half a full lane width. The limits of the FDR rehabilitation can be determined by visual inspection as part of the pavement survey. Only diamond-bladed concrete saw-cuts can be used to saw-cut the pavement sections. The saw-cut operations shall be adjusted so that the subsequent repair operations can immediately follow. Concrete used to rehabilitate rigid pavements shall conform to Items 360, 361, and 421 of *TxDOT Standard Specifications* with a maximum water-cement ratio of 0.45. Concrete strength shall be estimated using TxDOT Tex-426-A test (Estimating Concrete Strength by the Maturity Method).

Partial pavement depth repair (PDR) shall be limited to shallow spallings with depths less than four inches.

Concrete overlays can be used to rehabilitate CRCP pavements. The thickness of concrete overlays shall be determined based on the structural capacity of the existing pavement under the existing conditions and the design structural capacity required based on future traffic demands. Longitudinal steel shall be used in the overlay if the overlay thickness is more than 40% of the existing CRCP thickness. Concrete overlays shall only be placed on rough surfaces prepared using shotblasting to increase the bond between the overlay and the existing concrete pavements. The concrete and the aggregates of the concrete overlay shall be compatible with those of the existing pavement. The maximum aggregate size of the concrete overlay shall be less than one-third the overlay thickness.

8.3 Construction Requirements

8.3.1 Pavement Materials Requirements

The Developer shall incorporate the following requirements into the preparation of the initial pavement designs for the proposal and the subsequent final pavement designs, plans, quality control and quality assurance programs, and the field construction procedures. Subject to approval by the TxDOT, alternate material specifications and construction requirements may be proposed by the Developer provided the objectives of the Project are met and an equivalent pavement structure is provided.

Subgrade Material Composition. The Developer shall analyze subgrade material composition, design the pavement structure, and perform necessary construction procedures to eliminate soluble sulfate induced heave. When soluble sulfates may present a potential for a reaction detrimental to the pavement structure, Developer shall submit alternate designs and/or construction procedures for TxDOT approval.

When quantities of soluble sulfates detected are greater than 500 ppm, the Developer shall determine the source of the sulfate and whether there are greater concentrations existing or that would be created when pulverized in and surrounding the sampled location. Use the TxDOT Guidelines for Treatment of Sulfate-Rich Soils and Bases in Pavement Structures to assist with testing and detection and construction practices. No soil shall have additives introduced to such material that would cause a detrimental reaction to the pavement structure or its ride quality as measured by the International Roughness Index (IRI).

Effective Plasticity Index (PI). The same method of determining Effective PI shall be used for both design and verification of design. Developer shall determine the Effective PI for un-stabilized subgrade to the depth specified below finished pavement surface. The Effective PI shall be determined, using Tex-106-E, via a process that proportionately accounts for the plasticity contribution of the soil binder (material passing the #40 sieve) for each individual one foot layer, or portion thereof, to the depth specified. The Effective PI is ultimately a weighted average of the Plasticity Indices of the material in the soil column analyzed. For example, the sum of all PI measurements representative of each one foot deep sample tested divided by the total depth designated by the pavement type. Use soil to the depth of 8 feet for mainline pavements and 7 feet for non-mainline pavements for calculation of Effective PI. Concrete, hot mix asphaltic concrete, stabilized base courses, granular base, and stabilized subgrade/embankment are considered to be non-swelling with no PI. Stabilized materials shall meet material requirements stated herein.

Unbound Base. Provide the appropriate unbound base as recommended in the TxDOT *Pavement Design Guide*. A minimum placement thickness of 6 inches is required.

Stabilized Base. Stabilized base may either be modified with chemical additives or asphaltic binders. Materials to be stabilized shall meet the requirements of either Grade 1, Grade 2, or Grade 5 base as defined by Item 247 of the TxDOT *Standard Specifications* or appropriate special provisions, and shall have a minimum thickness of 6 inches. Asphalt stabilized base material will meet the requirements of Item 292 of the TxDOT *Standard Specifications*. When chemical additives are used to stabilize base, Table 5 will be used to determine the stabilizer content. Stabilized base will be designed to achieve the unconfined compressive strength shown in Table 5 immediately following a ten (10) day capillary moisture conditioning. Moisture conditioning will be conducted in a similar method as that used in TEX-121-E.

Table 8-5. Minimum and maximum retained unconfined compressive strength values to be achieved when using chemical additives for stabilization, by pavement type.

Pavement Type	Minimum UCS (psi)	Maximum UCS (psi)
Flexible Pavement	300	500
Rigid Pavement	500	750

Subbases.

(a) ***Granular Materials***. Materials classified by the Unified Soil Classification System as any of the following: GP, GM, SW, SP, SM, SC, ML, shall be stabilized if present within 30 inches of the finished pavement surface. The aforementioned materials may be used as a subbase and included as a structural layer when stabilized and meet the requirements of stabilized subbase as defined herein. These materials shall be stabilized, when required, to achieve a minimum layer thickness of 6 inches. Untreated granular base meeting the requirements of Item 247, Grade 1 or 2 may replace these materials without restriction.

(b) ***Stabilized Subbase.*** Materials not included in Granular Materials above, do not meet the requirements of Item 247, TxDOT Standard Specifications, or materials that have a Plasticity Index (PI) value less than 25, may be stabilized and used as a structural layer. For structural layers, provide a minimum 6-inch thickness of compacted material. Stabilized subbase materials shall be designed to achieve not less than 100 psi unconfined compressive strength immediately following a ten (10) day capillary moisture conditioning. Moisture conditioning will be conducted in a similar method as that used in TEX-121-E. These materials shall be designed as defined in test methods used for the selected additive.

(c) ***Stabilized Subgrade.*** If subgrade stabilization is used for purposes of providing a working platform then no structural benefits can be claimed and the stabilized subgrade shall not be included in the pavement design. For structural layers, provide a minimum 6-inch thickness of compacted material. If a structural layer is required, design and mold subgrade material with the desired additive using the TxDOT test method appropriate for the additive incorporated. The design shall achieve not less than 100 psi unconfined compressive strength immediately following a ten (10) day capillary moisture conditioning conducted in a method similar to that used in TEX-121-E.

Underseal. The developer shall place a one (1) course surface treatment as an underseal directly on top of any untreated or treated base layer and/or prior to all hot mix asphalt concrete overlays.

Surface Course. The surface course for all roadways utilizing flexible pavement design shall be a minimum of 2 inches of asphaltic concrete pavement.

Mix Selection. Where flexible pavement structures are selected, the final surface mix for mainline lanes and ramps shall be Stone Matrix Asphalt (SMA) meeting the requirements of Item 346 or a Permeable Friction Course (PFC) meeting the requirements of Item 342. The final surface mix for frontage roads and cross roads shall be Stone Matrix Asphalt (SMA) meeting the requirements of Item 346 when the combined HMA thickness is greater than 6.0 inches, or a regular dense-graded mix Type C or Type D meeting the requirements of Item 341 when the combined HMA thickness used is less than 6.0 inches.

8.3.2 Construction Verification

General. The independent Construction Quality Assurance Firm (CQAF) shall perform the Developer's quality acceptance. The construction verification tasks described below are part of the CQAF quality acceptance efforts.

Effective Modulus of Subgrade Reaction. The Developer shall verify that the design effective modulus of subgrade reaction has been achieved through the field construction activities. This verification process shall include field sampling and testing activities designed to provide confirmation of the design effective

modulus of subgrade reaction. This verification process shall be described in a plan that includes, but not limited to, the verification methodology, example calculations, reference documents, and frequency of field sampling and testing. The Developer shall submit this verification plan to the TxDOT for review and comment.

Effective Resilient Modulus, (MR). The Developer shall provide subgrade modulus verification testing in accordance with AASHTO T307. Retrieve a randomly selected verification sample at a minimum rate of one sample (three replicates per sample) for each 2500 linear feet of roadbed; where the roadbed has a dimensioned width greater than 100 feet, one additional sample will be collected and tested. Frontage and other access roads are sampled and tested independently if more than 100 feet separates the roadbeds or are not parallel to the mainline alignment. Additional samples shall also be taken at each location where a significant and recognizable change in subgrade material (a change in USCS classification) is encountered during grading operations.

Where multiple layers of material are present, MR shall be determined for the representative soil within three feet in depth from the finished pavement subgrade elevation. Where rock is the predominant subgrade and MR determination is not practical, a maximum MR of 25,000 psi may be assumed.

Regardless of the position of the layer or material sampled and tested, use only the AASHTO T307 load sequence number 7 of 15 for verification testing (4 psi confining pressure, 4 psi maximum axial stress for Type 2 materials; 10 psi confining pressure, 10 psi maximum axial stress for Type 1 materials). The MR results from this testing shall be compared to the Effective MR selected for use in designing the pavement structure, to confirm that the material meets the design criteria. If the materials fail to meet the criteria, Developer shall be responsible to take corrective action that is acceptable to the TxDOT.

Effective Plasticity Index (PI). The Developer shall demonstrate to TxDOT that the specified design requirements are met by randomly selecting at least one location per 2,500 linear feet of roadbed and shall sample the subgrade materials to a depth below finished pavement surface as designated by the pavement design. Mainline roadbeds, ramps, and frontage roadbeds are considered independently. Sampling shall also take place when a recognizable change in the subgrade material is encountered during grading operations as determined by a change in Unified Soil Classification System classification.

The Developer shall provide for the testing of these materials in accordance with Tex-106-E to determine the Effective PI. The results shall be compared to design requirements to confirm that the strata meet the design criteria. If the materials fail to meet the criteria, Developer shall be responsible to take corrective action that is acceptable to TxDOT.

Smoothness Specification. Smoothness of the pavement constructed shall conform to the requirements of TxDOT Item 585, Ride Quality for Pavement Surfaces, amended as cited below:

Article 585.3D. Acceptance Plan and Pay Adjustments. The entire section is voided and replaced by the following:

TxDOT will evaluate profiles based on the CQAF test results to determine acceptance and corrective action. Corrective action acceptable to TxDOT is required, at Developer's sole expense, for any 0.1-mile section that measures an average IRI in excess of 75 inches per mile for rigid pavements, or in excess of

65 inches per mile for flexible pavements. After making corrections, re-profile the pavement section to verify that corrections have produced the required improvements.

Use diamond grinding or other methods approved by TxDOT to correct surface areas that have more than 1/8 inch variation between any two contacts on a 10-foot straightedge. Use diamond grinding or other approved methods to remove localized roughness as determined using an inertial profiler in accordance with TEX-1001-S. For asphalt concrete pavements, fog seal the aggregate exposed from diamond grinding.

Article 585.4 Measurement and Payment. The entire section is voided.

9 LAND SURVEYING

9.1 General Requirements

Developer shall provide accurate and consistent land surveying and mapping necessary to support ROW acquisition, design, and construction of the Project.

Developer shall review existing survey data and determine the requirements for updating or extending the existing survey and mapping data. Developer is responsible for the final precision, accuracy, and comprehensiveness of all survey and mapping.

9.2 Administrative Requirements

9.2.1 Standards

Developer shall ensure that all surveying conforms to the *General Rules of Procedures and Practices* of the Texas Board of Professional Land Surveying. Developer shall ensure that any person in charge of a survey field party is proficient in the technical aspects of surveying.

9.2.2 Right-of-Entry

Developer shall secure written permission prior to entering any private property outside the ROW. It shall be Developers' sole responsibility to negotiate this permission and Developer shall be responsible for any and all damages and claims resulting from that ingress. Proper documentation of right-of-entry shall be maintained at all times by Developer.

9.2.3 Survey by TxDOT

In performing surveys for other adjoining projects, TxDOT may need to verify and check Developer's survey work. Developer shall coordinate with the developer of the adjoining project regarding planned construction activities. Developer shall notify TxDOT within two (2) Business Days if TxDOT stakes and marks are altered or disturbed.

9.3 Design Requirements

9.3.1 Units

All survey Work shall be performed in the U.S customary units system of measurement. Work shall conform to state plane coordinates. The surface adjustments factors for the Project are as follows:

	State plane to surface		**Surface to state plane**	
	NAD 83	NAD 27	NAD 83	NAD 27
Dallas	1.000136506	1.000120000	0.999863513	0.999880014
Denton	1.000150630	1.000120000	0.999849393	0.999880014

9.3.2 Survey Control Requirements

Developer shall base all additional horizontal and vertical control on the Level 2 and Level 3 control provided by TxDOT.

Developer shall establish and maintain additional survey control as needed and final ROW monumentation throughout the duration of the Project. Developer shall tie any additional horizontal and vertical control for the Project to the TxDOT-supplied Secondary (Level 3) control network. If Developer chooses to use GPS methods, Developer shall meet the accuracy of the appropriate level of survey as defined in the TxDOT *GPS User's Manual* and shall utilize the survey control to be provided by TxDOT. Additionally, GPS survey shall require the use of the State's VRS Network, observed three (3) times during the day and read to +/- 0.04 hundredth of a foot.

All control points shall be set and/or verified by a Registered Professional Land Surveyor licensed in the State of Texas.

Developer shall establish and maintain a permanent survey control network. The control network should consist of, at a minimum, monuments set in intervisible pairs at spacing of no greater than two (2) miles.

Monuments shall be TxDOT bronze survey markers installed in concrete and marked as directed by the most current edition of the TxDOT Survey Manual. Developer shall replace all existing survey monuments and control points disturbed or destroyed. Developer shall make all survey computations and observations necessary to establish the exact position of all other control points based on the primary control provided.

Developer shall deliver to TxDOT a listing of all primary and secondary control coordinate values, original computations, survey notes, and other records, including GPS observations and analysis made by Developer as the data are available.

9.3.3 Conventional Method (Horizontal & Vertical)

If Developer chooses to use conventional methods to establish additional horizontal control, Developer shall meet the accuracy of the appropriate level of survey as defined in the following tables.

9.3.3.1 Horizontal Accuracy Requirements for Conventional Surveys

Horizontal control is to be established (at a minimum) on the Texas State Plane Coordinate System NAD 83.

	Level 3	Level 4	Remarks and Formulae
Error of Closure	1: 50,000	1:20,000	Loop or between monuments
Allowable Angular Closure	± 3" $\sqrt{N}$	± 8" $\sqrt{N}$	N= number of angles in traverse
Accuracy of Bearing in Relation to Course *	± 04"	± 10"	Maximum for any course
Linear Distance Accuracy (Minimum Length of Line)	1: 50,000 (2,500 feet)	1: 20,000 (1,000 feet)	
Positional Tolerance of Any Monument	AC/50,000	AC/20,000	AC = length of any course in traverse

Adjusted Mathematical Closure of Survey (No Less Than)	1:200,000	1:200,000	

* TxDOT policy requires all bearings or angles be based on the following source: Grid bearing of the Texas Coordinate System of 1983, with the proper zone and epoch specified.

All data shall be tied to TxDOT's VRS network, collection of data shall be adjusted to Dallas and Denton County scale factor.

9.3.3.2 Vertical Accuracy Requirements for Conventional Surveys

Vertical control shall be established (at a minimum) on the North American Vertical Datum of 1988 (NAVD 1988).

	1st ORDER	2nd ORDER	3rd ORDER	REMARKS AND FORMULAE
Error of Closure	0.013 feet $\sqrt{K}$	0.026 feet $\sqrt{K}$	0.039 feet $\sqrt{K}$	Loop or between control monuments
Maximum Length of Sight	250 feet	300 feet		With good atmospheric conditions
Difference in Foresight and Backsight Distances	±10 feet	±20 feet	±30 feet	Per instrument set up
Total Difference in Foresight and Backsight Distances	±20 feet per second	±50 feet per second	±70 feet per second	Per total section or loop
Recommended Length of Section or Loop	2.0 miles	3.0 miles	4.0 miles	Maximum distance before closing or in loop
Maximum Recommended Distance Between Benchmarks	2000 feet	2500 feet	3000 feet	Permanent or temporary benchmarks set or observed along the route
Level Rod Reading	± 0.001 foot	± 0.001 foot	± 0.001 foot	

Recommended Instruments and Leveling Rods	Automatic or tilting w/ parallel plate micrometer precise rods	Automatic or tilting w/ optical micrometer precise rods	Automatic or quality spirit standard, quality rod	When two or more level rods are used, they should be identically matched
Principal Uses	Broad area control, subsidence or motion studies jig & tool settings	Broad area control, engineering projects basis for subsequent level work	Small area control, drainage studies, some construction and engineering	

9.3.4 Right of Way Surveys

Developer shall base all surveys on the horizontal and vertical control network provided by TxDOT.

9.3.4.1 Accuracy Standard

In performing right of way surveys consisting of boundary locations, Developer shall meet the accuracy standards of the appropriate level of survey as defined in the following table.

CHART OF TOLERANCES

	URBAN / RURAL	URBAN BUSINESS DISTRICT	REMARKS AND FORMULAE
Error of Closure	1:10,000	1:15,000	Loop or between Control Monuments
Angular Closure	15" $\sqrt{N}$	10" $\sqrt{N}$	N = Number of Angles in Traverse
Accuracy of Bearing in Relation to Source *	20 "	15 "	Sin α = denominator in error of closure divided into 1 (approx.)
Linear Distance Accuracy	0.1 foot per 1,000 feet	0.05 foot per 1,000 feet	Sin α x 1000 (approx.) where ± = Accuracy of Bearing
Positional Error of any Monument	AC/10,000	AC/15,000	AC = length of any course in traverse
Adjusted Mathematical Closure of Survey (No Less Than)	1:50,000	1:50,000	

* TxDOT policy requires all bearings or angles be based on the following source: Grid bearing of the Texas Coordinate System of 1983, with the proper zone and epoch specified.

9.3.5 Survey Records and Reports

Developer shall produce a horizontal and vertical control report including coordinate listing, maps showing control, preparation of standard TxDOT data sheets for all primary control, monument description and location description of all primary and secondary survey control points installed, marked and referenced along with a listing of the existing control used to create the installed control points. Control from adjoining, incorporated, or crossed roadway projects, which are currently in design, will be located and a comparison of the horizontal and vertical values will be shown. Developer shall provide survey records and reports to TxDOT upon request.

Developer may use an electronic field book to collect and store raw data. Developer shall preserve original raw data and document any changes or corrections made to field data, such as station name, height of instrument, or target. Developer shall also preserve raw and corrected field data in hardcopy output forms in a similar manner to conventional field book preservation.

Field survey data and sketches that cannot be efficiently recorded in the electronic field book shall be recorded in a field notebook and stored with copies of the electronic data.

All field notes shall be recorded in a permanently bound book. (Loose leaf field notes will not be allowed). Developer shall deliver copies of any or all field notebooks to TxDOT upon request.

9.4 Construction Requirements

9.4.1 Units

All survey Work shall be performed in the U.S customary units system of measurement. Work shall conform to state plane coordinates.

9.4.2 Construction Surveys

Developer shall perform all construction surveys in accordance with the design requirements.

9.5 Deliverables

9.5.1 Survey Records

Developer shall deliver to TxDOT, for its review and acceptance, a listing of all primary, secondary control coordinate values, original computations, survey notes and other records including GPS observations and analysis made by Developer within ninety (90) days of Final Acceptance.

9.5.2 Final ROW Surveying and Mapping

Developer shall coordinate with TxDOT regarding the assignment of right of way Control Section Job (CSJ) numbers for each new mapping project.

The documents produced by the Surveyor, or the Surveyor's Subcontractors, are the property of TxDOT, and release of any such document must be approved by TxDOT. All topographic mapping created by Developer shall be provided to TxDOT in digital terrain model format using the software and version thereof being used by TxDOT at the time the mapping is developed.

9.5.3 ROW Monuments

Upon final submittal of the ROW documents to TxDOT, Developer shall set, using permanent and stable monuments as defined in Section 663.17 of the General Rules of Procedures and Practices of the Texas Board of Professional Land Surveying (TBPLS), all significant points along all ROW lines of the Project including the following:

a) Points of curvature (PCs)

b) Points of tangency (PTs)

c) Points of intersection (PIs)

d) Points of compound curvature (PCCs)

e) Points of reverse curvature (PRCs)

f) All intersecting crossroad ROW lines and all property line intersections with the ROW line. These monuments shall be ½-inch iron rods, driven just below surface level, capped by a TxDOT-labeled aluminum cap (rod-and-cap monument)

g) All beginning and ending points of Control of Access (Denied) lines

Upon completion of the ROW acquisition and all construction work, such that the final ROW lines will not be disturbed by construction, Developer shall replace all rod-and-cap monuments located on the final ROW line at all points of curvature (PCs), points of tangency (PTs), points of intersection (PIs), points of compound curvature (PCCs), and points of reverse curvature (PRCs), and all intersecting crossroad ROW lines, with TxDOT Type II monuments (constructed according to current TxDOT specifications). Developer shall monument with a TxDOT Type II monument all final ROW lines where the distance between such significant ROW line points exceeds 1500 feet. ROW line intersections with property lines shall remain monumented by a ½-inch iron rod with a TxDOT aluminum cap (rod-and-cap monument).

Developer shall purchase all materials, supplies, and other items necessary for proper survey monumentation.

Developer shall submit updated maps with the monumentation information. (This is for final monumentation set, for example, type II, and type of monuments set, etc.) All deed recording information to be added to the map sheets in the ownership blocks on the map sheets.

9.5.4 Record Drawings and Documentation

Developer shall submit the following as part of the Record Drawings and as a condition of Final Acceptance:

a) A listing of all primary and secondary control coordinate values, original computations and other records including Global Positioning System (GPS) observations and analysis made by Developer

b) Copies of all survey control network measurements, computations, unadjusted and adjusted coordinate and evaluation values; and

c) Survey records and survey reports.

Developer shall produce reports documenting the location of the as-built alignments, profiles, structure locations, Utilities, and survey control monuments. These reports shall include descriptive statements for the survey methods used to determine the as-built location of the feature being surveyed. Developer's as-built data shall include the coordinate types (x, y, and/or z) and feature codes in the same format in which the preliminary construction data was generated. Where data has been provided to Developer from TxDOT in an x, y, z only coordinate format, or z only coordinate format, Developer shall provide TxDOT with data in an x, y, z only coordinate format or z only coordinate format.

10 GRADING

10.1 General Requirements

Developer shall conduct all work necessary to meet the requirements of grading, including clearing and grubbing, excavation and embankment, removal of existing buildings, pavement and miscellaneous structures, subgrade preparation and stabilization, dust control, aggregate surfacing and earth shouldering, in accordance with the requirements of this Section 10.

Developer shall demolish or abandon in place, all existing structures within the Project ROW, including but not limited to, pavements, bridges, and headwalls that are no longer required for service, or are required to be treated as described in Section 4 (Environmental). Any features that are abandoned in place shall be removed to at least 2 feet below the final finished grade or 1 foot below the pavement stabilized subgrade and drainage structures. Developer shall ensure that abandoned structures are structurally sound after abandonment.

10.2 Preparation within Project Limits

Developer shall develop, implement, and maintain, for the Term, a Demolition and Abandonment Plan that considers types and sizes of Utilities and structures that will be abandoned during the Term. The plan shall ensure that said structures are structurally sound after the abandonment procedure. The plan shall account for conditions in the Ultimate Project and Draft Interim Schematic configuration and shall be submitted to TxDOT for approval no later than sixty (60) days prior to the scheduled date for NTP2.

TxDOT reserves the right to require Developer, at any time to salvage and deliver to a location designated by TxDOT within the TxDOT District in which the Project is located, any TxDOT-owned equipment and materials in an undamaged condition. TxDOT reserves the right to require Developer to salvage and deliver to a reasonable location designated by TxDOT any ITS equipment and materials in an undamaged condition.

Unless otherwise specified by TxDOT, the material from structures designated for demolition shall be Developer's property. All material removed shall be properly disposed of by Developer outside the limits of the Project.

TxDOT reserves the right to remove buildings to level one finished floor or other appropriate condition on ROW acquired by TxDOT for the Project.

10.3 Slopes and Topsoil

Developer shall exercise Good Industry Practice regarding design limitations and roadside safety guidelines associated with the design of slopes along roadways. Developer shall adjust grading to avoid and minimize disturbance to the identified waters of the U.S.

Developer shall perform finished grading and place topsoil in all areas suitable for vegetative slope stabilization (and areas outside the limits of grading that are disturbed in the course of the Work) that are not paved. Developer shall use only materials and soils next to pavement layers that do not cause water or moisture to accumulate in any layer of the pavement structure. For areas outside Developer's limits of maintenance, Developer shall provide stable slopes. For slopes steeper than 4:1, Developer shall submit to TxDOT a slope stability analysis that demonstrates the adequacy of Developer's design. Developer shall submit the slope stability analysis to TxDOT for approval with the Released for Construction Documents.

10.4 Sodding

Block sod shall be placed at all grate inlets, manholes and culvert headwalls.

11 ROADWAYS

11.1 General Requirements

The objectives of the Project include the provision of a safe, reliable, cost-effective, and aesthetically-pleasing corridor for the traveling public. The requirements contained in this Section 11 provide the framework for the design and construction of the roadway improvements to help attain the Project objectives.

Developer shall coordinate roadway design, construction, and maintenance with other Elements of the Project to achieve the objectives of the Project.

Where changes to the roadway geometrics result in revisions to the Project ROW, Developer is responsible for demonstrating the proposed change is an equally safe alternative as well as the initiation and progression of all environmental and public involvement processes in coordination with TxDOT. Developer shall perform all ROW services that are necessitated by proposed changes in accordance with the Contract Documents.

11.2 Design Requirements

Developer shall coordinate its roadway design with the design of all other components of the Project, including aesthetics. The Project roadways shall be designed to integrate with streets and roadways that are adjacent or connecting to the Project. All design transitions to existing facilities shall be in accordance with the TxDOT *Roadway Design Manual*.

Developer shall design all Elements in accordance with the applicable design criteria and Good Industry Practice based on the Design Speeds for various Elements.

The Project roadways shall be designed to incorporate roadway appurtenances, including fences, noise attenuators, barriers, and hazard protection as necessary to promote safety and to mitigate visual and noise impacts on neighboring properties.

Existing concrete traffic barrier may be reused on the Project. The reused concrete traffic barriers shall be free of Defects, appropriately placed and correctly installed at the correct height and distance from roadway or obstacles. Installation and repairs shall be carried out in accordance with the requirements of NCHRP 350 standards.

11.2.1 Control of Access

Unless shown to be deleted in the Draft Interim Schematic, Developer shall maintain all existing property accesses, including those not shown on the Draft Interim Schematic, and shall not revise control of access without TxDOT review and the written agreement of the affected property owner. Developer shall not be required to maintain property access directly adjacent to the depressed section of the Belt Line Interchange improvements. Station ranges corresponding to this section are as follows:

- Northbound Frontage Road: Station 737+55 to Station 758+05
- Southbound Frontage Road: Station 738+61 to Station 757+91
- Belt Line Road: Station 102+00 to Station 123+25

11.2.2 Roadway Design Requirements

Developer shall design the Elements of the Project to meet or exceed the geometric design criteria as shown in Attachment 11-1 Roadway Design Criteria.

Developer shall coordinate, design and construct the improvements on crossing streets in accordance with the Governmental Entity having jurisdiction of said roadway.

At newly constructed intersections the Developer shall design and construct the following improvements:

- Cross sectional elements as shown in the Draft Interim Schematic.
- Roadside features as shown in the Draft Interim Schematic and/or IH-35E Corridor Aesthetic Guidelines.
- Utilities shall be installed and/or adjusted as needed to accommodate the intersection construction.
- Street crossings including curb ramps and crosswalks as needed to accommodate pedestrian travel.

At reconstructed intersections the Developer shall design and construct or adjust existing facilities as needed to implement the following improvements:

- Cross sectional elements as shown in the Draft Interim Schematic.
- Roadside features as shown in the Draft Interim Schematic and/or IH-35E Corridor Aesthetic Guidelines.
- Utilities shall be adjusted as needed to accommodate the intersection reconstruction.

11.2.3 Superelevation

Existing superelevation in areas where ramps are to connect to existing pavement may be retained at existing superelevations. Pavement widening may be constructed by extending the existing pavement cross slope. Superelevation transitions shall be designed and constructed such that zero percent cross-slopes will not occur on bridges or on grades flatter than 0.35 percent.

Developer may maintain the existing pavement normal crown in overlay sections so long as it shall not be flatter than 1.5 percent. At normal crowns, pavement widening adjacent to existing pavement shall be constructed on a 2.5 percent cross slope. The transition from existing cross slope to 2.5 percent shall occur within 1-foot of the closest lane line to the roadway widening.

11.2.4 Roadway Design Deviations

TxDOT will provide design exceptions for the Draft Interim Schematic at the locations indicated below. If, upon further design, additional deviations are identified, the Developer shall submit a request for design exception, variance, or waiver to TxDOT for review. Any additional design exceptions, variances, or waivers not listed below are the responsibility of Developer and subject to TxDOT and FHWA Approval.

11.2.4.1 Design Exceptions

Lane Width

The width of the proposed northbound and southbound General Purpose lanes may be reduced from 12-ft to 11-ft at the following station limits:

Northbound General Purpose Lanes:

- 11 ft from STA 584+00 to STA 1887+35
- 11 ft from STA 1933+85 to STA 2106+00

Southbound General Purpose Lanes:

- 11 ft from STA 587+00 to STA 1860+10
- 11 ft from STA 1934+63 to STA 2106+00

Shoulder Width

The General Propose Lanes may have reduced shoulder widths as indicated below at the following station limits:

Northbound General Purpose Lanes – Inside Shoulder:

- 2 ft from STA 584+00 to STA 660+23
- 2 ft from STA 661+37 to STA 670+20
- 2 ft from STA 671+99 to STA 680+59
- 2 ft from STA 691+70 to STA 779+11
- 2 ft from STA 795+56 to STA 831+12
- 2 ft from STA 841+12 to STA 857+55
- 2 ft from STA 898+62 to STA 970+17
- 2 ft from STA 987+97 to STA 1031+25
- 2 ft from STA 1038+35 to STA 1045+79
- 2 ft from STA 1063+88 to STA 1124+60
- 2 ft from STA 1135+67 to STA 1232+22
- 2 ft from STA 1244+09 to STA 1292+48
- 2 ft from STA 1357+82 to STA 1376+05
- 2 ft from STA 1448+48 to STA 1619+00
- 2 ft from STA 1626+81 to STA 1682+70
- 5 ft from STA 1691+67 to STA 1706+11
- 2 ft from STA 1717+19 to STA 1777+27
- 2 ft from STA 1786+06 to STA 1840+08
- 4 ft from STA 1846+20 to STA 1885+35
- 2 ft from STA 1934+28 to STA 2105+99

Northbound General Purpose Lanes – Outside Shoulder:

- 8 ft from STA 661+38 to STA 670+20
- 8 ft from STA 1390+38 to STA 1414+00

Southbound General Purpose Lanes – Inside Shoulder:

- 2 ft from STA 587+18 to STA 690+23
- 2 ft from STA 719+65 to STA 818+91
- 2 ft from STA 825+70 to STA 870+98
- 2 ft from STA 898+62 to STA 962+86
- 2 ft from STA 988+44 to STA 1015+57
- 2 ft from STA 1026+00 to STA 1044+68
- 2 ft from STA 1054+58 to STA 1086+98
- 2 ft from STA 1095+51 to STA 1144+35

- 2 ft from STA 1153+14 to STA 1221+73
- 2 ft from STA 1223+68 to STA 1440+97
- 2 ft from STA 1449+55 to STA 1584+61
- 2 ft from STA 1592+53 to STA 1789+36
- 2 ft from STA 1798+58 to STA 1840+00
- 8 ft from STA 1882+31 to STA 1885+35
- 2 ft from STA 1934+28 to STA 2105+99

Stopping Sight Distance

The minimum stopping sight distance (SSD) cannot be attained for the General Purpose lanes (GP), Managed Lanes (ML), and Direct-Connecter ramps (DC) at number of locations. The maximum stopping sight distances at these locations -that can be attained, along with their associated speeds,- are as follows:

70 mph required:

+/-STA 736+31 (SB GP Lanes)	SSD=694 ft (68 mph)
+/-STA 1263+98 (SB GP Lanes)	SSD=693 ft (68 mph)
+/-STA 1273+66 (SB GP Lanes)	SSD=693 ft (68 mph)
+/-STA 1284+47 (NB GP Lanes)	SSD=626 ft (64 mph)
+/-STA 1284+88 (NB ML)	SSD=644 ft (64 mph)
+/-STA 1306+45 (NB GP Lanes)	SSD=691 ft (68 mph)
+/-STA 1458+71 (NB GP Lanes)	SSD= 490 ft (54 mph)
+/-STA 1463+07 (NB ML)	SSD=561 ft (59 mph)
+/-STA 1475+91 (NB GP Lanes)	SSD=512 ft (56 mph)

50 mph required:

+/-STA 560+00 (SB ML Ramp to IH 35E SBFR) (DC HA-4)	SSD=272 ft (38 mph)
+/-STA 564+00 (SB ML Ramp to IH 35E SBFR) (DC HA-5)	SSD=316 ft (41 mph)
+/-STA 560+50 (NB from IH 35E NBFR to NB ML) (DC HB-4)	SSD=270 ft (38 mph)
+/-STA 562+00 (NB from IH 35E NBFR to NB ML) (DC HB-5)	SSD=318 ft (41 mph)
+/-STA 607+40 (SB: ML to IH 35E SBFR) (DC HC-1)	SSD=275 ft (39 mph)
+/-STA 613+80 (SB: ML to IH 35E SBFR) (DC HC-2)	SSD=316 ft (41 mph)
+/-STA 592+25 (WB IH635 to NB ML) (DC HD-1)	SSD=318 ft (41 mph)
+/-STA 980+60 (EB SH 121 /SRT to NB IH 35E) (DC HK-~~1~~3)	SSD=304 ft (39 mph)
+/-STA 979+40 (SB IH 35E to EB SH 121 /SRT) (DC HM-3)	SSD=304 ft (39 mph)
+/-STA 986+00 (WB SH 121 /SRT to NB IH 35E) (DC HP-2)	SSD=318 ft (41 mph)
+/-STA 1863+96 (NB GP Lanes)	SSD=424 ft (49 mph)

40 mph required:

+/-STA 983+00 (SB IH 35E to WB SH 121 /SRT)(DC HN-6)	SSD=252 ft (35 mph)

Vertical Clearance

A 16.5' minimum vertical clearance over the useable roadway cannot be attained at the following locations:

- Sta. 812+00 SB GP Bridge over Sandy Lake Road/Whitlock Ln – 15'-2"

- Sta. 1177+00 Fox Ave. Bridge over IH 35E – 15'-11"
- Sta. 1214+00 FM 1171 Bridge over IH 35E – 16'-2"
- Sta. 1762+00 NB GP and SB GP Bridges over Mayhill Rd/St. School Rd - 14'-9" and 15'-1" respectively

The following clearance distances are pending survey verification:

- Sta. 599+00 NB GP /SB GP Bridges over Harry Hines Blvd. (TBD)
- Sta. 634+00 NB GP /SB GP Bridges over Valley View Lane – 14'-5" (TBD)
- Sta. 692+00 NB GP /SB GP Bridges over Valwood Parkway – 14'-8" (TBD)
- Sta. 725+00 NB GP /SB GP Bridges over Crosby Street - 14'-5" (TBD)
- Sta. 812+00 NB GP Bridge over Sandy Lake Road/Whitlock Ln – 14'-3" (TBD)
- Sta. 983+00 WB GP /EB GP Bridges over SH121 – 16'-3" (TBD)
- Sta. 1030+00 Round Grover over IH 35E – 16'-6" (TBD)
- Sta. 1083+00 Corporate Drive over IH 35E – 16'-7" (TBD)
- Sta. 1137+00 NB GP /SB GP Bridges over SH 121 Business – 15'-9" (TBD)
- Sta. 1250+00 Valley Ridge Blvd. over IH 35E – 16'-9" (TBD)
- Sta. 1270+00 KCS RR over IH35E – 15'-7" (TBD)
- Sta. 1540+00 NB GP /SB GP Bridges over Teasley/Swisher – 16'-6" (TBD)
- Sta. 1835+00 NB GP /SB GP Bridges over Loop 288 – 15'-1" (TBD)
- Sta. 1863+00 NB GP Bridge over SB GP US 77 – 15'-1" (TBD)
- Sta. 1890+00 NB GP /SB GP Bridges over Teasley – 16'-1" (TBD)
- Sta. 1971+00 NB GP /SB GP Bridge over McCormick –16'-3"(TBD)
- Sta. 2021+00 NB GP /SB GP Bridges over Bonnie Brae –15'-5" and 15'-8" (TBD)
- Sta. 2021+00 NB Ramp to IH35W Bridge over Bonnie Brae – 15'-6"(TBD)
- Sta. 2021+00 IH35W to SB Ramp Bridge over Bonnie Brae – 15'-3" (TBD)

Superelevation

The Developer shall notify TxDOT in the event that widening an existing roadway in a superelevation transition area will result in the transition rate falling below TxDOT standard or Section 11.2.3. The developer shall submit a design exception for TxDOT review for each area where this condition exists.

The minimum superelevation rates for a design speed of 70 mph cannot be attained for the managed and general purpose lanes at the following locations:

- +/-STA 1346+82 NBGP e = 2.9%
- +/-STA 1356+23 NBGP e = 3.0%

The minimum superelevation rates for a design speed of 50 mph cannot be attained for the managed and general purpose lanes at the following locations:

- +/-STA 1867+94 SBGP e = 3.4%
- +/-STA 1863+96 NBGP e = 2.4%
- +/-STA 1943+97 NBGP/SBGP e = 3.3%
- +/-STA 2032+55 NBGP/SBGP e = 2.5%

11.2.4.2 Design Waivers

Weaving Distances

TxDOT will provide approved design waivers for the Project Schematic at the following locations. If, upon further design, additional deviations are identified, the Developer shall submit a request for design waiver to TxDOT for review. Any additional waivers not listed below are subject to TxDOT approval.

Weaving length: from tip to tip of intersecting travel lanes between entrance and exit ramps on main lanes with or without auxiliary lane.

- Weaving distances shall be reduced from 1,500 ft at the following locations. Minimum weaving distances at each location are shown in parentheses.
    - Northbound on and off ramps between Valwood Parkway and Crosby (1300')
    - Northbound on and off ramps between Valwood Parkway and Crosby (1275')
    - Southbound on and off ramps between Valwood Parkway and Crosby (1275')
    - Northbound on and off ramps between FM-407 and Garden Ridge Blvd. (1360')
    - Southbound on and off ramps between US-77 and Teasley (FM-2181) (690')
    - Northbound on and off ramps between Ft. Worth Drive and McCormick (410')
    - Southbound on and off ramps between Ft. Worth Drive and McCormick (970')
    - Northbound on and off ramps between N. TX Blvd. and IH-35W (780')
    - Southbound on and off ramps between N. TX Blvd. and IH-35W (1210')
    - Southbound on and off ramps at FM 2499 (State School/Mayhill) (1400')

11.2.5 Miscellaneous Roadway Design Requirements

All newly constructed roadside safety devices used on the Project shall meet current crash test and other safety requirements in accordance with TxDOT standards. Developer shall evaluate and upgrade safety devices in accordance with Chapter 4, Section 3 "Safety Enhancements" of the TxDOT Roadway Design Manual in areas of the project where no work will be performed or where work is limited to pavement rehabilitation. All existing roadside safety devices used on the Project shall meet the requirements of Table 19-1 as appropriate.

Driveways shall be designed in accordance with the guidelines, which will be considered requirements, specified in TxDOT's *Roadway Design Manual* – Appendix C, "Driveways Design Guidelines" to be functionally adequate for land use of adjoining property.

The border width, measured from back of curb or from edge of pavement in areas without curb, along frontage roads and crossing streets shall be 12 feet minimum unless specified otherwise.

Unless specified otherwise in these documents, all ramps, bullnoses, tie-ins and ramp terminals in areas where the Ultimate Project is specified in Section 1.2 of the Technical Provisions shall be located horizontally and vertically to accommodate the Ultimate Project such that the Ultimate Project can be implemented with little or no impact on traffic and/or rework. All other areas shall allow for a reasonable future transition to the Ultimate Project.

11.3 Minimum Requirements for Declaration Areas

Not applicable.

12 DRAINAGE

12.1 General Requirements

Efficient performance of the drainage system is an integral part of the performance of the Project. Developer shall account for all sources of runoff that may reach the Project, whether originating within or outside the Project ROW, in the design of the drainage facilities.

If existing drainage conditions are revised due to the Work, then the Developer shall design and construct a solution that does not adversely impact property owners outside the ROW. The Price shall include the cost for areas needed for detention, either through additional ROW or drainage easements.

12.2 Administrative Requirements

12.2.1 Data Collection

To establish a drainage system that complies with the requirements and accommodates the historical hydrologic flows in the Project limits, Developer is responsible for collecting all necessary data, including those elements outlined in this Section 12.2.1.

Developer shall collect available data identifying all water resource issues, including water quality requirements as imposed by State and federal government regulations; National Wetland Inventory and other wetland/protected waters inventories; in FEMA mapped floodplains; and official documents concerning the Project, such as the FEIS or other drainage and environmental studies. Water resource issues include areas with historically inadequate drainage (flooding or citizen complaints), environmentally sensitive areas, localized flooding, maintenance problems associated with drainage, and areas known to contain Hazardous Materials. Developer shall also identify watershed boundaries, protected waters, county ditches, areas classified as wetlands, floodplains, and boundaries between regulatory agencies (e.g., watershed districts and watershed management organizations).

Developer shall acquire all applicable municipal drainage plans, watershed management plans, and records of citizen concerns. Developer shall acquire all pertinent existing storm drain plans and/or survey data, including data for all culverts, drainage systems, and storm sewer systems within the Project limits. Developer shall also identify existing drainage areas that contribute to the highway drainage system and the estimated runoff used for design of the existing system.

Developer shall obtain photogrammetric and/or geographic information system (GIS) data for the Project limits that depicts the Outstanding National Resource Waters and/or impaired waters as listed by the TCEQ. Developer shall conduct surveys for information not available from other sources.

If documentation is not available for Elements of the existing drainage system within the Project limits and scheduled to remain in place, Developer shall investigate and videotape or photograph the existing drainage system to determine condition, size, material, location, and other pertinent information.

The data collected shall be taken into account in the Final Design of the drainage facilities.

12.2.2 Coordination with Other Agencies and Local Governmental Entities

Developer shall coordinate all water resource issues with affected interests, Governmental Entities and regulatory agencies. Developer shall document the resolutions of water resource issues.

Drainage improvements determined necessary by local Governmental Entities that exceed the requirements of the Contract Documents shall be handled by Developer with a third party agreement between the local Governmental Entity and the Developer. The cost associated with any such third party

agreements shall be the responsibility of the Developer and the Governmental Entity~~ and shall be considered as part of the Price~~. Such third party agreement shall be subject to TxDOT approval and shall be provided to TxDOT for review thirty (30) days prior to the anticipated date of execution of the agreement.

The Developer shall prepare the required documentation, perform the necessary calculations and design, and provide to the local floodplain administrators all information and technical data needed to file Conditional Letters of Map Revision (CLOMR) and Letters of Map Revision (LOMR) with FEMA.

Drainage areas and structures that fall under the jurisdiction of the United States Army Corps of Engineers (USACE) shall comply with all USACE requirements. Developer shall coordinate review and approval of the design and construction, if necessary, with the USACE on any such facilities. Information regarding the status of permits for work with the USACE is included in the Reference Information Documents.

In areas surrounding railroad facilities, the Developer shall coordinate with the appropriate railroad owner in accordance with Section 14.

12.3 Design Requirements

Developer shall design all Elements of the drainage facilities in accordance with the applicable design criteria, TxDOT's Hydraulic Design Manual, and Good Industry Practice.

Drainage design shall include reconfiguration of the existing drainage features and design of new drainage features within the Project limits~~.~~. The Draft Interim Schematic provides guidance on the design of new and upgrading existing drainage structures as a reference. The Developer is responsible for the final design of all drainage facilities in accordance with this Section 12.

Developer shall provide facilities compatible with existing drainage systems and all applicable municipal drainage plans or approved systems in adjacent properties. Developer shall preserve existing drainage patterns wherever possible. Section 1.2 of the Technical Provisions gives the location for areas of Ultimate Areas and Interim Areas. Hydrologic and hydraulic criteria differ for these areas. The major differences in criteria for interim and Ultimate Project areas are those pertaining to hydrology and freeboard requirements. These differences are detailed in the remaining portions of this Section 12.

Ultimate Areas:

Hydrology for structures in the areas described as the Ultimate Project in Section 1.2 of the Technical Provisions is to be based on fully-developed conditions outside the ROW and the Ultimate Project within the ROW. Developer shall design and construct drainage features to meet the drainage performance requirements, as defined in this Section 12.

Developer may make use of existing drainage facilities, provided overall drainage requirements for the Project are achieved and the combined drainage system functions as intended. Elements of the existing drainage system determined by Developer to remain in place as part of the drainage system for the Ultimate Project must meet the requirements as detailed in Section 12 (Drainage) and Section 13 (Structures). If any Elements of the existing system do not comply with the requirements of Section 12 or Section 13 on their own, those Elements shall be replaced, modified, or supplemented by the Developer to meet the criteria or the Developer shall submit an alternative mitigation plan for TxDOT Approval.

The following list contains known structures located in areas along the corridor with all, or the great majority, of the structure within an Ultimate Project area. This list does not limit the Developer's responsibility for design and construction of drainage structures discovered during detailed design and

construction within the limits of Ultimate Project areas. All structures within Ultimate Project areas and all structures listed below are to be designed and constructed for the Ultimate Project with fully-developed hydrology inside and outside the ROW.

- Station 732+51 (Existing 3-6'x3' MBC and 5-Des 8 Arch Pipes)
- ~~Station 1271+00 (KCS rail culvert to be removed and replaced – see Plans for CSJ:0916-02-120)~~
- Station 1271+00 (Drainage Improvements passing under the KCS railroad shall meet the requirements for ultimate areas. This includes improvements to the 6'x5' SBC upstream and the 2-8'x8' MBC downstream and associated channel improvements – see report for IH 35E Preliminary Hydrology and Hydraulic Summary from IH 635 to US 380, page 973, Culvert PC-1; and the final drainage design from the KCS Exhibit A plan sheets, CSJ 0196-02-114. The 3-9'x5' MBC passing under IH 35E north of the KCS railroad shall meet the requirements for interim areas.)
- Station 1304+35 (Existing 2-6'x3' MBC)
- Station 1304+50 (new structure -see Plans for CSJ: 0916-02-120)
- Station 1475+78 (Existing 1-36" RCP)
- Station 1495+64 (Existing 1-18" RCP)
- Station 1625+06 (Existing 2-6'x6' MBC "Lynchburg Creek")
- Station1640+69 (Existing 2-36" RCP north of Corinth Pkwy)
- Station 1686+51 (Existing 1-6'x3' SBC)
- Station 1706+02 (Existing 1-7'x7' SBC)

The ultimate structures at the above locations shall be designed to efficiently connect the upstream and downstream channel which may result in a revised alignment to that of the existing culvert.

Interim Areas

Hydrology for structures in the areas described as interim in Section 1.2 of the Technical Provisions is to be based on existing conditions outside the ROW and the interim corridor within the ROW. The Developer shall design and construct drainage features to meet the drainage performance requirements, as defined in this Section 12.

Developer may make use of existing drainage facilities, provided overall drainage requirements for the Project are achieved and the combined drainage system functions as intended. If the existing drainage elements fail to meet the criteria of this Section 12 on their own, then supplemental new drainage elements will be required as necessary to meet the criteria.

Elements of the existing drainage system determined by Developer to be sufficient to remain shall be analyzed per Section 13 (Structures). Unless otherwise specified below, existing elements in interim locations are not required to meet the requirements of Section 12.4.2.1. Any existing steel reinforced concrete pipe and culverts located in tolling zones shall be replaced with pipe and culverts containing glass fiber-reinforced polymer rebar (GFRP).

General

Developer shall provide calculations and other information for the design of these systems in the Drainage Design Report.

In areas within the Project ROW where Work is not being performed such as along some frontage road areas, and no additional runoff is being conveyed by the Project, the Developer shall assess the adequacy of existing drainage features and upgrade or provide rehabilitation measures for those features if needed to allow for their intended hydraulic capacity and performance.

Developer shall submit a plan narrative addressing the future expansion of new and existing Elements of the drainage system as needed to allow for the transition to the Ultimate Project as part of the Drainage Design Report. The plan should also include analysis of areas where the existing system will be replaced during Ultimate Project construction.

Developer shall base its Final Design on design computations and risk assessments for all aspects of Project drainage.

Developer shall design roadside open channels such that the profiles have adequate grade to minimize sedimentation.

At newly constructed intersections the Developer shall design and construct drainage features as needed to ensure adequate drainage through the intersection.

At reconstructed intersections the Developer shall design and construct or adjust existing drainage features as needed to ensure adequate drainage through the intersection.

At intersections which will be re-used or undergo only minor rehabilitation the Developer shall assess the adequacy of existing drainage features that may be impacted by the Project and upgrade or provide rehabilitation measures for those features if needed to allow for their intended hydraulic capacity and performance.

The Developer shall utilize the TxDOT Dallas District Drainage Standards and TxDOT Statewide Drainage Standard Sheets, in that order of preference, for inlets, manholes, and additional details.

12.4 Surface Hydrology

12.4.1 Design Frequencies

Developer shall use the design frequencies listed in Table 12-1 below.

Table 12-1: Drainage Design Frequencies

Functional classification and structure type	Design Annual Exceedance Probability (AEP)				
	50% (2-yr)	20% (5-yr)	10% (10-yr)	4% (25-yr)	2% (50-yr)
Freeways (main lanes):					
Culverts					X
Bridges					X
Principal arterials:					
Culverts				X	
Small bridges				X	

Major river crossings					X
Minor arterials and collectors (including frontage roads):					
Culverts			X		
Small bridges				X	
Major river crossings					X
Local roads and streets:					
Culverts		X			
Small bridges		X			
Off system projects					
Culverts	FHWA policy is "hydraulically same or slightly better" than existing.				
Bridges					
Storm drain systems on interstates and controlled access highways (main lanes):					
Inlets			X		
Storm drain pipes			X		
Inlets for depressed roadways*					X
Storm drain systems on other highways and frontage roads:					
Inlets and drain pipe		X			
Inlets for depressed roadways*				X	

Notes.

* A depressed roadway provides nowhere for water to drain even when the curb height is exceeded.

Storm drains on facilities such as underpasses, depressed roadways, etc., where no overflow relief is available should be designed for the 2% AEP event.

All facilities must be evaluated to the 1% AEP event.

The intent of evaluating the 1% AEP event is not to force the 1% AEP through the storm drain, but to examine where the overflow would travel when this major storm does occur and to ensure there are no adverse downstream impacts.

For structures extending under both general purpose lanes and frontage roads, the structure shall be designed using the design frequency established for general purpose lanes.

12.4.1.1Hydrologic Analysis

Hydrologic calculations for use in the design of all drainage structures are dependent on the location of the structure along the corridor improvements.

Ultimate Areas:

Developer shall determine peak runoff to all drainage features assuming fully developed conditions outside the ROW and the Ultimate Project within the ROW in accordance with the projected development policies of adjoining communities.

Developer shall design drainage structure capacities for the frequencies for the maximum hydrologic conditions as described in Table 12-1 above.

Interim Areas:

Developer shall determine peak runoff to all drainage features assuming existing conditions outside the ROW and the Project within the ROW.

Developer shall design drainage structure capacities for the frequencies for the maximum hydrologic conditions as described in Table 12-1 above.

12.4.2 Storm Sewer Systems

Where precluded from handling runoff with open channels by physical site constraints, or as directed in this Section 12, Developer shall design enclosed storm sewer systems to collect and convey runoff to appropriate discharge points.

Developer shall prepare a storm sewer drainage report encompassing all storm sewer systems that contains, at a minimum, the following items:

a) Drainage area maps for each storm drain inlet with pertinent data, such as boundaries of the drainage area, topographic contours, runoff coefficients, time of concentration, and land use with design curve number and/or design runoff coefficients, discharges, velocities, ponding, and hydraulic grade line data.

b) Location and tabulation of all existing and proposed pipe and drainage structures. These include size, class or gauge, catch basin spacing, detailed structure designs, and any special designs.

c) Specifications for the pipe bedding material and structural pipe backfill on all proposed pipes and pipe alternates.

d) Complete pipe profiles, including pipe size, type, and gradient; station offsets from the centerline of the roadway; length of pipe; class/gauge of pipe; and numbered drainage structures with coordinate location and elevations.

This report shall be a component of the Drainage Design Report.

Freeboard for storm sewer systems is dependent on the location of the structure along the corridor improvements.

Ultimate Areas

The maximum allowable hydraulic grade line elevation for the design frequency shall not exceed one foot below:

a) the lip of gutter; and

b) the top of manhole cover.

Interim Areas

The maximum allowable hydraulic grade line elevation for the design frequency shall not exceed:

a) the lip of gutter; and

b) the top of manhole cover.

General

Runoff within the jurisdiction of the USACE shall be conveyed in accordance with applicable laws and permits.

12.4.2.1Pipes

All new storm sewer pipes shall meet the requirements of this Section 12.4.2.1 of the Technical Provisions:

Storm sewer pipes with design flow velocities less than 3 feet per second (fps) shall be designed for full flow at 80% of the internal diameter to account for sedimentation in the pipe. Other storm sewer pipes shall be designed using the full internal diameter. Storm sewers shall be designed to prevent surcharging of the system at the flow rate for the design year event. All storm sewers shall be designed and constructed to sustain all loads with zero deflection and shall have positive seals at the pipe joints.

All pipes shall be reinforced concrete except in toll gantry areas (See Section 21).

The minimum pipe size inside diameter shall be 18" for laterals, 24" for laterals placed under pavement, and 24" for trunk lines. The minimum box culvert height, inside dimension, shall be 2 feet.

Pipes shall be designed with the following additional requirements:

- Pipe depth of cover: 1 ft. desirable, 6 inches minimum (top of pipe to bottom of treated subgrade)
- Lateral connection will be 45°/60° to trunk line in direction of flow.
- Pipe Slope: ≥0.50% Desirable, 0.30% Minimum
- Outfall Velocity Criteria: 6 Fps Desirable, > 8 Fps Provide Outfall Protection.
- When outfall protection is provided, calculations must be performed to determine the protection material and area protected downstream of the outfall location.

12.4.2.2Ponding

Developer shall design drainage systems to limit ponding to the widths listed below for the design frequency event:

Table 12-2: Allowable Ponding Widths by Roadway Classification

Roadway Classification	Design Storm Allowable Ponding Width	Check Storm Allowable Ponding Width
Interstate, Controlled Access Highways	Low shoulder plus one-half the width of the outer lane	One lane free of encroachment
Barrier-Separated Managed Toll Lanes: Single Lane Multiple Lanes	 Low shoulder plus 2 ft. Low shoulder plus one-half width of the outer lane	Safe passage of one lane of traffic in each direction
Principal Arterials/Highways*	Low shoulder plus 1 lane	Safe passage of one lane of traffic in each direction
Ramps, Direct Connectors	Low shoulder plus 2 ft.	Safe passage of one lane of traffic
Frontage Roads	Low shoulder plus 1 lane	Safe passage of one lane of traffic in each direction
Minor Cross Streets	Width and depth to allow safe passage of one lane of traffic in each direction	No adverse impact on adjacent property

* Highways with two or more lanes in each direction

12.4.3 Miscellaneous Drainage Design Requirements

12.4.3.1 Drainage Software

Developer shall employ software that is compatible with the software in use by TxDOT or fully transferable to TxDOT's systems.

12.4.3.2 Roadside Channel Design

Ultimate Areas

Roadside ditches will be designed to convey the 10-yr design storm and provide a minimum of 0.5 feet of freeboard from the bottom of treated subgrade or to top of ditch, whichever is lowest.

Interim Areas

Roadside ditches shall be designed to convey the 10-yr design storm with a maximum water surface elevation below the edge of pavement.

General

For both Ultimate and Interim areas, if a roadside ditch lies within a depressed area and it is the only means of outfall, it shall be designed to convey the 50-yr event.

12.4.3.3 Pump Stations

12.4.3.3.1 Pump Station Design

The existing pump station at Belt Line Road shall be replaced in kind, however, updated to accommodate drainage associated with the 2% AEP for the Ultimate Project. The pump bay shall have submersible, non-clogging, non-overloading, centrifugal type pumps that provide adequate redundant capacity to pump 100% of the Developer's calculated design flow with a failure of one pump. The automatic pump control

system shall provide for equal operating time for each pump and prevent pumps from overheating. A natural gas backup generator shall be provided for standby power.

12.4.4 Stormwater Storage Facilities

Developer shall complete design of the stormwater storage facilities to meet requirements for water quality, water quantity, and rate control, as determined by the Texas NPDES regulations. .

Developer shall ensure that stormwater storage facilities meet the requirements listed above by performing all required analyses. Such analyses shall include flood routing analysis, which includes a detailed routing analysis for ponds affected by significant environmental issues such as hazardous waste or groundwater concerns.

12.4.5 Hydraulic Structures

12.4.5.1Culverts

Developer shall analyze existing and proposed culverts and drainage-ways impacted, replaced, or created by the Project design, for flooding problems.

Where culvert design is influenced by upstream storage, the analysis of the storage shall be incorporated into the design of the culvert.

Culvert freeboard is dependent on the location of the structure along the corridor improvements.

Ultimate Areas

The maximum allowable headwater elevation for the design frequency shall not exceed one foot below the shoulder point of intersection elevation or one and a half (1.5) feet below the top of curb point of intersection elevation of the applicable roadway low point.

Interim Areas

The maximum allowable headwater elevation for the design frequency shall be the edge of pavement elevation or the top of curb of the applicable roadway low point.

General

In all areas, the maximum allowable headwater elevation shall not exceed the high point flow line of an adjacent roadside ditch.

Culverts are classified as major or minor, as follows:

- Major Culvert: A culvert that provides an opening of more than 35 square feet in a single or multiple installations. A major culvert may consist of a single round pipe, pipe arch, open or closed-bottom box, bottomless arch, or multiple installations of these structures placed adjacent or contiguous as a unit. Certain major culverts are classified as bridges when they provide an opening of more than 20 feet, measured parallel to the roadway; such culverts may be included in the bridge inventory. Bridge class culverts shall have a minimum rise of 4'.
- Minor Culvert: Any culvert not classified as a major culvert.

Existing culverts to remain will be studied in the following manner to ensure their long-term integrity. Bridge class culverts shall be rehabilitated in accordance with provisions of Section 13.2.8, Bridge *Class Drainage Structures.* Other major and minor culverts (non-bridge class) shall be inspected and rehabilitated as necessary to a good condition of equal standard to rehabilitated bridge class culverts. Developer shall perform a load rating for all culverts subject to traffic loading. Structures failing to meet

an ~~inventory~~operating load rating of HS20 shall be rehabilitated. Existing structures shall be rehabilitated to provide a minimum twenty (20)-year service life extension for the existing structures.

Outfall velocities greater than 8 fps should incorporate adequate outfall protection to protect against erosion. Minimum velocities shall be established to avoid sedimentation, and appropriately designed erosion protection shall be used in areas where erosion potential exists.

12.4.5.2 Bridges

All bridge hydraulic computations, designs, and recommendations shall be consistent with past studies and projects in the area by the USACE and other State or federal agency studies and projects.

Where bridge design is influenced by upstream storage, the analysis of the storage shall be considered in the design of the bridge.

Developer shall evaluate bridges for contraction scour and pier scour concerns and incorporate protection in accordance with Good Industry Practice. Developer shall provide a scour analysis in accordance with TxDOT's Geotechnical Manual (Chapter 5-Section 5, Scour) for all new bridges. If necessary, the Developer shall provide countermeasures for any instability and scour problems in accordance with FHWA Hydraulic Engineering Circular No. 23 - *Bridge and Scour and Stream Instability Countermeasures Experience Selection and Design Guidance*.

Developer shall design riprap at abutments in accordance with the procedures outlined in HEC-23. For bridge abutments in urban areas, Developer shall install protection in accordance with the Project's aesthetic plan.

Ultimate Areas

Bridges shall provide a minimum of two (2) feet of freeboard under the bridge low chord for the design storm. The 100-year water surface elevation shall be under the bridge low chord elevation. Bridges shall be designed to maintain their integrity during a 500-year flood event.

Interim Areas

Bridges shall pass the design event beneath the structure without overtopping the edge of the roadway. For all spans where negative or zero freeboard conditions occur, provide shear keys between the outside beam and the first interior beam on the upstream side of the structure at abutments and bents of affected spans. Shear key details may be obtained as working drawings from TxDOT's Bridge Division.

12.4.5.3Method Used to Estimate Flows

Developer shall ensure that the selected hydrologic method is appropriate for the conditions in the watershed.

For all crossings located within a FEMA studied floodplain (Zone AE) with peak flow information, Developer shall gather and utilize, as appropriate, the current effective model. For a crossing not located within a FEMA Zone AE but on the same waterway as a stream gauging station with a length of record of at least twenty-five (25) years, Developer shall collect and use the flow data available from the station, as appropriate, to determine design flows within the following limitations, provided there is no major control structure (e.g., a reservoir) between the gauge and the Project:

a) For crossings near the gauging station on the same stream and watershed, use the discharge directly for a specific frequency from the peak stream flow frequency relationship.

b) For crossings within the same basin but not proximate to the gauging station, transposition of gauge analysis results is allowable.

c) For crossings not within a gauged basin, the peak-flow flood frequency shall be developed using data from a group of several gauging stations based on either a hydrologic region (e.g., regional regression equations), or similar hydrologic characteristics.

d) If no significant changes in the channel or basin have taken place during the period of record, the stream gauging data may be used. The urbanization character of the watershed must not be likely to change enough to affect significantly the characteristics of peak flows within the total time of observed annual peaks and anticipated service life of the highway drainage facility.

For crossings not located within a FEMA Zone AE or on a gauged waterway, Developer shall select the appropriate method for calculating the design flows based on site conditions, and Good Industry Practice.

12.4.5.3.1 Design Frequency

Major river crossings, bridges, culverts and storm drain systems shall be designed for the frequency corresponding to the functional classification of the associated roadway. The functional classification for each roadway is shown in Section 11.

12.4.5.3.2 Hydraulic Analysis

Developer shall select the appropriate method for calculating hydraulics based on site conditions, and Good Industry Practice.

12.4.5.3.3 Bridge/Culvert Waterway Design

Bridge waterway design shall maintain the existing channel morphology through the structure, if possible.

12.4.5.3.4 Bridge Deck Drainage

Stormwater flowing toward the bridge shall be intercepted upstream from the approach slab. Runoff from bridge deck drainage shall be treated as required by TCEQ or other applicable regulation prior to discharge to the natural waters of the State.

Open deck drains are not permissible for bridges passing over waterways or other roadways. If ponding width limits require, runoff shall be conveyed in a closed system through the bridge columns to the roadway drainage system below. The bridge deck drainage system shall outlet at the bottom of the substructure either into a storm sewer system or into an open channel and in no case shall be allowed to discharge against any part of the structure.

12.4.5.3.5 Drainage Report for Major Stream Crossings

Developer shall prepare a report for each major stream crossing. Major stream crossings are defined as waterways listed as a FEMA studied floodplain (Zone AE) or requiring a bridge or major culvert structure. The report shall include the detailed calculations and electronic and printed copies of the computer software input and output files, as well as a discussion about hydrologic and hydraulic analysis and reasons for the design recommendations. At a minimum, for each crossing the report shall include the requirements provided in Attachment 12-1.

This report shall be a component of the Drainage Design Report.

Major stream crossings are waterways with a FEMA studied SFHA or requiring a bridge class structure, which is defined as any bridge or a culvert with a total opening width greater than or equal to twenty feet. and a minimum depth of four (4) feet. Any other waterway will be by default a minor stream crossing.

12.5 Drainage Design Report

A preliminary Drainage Design Report shall be submitted with prefinal set of construction plans. The preliminary Drainage Design Report shall include preliminary design of all components that will be included in the final Drainage Design Report. Thirty days prior to construction of any drainage element, Developer shall submit a final Drainage Design Report for that drainage element to TxDOT.

Within 30 days of Substantial Completion, Developer shall submit to TxDOT, as part of the record set documents, a final Drainage Design Report, which shall be a complete documentation of all components of the Project's drainage system.

At a minimum, the Drainage Design Report shall include:

a) Record set of all drainage computations, both hydrologic and hydraulic, and all support data.
b) Hydraulic notes, models, and tabulations
c) Bridge and culvert designs and reports for major stream crossings
d) Pond designs, including graphic display of treatment areas and maintenance guidelines for operation
e) Correspondence file
f) Drainage system data (location, type, material, size, and other pertinent information) in a suitable electronic format
g) Storm sewer drainage report

12.6 Construction Requirements

Developer shall design drainage to accommodate construction staging. The design shall include temporary erosion control ponds and other Best Management Practices needed to satisfy the NPDES and other regulatory requirements. The water resources notes in the plans shall include a description of the drainage design for each stage of construction.

13 STRUCTURES

13.1 General Requirements

The structural Elements of the Project, including bridges, culverts, drainage structures, signage supports, illumination assemblies, traffic signals, retaining walls, and sound walls, shall be designed and constructed in conformance with the requirements of the Contract Documents, the current AASHTO *LRFD Bridge Design Specifications*, and *TxDOT Standard Specifications* except where directed otherwise by the TxDOT *Bridge Design Manual – LRFD* and the TxDOT *Geotechnical Manual*, in order to provide the general public a safe, reliable, and aesthetically-pleasing facility.

For bridges, walls, bridge class culverts, sign structures and other miscellaneous structures, a Corridor Structure Type Study and Report shall be submitted to TxDOT for review and comment prior to design of these Elements. At a minimum, structural concepts, details and solutions, soil parameters, hydraulics, environmental requirements, wetland impacts, safety, highway alignment criteria, constructability, aesthetics requirements, and continuity for the Project shall be evaluated in the Study and Report. Evaluation of existing structures that will be retained shall be included in the Study and Report. The Study and Report shall clearly define Developer's action to achieve a one hundred (100)-year service life for new Project bridges, walls, culverts and miscellaneous structures; and a minimum twenty (20)-year service life extension for existing structures that are rehabilitated except in cases of fatigue as described in the Technical Provisions Section 13.2.10.

Developer shall submit to TxDOT an inventory and operating ratings of constructed structures with the Record Drawings.

13.2 Design Requirements

Developer shall obtain National Bridge Inventory (NBI) numbers from TxDOT for all bridges and bridge class culverts. The NBI numbers shall be shown on the applicable layout sheets of the Final Design Documents.

All components of new structures and exterior caps, columns, beams, railing, and retaining walls of widened structures shall include aesthetic treatments in accordance with the IH-35E Corridor Aesthetic Guidelines. Lengthened portions of existing bridges shall match existing aesthetic treatments.

13.2.1 Design Parameters

Unless otherwise noted, design for all roadway and pedestrian structural elements shall be based on the Load and Resistance Factor Design (LRFD) methodology included in TxDOT's *Bridge Design Manual – LRFD* and the most recent AASHTO *LRFD Bridge Design Specifications*, including all interim revisions. *LRFD* provisions apply to both new structures and widened portions of existing structures. Unmodified portions of existing structures will be governed by their original design requirements but never less than HS-20 loading.

Sidewalks shall be provided on bridge structures in accordance with Section 20.

Steel bridges design shall comply with *TxDOT Preferred Practices for Steel Bridge Design, Fabrication, and Erection.*

Corrosion protection measure shall be in accordance with TxDOT Bridge Division and District practices.

Segmental bridges shall additionally conform to the requirements of AASHTO *Guide Specifications for Design and Construction of Segmental Concrete Bridges*.

Pedestrian bridges shall additionally conform to the requirements of AASHTO *LRFD Guide Specifications for Design of Pedestrian Bridges*.

The Developer shall proportion bridge spans to avoid uplift at supports.

Developer shall ensure that new bridges crossing over waterways withstand a 500-year frequency event with no loss of structural integrity in accordance with *FHWA Hydraulic Engineering Circular (HEC)-18 and HEC-23.* Developer shall analyze scour at existing structures and reconstruct substructures or provide scour countermeasures for structural components failing to meet original design standards. Hydraulic design shall be in accordance with *TxDOT Hydraulic Manual.*

Developer shall inspect all structures that are to be reused, lengthened or widened in accordance with AASHTO's *Manual for Bridge Evaluation* and *TxDOT Bridge Inspection Manual*.

Interim Areas

In areas that are not specified as Ultimate Project in Section 1.2 of the Technical Provisions, bridges that are all new—except for lengthened bridges and new bridges on northbound IH 35E at Harry Hines Boulevard, new bridges between PGBT and SH 121, at Fox Avenue, at FM 1171, and on IH 35E at McCormick Avenue—shall at a minimum be designed to accommodate the Project and all planned expansions or updates of each facility by its respective owner as designated in the owner's current transportation master plan [If Work Package 2, 3 or 4 is Awarded, the list above shall be modified as follows: except for lengthened bridges and ~~new bridges on northbound IH 35E at Harry Hines Boulevard,~~ new bridges between PGBT and SH 121, at Fox Avenue, at FM 1171, and on IH 35E at McCormick Avenue.]. Existing bridges, including widenings, shall accommodate the Project, but provide no less than 14'-6" vertical clearance (See Section 11.2.2) for side roads over IH 35E. Existing side roads under IH 35E not meeting 14'-6" vertical clearance may remain, however, proposed widening shall not further reduce vertical clearance. Alignments shall meet the requirements indicated in Section 11 for the functional classification of each roadway.

Ultimate Areas

In areas where the Ultimate Project is specified in Section 1.2 of the Technical Provisions, Developer shall design bridge structures to accommodate the Ultimate Project. Developer shall also design and construct the bridges at the following locations to the width required for the Ultimate Project: IH 35E at FM 407, North Texas Boulevard, and Dickerson Parkway. [If Work Package 3 or 4 is Awarded, the list above shall be modified as follows: IH 35E at FM 407, and North Texas Boulevard.~~, and Dickerson Parkway~~] Accommodations include locating abutments, retaining walls, foundations and substructures in the Ultimate Project location. Developer shall ensure that bridges constructed for the Draft Interim Schematic can be widened to the Ultimate Project width at a later date with minimal or no impact to aesthetics and traffic. Developer shall provide schematic level design, as outlined in Section 1.3, illustrating the transition from the Project Scope to the Ultimate Project.

General

If a new bridge is part of the Ultimate Project, but is constructed only to an interim width, and if the outside columns of this bridge are not constructed until the Ultimate Project, then —the outside bridge columns at the interim width are not required to meet the outside bridge column aesthetics requirement of the Ultimate Project bridge.

Direct-connect structures shall be constructed to satisfy the Ultimate Project. In locations where the Draft Interim Schematic does not call for the construction of the direct-connect structures, Developer shall make provisions to allow for the future transition to the Ultimate Project construction.

All electronic and paper files and calculations design notebooks shall be made available at TxDOT's request.

13.2.2 Bridge Design Loads and Load Ratings

a) Live Loads

All roadway bridges and bridge class culverts shall be designed to accommodate the following live loads:

New Construction: An HL-93 truck or a tandem truck plus lane load as defined in the AASHTO *LRFD Bridge Design Specifications* shall be utilized for bridges except pedestrian bridges.

Existing Bridge Structures: Inventory load rating of HS-20. Structures failing to meet this standard shall be rehabilitated to an inventory load rating of HS-20 or replaced using LRFD design and HL-93 loading.

Existing Bridge Class Culverts: Operating load rating of HS-20. Structures failing to meet this standard shall be rehabilitated to an operating load rating of HS-20 or replaced using LRFD design and HL-93 loading.

Widenings: HL-93 loading for widening and HS-20 for existing portion (designate both existing and widening loading on bridge layouts).

Partial Replacement: HL-93 loading for portions replaced and HS-20 for existing remaining in place (designate both existing and partial replacement loading on bridge layouts).

Pedestrian bridges and sidewalks of vehicular bridges shall be loaded in accordance with requirements in the AASHTO *LRFD Bridge Design Specifications* and the AASHTO *LRFD Guide Specifications for Design of Pedestrian Bridges*. In addition, all pedestrian bridges shall also be designed for an AASHTO H-10 truck live load as defined in the AASHTO *Standard Specifications for Highway Bridges*, 17th edition to account for maintenance and emergency vehicles.

b) Additional Loads

Outside bays of new and widened structures shall each be designed for an additional 400 plf utility load to be distributed between two beams. Developer shall not be required to design for the additional 400 plf utility loading at the following structures:

- Direct Connects
- Collector Distributors

Developer shall not be required to design specifically for the additional 400 plf utility loading at the Lake Lewisville Bridge but shall design for additional loading as needed to accommodate tolling and ITS equipment and conduit to be placed on the structure.

Generally utility attachment to bridges shall be prohibited. In the event a utility is unable to identify an alternative to bridge attachment, the Developer may request a waiver from TxDOT. TxDOT at its sole discretion may grant or reject requests for utility attachment.

Developer shall provide to TxDOT both an inventory and an operating rating of the constructed structures and provide TxDOT with a copy of the signed and sealed calculations. Load ratings shall be in accordance with AASHTO's *Manual for Bridge Evaluation and TxDOT's Bridge Inspection Manual*.

13.2.3 Bridge Decks and Superstructures

Fracture critical members shall not be used for bridges without written authorization from TxDOT and if allowed by TxDOT, fracture critical members shall be designed to allow full access for inspection.

The type of bridge shall not be restricted to those typically used by TxDOT. Other types and components may be used, but will be allowed only if:

a) They have been accepted for general use by the Federal Highway Administration (FHWA); and

b) Developer can demonstrate that the design of the bridge type and components will meet the functional requirements of the Project.

Modular joints shall be used when anticipated movement exceeds 5 inches and shall be designed and tested for fatigue loading.

Developer shall minimize the number of deck joints wherever possible. Developer shall locate joints to provide for maintenance accessibility and future replacement. Joints for all grade separation structures shall be sealed.

Developer shall design sidewalks to meet the criteria of the AASHTO *Roadside Design Guide* and protect sidewalks from vehicular impact by a TxDOT-approved bridge railing as required in the TxDOT *Bridge Railing Manual* based on roadway Design Speed. For the Project, pedestrian rail shall be used along structure pavement edges and installed to minimize future damage when accommodating the Ultimate Project in areas where the Ultimate Project is specified in Section 1.2 of the Technical Provisions.

To the extent possible, Developer shall make bridge superstructures, joints, and bearings accessible for long-term inspection and maintenance. Developer shall make open-framed superstructures accessible with walkways or by use of ladders or an under-bridge inspection truck.

Steel and concrete box girders and caps (substructure) shall be accessible without impacting traffic below. All Bridges shall either be accessible from below or from the bridge deck using an underbridge inspection truck. Developer shall make steel and concrete box girders and caps (substructure) with a minimum inside depth of 6 feet to facilitate interior inspection. Developer shall include a minimum access opening of 3'-0" diameter into all cells and between cells of the girders to allow free flow of air during inspections. The outside access opening cover shall hinge to the inside of the box girder and caps (substructure). An electrical system (110V and 220V) shall be incorporated inside the box girder and caps (substructure) with lighting and power outlets. Developer shall provide vented/drained structures that are detailed to prevent ingress by wildlife with locked entryways on all hatches and points of access.

Segmental bridges shall additionally conform to the following:

a) Segmental bridge decks shall use deck protection systems to prevent infiltration of corrosive agents into reinforcing in the superstructure. The deck protection system used shall be such that cracking is minimized and adequate bond strength is developed with the superstructure.

b) If monolithically cast overlay is used as part of the deck protection system, the Developer shall develop fully engineered design guidelines for the thickness of the monolithic concrete removed and replaced in a manner that keeps distress and changes in surface profile at the time of concrete removal to levels that do not reduce the structural integrity of the structure.

c) All expansion joints shall be sealed or drained. External tendons, if used, shall be protected with a water-tight duct jointing system.

d) The design, detail and construction of segmental bridges shall provide for the easy addition of supplemental post-tensioning.

13.2.4 Bridge Foundations

Integral abutments, where the superstructure is structurally framed (either completely or partially) into the abutment, shall not be permitted. Mechanically Stabilized Earth (MSE) walls shall not serve as structural foundations for bridges on the Project and shall not be subjected to vertical loads from the bridges. Bridge approach slabs shall be designed and constructed to mitigate settlement immediately behind abutment backwalls.

Spread footing foundations are not allowed.

Design of foundations shall in compliance with provisions of the *TxDOT Geotechnical Manual*.

13.2.5 Bridge Railing and Barriers

All barrier systems used on the Project shall meet current crash test and other safety requirements as determined by TxDOT. All testing and associated costs for non-standard railings shall be the sole responsibility of Developer and shall be accomplished through a third party acceptable to TxDOT. A current list of standard railing is provided in TxDOT *Bridge Railing Manual*. Developer shall protect sidewalks from vehicular impact by using TxDOT-approved bridge railings. For Draft Interim Schematic configuration, pedestrian rail shall be used along structure pavement edges and installed to minimize future damage when accommodating the Ultimate Project in areas where the Ultimate Project is specified in Section 1.2 of the Technical Provisions.

13.2.6 Retaining Walls

Wall types and components will be allowed only if:

a) They have been accepted for general use by FHWA, and

b) The design of the wall type and components meets the functional requirements of the Project.

Modular walls employing interlocking blocks shall not be used where surcharge loads from vehicular traffic are present.

Modifications to wall standards shall be detailed on plan sheets and communicated to wall suppliers.

The design of wall structures shall take into account live load surcharges. The Developer shall apply the appropriate live loading condition (vehicular, heavy rail, transit etc.) that each wall is subjected to. The

design shall be in accordance with *TxDOT Geotechnical Manual*, American Railway Engineering and Maintenance of Way Association (AREMA) specifications, or the requirements of the specific railroad and transit owner/operator, as appropriate.

Summaries of retaining wall analyses shall be provided on a wall by wall basis with results provided for each critical wall section.

Structural integrity of retaining walls shall be inspected and monitored in accordance with Good Industry Practice. Tolerances and mitigation measures shall be in accordance with the Maintenance Management Plan and Good Industry Practice.

The retaining wall layout shall address slope maintenance above and below the wall.

To the extent possible, Developer shall design and construct components of the Project to provide embankments without the use of retaining walls. Where earthen embankments are not feasible, Developer may use retaining walls. These retaining walls shall be located and designed such to allow for the future transition to the Ultimate Project in areas where the Ultimate Project is specified in Section 1.2 of the Technical Provisions, unless specified otherwise, with little to no rework or impact on traffic. Developer shall provide schematic level design, as outlined in Section 1.3, illustrating the transition from the Project Scope to the Ultimate Project. The Draft Interim Schematic foundations shall be designed and constructed to include any additional height and weight associated with the Ultimate Project.

Metal walls, including bin walls and sheet pile walls, recycled material walls and timber walls are not allowed.

If pipe culverts are to extend through the retaining walls or noise walls, the pipe shall be installed so that no joints are located within or under the wall.

No weep holes through the face of the retaining walls will be allowed, except at the base of the walls.

13.2.7 Noise/Sound Walls

Developer shall design and construct the noise/sound walls to achieve the decibel reduction requirement in the NEPA Approval(s).

Design shall be in accordance with *AASHTO Guide Specification for Structural Design of Sound Barriers*. Developer shall submit sound wall system to TxDOT for approval. Proprietary systems represent maintenance difficulties when replacing damaged elements and as such shall not be permitted. Panel design and construction shall limit the risk of falling debris resulting from traffic impacting the sound wall.

Timber sound walls are not allowed.

13.2.8 Bridge Class Drainage Structures

In developing the design of drainage structures, Developer shall account for maximum anticipated loadings in both the Draft Interim Schematic configuration and Ultimate Project in areas where the Ultimate Project is specified in Section 1.2 of the Technical Provisions.

Energy dissipaters, if used, shall be considered as structural Elements.

Developer shall use the most current TxDOT bridge inspection and inventory reports to determine overall adequacy of existing structures. Any component with a condition rating less than 7 as reflected on the bridge inspection reports and any other defects discovered by the Developer shall be rehabilitated. Developer shall perform inspections using inspectors, pre-approved by TxDOT, with previous experience inspecting TxDOT bridge inventory. The inspectors shall confirm rehabilitation has achieved a minimum condition rating of 7 for each structural component at Substantial Completion. The Reference Information Documents contains a table that provides the most current available condition ratings for structures. Developer shall submit a rehabilitation report to TxDOT for approval 60 Days prior to performing rehabilitation activities on the bridge. This table also includes a specific list of structures along the corridor that are not included in the Project and are not subject to the requirements of this Section 13.

For drainage structures that are to be reused or widened, Developer shall perform video inspections. Developer shall submit 3 copies of the video to TxDOT. Developer shall analyze those structures and shall include recommendations for rehabilitation or replacement efforts as needed to accommodate the Project. These analyses and subsequent recommendations shall be subject to TxDOT Approval.

Structures carrying railroad shall comply with requirements of American Railway Engineering and Maintenance of Way Association (AREMA) specifications

Developer shall analyze existing drainage structures for capacity to accommodate any additional loads, settlements, and/or other structural impacts associated with the Project.

13.2.9 Sign, Illumination, and Traffic Signal Supports

For bridges and walls longer than 500 feet, sign supports shall be provided at 500-foot intervals. The sign supports shall accommodate sign areas up to and including 16 square feet.

Developer shall design overhead and cantilever sign supports to accommodate the Ultimate Project in areas where the Ultimate Project is specified in Section 1.2 of the Technical Provisions. Cantilever and sign bridge supports shall be placed outside the clear zone or shall be otherwise protected by appropriate safety measures.

13.2.10 Rehabilitation of Structures to be, Widened, Extended, or Reused

For existing structures to be widened, extended, or reused, Developer shall perform a condition survey including the location, condition rating, load rating, remaining service life and recommended rehabilitation or replacement measures.

The most current TxDOT bridge inspection and inventory reports shall be used to determine existing overall adequacy of each structure and its individual component ratings. Developer shall inspect all structures to be widened, extended or reused in accordance with the *AASHTO's Manual for Bridge Evaluation and TxDOT Bridge Inspection Manual*. Any component with a condition rating less than 7 as reflected on the TxDOT bridge inspection reports and any other defects discovered by the Developer shall be rehabilitated. Developer shall perform inspections using inspectors, pre-approved by TxDOT, with previous experience inspecting TxDOT bridge inventory. The inspectors shall confirm rehabilitation has achieved a minimum condition rating of 7 for each structural component at Substantial Completion. The

Reference Information Documents contains a table that provides the most current condition ratings for structures. This table includes a specific list of structures along the corridor that are not included in the Project and are not subject to the requirements of this Section 13. For all other structures to be rehabilitated, Developer shall submit a rehabilitation report to TxDOT for approval 60 Days prior to performing rehabilitation activities on the bridge.

Developer shall clean and repair existing expansion joints and provide new seals full width of existing and widened structures.

Developer shall inspect all existing bridge bearings. As necessary, Developer shall rehabilitate, repair, or replace existing bridge bearings to accommodate design loads and expansion.

Developer shall patch and repair concrete spallings, concrete delaminations, clean and repair exposed reinforcing, seal cracks and repair or replace structurally damaged elements of existing structures.

Developer shall remove rust, clean, and paint all existing steel bridge superstructures and associated steel bridge bearings. Developer shall perform a paint condition assessment for all painted structures prior to any rehabilitation activities. Recommendations to leave any existing coatings intact shall be submitted to TxDOT for approval.

Developer shall repair observed fatigue defects; however, Developer is not required to extrapolate remaining fatigue life out of existing structures where no current fatigue defect is present.

Full deck replacements, as specified in Section 1.2 of the Technical Provisions, shall consist of 8.5" thick class S concrete deck. Bridge beams/girders and substructures shall be rehabilitated or replaced as required to support the new bridge deck load in combination with live load specified in section 13.2.2.

For existing bridge structures that are to be lengthened or widened with a current asphalt overlay, Developer shall mill and overlay with overlay extending across ~~widening~~the widened or lengthened portion of the structure.

Developer shall rehabilitate the bridge on Bonnie Brae Avenue within 365 days after NTP2.

13.3 Construction Requirements

13.3.1 Concrete Finishes

All concrete surfaces that do not have aesthetic treatments shall have a uniform texture and appearance. Color treatment, where required as an aspect of the aesthetic treatment of the concrete, shall be uniform in appearance. Ordinary Surface Finish as defined by the TxDOT Standard Specifications for Construction and Maintenance of Highways, Streets, and Bridges, latest version, shall be applied to the following as a minimum:

a) Inside and top of inlets

b) Inside and top of manholes

c) Inside of sewer appurtenances

d) Inside of culvert barrels

e) Bottom of bridge slabs between girders or beams

f) Vertical and bottom of surfaces of interior concrete beams or girders.

13.3.2 Structure Metals

Welding shall be in accordance with the requirements of the *AASHTO/AWS DI.5 Bridge Welding Code* and *TxDOT Standard Specification Item 448, Structural Field Weldin*g.

13.3.3 Steel finishes

Except for weathering steel, all structural steel shall be protected. The color for structural steel paint shall conform to the aesthetic scheme of the Project.

If weathering steel is used, the Developer shall protect all components of the structure (superstructure and substructure) that are susceptible to corrosion and/or staining from weathering steel run-off.

13.3.4 Steel Erection

Steel Erection shall be in accordance with AASHTO/NSBA Steel Collaboration 510.1-2007. Inspection of steel erection will include oversight by TxDOT personnel.

14 RAIL

14.1 General Requirements

This section sets forth the criteria a) for Work impacting existing railroad ROW and b) to accommodate and/or construct a rail corridor.

14.2 Projects Impacting Railroad ROW

Developer shall coordinate with the railroad and all applicable Governmental Entities in the development of the Project.

~~Developer shall provide appropriate widths to allow for a double track at the Cotton Belt railroad and Madill (BNSF) Line rail crossing in the Belt Line Road interchange area.~~

In the Belt Line Road interchange area where the IH 35E highway bridge remains in place, the Developer shall maintain the existing alignments of the Cotton Belt, Madill (BNSF), and the DGNO rail lines. If the IH 35E highway bridge is replaced, Developer shall maintain the existing alignments of the Cotton Belt, Madill (BNSF), and the DGNO rail lines and shall provide the appropriate roadway bridge widths, heights, clearances, and locate bridge abutments and bent locations to accommodation the preferred alignments of Dallas Area Rapid Transit (DART), including double tracks of the Cotton Belt and Madill (BNSF) rail lines. The Price shall include all Work that results from the fully executed railroad agreement with Developer, TxDOT and DART.

14.3 Railroad Agreements

Developer shall obtain all approvals, permits and agreements as required prior to any Work impacting the railroad being performed. Construction and Maintenance (C&M) Agreements shall be between TxDOT, Developer, the appropriate railroad company and appropriate Governmental Entities and may take twelve (12) months or more to obtain from the railroad company. Current approved templates for TxDOT/railroad company agreements are available from the TxDOT Rail Division at Rail-Highway.Section@txdot.gov.

The following agreements may be required based upon the railroad's requirements:

a) Preliminary Engineering – Most railroads require preliminary engineering agreements in order to proceed with the development and review of plans. This agreement authorizes reimbursement to the railroad company for preliminary engineering and estimating performed by the railroad or their consultant(s).

b) License to Cross and C&M Agreement – Developer shall prepare template agreement to be executed between railroad, Developer and TxDOT. A License to Cross railroad right of way is normally required when the highway project involves a new crossing or grade separation of the railroad. A separate easement agreement may be obtained in lieu of the License to Cross. Developer shall prepare all the documents required to obtain the License and C&M Agreement, including preparation of the plans and specifications and estimates, making necessary modifications as required on behalf of TxDOT. Developer shall submit the draft License and C&M Agreement to TxDOT for transmittal to the railroad. After all comments have been incorporated or satisfactorily resolved by either Developer, railroad or TxDOT, Developer shall submit a complete and final agreement to TxDOT for execution. This agreement shall include

provisions for each party's access to the facilities for regular inspection, maintenance as well as emergency repairs as required.

c) Aerial Easements (for grade separations only) - Developer may be required by the railroad company to enter into a separate easement agreement to obtain air rights to cross railroad ROW. If an aerial easement is required, the "License" portion of the C&M Agreement will be modified to identify the aerial easement as right to cross railroad right of way with the new highway facility.

d) Temporary Construction Easements - Developer may be required to purchase a temporary construction easement for the railroad company. This requirement will be stipulated in and be a part of the C&M Agreement.

e) Railroad's Contractor Right-of-Entry Agreements (Texas approved versions only) – In order to enter the railroad's right-of-way to perform the Work, Developer or their Subcontractor shall secure a railroad Right-of-Entry agreement and shall coordinate the arrangements of the necessary agreements directly with the railroad.

All executed agreements shall be submitted in their entirety as part of the Final Design Documents.

14.4 Railroad Design Standards

The design for all railroad elements of the Project shall be based on the most recent American Railway Engineering and Maintenance of Way Association (AREMA) guidelines including but not limited to the *Manual for Railway Engineering* and *Communications & Signal Manual of Recommended Practices* and the requirements of the railroad. Developer's design shall minimize service interruptions to existing rail lines to the maximum extent possible with the use of non-revenue/non-operating service hours as the primary option. If the railroad elements of the Project are being constructed within an existing Quiet Zone, any new or changes to existing crossing protection(s) must be approved by the Railroad Company and comply with the Supplemental Safety measures as outlined in 49 CFR Parts 222 and 229 and must not negatively impact or degrade the existing Quiet Zone classification.

All work involving railroad companies, work on railroad Right of Way (ROW), and the development and execution of railroad programs shall be in accordance with State and federal law and the practices, guidelines, procedures and methods contained in the TxDOT *Traffic Operations Manual*, Railroad Operations Volume and *Amendments for the TxDOT's Traffic Operations Manual*, Railroad Operations Volume, February 2000. Additionally, the requirements of the owner of each facility crossed shall be compared to the requirements in the TxDOT manual, and the most restrictive criteria shall be utilized.

At highway-rail grade crossings, the roadway and drainage design parameters shall be maintained at the crossing with exception to the cross slope of the pavement which may be transitioned to match the grade across the rail line. The structural design of any Utilities, including drainage structures, installed by the Developer and crossing a rail line, shall be in accordance with the operating railroad's design criteria. Developer shall coordinate the design, construction and the construction staging, including any temporary track detours (shooflies), with the operating railroad.

Developer's design shall minimize service interruptions to existing rail lines. Coordination with the impacted railroad and other appropriate Governmental Entities for anticipated service interruptions shall be thirty (30) Business Days in advance.

Where signalized intersections occur near new or existing at-grade rail crossing, the Developer's design shall minimize the potential for traffic stacking across the railroad tracks and provide adequate turn lanes of sufficient length and appropriate crossing protection.

14.4.1 Design Criteria

Developer shall coordinate with the railroad owner and ensure that the Project design meets any Project specific criteria.

14.5 Administrative Requirements

14.5.1 Project Work Affecting Railroad Operations

Should the Project cross a railroad right of way owned by an operating railroad, Developer shall coordinate the Work with the operating railroad. The design and installation of all railroad warning devices and traffic signals shall be coordinated with the appropriate Governmental Entities and operating railroads.

14.5.2 Railroad Agreement

Developer shall be responsible for obtaining the required approvals, permits, and agreements as required for the Work, including any railroad related Work.

14.5.3 Agreement for Construction, Maintenance and Use of Right of Way

Construction & Maintenance (C&M) Agreements shall be between TxDOT, Developer, the appropriate railroad company and appropriate Governmental Entities and may take twelve (12) months or more to obtain from the railroad company. Current approved templates for TxDOT/railroad company agreements are available from the TxDOT Rail Division at Rail-Highway.Section@txdot.gov.

The following agreements may be required based upon the railroad's requirements:

a) Preliminary Engineering – Most railroads require preliminary engineering agreements in order to proceed with the development and review of plans. This agreement authorizes reimbursement to the railroad company for preliminary engineering and estimating performed by the railroad or their consultant(s).

b) License to Cross and C&M Agreement – Developer shall prepare template agreement to be executed between railroad, Developer and TxDOT. A License to Cross railroad right of way is normally required when the highway project involves a new crossing or grade separation of the railroad. A separate easement agreement may be obtained in lieu of the License to Cross. Developer shall prepare all the documents required to obtain the License and C&M Agreement, including preparation of the plans and specifications and estimates, making necessary modifications as required on behalf of TxDOT. Developer shall submit the draft License and C&M Agreement to TxDOT for transmittal to the railroad. After all comments have been incorporated or satisfactorily resolved by either Developer, railroad or TxDOT, Developer shall submit a complete and final agreement to TxDOT for execution. This agreement shall include provisions for each party's access to the facilities for regular inspection, maintenance as well as emergency repairs as required. Developer shall be responsible for all costs associated with the construction of the crossing including any construction performed by the railroad company as

specified in the railroad agreement. The railroad company shall be responsible for constructing the track, signal, warning protection improvements portion of the crossing and any grade crossings or other permitted improvements located within the rail ties; or as otherwise specified in the railroad agreement.

c) Aerial Easements (for grade separations only) - Developer may be required by the railroad company to enter into a separate easement agreement to obtain air rights to cross railroad ROW. If an aerial easement is required, the "License" portion of the C&M Agreement will be modified to identify the aerial easement as right to cross railroad right of way with the new highway facility.

d) Temporary Construction Easements - Developer may be required to purchase a temporary construction easement for the railroad company. This requirement will be stipulated in and be a part of the C&M Agreement.

e) Railroad's Contractor Right-of-Entry Agreements (Texas approved versions only) – In order to enter the railroad's right-of-way to perform the Work, Developer or their Subcontractor shall secure a railroad Right-of-Entry agreement and shall coordinate the arrangements of the necessary agreements directly with the railroad.

All executed agreements shall be submitted in their entirety as part of the Final Design Documents.

Whenever a license agreement for construction, maintenance, and use of railroad ROW (hereinafter called the "License Agreement") between the operating railroad and TxDOT is required, Developer shall prepare all the documentation required to obtain the License Agreement, including preparation of the License Agreement application on behalf of TxDOT, the Plans and specifications, making necessary modifications as required, and preparation of the License Agreement.

Developer shall submit the draft License Agreement to TxDOT for transmittal to the operating railroad. After all comments have been incorporated or satisfactorily resolved by either Developer, railroad or TxDOT, Developer shall submit a complete and final License Agreement to TxDOT for execution.

14.5.4 Operation Safety

Developer shall arrange with the operating railroad for railroad flagging as required. Developer shall comply with the operating railroad's requirements for contractor safety training prior to performing Work or other activities on the operating railroad's property.

14.5.5 Railroad Right of Entry Agreement

In order to enter the operating railroad's right-of-way to perform the Work, Developer shall secure a railroad Right of Entry Agreement and shall coordinate the arrangements of the necessary agreements directly with the operating railroad.

Executed railroad agreements in entirety, shall be submitted as part of the Final Design Documents.

14.5.6 Developer Right of Entry Agreement

Developer shall cooperate and coordinate with all operating railroads for access by the operating railroad and/or their agents to the rail ROW as necessary for rail maintenance and operations activities, inspection, repair and emergency responses.

14.5.7 Insurance Requirements

Developer shall procure and maintain, prior to working adjacent to and entry upon operating railroad property, insurance policies naming TxDOT, TxDOT's Consultants, and railroad as named insured.

Developer shall obtain the insurance as required in Exhibit 14 of the Agreement.

All insurance policies shall be in a form acceptable to the operating railroad. Copies of all insurance policies shall be submitted to TxDOT prior to any entry by Developer upon operating railroad property.

14.6 Construction Requirements

Developer shall comply with all construction requirements and specifications set forth by the operating railroad and shall invite the appropriate railroad company to all pre-construction meetings.

Developer shall be responsible for scheduling the work to be completed by operating railroad as well as the work to be completed by its own forces. Developer shall be responsible for all costs associated with the railroad/transit force account work.

14.6.1 Flagging

Developer shall arrange for railroad flagging as required with the railroad company to ensure the safe passage of rail traffic throughout the Project limits effecting railroad right of way.

Developer shall notify the railroad representative at least ten (10) Business Days in advance of Developer commencing its work and at least thirty (30) Business Days in advance of any Work by Developer in which any person or equipment will be within twenty-five (25) feet of any track or will be near enough to any track that any equipment extension such as, but not limited to, a crane boom will reach to within twenty-five (25) feet of any track. No Work of any kind shall be performed, and no person, equipment, machinery, tool(s), material(s), vehicle(s), or thing(s) shall be located, operated, placed, or stored within twenty-five (25) feet of any track(s) unless authorized by the railroad. Upon receipt of such thirty (30)-day notice, the railroad representative will determine and inform Developer whether a flagman need be present and whether Developer needs to implement any special protective or safety measures.

14.6.2 Safety Certification

Developer shall comply with the railroad's requirements for contractor safety training prior to performing Work or other activities on the railroad's right-of-way and shall maintain current registration prior to working on railroad property.

14.6.3 Rail Corridor

If the Project includes a rail corridor within the Project ROW, Developer shall prepare a geometric design for the rail corridor. Developer's PMP shall set forth an approach, procedures, and methods for the rail corridor design and construction meeting the requirements set forth in the Contract Documents.

Developer shall demonstrate with the submittal of the Final Design Documents that the potential rail corridor design accommodates and is compatible with the requirements of the Ultimate Project.

15 AESTHETICS AND LANDSCAPING

15.1 General Requirements

This Section 15 defines requirements with which Developer shall design and construct aesthetic treatments for the roadway, structures, drainage, and landscaping Elements of the Project. Aesthetic treatments shall be designed to harmonize with the local landscape and architecture, as well as the developed themes of the local setting. Developer shall coordinate with local and State agencies to achieve this harmonization.

15.2 Administrative Requirements

This Section 15 presents minimum aesthetics and landscape design requirements for Project designs. For purposes of this Section 15, the following list of items will be considered the aesthetics Elements of the Project design:

a) Material, finish, color, and texture of bridge Elements

b) Materials, finish, and color of barriers and railings

c) Paved slope treatments

d) Finish, color, and texture of retaining and noise walls

e) Contour grading, slope rounding, channel treatments, and drainage

f) Sculptural and artistic features of other structures

g) Sidewalks, median or pedestrian specialty paving, including material, finish, and color

h) Hardscape at interchanges and intersections

i) Fencing

j) Signage – overhead, attached, and ground-mounted

k) Gantries

l) Any permanent building construction within the Project, including ancillary support, operational, and toll collections

m) Light fixture, ambient light colors, and general layout conditions

n) Material finish and color of light poles and mast arms, ambient lighting colors, and general layout conditions

15.2.1 Aesthetics Concepts

Aesthetic Elements shall be designed as corridor-wide enhancements. To the extent practicable, the aesthetic Elements shall remain consistent in form, materials, and design throughout the length of the Project where applied.

Aesthetic Design Guidelines have been developed for the Project. The approved aesthetic concept shall be incorporated into the Aesthetics and Landscaping Plan for TxDOT approval. All finishes, textures, colors, features, hardscapes, softscapes, fencing, signs, gantries, and any other Element of the Project shall comply with the Baseline Aesthetic Treatments and Accent Aesthetic Treatments as described in the Aesthetic Design Guidelines and the Aesthetic Master Plan. Detailed dimensions for structural elements provided in the Aesthetic Design Guidelines are representative. Final design dimension shall be the

responsibility of the Developer, however, proposed dimensions of the structural elements shall be proportionate to those provided in the Aesthetic Design Guidelines in order to maintain the aesthetic intent and will be further reviewed and approved for compliance. Before presenting the aesthetics concepts to the public, Developer shall meet and review the proposed aesthetics concepts with TxDOT.

15.2.2 Aesthetics and Landscaping Plan

Developer shall prepare an Aesthetics and Landscaping Plan(s) in conformance with the Baseline Aesthetic Treatments and Accent Aesthetic Treatments as described in the IH 35E Aesthetic Design Guidelines and Aesthetic Master Plan which provides guidelines and requirements for the aesthetics design of the Project. Developer shall submit the Aesthetics and Landscaping Plan(s) to TxDOT for review and approval in its good faith discretion within one hundred twenty (120) Days of issuance of NTP1. Approval of the Aesthetics and Landscaping Plan(s) shall be a condition of NTP2.

The Aesthetics and Landscaping Plan(s) shall include all Elements to fully communicate the proposed aesthetic treatment to TxDOT and shall address:

- Aesthetics Plans
    - a) All plans, sections, elevations, perspectives, isometrics, etc., as needed to fully communicate the aesthetic treatment and approach to aesthetic Elements including: walls, noise walls, bridges, traffic rail, and signage structures.
    - b) Incorporate the IH 35E Aesthetic Master Plan and Baseline Aesthetic Treatments and Accent Aesthetic Treatments as described in the Aesthetic Design Guidelines provided in the Reference Information Document.
    - c) Drawing showing the location of Utilities as they relate to the location of aesthetic improvements. Developer shall provide composite drawings showing potential conflicts for proposed improvements.
    - d) Color schemes and their locations
- Landscaping Plans
    - a) A plan that indicates plant palettes, locations of plants, plant types, and planting dates
    - b) A maintenance program
    - c) Composite drawings of all utilities and easements that would interfere with landscaping, markers, or any other identified enhancements
    - d) Developer shall provide a landscaping plan in accordance with the Baseline Aesthetic Treatments and Accent Aesthetic Treatments as described in the IH 35E Aesthetic Design Guidelines and Aesthetic Master Plan

The Aesthetic and Landscaping Plan(s) shall include all plans, elevations, perspectives, isometrics, etc., as needed to fully convey the aesthetic treatment.

Upon completion of the Aesthetic and Landscaping Plan(s), Developer shall consolidate the information, which establishes the requirements for engineering of the highway corridor aesthetics. The guidelines shall serve as the primary standard guidance necessary to produce the intended aesthetic form, function, and appearance of this and future similar projects.

This Aesthetics and Landscaping Plan(s) shall be presented in the following format:

a) 11x17 format

b) Front sided only

c) Eight paper copies, in color

d) Eight (8) CD copies, with guidelines in portable document format (PDF)

The Aesthetics and Landscaping Plan(s) shall be incorporated into the final engineering design.

TxDOT approval of the Aesthetics and Landscape Plan(s) is required prior to construction of any Elements affected by the Plan.

15.2.3 Personnel

Developer shall provide a landscape architect, registered in the State of Texas, with a minimum five (5) years experience in designing aesthetics and landscaping Elements for roadway projects of similar scope and size, to develop the Aesthetics and Landscaping Plan.

15.3 Design Requirements

15.3.1 Aesthetics Principles and Strategies

Developer shall follow the guidelines and requirements of the approved Aesthetics and Landscaping Plan, as well as the aesthetics principles, requirements, and strategies established by TxDOT for the Project design, including the following:

a) Aesthetics shall not interfere with safety, constructability and maintenance requirements.

b) The Project design shall minimize impact on the existing natural environment to the extent possible.

c) The Project design shall emphasize and enhance the existing natural context and landscape to the fullest extent possible.

d) Simple geometric shapes for structures shall be used to the extent possible for continuity along the entire length of the Project.

e) All bridges and other structures shall be simplified in their design, and to the greatest extent possible kept small in size, bulk, and mass.

f) All structures shall be carefully detailed so as to achieve the greatest level of aesthetic quality and fit within the regional context.

g) Color, texture, and form shall be used appropriately for all structures.

h) Graphics, signage, and lighting shall be consistent along the entire length of the Project.

i) Existing trees and natural features shall be preserved to the greatest extent possible.

j) Aesthetics Elements shall be fully integrated with the overall landscape design.

k) Visual quality of the landscape shall be consistent along the entire length of the Project.

l) Native-area and/or naturalized plant materials that exhibit good drought tolerance shall be used to the extent possible.

m) Aesthetic Elements shall be easy to maintain and resistant to vandalism and graffiti.

n) Aesthetic Elements shall conform to the IH 35E Aesthetic Master Plan and Aesthetic Design Guidelines as well as the Green Ribbon Program Design Guidelines and approved Dallas District Standards.

o) All Project improvements in the IH 35E / IH 635 interchange shall comply with the LBJ/635 Managed Lanes Project aesthetics guidelines.

15.3.2 Walls

Developer shall design noise/sound walls to be similar in color, texture, and style to those of retaining walls, and shall develop an aesthetics treatment that is consistent with other physical features such as structures, landscaping, and other highway components.

Developer shall apply aesthetic treatments to the vertical surfaces of retaining and noise/sound walls where the surface is visible from the roadway or adjacent houses. Consistent treatments shall be used for retaining and noise/sound walls that articulate the design themes established for the Project.

The Developer shall clearly detail and identify how wall patterns shall be incorporated into the chosen design solution.

The roadside face of noise walls shall have a consistent appearance throughout their length. The side of the noise walls facing away from the roadway may vary based upon community input gathered by the Developer.

15.3.3 Bridges and Other Structures

All aesthetic treatments for new structural Elements shall be coordinated with Developer's structural design team to facilitate constructability and maintain safety requirements. All components of new structures and exterior caps, columns, beams, railing, and retaining walls of widened structures shall include aesthetic treatments in accordance with the Baseline Aesthetic Treatments and Accent Aesthetic Treatments as described in the IH-35E Corridor Aesthetic Guidelines. Lengthened portions of existing bridges shall match existing aesthetic treatments.

No exposed conduits or drain pipes will be allowed on bents, columns, bridge beams, retaining walls, or any other visible surface on any new bridge or widened portion of any existing bridges.

Developer shall ensure that a constant superstructure depth is maintained throughout the bridge length for all new bridges other than direct connection structures and braided ramps. For direct connection structures and braided ramps, concrete beam spans shall be of constant depth throughout the structure.

15.3.4 Trees, Shrubs, and Other Plant Materials

All trees, shrubs, deciduous vines, and perennials shall comply with the applicable requirements of *ANSI Z60.1 American Standard for Nursery Stock*. Developer shall consult with the agricultural extension agent of the applicable county and TxDOT for recommended plant species lists. Developer shall use plant species native to the area or naturalized for the Project site.

In order to monitor and control weeds, Developer shall provide weed control measures in the Aesthetics and Landscape Plan.

Vegetation provided as a part of Developer's Aesthetic and Landscaping plan, other than grassing, and erosion control measures, shall be incorporated with the following guidelines:

- Trees, if used shall be placed in accordance with TxDOT's minimum clearance zones and shall be placed in the Project ROW between mainlanes and frontage roads. Trees shall be a minimum of 6 feet high and shall have a 3 inch caliper minimum.
- Trees shall conform to the IH 35E Aesthetic Master Plan and Aesthetic Design Guidelines as well as the Green Ribbon Program Design Guidelines.
- The mature canopy shall not overhang the travel lane or shoulder of any part of the roadway.

15.3.5 Riprap

Concrete paving shall be used in hard to reach mowing areas or under structures such as, but not limited to, areas between, near, or next to guard fence posts, sign posts, bent columns, retaining walls, freeway ramp gores, paved ditches, flumes, and ditch inlets to improve roadway appearance.

15.3.6 Lighting

Developer shall design the aesthetic enhancement lighting with the following aesthetic criteria:

- One pole type for the entire corridor during the design and construction phase and, to the extent practicable, the Operating Period. Developer shall provide a lighting layout plan that addresses each light fixture (i.e. roadside lighting, high mast lighting, under bridge fixture, etc.) and type of light fixture (i.e. LED lighting, point source lighting, HID, etc.)

15.3.7 Color Pallet

As part of the Aesthetics and Landscaping Plan, Developer shall submit a plan that indicates where each color is to be applied. This plan can be diagrammatic in nature, but shall list each element and its colors. In addition to integrated colors, painting, and staining, Developer may use colored lighting in selected areas to add color.

15.4 Construction Requirements

Developer shall provide TxDOT sample panels a minimum of sixty (60) Days in advance of starting construction of textured concrete surfaces. Developer shall construct sample panels in accordance with TxDOT *Standard Specifications for Construction and Maintenance of Highways, Streets, and Bridges* Item 427.4.B.2.d (Form Liner Finish) that comply with the principles, requirements, and strategies established by TxDOT and the approved Aesthetics and Landscaping Plan. TxDOT must review and approve the sample panels before any construction form liners may be ordered, obtained, or used. Developer shall provide sample panels having a textured portion at least 5.0 feet by 5.0 feet with a representative un-textured surrounding surface.

The approved sample panel shall be the standard of comparison for the production concrete surface texture.

For textured panels or concrete surfaces finished with a coating of paint or stain, Developer shall prepare a corresponding coated panel or surface area of an in-place Element for approval prior to the coating operation.

Color samples shall be provided from the Federal Standard 595B Colors Fan Deck. All sample panels shall be representative of the actual panel that will be placed. Primary, secondary and accent colors shall be displayed.

15.5 Aesthetic Enhancements

The Developer shall provide adjacent Governmental Entities the opportunity to enhance aesthetic and landscaping features consistent with the requirements herein and categorized as "Enhanced Aesthetic Treatments" in the following documents provided in the Reference Information Documents:

- IH-35E Corridor – Aesthetic Master Plan – October 25th, 2011
- IH-35E Corridor – Aesthetic Design Guidelines – October 25th, 2011

The additional capital and maintenance costs of the adjacent Governmental Entity improvements (Aesthetic Enhancements) beyond what would be attributable to the Baseline Aesthetic Treatments and

Accent Aesthetic Treatments as described in the Aesthetic Design Guidelines shall be the responsibility of the adjacent Governmental Entity. Developer shall coordinate the necessary arrangements directly with the appropriate local Governmental Entity for Aesthetic Enhancements within the local Governmental Entity's jurisdiction if so required by the Work. Not withstanding the foregoing, Enhanced Aesthetic Treatments have been requested by the City of Lewisville for FM 407, as provided in the Reference Information Documents as "FM 407 Aesthetics", and shall be included in the Project and Price.

Aesthetic Enhancements shall be incorporated into the final aesthetic concept plan to be submitted to TxDOT for approval.

16 SIGNING, DELINEATION, PAVEMENT MARKING, SIGNALIZATION, AND LIGHTING

16.1 General Requirements

This Section 16 includes requirements with which Developer shall design, construct, and maintain all signing, delineation, pavement markings, signalization, and lighting, for the Project.

16.2 Administrative Requirements

16.2.1 Meetings

Developer shall arrange and coordinate all meetings with local agencies that will assume responsibility for maintaining and operating traffic signals and roadway lighting. Developer shall provide TxDOT with notification of such meetings a minimum of 48 hours prior to the start of the meeting. TxDOT, in its discretion, may attend such meetings.

Developer shall arrange and coordinate all meetings with requesting agencies or individuals regarding special signs.

16.3 Design Requirements

The Developer shall design all signing, delineation, pavement marking, and signalization in accordance with the Texas Manual on Uniform Traffic Control Devices (TMUTCD) and TxDOT's *Standard Highway Sign Design for Texas* (SHSD), and TxDOT's Traffic Engineering Standard Sheets and TxDOT specifications.

Developer's design shall incorporate the following requirements:

- Minimum size for all the proposed warning signs shall be 36"x36".
- Install warning signs W18-13T (48"x48") "WATCH FOR ICE ON BRIDGE" in advance of all bridges.
- Use R3-7R "RIGHT LANE MUST TURN RIGHT" and R3-7L "LEFT LANE MUST TURN LEFT" signs where required. Do not use R3-5R or R3-5L "Arrow and ONLY" signs. These signs shall not be installed at dedicated turn bays.
- Install object markers OM-2Y under the route marker assembly located at the entrance ramp gore between the frontage road and mainlanes.
- Install object markers OM-1 on each leg of large ground mounted signs where the signposts are not protected by concrete barrier or metal beam guard fence, similar to the exit sign at the exit gore.
- Install appropriate added lane sign W4-3R (48"x48") or merge sign W4-1R (48"X48") on the mainlanes of the freeway in advance of each entrance ramp.
- Install advisory exit speed limit sign W13-2 (48"x60") on the mainlanes in advance of each exit ramp.
- Design guide sign details according to the Standard Highway Sign Designs for TxMUTCD and TxDOT current standard drawings "Typical Sign Requirements", and the TxDOT Freeway Signing Handbook Manual

- Use the B-3 arrow for overhead guide sign panel at the exit ramps.
- Design all overhead sign structures for Zone 1, 100 mph wind zone.
- All proposed overhead sign panels shall be 46% below the centerline of the overhead sign structure truss (see standard SB (SWL-1)).
- Advance and sequential signs outside the Project limits shall have mileages verified and adjusted as needed due to the removal and / or relocation of an exit.
- The bottom of the proposed overhead sign panels facing the same direction of traffic shall be on the same horizontal plane.
- All the small signs shall be Aluminum Type A.
- Design all large ground mounted signs for Zone 1 (Type 100) which is 90 mph wind zone. (See TxDOT current drawing "Roadside Guide Sign Post Selection Worksheet).
- All overhead sign panels shall be extruded aluminum.
- All large ground mounted signs shall be extruded aluminum.

At newly constructed intersections the Developer shall design and install signing including general, street name signs, pedestrian signs, regulatory signs, warning signs, and guide signs.

At reconstructed intersections the Developer shall design and install or adjust signing including general, street name signs, pedestrian signs, regulatory signs, warning signs, and guide signs.

At intersections which will be re-used or undergo only minor rehabilitation the developer shall adjust signing including general, street name signs, pedestrian signs, regulatory signs, warning signs, and guide signs as needed.

16.3.1 Final Design

Developer shall advance the Final Design of the signing, delineation, pavement marking, signalization, and lighting based on the preliminary operational signing schematic received with the Proposal. If a preliminary operational signing schematic does not exist, Developer shall prepare and submit a preliminary operational signing schematic for review and approval by TxDOT and Federal Highway Administration (FHWA) prior to commencing Final Design. Before placing any signs, delineation, advance toll warning signs, third party signs, non-standard sign structures, pavement markings, traffic signals, and lighting, Developer shall provide TxDOT a layout indicating the proposed location of such items.

16.3.2 Signing and Delineation

Developer shall design and install all signs as shown on the Final Design. Signs include new signs, as well as modifications to existing sign panels and structures. Developer's design shall include the locations of ground-mounted and overhead signs, graphic representation of all signs, proposed striping, delineation placement, guide sign and special sign details, and structural and foundation requirements. Signs shall be located in a manner that avoids conflicts with other signs, vegetation, dynamic message signs (DMS), lighting, and structures.

Developer shall ensure that signs are clearly visible, provide clear direction and information for users, and comply with all applicable TMUTCD requirements.

Developer shall review with TxDOT all requests for new signs, including traffic generators, or modifications of existing sign text. Such requests are subject to TxDOT's approval.

Developer's design of delineators and object markers shall comply with TMUTCD requirements.

Signs shall meet the requirements of TxDOT's *Standard Highway Sign Design for Texas*.

16.3.3 Project Signs – Outside the Project ROW

For signs located outside the Project ROW but within a public ROW, Developer shall install the signs in existing rights-of-way controlled by local or other State agencies. Developer shall coordinate with appropriate Governmental Entities for the design and installation of such signs.

16.3.4 Advance Toll Information Signs

For advance toll information signs, Developer shall be responsible for determining sign locations and foundation types, and design and installation of the new signs. The Developer shall prepare and submit a preliminary advance toll information signing schematic for review and approval by TxDOT a minimum of six (6) months prior to Substantial Completion.

Developer shall coordinate with all local toll entities in the area and shall use Good Industry Practice in determining the locations for advance toll information signs. At a minimum, advance toll information signs shall be installed at the following locations:

- At all locations with public access to the managed lanes
- Prior to all entrance ramps to the Project

16.3.5 Third-Party Signs

In addition to the warning, regulatory, and guide signs within the Project ROW, TxDOT or Governmental Entities may request that third-party signs, including logo signs, be installed by a third party. Developer shall coordinate and cooperate with any third party performing such work. TxDOT may solicit input from Developer in reviewing applications for new third-party signs, but will retain sole authority for approving installation of these signs. All costs associated with fabricating and installing these signs shall be borne by the sign applicant. If approved by TxDOT, TxDOT may require Developer to fabricate and/or install these signs as a TxDOT-Directed Change.

16.3.6 Sign Support Structures

Developer shall determine foundation types and design sign foundations based upon geotechnical surveys/tests using Good Industry Practices. Designs for sign supports shall also comply with requirements in Sections 13 (Structures) and 15 (Aesthetics and Landscaping).

Developer shall design sign support structures to provide a vertical clearance of not less than 17'6" between the roadway and the bottom of the sign.

16.3.7 Pavement Marking

Developer shall ensure that the design and installation of all pavement markings comply with applicable TMUTCD requirements and TxDOT's Traffic Engineering Standard sheets.

Developer shall mark median noses of all raised islands and inside edges of exclusive turn lanes (channelized curbs) in accordance with the requirements of TMUTCD and TxDOT's Traffic Engineering Standard sheets.

Developer shall use contrast markings for skip lines on the controlled access main lanes where light-colored pavement does not provide sufficient contrast with the markings. Contrast markings consist of black background in combination with standard TMUTCD marking colors.

Developer shall provide shoulder texturing in accordance with TxDOT's Traffic Engineering Standards sheets. Shoulder texturing shall not be used on direct connectors, on bridges, or across ramp pavement.

16.3.8 Signalization

Traffic signal designs and modifications to existing traffic signals shall be completed in accordance with the current TxDOT standards and specifications, the TMUTCD, and the requirements of the appropriate Governmental Entity.

16.3.8.1 Traffic Signal Requirements

Developer shall design and install fully-actuated permanent traffic signals at all TxDOT-authorized intersections within Project limits. In addition, Developer shall modify, as appropriate, any existing traffic signals impacted by the Final Design. Developer shall coordinate with TxDOT and the appropriate Governmental Entities to define appropriate traffic signal design requirements, local agency oversight of Developer's Work, and final acceptance of traffic signals. Developer shall coordinate with the appropriate Governmental Entities for synchronization of traffic signal networks.

Developer shall provide interconnection systems between new or modified signals and any other signal system within the Project site as required by TxDOT or the appropriate local Governmental Entity. Developer shall make existing signal systems compatible with the proposed interconnections. Developer shall ensure continuous communication with the traffic signal system within the Project site, and shall provide all communication hardware/equipment for TxDOT or the appropriate local Governmental Entity to communicate with the signal systems within the Project site.

Developer shall provide pedestrian detectors and signals at all traffic signals within the Project site and shall comply with TxDOT's *Accessible Pedestrian Signal (APS) Guidelines*.

Developer is responsible for preparing traffic signal agreements (or supplements thereto) for execution by TxDOT and the appropriate Governmental Entity having operation and/or maintenance responsibilities.

At newly constructed intersections the Developer shall design and install traffic signals, as warranted and authorized as well as any signal support systems and cabinets.

At reconstructed intersections the Developer shall assess the adequacy of existing traffic and pedestrian signals and upgrade as needed to accommodate intersection and overall Project improvements, as well as any signal support systems and cabinets.

At intersections which will be re-used or undergo only minor rehabilitation the developer shall review the existing traffic and pedestrian signal timing and coordinate with local Governmental Entities in accordance with any existing or new municipal maintenance agreements and adjust timing where applicable and as needed to accommodate traffic flows impacted by the Project.

16.3.8.2 Traffic Signal Timing Plans

Developer shall design signal timing plans for all new and modified traffic signals and shall submit to TxDOT for review. Developer shall coordinate and implement signal timing plans that

optimize traffic flows and provide signal coordination with adjacent intersections and arterials for all existing and new traffic signals, modified signals, and interconnected signals. Unless timing maintenance is otherwise provided by a Governmental Entity, Developer shall be responsible for updating signal timing as necessary to maintain optimized flow. Signal timing and phasing plans at diamond interchanges shall conform to the coordinated signal phasing and timing of the corridor.

Developer shall provide copies of all final implemented signal timing plans.

16.3.8.3 Traffic Signal Warrants

As part of the Final Design process, Developer shall collect traffic data and prepare traffic warrant studies for intersections not signalized at the time of NTP1 and shall submit these signal warrant studies to TxDOT for review. The warrant studies shall address all signal warrant criteria in the TMUTCD. Developer shall make recommendations for new signal installations based on these warrant studies in consultation with TxDOT and the appropriate Governmental Entities. TxDOT will reasonably determine if a signal or modification is required, based upon the warrant study.

All requests for signals within the Project ROW throughout the Term of the Agreement shall be subject to TxDOT approval.

Signal warrant studies shall be based on actual traffic and/or opening year traffic projections. If actual traffic volumes are not available, but opening year traffic is available, Developer shall use the procedure in Section 3.5 of the TxDOT *Traffic Signals Manual* to determine the volumes to be analyzed. If opening year traffic volumes are not available, opening year traffic volumes shall be calculated by applying a 50-percent reduction to the Design Year traffic projections. Developer shall conduct additional traffic signal warrant studies for all intersections located in the Project ROW, commencing six months after the Project is opened for traffic. If additional signals or modifications to existing signals are warranted, based on the traffic volumes obtained through these studies, Developer shall be responsible for installation of additional traffic signals or modification of previously-installed traffic signals. If, based on the above traffic counts, the need for a signal or signal modification is unclear; TxDOT will reasonably determine if the new signal or signal modification is required.

16.3.8.4 Traffic Signal Support Structures

Developer shall coordinate with TxDOT and the appropriate Governmental Entities to determine the type of traffic signal support structures. Developer shall obtain the maintaining Governmental Entities' approval of traffic signal support structures to be used on new signal installations.

16.3.8.5 Traffic Signal Systems

Developer shall provide interconnection systems between new or modified signals and any other signal system within one-half mile of the Project as required by TxDOT or the appropriate Governmental Entity. Developer shall make existing signal systems compatible with the proposed interconnections. Developer shall ensure continuous communication with the traffic signal system within the Project, and shall provide all communication hardware/equipment for TxDOT or the appropriate Governmental Entity to communicate with the signal systems within the Project site.

Developer shall provide to TxDOT, as part of the Final Design Documents, an Acceptance Test Plan (ATP) for all traffic signals. This ATP shall also be submitted to the appropriate Governmental Entity. The Developer shall conduct testing in accordance with the ATP and document those results to show conformance.

16.3.9 Lighting

Developer shall provide roadway lighting along the general purpose lanes, managed lanes, ramps, collector distributor lanes, interchanges, and cross street intersections. Lighting along frontage roads shall be provided in locations where lighting systems are currently provided within the Project limits.

At newly constructed and reconstructed intersections the Developer shall design and install lighting as required by the TxDOT Highway Illumination Manual.

At intersections which will be re-used or undergo only minor rehabilitation the developer will not be required to install additional lighting.

Developer shall prepare lighting studies that consider illumination levels, uniformity, and sources for the roadways, interchanges, and special areas. Developer shall maintain an average horizontal luminance on the roadways as described below. Developer shall submit the photometric data results for all lighted areas within the Project limits to TxDOT for review.

All third-party requests for lighting within the Project site shall be subject to TxDOT approval.

Developer shall provide an average to minimum uniformity ratio of 3.1, with a minimum lux of 1.85 and an average lux of 6.5 to 8.6 on all traveled roadways to be illuminated. Traveled roadways include: tolled lanes, general use lanes, HOV lanes, auxiliary lanes, ramps, frontage roads (if required), interchanges and ramp terminal intersections with cross streets.

Developer shall design the lighting system to minimize or eliminate illumination of areas outside the Project ROW. Developer shall design continuous and safety lighting systems in accordance with Chapters 5, 6, 7, and 9 of the TxDOT *Highway Illumination Manual* and the NEC. At all times during the Term of the Agreement, Developer shall maintain safe lighting conditions along the Project roadway.

Luminaire poles and breakaway bases shall be designed in accordance with AASHTO's *Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals*. For all poles located within the clear zone of the roadways, Developer's design shall incorporate breakaway devices that are pre-qualified by TxDOT.

Developer shall place all understructure lighting in a configuration that minimizes the need for lane closures during maintenance.

Developer shall determine and design appropriate foundation types and lengths for permanent lighting structures if not using TxDOT standards.

Developer shall not place ITS cable, fiber-optic lines, signal conductors, or any other non-lighting related cables or conductors in the lighting conduit, ground boxes, or junction boxes.

Developer shall minimize the potential hazards of lighting poles through the careful consideration of mounting options and pole placements, including the following options:

- Placing mast arms on traffic signal poles
- Placing pole bases on proposed concrete traffic barrier
- Placing poles behind existing or proposed concrete traffic barrier or metal beam fence
- Placing high mast lighting outside the clear zone, especially in roadway horizontal curves

Developer shall ensure that lighting structures comply with FAA height restrictions near airport facilities. In the event that proposed or existing luminaires, mast arms, or poles infringe into an airport's or heliport's base surface, Developer shall coordinate with the FAA and TxDOT to permit or relocate such structures. If FAA restrictions prohibit lighting structures from being placed in certain areas near an airport facility, Developer shall find alternative ways of providing the required level of lighting.

Developer shall coordinate with TxDOT and the appropriate government entities to define additional illumination design preferences of the local maintenance and operation agency.

16.3.9.1Additional Requirements

Additional requirements are as follows:

a) High-mast lighting must not infringe into residential areas adjacent to the Project ROW.

b) Developer must coordinate with the FAA regarding installation of obstruction lights, if any, on a case-by-case basis.

c) At a minimum, underground conduit in interchange areas or temporary detours shall not be less than 2" or Schedule 40 polyvinyl chloride (PVC).

d) The minimum conductor size shall be #8 AWG copper for primary circuits and #12 AWG for underpass lights on the load side of the fusible disconnect. Developer shall not use duct cable for illumination purposes.

e) Developer shall place bridge lighting brackets no more than 10 feet from abutments or bents; however, in special circumstances, the bridge lighting brackets may be placed a maximum of 20 feet from abutments and piers.

f) If overhead electric lines confine the placement of luminaires, Developer may use special davit-arm luminaires.

g) Minimum inside dimensions for ground boxes shall be 11.5 inches (width) by 21 inches (length) by 10 inches (depth) (TxDOT Type A)

h) Ground box covers shall be 2-inch-thick (nominal), nonconducting material and labeled "Danger High Voltage Illumination".

i) Riprap aprons shall be provided to ground boxes located in grassy areas.

j) Electrical services shall have an identification tag denoting a contact person or office in case of emergency or for maintenance, and the address and telephone number.

k) Electrical part of the installation shall be designed and installed in conformance with the National Electrical Code (NEC).

16.3.10 Visual Quality

Notwithstanding the requirements of Section 16.3.8 (Permanent Signalization), Developer shall make a reasonable attempt to provide luminaires of equal height along the roadway.

Developer shall not use timber poles for permanent installation.

Developer shall re-sod or re-seed areas of construction disturbed by the installation of signs, traffic signal systems, or lighting systems after final installation.

16.4 Construction Requirements

16.4.1 Permanent Signing and Delineation

Developer shall use established industry and utility safety practices to erect and remove signs located near any overhead or underground utilities, and shall consult with the appropriate Utility Owner(s) prior to beginning such Work. Developer shall stake each sign location in the field and provide TxDOT 72 hours notice prior to installation of any sign.

Developer shall leave all applicable advance guide signs and/or exit direction signs in place at all times and shall not obstruct the view of the signs to the motorist. Developer shall replace any other removed signs before the end of the work day.

Developer shall affix a sign identification decal to the back of all signs for inventory purposes and shall submit inventory information to TxDOT in a TxDOT-compatible format.

All installed signs are required to meet the minimum retro-reflectivity values specified in TMUTCD Table 2A-2.1 (Minimum Maintained Retroreflectivity Levels).

Table 16-2: Retroreflectivity Values

Sign Colors	Sheeting Type (ASTM D4956-04)				Additional Criteria
	I	II	III	VII, VIII, IX	
White on Green	W*; G _	W*; G 15	W*; G 25	W 250; G 25	Overhead
	W*; G 7	W 120; G 15			Ground-mounted
Black on Orange or Black on Yellow	Y*; O*	W _50; G 50			See Note 1
	Y*; O*	W 75; G 75			See Note 2
White on Red	W 35; R 7				See Note 3
Black on White	W 50				—

Notes:

The minimum maintained retro-reflectivity levels shown in this table are in units of candelas per lux per square meter (cd/lx/m^2), measured at an observation angle of 0.2° and an entrance angle of -4.0°.

1 For text and fine symbol signs measuring at least 1200 millimeters (mm) (48 inches) and for all sizes of bold symbol signs

2 For text and fine symbol signs measuring less than 1200 mm (48 inches)

3 Minimum Sign Contrast Ratio _ 3:1 (white retroreflectivity ÷ red retroreflectivity)

* This sheeting type should not be used for this color for this application.

Bold Symbol Signs

W1-1, -2 – Turn and Curve
W1-3, -4 – Reverse Turn and Curve
W1-5 – Winding Road
W1-6, -7 – Large Arrow
W1-8 – Chevron
W1-10 – Intersection in Curve
W1-11 – Hairpin Curve
W1-15 – 270 Degree Loop
W2-1 – Cross Road
W2-2, -3 – Side Road
W2-4, -5 – T and Y Intersection
W2-6 – Circular Intersection

W3-1 – Stop Ahead
W3-2 – Yield Ahead
W3-3 – Signal Ahead
W4-1 – Merge
W4-2 – Lane Ends
W4-3 – Added Lane
W4-5 – Entering Roadway Merge
W4-6 – Entering Roadway Added Lane
W6-1, -2 – Divided Highway Plaques Begins and Ends
W6-3 – Two-Way Traffic
W10-1, -2, -3, -4, -11, -12 – Highway-Railroad Advance

W11-2 – Pedestrian Crossing
W11-3 – Deer Crossing
W11-4 – Cattle Crossing
W11-5 – Farm Equipment
W11-6 – Snowmobile Crossing
W11-7 – Equestrian Crossing
W11-8 – Fire Station
W11-10 – Truck Crossing
W12-1 – Double Arrow
W16-5p, -6p, -7p – Pointing Arrow Plaques
W20-7a – Flagger
W21-1a – Worker

Fine Symbol Signs – Symbol signs not listed as Bold Symbol Signs.

Special Cases

W3-1–Stop Ahead: Red retroreflectivity, 7

W3-2–Yield Ahead: Red retroreflectivity, 7, White retroreflectivity, 35

W3-3–Signal Ahead: Red retroreflectivity, 7, Green retroreflectivity, 7

W3-5–Speed Reduction: White retroreflectivity,_50

For non-diamond-shaped signs such as W14-3 (No Passing Zone), W4-4p (Cross Traffic Does Not Stop), and W13-1, -2, -3, -5 (Speed Advisory Plaques), use largest sign dimension to determine proper minimum retroreflectivity level.

16.4.2 Permanent Pavement marking

Developer shall meet the following minimum retro-reflectivity values for edge line markings, centerline/no passing barrier line markings, and lane line markings when measured any time after three (3) days but not later than ten (10) days after application:

a) Type I, Thermoplastic, Pavement Markings:

- White markings: 250 millicandelas per square meter per lux (mcd/m2/lx)
- Yellow markings: 175 mcd/m2/lx

b) Type II, Paint & Beads, Pavement Markings:

- White markings: 175 mcd/m2/lx
- Yellow markings: 125 mcd/m2/lx

Lane line striping shall be 6" for the mainlanes and 4" for the edge lines.

16.4.3 Permanent Signalization

Developer shall coordinate with the Utility Owner(s) and ensure necessary power service is initiated and maintained for permanent signal systems. Developer shall ensure power is provided to all Developer-installed signals. Developer shall stake each pole location in the field and provide TxDOT a 72 hour notice prior to installation of any foundation.

Developer shall provide TxDOT with copies of all signal warrant studies as required in this Section 16. Developer shall also provide copies of all final signal timing.

Before placing any permanent traffic signals, Developer shall provide TxDOT a complete traffic signal design for review.

16.4.4 Permanent Lighting

Developer shall coordinate with the Utility Owner(s) and ensure power service is initiated and maintained for permanent lighting systems. Where the Work impacts existing lighting, Developer shall maintain existing lighting, as temporary lighting during construction and restore or replace prior to Substantial Completion. At all times during the Term, safe lighting conditions shall be maintained along the Project roadway. Developer shall stake each pole location in the field and provide TxDOT a72 hour notice prior to installation of any foundation.

Developer shall remove all old illumination-related cable and conduit that does not have existing pavement or riprap above it; any existing illumination-related cable and conduit that is under the existing pavement or riprap may be abandoned.

Developer shall place all bore pits safely away from traffic, provide positive barrier protection, and provide necessary signs to warn of the construction area.

Developer shall contact Utility Owners regarding their specific required working clearance requirements.

Developer shall affix an identification decal on each luminaire, ground box, and electrical service maintained and/or operated by TxDOT for inventory purposes and shall submit inventory information to TxDOT in a TxDOT-compatible format. This identification shall denote that these are property of TxDOT and shall provide a contact phone number and address in the event of Emergency or necessary maintenance

17 INTELLIGENT TRANSPORTATION SYSTEMS

17.1 General Requirements

An Intelligent Transportation System (ITS) is necessary for monitoring the Project's traffic flow and performance both during construction and as a permanent installation. The Project ITS must accurately detect traffic and traffic operational conditions throughout the Project limits, and clearly communicate relevant and useful travel information to the people using the facility.

TxDOT is operating an ITS network that will need to connect to the new system provided by Developer. The Project ITS must be compatible with such in-place system(s) that TxDOT and other agencies (including other developers) are currently operating. Developer shall coordinate the ITS planning and implementation with TxDOT~~, other agencies~~, and other Governmental Entities that have roadways within or intersecting the Project.

Developer shall maintain and protect the use of the existing ITS functionality within the Project at all times, except for system crossovers that are approved by TxDOT. The Developer shall utilize the existing ITS infrastructure to the greatest extent possible. The Developer shall conduct a survey of existing ITS infrastructure available within the Project corridor and provide TxDOT with a report of deviations from the provided ITS as-built information and conditions of the infrastructure. The Developer is responsible for repairing any damaged infrastructure prior to utilization on the Project.

The Project ITS shall conform to the Regional Data and Video Communications System (RDVCS) of the North Texas Regional Comprehensive ITS Architecture~~.~~ and have physical connections with the existing TxDOT ITS communication network on major freeways. The functionality of the ITS shall be such that command and control of appropriate field devices is exchanged with appropriate Governmental Entities.

Developer shall be responsible for the planning, design, installation, maintenance, and operation of safe and functional ITS for the Project using Good Industry Practice. All components of the ITS shall conform to the provisions of the National Transportation Communication for ITS Protocol (NTCIP). Developer shall maintain ITS interoperability over the Term of the Agreement with TxDOT~~, other agencies,~~ and other Governmental Entities. The ITS shall be coordinated with the Electronic Toll Collection System (ETCS) such that the communication requirements of the ETCS system are accommodated.

The Project ITS shall operate under the North Texas Regional ITS Architecture and Center-to-Center (C2C) concept of operations. ~~The Project ITS shall include a Traffic Management Center~~DalTrans shall be the main traffic management center (TMC) for ~~the Project corridor to support mobility equally along the I-35E corridor.~~this project. Communication and interoperability shall be achieved with other TMCs in the region~~, including but not limited to DalTrans,~~ such that with appropriate privileges, access to data, command, control and information sharing can occur among centers. All communication and access of information shall occur in real-time (within logistical restraints).

To assist the Developer, the most recent Special Specifications for the following ITS elements are:

- SS6014 – Fiber Optic Cable (Single Mode)
- SS6025 – CCTV Field Equipment
- SS6229 – Camera Pole Structure w/Cabinet (60 FT)

- SS6277 – Multiduct Conduit System
- SS6278 – RS232 Fiber Data Modem (One-time use)
- SS6890 – CCTV Central Equipment (One-time use)
- SS6893 – Communication Building (Satellite) (10' x 15') (One-time use)
- SS6894 – Communication Cabinet (Hub) (59" x 26") (One-time use)
- SS6896 – Fiber Optic Video Transmission Equipment
- SS8695 – CCTV High Mast Assembly
- SS8696 – System Integration (One-time use)
- SS8743 – Remove CCTV Field Equipment (One-time use)
- SS8791 – Install DMS (One-time use)
- SS8821 – Radar Vehicle Sensing Device (RVSD) (One-time use); Also use Spec. Prov. 8821-001 for HD

17.2 Design Requirements

Developer shall provide a complete and operational ITS network throughout the Project that is expandable as capacity is increased along the Project roadways, utilizes hardware and software components consistent and compatible with TxDOT in the manner described in this Section 17.2 and the other affected Governmental Entities, resistant to weather encountered in the Project area, and places components in locations that are not hazardous to Users. Prior to beginning ITS and toll design efforts, the Developer shall conduct an ITS and toll design workshop with TxDOT and affected Governmental Entities (per TxDOT's direction) to confirm TxDOT's operational requirements, review the Developer's survey of existing ITS infrastructure and condition assessment, discuss concepts, identify potential resolutions for site-specific issues (as identified by the Developer) and confirm requirements of other affected Governmental Entities. Developer shall prepare a preliminary ITS layout for review and concurrence by TxDOT to ensure adequate planning of the ITS implementation.

Subject to the specific requirements of this Section 17, Developer shall determine the number and specific locations of all ITS components.

Developer shall provide safe ingress/egress areas and structures to accommodate authorized personnel access to ITS components for maintenance and operation activities.

All components of the ITS shall conform to the provisions of the National Transportation Communication for ITS Protocol (NTCIP) and be compatible with the latest operating system being used by the Dallas District~~.~~ (DalTrans) for traffic management. In the event of a conflict between NTCIP and RDVCS, the standard utilized by DalTrans' traffic management system shall prevail.

All ITS devices and associated mountings shall meet the100 mph wind load design standards.

The installed ITS Equipment shall provide TxDOT access to accurate and reliable data and quality video images and accurate control of field devices from DalTrans on a real-time basis 24 hours a day, 7 days a week. Real-time is defined as correct data being available at DalTrans within thirty (30) seconds of being processed or the correct response of a field component within one (1) millisecond of the command being sent.

Developer shall be responsible for ensuring the CCTV, DMS, and vehicle detection systems meet the reliability requirements specified in the most current TxDOT statewide and~~/or~~ Dallas District

specifications as well as any standard publications provided by TxDOT at the time of actual design work.

The design and construction requirements, together with the design criteria presented in the most current TxDOT statewide and~~/or~~ Dallas District specifications as well as any standard publications provided by TxDOT at the time of the actual design work define the minimum standards and scope that must be met by the Developer. Any recommended modifications to the specifications shall be presented by the Developer at the ITS and toll design workshop and shall be subject to TxDOT approval. The Developer may supplement these requirements in order to access the data and video images and control of the CCTV for the sole purpose of managing the Project. As between the parties, TxDOT shall retain ownership and all rights to the data and video images and the Developer shall not provide access to the data or video images to any third party without the authorization of TxDOT's representative.

The Developer is responsible for designing and constructing lightning protection, grounding and surge suppression for each ITS structure and equipment cabinet. Ground mounted equipment cabinets next to ITS support structures will not be allowed and must be mounted to the support structure.

Developer shall be responsible for the design, installation and access to power required to operate the ITS devices including all utility costs until Substantial Completion of the Segment and Project Final Acceptance by TxDOT~~.~~, at which time the utilities will be transferred to TxDOT.

Additional design requirements are provided in Attachment 17-1.

17.2.1 ITS Communications Requirements

Developer shall provide a communications network that has redundant routing capabilities. The communications network shall serve the highway ITS components along the highway Elements of the Project. ~~Where necessary, as determined by TxDOT,~~ The Developer shall provide additional communication ~~node buildings and~~ cabinets~~-~~, as determined by TxDOT, to support the communications network.

The current TxDOT communications network backbone is a 10 Gigabit Multiple Protocol Label Switching (MPLS) Ethernet network.

Each field network switch shall provide a primary and secondary fiber path of two fibers each from the field cabinet to separate satellite buildings. The maximum number of Layer 2 field network switches forming a network path between an end device (TxDOT ITS) and a satellite building based data aggregating Layer 3 network switch shall not exceed 12. The calculated data throughput assigned to any sub-network path shall not exceed 50% of the path's throughput capacity. Calculations for band usage shall be provided during the preliminary design efforts.

New devices and existing devices shall not be assigned within the same network path or otherwise daisy-chained to avoid possible inconsistencies in communication protocols.

The Developer shall install 48 strands of fiber between satellite buildings to connect to ITS devices, plus another 48 strands of fiber between satellite buildings as spare fibers. No splicing of the spare fiber is allowed unless approved by TxDOT. Pull boxes shall be spaced at each ITS device location, Toll Zone, satellite building and a maximum of every 700' along the Project corridor. The Developer is responsible for confirming that 48 strands of fiber can support the proposed ITS deployment and providing additional fiber at no cost to TxDOT, as needed, to ensure that no more than 50% of the throughput capacity of a sub-network path is exceeded.

Furthermore, the Developer shall provide, install and test single mode fiber for toll systems communications. Fiber shall be placed in a dedicated vault in the duct banks along the corridor and shall consist of four (4) strands for each Toll Zone – two from the closest satellite buildings north and south of the Toll Zone. Daisy-chaining of toll zones will not be permitted. All fiber, conduit and ground boxes for the toll systems shall be separate from those used for ITS and shall be exclusive to the toll systems. Fiber strands for any ITS devices which will be connected to the tolling communication network shall adhere to the general ITS communication network requirements identified above. The Developer shall calculate the number of fiber strands needed for tolling and toll-related ITS purposes, provide 100% spares and round to the next standard number of ITS strands. These calculations shall be provided to TxDOT as part of the preliminary plans.

The Developer shall provide terminal servers, video encoders, and media converters and modems to establish communications as required. Video encoding shall meet MPEG-4 standards and be compatible with TxDOT's traffic management system software requirements for TxDOT CCTV.

17.2.2 Conduit

Developer shall determine the type, quantity, and design of the conduit above and below ground, ground boxes, and all communication cable and electrical conductors to support the ITS network and operations. No exposed conduit sections will be permitted. All sections shall be bored, or in the case of large bridge crossings, built into the bridge structure, unless approved by TxDOT during preliminary design efforts. Options for crossing Lewisville Lake shall be discussed during the pre-design workshop. The conduit duct bank must support the number of existing duct bank conduits plus any new conduits needed for communication and power (assuming there are no spares in existing duct banks), plus two spare conduits for future expansion. One conduit will be used for tolling. The Contractor shall provide separate conduits for tolling and toll-related ITS communication, tolling and toll-related ITS power, general ITS communication and general ITS power.

TxDOT believes that an existing spare 3" conduit exists in the fiber duct bank between IH-635 and PGBT and is available for Developer use, however the Developer shall confirm this in accordance with the Technical Provisions Section 17.1. The Developer may discuss alternative inter-duct options within existing duct banks, such as the use of mesh conduits, with TxDOT during the pre-design workshop and during preliminary design efforts. Acceptance of alternative approaches is in TxDOT's sole discretion.

Developer shall repair each communication cable or electrical conductor that is severed or otherwise rendered not usable.

The Developer shall provide materials and use construction methodology in conformance at a minimum with the most current or applicable TxDOT statewide and~~/or Dallas District specifications~~ Dallas District specifications, including placement of a trace wire within duct bank, encasing the duct bank in concrete, placing locator tape and installing above ground markers. During the pre-design workshop, the Developer shall provide alternatives to TxDOT's current practices for securing ground box lids.

17.2.3 CCTV Cameras

Developer shall provide color CCTV cameras for Incident verification~~ and~~, traffic management~~.~~, emergency management, security and support for necessary maintenance of the system. The system of cameras shall provide operators with the ability to clearly view and accurately identify all vehicle(s) involved in an Incident or Emergency, the extent of vehicle(s) damage, and if

applicable the likelihood of personal injury. Operation of the cameras shall result in no visual delay in response of the camera pan/tilt/zoom by a user.

Additionally, the CCTV cameras will be utilized extensively during the reversible lane operations. Specifically, the cameras will be used to sweep the Managed Lanes and access ramps to remotely verify that there are no vehicles or obstructions within the Managed Lanes, and to verify the status of the gates, messages on the advanced traveler notification signs and the toll rate signs.

17.2.3.1Equipment

Developer shall provide all necessary ~~CCTV~~ pan-tilt-zoom (PTZ) CCTV support structures, equipment, including, but not limited to, cameras, camera controls, cables, and connections.

Developer shall provide ~~all the equipment necessary for TxDOT secondary control of all CCTV cameras. The method of secondary control shall be in accordance with TxDOT standards and specifications.~~

~~Developer shall provide an analog~~a digital video format and communications protocol at all connections~~ with TxDOT systems.~~. The digital format and protocol provided by Developer shall be compatible with systems in use by TxDOT at DalTrans, and if necessary ~~convertible~~converted for use by TxDOT's in-place ITS network.

17.2.3.2Placement

Developer shall provide overlapping roadway coverage by CCTV cameras for all highway lanes and intersecting cross streets within the Project limits to provide redundant camera field of view. CCTV cameras shall be placed to enable Developer or TxDOT to monitor traffic conditions on highway lanes, frontage roads, connecting facilities, and entrance and exit ramps, and messages displayed on any remotely-controlled dynamic message signs in the Project area. To provide a stable video image, Developer shall mount cameras on dedicated structures unless otherwise approved by TxDOT.

The Developer shall utilize multiple CCTV camera installations at multi-level interchanges to ensure complete visual coverage of the interchange.

~~Distance between CCTV cameras shall not exceed 1.0 miles.~~

Distance between CCTV cameras shall not exceed 0.5 mile, however the Developer is responsible for placing cameras to ensure 100% coverage of the Managed Lanes and associated shoulders, slip ramps, interchange access points and ramps, and all toll related signing. 100% coverage shall be defined as no blind spots for any reason, including but not limited to: trees, bridge structures, horizontal or vertical alignment, overhead or side mounted sign structures, or toll gantries. Additionally, each CCTV camera shall be able to view the CCTV camera immediately upstream and downstream from itself unless approved by TxDOT.

17.2.3.3Video Requirements

Developer shall provide state-of-the-art CCTV cameras that meet the ~~following~~ requirements~~.~~ of the most applicable TxDOT statewide or DalTrans standard. Should any CCTV cameras fail to meet ~~any of the following criteria~~the latest TxDOT statewide or DalTrans standard specifications at the time of design, Developer shall replace such cameras within 48 hours of discovery of lack of compliance.

~~a) Solid-state design with digital signal processing (DSP) for digital zoom~~

- ~~for auto/manual long-term integration (exposure) control, with built-in frame buffer~~
- ~~for auto-focus; for built-in I.D. generator, with white letters and black outline~~

~~b) Conformance to a minimum of National Television System Committee (NTSC) video output and Electronic Industries Alliance (EIA) 170A standards~~

~~c) No less than 30 frames per second (fps) color~~

~~d) Able to produce clear, low-bloom, low-lag video pictures under all conditions, from bright sunlight to nighttime scene illumination of 0.02 foot-candles~~

~~e) Maintenance of color quality by a continuous, through-the-lens, automatic, white balance for color temperatures from 2850 degrees Kelvin to greater than 5100 degrees Kelvin, with less than 10 Institute of Radio Engineers (IRE) units unbalance~~

~~f) Aspect ratio of 4:3~~

~~g) Zero geometric distortion~~

~~h) Signal to noise distortion of 55 dB with AGC off~~

~~i) Built-in auto focus and auto iris~~

~~j) Overexposure protection to prevent permanent damage to cameras when pointed at strong light sources, including the sun, for brief periods of time~~

~~k) Built-in ID Generator~~

17.2.3.4 Operating Requirements

Developer shall provide cameras with built-in heaters, mounting structure, and related equipment capable of operating within the following weather conditions:

a) Wind load of 100 mph without permanent damage to mechanical and electrical equipment

b) Ambient temperature range of -35 degrees Fahrenheit to +140 degrees Fahrenheit

c) Relative humidity range not to exceed 95 percent within the temperature range of +40 degrees Fahrenheit to +110 degrees Fahrenheit

d) Humidity range of 0 to 100 percent condensing

17.2.3.5 Control Requirements

~~Developer shall provide cameras and related equipment capable of operating with the following pan-tilt unit requirements:~~

~~a) Vertical movement of + 40 degrees to – 90 degrees~~

~~b) Horizontal movement of 360 degrees~~

~~c) Tilt speed of 20 degrees per second~~

~~d) Pan speed of 100 degrees per second~~

~~e) Simultaneous pan and tilt~~

~~f) RS-232 serial communications~~

The Developer shall supply CCTV equipment on this ~~Project~~project which is fully compatible with the existing CCTV control system operated from DalTrans. In order to prove compatibility and operability of CCTV systems submitted for use on this ~~Project~~project, deliver one complete set of CCTV equipment to DalTrans for testing by DalTrans ~~information technology personnel~~Information Technology Personnel as part of the equipment submittal and approval process. Allow a minimum of 30 days for testing by DalTrans IT personnel. Submit the CCTV equipment for testing no later than 60 days after completion of TxDOT submittal review. The equipment submitted for testing must be fully assembled and in a fully operational condition. Configure all equipment submitted for testing as is intended for use on the ~~Project~~project. Prototype equipment will not be allowed. The equipment will be interconnected to the existing CCTV control system and must be fully operational using that system. No modifications to the existing CCTV control system will be made to accommodate the submitted CCTV equipment. To be considered fully operational, as a minimum, the equipment must correctly respond to the following commands:

pan left	focus far
pan right	iris override
tilt up	iris open
tilt down	iris close
Zoom in	Camera power (latching)
Zoom out	pan tilt position preset
Focus near	~~Vertical movement of +~~

Upon completion of installation, test the communications link installed between the ~~communications hub~~satellite building and the CCTV field equipment locations. Perform the test at all CCTV locations on the ~~Project~~project.

Use a test signal generator and a video monitor to demonstrate the ability of the video signal link to transmit a NTSC compliant video signal from the CCTV cabinet to the ~~communications hub~~satellite building. After completion of testing with the signal generator, connect the CCTV camera to the link and use a video monitor at the ~~communications hub~~satellite building to verify the presence of an NTSC compliant video signal. No degradation of the video signal must be discernible using the video monitor.

Connect a laptop computer containing TxDOT-supplied CCTV control software on the link and used to control the CCTV movement and control functions from the ~~communications hub~~satellite building utilizing the data link. Demonstrate the ability to control all CCTV functions outlined in the specifications.

Supply all test equipment, cabling and connectors necessary for performing the tests by the ~~Subcontractor~~Developer.

The equipment must be fully operational using the existing control system from ~~Transtar~~DalTrans. Equipment which in any manner is not fully operational with the control system will be considered as not passing the test. Equipment which does not pass the test will be allowed one chance to be retested. The retest must occur within 30 days after the initial test. All issues of non-compliance and all discrepancies must be resolved for the second test. Equipment which is not able to be retested within 30 days or which does not pass the second test will be rejected and cannot be used on the ~~Project~~project. No additional time or compensation will be granted for the testing of the CCTV equipment. Successful testing of the CCTV equipment must be completed prior to any construction activities at the CCTV locations. No camera poles, cabinets or any other CCTV related equipment shall be installed until successful CCTV equipment testing has occurred.

17.2.4 Vehicle Detection

Developer shall provide permanent high definition (HD) detection in each highway lane of the Project that measures vehicle classification, vehicular volume, lane occupancy, and speed information on the roadway. The detectors shall be non-intrusive to the roadway users. Spacing for the permanent vehicle detection shall be no greater than 0.5 ~~mile~~miles in each highway~~ lane, each entrance ramp lane and each exit ramp~~ lane in the Project or, at a minimum, provide detection for all highway lanes at one location between interchanges, each entrance ramp lane, and each exit ramp lane. ~~A highway lane includes general purpose, managed lanes and collector distributor lanes~~ For sensors which are not placed in the pavement, the Developer shall locate the devices on the side of the Project nearest the largest managed lane shoulder so as to limit the potential interference of the concrete traffic barrier on detecting vehicles and collecting information.

Vehicle detection sensors shall determine vehicle speed for each vehicle passing the sensor. ~~Developer~~The sensors shall provide ~~upon TxDOT request, the~~ raw speed data (volume, speed, lane occupancy and ~~speed)~~vehicle classification counts) and direction of travel for the General Purpose Lanes and the Managed Lanes for each vehicle detection sensor. Additionally, the sensors (or the software controlling the sensors) shall be capable of determining vehicles traveling in the wrong direction. For sensors that collect data across multiple lanes of traffic, data shall be collected and provided by lane. In areas where a sensor would have to collect data on more than twelve (12) lanes of traffic including shoulders or over distances greater than two hundred-fifty (250) feet, the Developer shall provide detectors on each side of the Project. TxDOT shall be able to adjust the frequency rates that the data files are provided by device.

In addition to supporting traffic management operations, some of the sensors will provide information to TxDOT's toll collection system to be used in establishing dynamic adjusted toll rates. The following table provides the number of shared VDS locations by toll group (note that VDS locations placed on opposite sides of the Project because of distance or number of lanes constraints shall be considered as a single shared VDS location):

Toll Group	Number of Shared VDS Locations
TG-1	2
TG-2	2
TG-3	3
TG-4	4

TG-5	4
TG-6	5
TG-7	5

Specific locations of the shared VDS devices shall be discussed during the pre-design workshop and confirmed during the preliminary design process. As the ITS and toll devices are on separate fiber backbones, the selected VDSs shall be configured to provide data feeds to two separate networks. For these shared VDS devices, the Developer shall be responsible for a full installation of the device for the general ITS purposes and for tolling purposes, installing conduits between the VDS device and the toll network equipment cabinet (installed by the Integrator) and running communication cable from the device into the toll network equipment cabinet.

Developer may attach detection units to existing structures with prior concurrence from TxDOT. Where an existing structure is not available, or in lieu of attaching the detection unit to an existing structure, Developer shall install a mounting pole solely for the vehicle detector. Any mounting poles placed specifically for ITS items shall conform to TxDOT specifications for CCTV mounting poles. Developer shall provide all necessary support structures, equipment, including, but not limited to, VDS devices, controls, cables, and connections.

17.2.5 Dynamic Message Signs (DMS)

Developer shall provide a comprehensive network of electronic DMS using only light-emitting diode (LED) display technology. DMS shall be uniform and, at a minimum, shall meet the Dallas District guidelines. The DMS shall support full matrix graphics and color.

Developer shall position each DMS to allow motorists to safely view the messages being displayed. Developer shall locate the DMS to comply with large guide sign spacing stated in the TMUTCD. ~~Developer shall coordinate with the Tolling Integrator a layout indicating the locations of all dynamic toll pricing signs.~~

DMS shall conform to the TxDOT special specification National Transportation Communications for ITS Protocol for Dynamic Message Signs and shall demonstrate compliance before installation of DMS.

DMS shall be used to inform motorist of the availability of alternate routes, and to advise travelers of adverse road conditions and congestion. DMS shall be placed to provide a driver-friendly sign-viewing angle at each DMS location. Additionally, two northbound and one southbound DMS over the Managed Lanes will be required to provide information directly to Users of the Managed Lanes. The Developer shall coordinate the location of the Managed Lane DMS with TxDOT during the preliminary design phase to maximize their value to DalTrans and Users of the Managed Lanes. The Developer shall coordinate with TxDOT on the location of the Managed Lane DMS during the ITS and toll design workshop.

~~DMS~~Developer shall ~~be uniform~~provide all necessary support structures and~~, at a minimum,~~ equipment, including, but not limited to, DMS devices, controls, cables, and connections.

DMS shall ~~meet~~have the ~~Dallas District guidelines~~ability to be controlled using the latest TxDOT DMS operating system being used at DalTrans.

~~The specific design and message(s) to be included on the dynamic toll pricing signs shall be determined during the sign design process by TxDOT, the Developer, and coordinated with the Tolling Integrator.~~

17.2.6 Lane Control Signals (LCS)

~~This section~~No LCS is ~~not used~~required.

17.2.7 Single-Line DMS (SDMS)

The SDMS shall be utilized to disseminate the status of the Managed Lanes (e.g. open or closed) and to notify users and potential users of the Managed Lanes of the toll rate in effect for the upcoming Toll Zone. These CMS panels will be mounted to the static signs for both advanced traveler information signs and toll rate signs.

Developer shall place SDMS over ~~through~~ travel lanes on existing or proposed overhead sign structures on managed and mainline roadways. ~~Average spacing of SDMS shall be approximately two miles, except where a DMS~~SDMS utilized as part of the advanced toll information signs, as described in the Technical Provisions Section 16.3.4, shall be spaced at minimum of one (1) mile, half (0.5) mile and immediate entrance distances from each access ramp. Toll rate signs shall be spaced between half (0.5) and one (1) mile from each access point and after each toll gantry, but before the exit after each toll gantry, on the Managed Lanes. The specific location ~~will satisfy both DMS and SDMS operational requirements and the exception is approved by TxDOT.~~of the toll rate signs shall be coordinated with the Integrator. All sign bridges shall be designed to accommodate SDMS brackets.

~~Developer shall provide LED technology SDMS composed of one-lane-wide, interconnecting modules with a lane control signal (LCS) functionality embedded in each module as required to provide individual lane availability information to each through travel lane.~~

~~*Communication Hub Enclosures*~~/The SDMS shall support full matrix graphics and color, and be able to display at least 10 characters of 18" font.

For the advanced traveler information sign SDMS, the Developer shall provide and install all necessary support structures and equipment, including, but not limited to, SDMS devices, controls, cables, connections and network equipment. For the toll rate sign SDMS, the Developer shall provide and install the toll rate sign foundation, static portion of the sign with cutouts for the SDMS panels, conduits through the vertical column of the sign support to a ground box at the base of the sign support, ground box, and electrical power and communication backbone in proximity of each sign. The Developer shall coordinate the design of the toll rate sign with the Integrator to incorporate the requirements of the Integrator's provided and installed SDMS.

Developer installed SDMS shall have the ability to be controlled using the latest TxDOT SDMS operating system being used at DalTrans.

17.2.8 Communication Cabinets

Developer shall coordinate with TxDOT the connection of all new ITS components to the existing ITS communication ~~hub enclosures and communication cabinets covering the Project~~cabinets covering the Project. Each ITS location shall require a communication cabinet and, unless approved by TxDOT, the communication cabinet shall be mounted to the ITS support structure. For those not mounted to a support structure, the Developer shall install the cabinet on a concrete pad protected from traffic.

Developer shall provide all necessary mounting equipment, including, but not limited to, cabinets, controls, cables, and connections.

17.2.9 Satellite Buildings

Developer shall coordinate with TxDOT the connection of all new ITS components to the existing ITS satellite buildings (communication hubs) covering the Facility and connections to the DalTrans Traffic Management Center.

Developer shall maintain and protect any existing satellite buildings within the Project limits. As necessary, Developer shall relocate or reconstruct the satellite buildings in accordance with the latest applicable standards.

The Developer shall install network equipment and racks which meet the equivalent standards in today's technology of the latest Dallas District specifications. The Developer shall obtain TxDOT approval of proposed network equipment prior to purchase and installation.

The Developer shall provide a new satellite building at the northern terminus of the Project at a location approved by TxDOT. The satellite building shall contain a driveway and fencing surrounding the building.

17.2.10 Travel Time Sensors

To assist TxDOT in minimizing the probability that a toll rate is calculated which is different than that seen by a User passing under a toll rate sign, the Integrator shall install an Automated Vehicle Identification (AVI) sensor over the leftmost travel lane on access ramps and over each travel lane in the Managed Lanes. The Developer shall coordinate the height of the sign support structure with the Integrator to ensure that the minimum vertical clearance of 17'6" between the lowest point of the AVI sensor and the top of the pavement is achieved. The travel time sensors shall be connected to the tolling network.

The Developer shall provide location information (station reference, offset from baseline, and latitude / longitude coordinates in degrees, minutes and seconds) to the Integrator for each travel time sensor site to assist the Integrator with submitting the paperwork for and obtaining the necessary FCC permits and licenses. The information shall be provided to the Integrator according to the Integrator's schedule for submitting the information to the FCC.

~~17.2.10~~17.2.11 Center-to-Center Interface

~~Developer~~TxDOT shall provide the center-to-center interface necessary to tie-in to the North Texas Regional Comprehensive ITS Architecture, however the Developer will be responsible for selecting devices that will support the regional agency-to-agency interoperability requirements.

17.2.12 Access Control System (ACS)

The ACS at each access location shall consist of a series of automated barricade gates on each side of a vehicle arresting barrier (VAB).

The automated barricade gate includes, but is not limited to the following:

- Gate support frame with built-in anchoring base
- Gate swing arm
- Horizontal FHWA approved NCHRP 350 crash tested swing gate
- Electrical linear actuator equipped with:

  - end of travel limit switches;
  - mechanical overload protection;
  - hand crank manual override
- Electrical components and associated equipment:
  - power control circuit for actuator operation;
  - 12 VDC battery charger;
  - full gate light power management and flashing logic
- Pushbutton Control Panel (remote)

The VAB is used to prohibit motor vehicles from entering a closed highway. The VAB must safely decelerate and stop a vehicle in accordance with NCHRP 350 guidelines, Test Level 3. Vehicles shall be limited to light cars up to busses with a maximum speed of 60 MPH and 40 MPH, respectively. The VAB includes, but is not limited to the following:

- Vehicle restraining mechanism
- Structural frame
- Lifting mechanism
- Local controls

The restraining mechanisms consist of, as a minimum, two energy-absorbing devices on either side of a restraining net. The devices travel with the lifting-lowering mechanism to open or close a road and have bi-directional vehicle stopping ability. The restraining net has high strength impact capacity and has a reflective stop sign attached to both sides of the net. The net entraps the vehicle and transfers the force of the impact to the energy-absorbing devices.

Both the gates and the VAB shall be connected to the ITS network and controllable in an automated manner both with systems in use by TxDOT at DalTrans and locally. Each device shall also be able to be lowered and raised manually.

17.3 Construction Requirements

17.3.1 General

Developer shall notify TxDOT thirty (30) days in advance of making connections to the existing TxDOT system.

Developer shall maintain existing ITS communications functionality during construction activities. Developer shall coordinate with Utility Owner(s) and ensure that power service is available for permanent ITS systems.

17.3.2 Salvaging Existing Items

TxDOT reserves the right to require Developer, at any time to salvage and deliver to a location designated by TxDOT within the TxDOT District in which the Project is located, any TxDOT-owned equipment and materials in an undamaged condition. TxDOT reserves the right to require Developer, at any time to salvage and deliver to a reasonable location designated by TxDOT any ITS equipment and materials in an undamaged condition.

17.3.3 Existing ITS Relocation

Developer shall relocate any existing ITS components, including hubs, satellite buildings, CCTV cameras, DMSs, detection devices, and fiber-links, as required to continue service from the existing components. Developer shall sequence construction and relocation of existing ITS components, facilities, and systems to prevent lapses in TxDOT's receipt of video or data within the Project area. The existing physical links and the proposed physical links shall be in separate physical conduits.

Before removing existing ITS items and before beginning construction of segments without existing ITS, Developer shall perform all activities necessary to maintain system operations during construction, including installing new ITS items, relocating or replacing existing ITS items, and connecting such ITS items to the existing network.

17.4 Testing

17.4.1 General

Developer shall conduct the tests identified in each of the TxDOT special provisions and special specifications for the applicable ITS element. The Developer shall provide test plans, procedures and schedule according to the testing requirements and prior to conducting testing activities.

Test results shall be provided to TxDOT in both hardcopy and digital format.

17.4.2 End-to-End Testing

Prior to Substantial Completion, Developer shall coordinate with TxDOT to allow for end-to-end testing of the Managed Lanes. Testing will occur during the twenty-one (21) calendar Day period prior to Substantial Completion and shall provide TxDOT, DalTrans and Integrator with an opportunity to conduct full system tests, conduct daily operations to confirm operation plans and standard operating procedures, and to otherwise prepare for operational use of the Managed Lanes facility. End-to-end testing will also occur after hours and on weekends. The Developer, TxDOT, DalTrans and Integrator shall have completed all its their testing, training of DalTrans and TxDOT staff, and acceptance requirements for Developer installed ITS devices, satellite buildings, communication and electrical networks, generators, and integration with DalTrans's traffic management system and TxDOT's back office toll collection system prior to the start of End-to-End Testing.

The Developer shall be responsible, at a minimum, for the coordinating the End-to-End Testing with TxDOT, DalTrans and the Integrator to ensure that there will be no conflicts between TxDOT, DalTrans, the Integrator and their affiliated contractors and the Developer's staff; provide providing temporary advance signing (if needed to avoid confusion) stating that the Managed Lanes are closed and testing is occurring; providing maintenance of traffic / traffic control at all access locations for a maximum of five full days which could include evenings and weekends and may not be consecutive; providing a safe environment free of obstacles and unauthorized personnel on the Managed Lanes; providing access to the Managed Lanes for authorized TxDOT, DalTrans and Integrator staff and contractors ; and repairing any issues found with the Developer's work efforts within one (1) calendar Days unless otherwise approved by TxDOT.

The Developer shall not expect to have access to nor conduct work within the Managed Lanes during the end-to-end testing, with the exception of providing services as described above. TxDOT may, at its own discretion, provide Developer access to the Managed Lanes to conduct work outside the services described above.

18 TRAFFIC CONTROL

18.1 General Requirements

Developer shall design and construct the Project, in conformance with the requirements stated in this Section 18, to provide for the safe and efficient movement of people, goods, and services, through and around the Project, while minimizing negative impacts to Users, residents, and businesses. Developer shall coordinate with local Government Entities on the development of the Traffic Management Plan (TMP).

During all phases, temporary or existing Intelligent Transportation System (ITS) equipment, illumination, and traffic signals shall remain in operation such that the new and existing equipment operate as a coherent system.

18.2 Administrative Requirements

18.2.1 Traffic Management Plan

Developer shall prepare and implement a TMP that includes the following items:

a) Descriptions of the qualifications and duties of the traffic engineering manager, traffic control coordinator, and other personnel with traffic control responsibilities

b) Procedures to identify and incorporate the needs of transit operators, Utility Owners, Governmental Entities, local governmental agencies, Emergency Service providers, school districts, business owners, and other related Users, Customer Groups or entities in the Project corridor and surrounding affected areas

c) Procedures for obtaining acceptance of detours, road and lane closures and other traffic pattern modifications from applicable Governmental Entities, and implementing and maintaining those modifications

d) Procedures for signing transitions during construction from one stage to the next and from Draft Interim Schematic to permanent signing

e) Procedures for maintenance and replacement of traffic control devices, including pavement markings and traffic barriers, if used, from one stage to the next and from Draft Interim Schematic to permanent placement

f) Procedures to regularly evaluate and modify, if necessary, traffic signal timings, and the procedures for the development, TxDOT approval, implementation, testing, and maintenance of all affected signals

g) Procedures to coordinate with the appropriate Governmental Entities operating signal networks along the Project or Project detour routes to ensure temporary system compatibility, establish responsibilities for temporary signal installation, maintenance, operation and removal, and coordinate traffic signal timing with local signal networks

h) Procedures and process for the safe ingress and egress of construction vehicles in the work zone

i) Provisions to provide continuous access to established truck routes and Hazardous Material (HazMat) routes, and to provide suitable detour routes, including obtaining any approvals required by the appropriate Governmental Entities for these uses

j) Procedures to modify plans as needed to adapt to current Project circumstances including a contingency plan to alleviate unreasonable construction-related back-ups that can be implemented immediately upon notification from TxDOT

k) Procedures to communicate TMP information to Developer's public information personnel and notify the public of maintenance of traffic issues in conjunction with the requirements of Section 3

l) Descriptions of contact methods, personnel available, and response times for any deficiencies or Emergency conditions requiring attention during off-hours

m) Procedures for night work (30 minutes after sunset to 30 minutes before sunrise) to include a work zone light system design in accordance with NCHRP Report 498 – *Illumination Guidelines for Nighttime Highway Work*

n) Developer shall notify the traveling public by placing changeable message signs a minimum of seven (7) Days in advance of actual roadway closure or major traffic modifications. Where available and when possible, the Developer shall coordinate and utilize Dynamic Message Signs on the regional ITS system.

o) Developer shall utilize uniformed police officers to effect main lane closures.

The Developer shall participate in coordination meetings scheduled by others. These meetings shall include Traffic Management Committee (TMC) meetings convened by Texas Transportation Institute (TTI) and consisting of local representatives and stakeholders impacted by the Project.

The TMP must be approved by TxDOT prior to the start of construction activities. Developer shall provide TxDOT sufficient time for review of, and comment on, the TMP. TxDOT retains the right to require revision and re-submittal of the TMP within a reasonable amount of time.

If at any time, TxDOT, in its sole discretion, determines that construction-related back-ups become unreasonable, modifications to alleviate the congestion shall be taken immediately. Contingency plans of how this will be determined and occur shall be included in the Traffic Management Plan. The development and implementation of these contingency plans shall be at the Developer's expense.

18.3 Design Requirements

18.3.1 Traffic Control Plans

Developer shall use the procedures in the TMP and the standards of the TMUTCD to develop detailed traffic control plans which provide for all construction stages and phasing, as well as all required switching procedures.

Developer shall produce a traffic control plan for each and every phase of Work that impacts traffic and involves traffic control details and shall coordinate with appropriate Governmental Entities on the development of the plan. Developer is responsible for obtaining all necessary permits from such local entities to implement the plans. Traffic control plans shall be designed, stamped, signed and dated by a Registered Professional Engineer in the State of Texas. All traffic control plans shall be subject to review by the Maintenance of Traffic Manager.

Each traffic control plan, including the contingency plan as described in Section 18.3.1.2, shall be submitted to TxDOT for review and approval a minimum of ten (10) Days prior to implementation. The traffic control plan shall include details for all detours, traffic control devices, striping, and signage applicable to each phase of construction. Information included in the traffic control plans shall be of sufficient detail to allow verification of design criteria and safety requirements, including typical sections,

alignment, striping layout, drop off conditions, and temporary drainage. The traffic control plans shall clearly designate all temporary reductions in speed limits. Changes to posted speed limits will not be allowed unless specific prior approval is granted to TxDOT by the Texas Transportation Commission. Maintenance of Traffic Manager shall be responsible for overseeing the implementation of all traffic control plans.

Opposing traffic on a normally divided roadway shall be separated with appropriate traffic control devices in accordance with Good Industry Practice and TMUTCD based on roadway design speed**.** Approved traffic control devices can be found in the *Compliant Work Zone Traffic Control Device List* (CWZTCD list). Any traffic control that involves the physical separation of contiguous lanes of the same roadway component (i.e. general purpose, frontage road, or managed lanes) traveling in the same direction will not be allowed.

Developer shall maintain signing continuity on all active roadways within or intersecting the Project at all times.

Throughout the duration of the Project, Developer shall ensure all streets and intersections remain open to traffic to the greatest extent possible by constructing the Work in stages. Developer shall maintain access to all adjacent streets and shall provide for ingress and egress to public and private properties at all times during the Project.

Developer shall prepare public information notices, in coordination with Section 3 (Public Information and Communications), in advance of the implementation of any lane closures or traffic switches. These notices shall be referred to as Traffic Advisories.

18.3.1.1Design Parameters for Traffic Control Plans

Design Vehicle. Turning movement on all local streets and driveways shall, at a minimum, provide similar characteristics as existing and accommodate a WB-62 design vehicle.

Design Speed. On Interstate and State Highways, the design speed shall be the existing posted speed limit or greater, except for major alignment transitions, where the design speed may be reduced by 10 mph if approved by TxDOT in its sole discretion.

Number of Lanes. The minimum number of lanes to be maintained and open to traffic during construction in each direction on each roadway component of the Project shall be in accordance with Tables 18-1A and 18-1B. Lane closures on other roadways may be considered and approved by TxDOT, within reason, so long as all traffic patterns and accesses are maintained.

Lane Widths. During construction, the minimum lane width for mainlanes is 11 feet. For frontage roads, major crossing streets and minor crossing streets, TxDOT may, in its sole discretion, temporarily allow 10-foot-lanes in limited circumstances during construction for short distances after reviewing the Developer's traffic control plan.

Shoulders. A minimum one foot offset from the edge of travel way to the edge of pavement or traffic barrier is required.

18.3.1.2Permitted Lane and Roadway Closures

Lane closures will only be permitted when the Developer can demonstrate that the closure will provide clear benefit to the progress of the Work. Developer may close the existing HOV lanes or repurpose the existing HOV lanes in order to maintain general purpose lane capacity during construction. Closures must be coordinated with adjacent projects and priority shall be given to the closure submitted first. Developer shall use the public information and communication methods available to inform the

appropriate Customer Groups of any lane closures. Lane closures, except for HOV lane closures, shall be in accordance with Tables 18-1A, 18-1B, and 18-2.

If at any time permitted lane closure backups become unreasonable (ex. motorist delay greater than 20 minutes), modifications to alleviate this congestion should be taken immediately. Developer shall provide a contingency plan showing how this lane closure modification will be implemented and identify the specific actions to alleviate congestion. If the Developer does not immediately implement the approved contingency plan, the congestion would be considered a lane closure and subject to Liquidated Damages for Lane Closures.

Developer shall construct all improvements to the FM 407 cross street and intersection prior to closing any access points to the DCTA facility and Eagle Point Marina adjacent to the Garden Ridge intersection.

If the construction of Garden Ridge Blvd. requires a full closure, Garden Ridge shall not be closed for longer than 60 days to allow for demolition of the existing bridge structure, beam and deck placement for the new bridge, and traffic switch.

Cross streets may temporarily be closed throughout the Project to allow for the construction of cross structures.

Any improvements at the U-Turns south of Corinth Parkway shall be completed prior to taking Corinth Parkway out of service and the U-Turns must remain fully open while Corinth Parkway is out of service. Post Oak Drive shall remain fully open while Corinth Parkway is out of service.

Southbound IH 35 to both southbound IH 35E and IH 35W shall be considered general purpose lanes. Both northbound IH 35E and IH 35W to northbound IH 35 shall be considered general purpose lanes.

Lane Closure.

Service periods for lane closures are defined as follows and are applicable to general purpose lanes:

Table 18-1A: Lane closure periods for three-lane section

	Northbound IH 35E				Southbound IH 35E			
	Sunday	Monday-Thursday	Friday	Saturday	Sunday	Monday-Thursday	Friday	Saturday
0:00	D	D	D	D	D	D	D	D
1:00	D	D	D	D	D	D	D	D
2:00	D	D	D	D	D	D	D	D
3:00	D	D	D	D	D	D	D	D
4:00	D	D	D	D	D	D	D	D
5:00	D	D	D	D	D	D	D	D
6:00	D	A	A	D	D	A	A	D
7:00	D	A	A	C	D	A	A	D
8:00	D	A	A	C	D	A	A	B
9:00	D	A	A	B	C	A	A	B
10:00	D	A	A	B	B	A	A	B
11:00	B	A	A	B	B	A	A	B
12:00	B	A	A	B	B	A	A	B
13:00	B	A	A	B	B	A	A	B
14:00	B	A	A	B	B	A	A	B
15:00	B	A	A	B	B	A	A	B
16:00	B	A	A	B	B	A	A	B
17:00	B	A	A	B	B	A	A	B
18:00	B	A	A	B	B	A	A	B
19:00	B	A	A	B	B	A	A	B
20:00	B	A	A	C	C	C	A	B
21:00	D	C	C	C	C	C	A	B
22:00	D	D	D	D	D	D	D	D
23:00	D	D	D	D	D	D	D	D

A	Weekday peak
B	Weekend peak
C	Off-peak
D	Night

Table 18-1B: Lane closure periods for two-lane section

	Northbound IH 35E				Southbound IH 35E			
	Sunday	Monday-Thursday	Friday	Saturday	Sunday	Monday-Thursday	Friday	Saturday
0:00	C	C	C	C	C	C	C	C
1:00	C	C	C	C	C	C	C	C
2:00	C	C	C	C	C	C	C	C
3:00	C	C	C	C	C	C	C	C
4:00	C	C	C	C	C	C	C	C
5:00	C	C	C	C	C	C	C	C
6:00	C	A	A	C	C	A	A	C
7:00	C	A	A	C	C	A	A	C
8:00	C	A	A	B	C	A	A	B
9:00	C	A	A	B	C	A	A	B
10:00	B	A	A	B	B	A	A	B
11:00	B	A	A	B	B	A	A	B
12:00	B	A	A	B	B	A	A	B
13:00	B	A	A	B	B	A	A	B
14:00	B	A	A	B	B	A	A	B
15:00	B	A	A	B	B	A	A	B
16:00	B	A	A	B	B	A	A	B
17:00	B	A	A	B	B	A	A	B
18:00	B	A	A	B	B	A	A	B
19:00	B	A	A	B	B	A	A	B
20:00	B	A	A	B	B	A	A	C
21:00	C	C	A	B	C	C	A	C
22:00	C	C	A	C	C	C	A	C
23:00	C	C	C	C	C	C	C	C

A	Weekday peak
B	Weekend peak
C	Off-peak/night

Table 18-2: Permitted Lane Closures Prior to Substantial Completion

	Permitted Lane Closures						
Category of Work	**Three-lane General Purpose Section Periods**				**Two-lane General Purpose Section Periods**		
	A	B	C	D	A	B	C
Any work necessary up to NTP2.	0	0	1	1	0	0	1
Work after commencement of construction: Placement of CTB, placement of pavement markings, full depth roadway repair, placement of bridge beams, bridge demolition or similar operations	0	0	1	1	0	0	1
Work after commencement of construction: Adjacent construction, lanes for construction traffic or similar operations	0	0	1	1	0	0	1

Notes:
1. **Period A** means the periods as described in Table 18-1.
2. **Period B** means the periods as described in Table 18-1.
3. **Period C** means the periods as described in Table 18-1.
4. **Period D** means the periods as described in Table 18-1.

a) Ramps

a. The Developer will not be allowed to close two consecutive entrance ramps or two consecutive exit ramps unless approved by TxDOT.

b. Developer shall provide 14 days advance notice of any ramp closures and shall also provide a staging analysis to the Governmental Entity having jurisdiction within and adjacent to the Project. When ramp movements are diverted or detoured along existing roads, Developer shall be responsible for any and all costs that may be assessed for the use of these existing roads. This may include an operational analysis, temporary traffic

control devices, road user costs, and any other costs associated with impacts to local facilities to the satisfaction of the Governmental Entity having jurisdiction.

c. The Developer shall provide ramps for entrance and exit for each direction at all times for cross streets shown in Table 18-3:

Table 18-3: Required Ramps at Cross Streets

NB Entrance Ramps	NB Exit Ramps	SB Entrance Ramps	SB Exit Ramps
	VALWOOD	VALWOOD	
	CROSBY[1]	CROSBY[1]	
BELT LINE	BELT LINE[1]	BELT LINE[1]	BELT LINE
	SANDY LAKE RD.	SANDY LAKE RD.	
SH 190	SH 190	SH 190	SH 190
	FRANKFORD		FRANKFORD
SH 121 DC	SH 121	SH 121 DC	
			VISTA RIDGE/ SH 121
HEBRON PKWY	HEBRON PKWY	HEBRON PRKY	HEBRON PKWY
	CORPORATE	CORPORATE	
BUS 121	BUS 121	BUS 121	BUS 121
FOX AVE		FOX AVE	
	MAIN ST. FM 1171	MAIN ST. FM 1171	MAIN ST. FM 1171

NB Entrance Ramps	NB Exit Ramps	SB Entrance Ramps	SB Exit Ramps
	VALLEY RIDGE BLVD	VALLEY RIDGE BLVD	
FM 407	FM 407		FM 407
LAKE PARK RD			
EAGLE POINT	EAGLE POINT		COPERAS BRANCH/ HIGHLAND VILLAGE
	S. DENTON DR / COUNTRY LANE	S. DENTON DR / COUNTRY LANE	
TURBEVILLE	TURBEVILLE	TURBEVILLE	
SWISHER			SWISHER
POST OAK	POST OAK	POST OAK	POST OAK
MAYHILL	MAYHILL	MAYHILL	MAYHILL
LOOP 288	LOOP 288	LOOP 288	LOOP 288
TEASELY/ FM 2181	TEASELY/ FM 2181	TEASELY/ FM 2181	TEASELY/ FM 2181
US 377 / FORT WORTH DR.	US 377 / FORT WORTH DR.	US 377 / FORT WORTH DR.	US 377 / FORT WORTH DR.
		McCORMICK	
	N. TEXAS BLVD	N. TEXAS BLVD	

NB Entrance Ramps	NB Exit Ramps	SB Entrance Ramps	SB Exit Ramps
	IH 35E NB to IH 35W SB DC	IH 35W NB to IH 35E SB DC	
	IH 35W NB to IH 35E SB FRONTAGE ROAD		
	BONNIE BRAE ST		
			OAK STREET
	US 380	US 380	

1. Belt Line Road entrance / exit ramp closures shall only be allowed on the condition that ramps allowing the same movements are open at Crosby Street
2. In the event that an existing access ramp listed above must be closed, Developer shall construct a temporary ramp to maintain access / movements as listed above

b) Frontage Roads
   a. For continuous frontage road sections (sections which contain a minimum of one frontage road lane between intersecting cross streets):
      i. Ramp closures of less than 24-hours are allowed.
      ii. Ramp closures of greater than 24-hours are allowed, with TxDOT approval, provided that an alternative ramp that maintains the same access is located within one mile of the cross street served by the closed ramp.
   b. For non-continuous frontage road sections:
      i. Ramp closures of less than 24-hours are allowed with TxDOT and appropriate Governmental Entity approval.
      ii. Ramp closures of greater than 24-hours are allowed with adequate detour routes approved by TxDOT and the appropriate Governmental Entity.
   c. Developer shall seek TxDOT approval if a reduction in the current number of frontage road or arterial street lanes are required.

c) Direct Connectors
   a. If Limited Access Highway to Limited Access Highway connectors are proposed for closure, a connector closure request shall be prepared and submitted to TxDOT for

Approval prior to closure of the connector. The connector closure request shall demonstrate the need for the closure relative to construction staging and provide supporting traffic analysis indicating detour routing, capacity analysis and proposed improvements along the detour route(s) and other impacted roads to accommodate the additional traffic.

d) Additional Constraints during construction:
   a. The Project scheduling and phasing shall also take account of:
   b. Developer shall maintain continuous construction Work adjacent to closed traffic lanes. Developer shall reopen closed traffic lanes during planned or actual periods of inactive construction Work greater than or equal to 14-days.
   c. Developer shall begin construction Work adjacent to a traffic shift or traffic detour within 7-days of shifting or detouring traffic.

e) Roads crossing over/under IH 35
   a. Developer to maintain the minimum number of lanes open as in Table 18-4. Reduction in capacity for successive cross streets will not be allowed simultaneously without the appropriate Governmental Entity approval.
   b. Developer shall maintain the same number of approach through lanes as shown in Table 18-4 through the intersection.

Table 18-4: Minimum approach lanes for roads crossing over/under Project

Cross Street	Type	EXISTING U-Turn @ X-street	Proposed U Turn	Existing				During Construction				
				N Bound[1]	S Bound[1]	E-Bound[1]	W Bound[1]	N Bound[1]	S Bound[1]	E-Bound[1]	W Bound[1]	U-Turns
4th St.	Under	NA	NA	T-T-TR	NA	T	R	T-TR	NA	T	NA	
Main W.	Under	NA	NA	TL-T-TR	TL-TR	TR	TR	TL-TR	TL-TR	TR	TR	
Belt Line Road[6]	Under	NA	NBSB SBNB	TL-T-R	TL-TR	T-T-T-R	T-T-TR	TL-TR	TL-TR	T-TR	T-TR	
Dickerson Pkwy.	Over	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
SH 121		NBSB SBNB		UL-TL-TR	U-L-TL-T-R	T-T-TR	T-T-T-R	UL-TL-TR	U-L-TL-T-R	T-T-TR	T-T-T-R	NBSB SBNB
FM 3040/HEBRON	Over	NA	NA	L-T-R	L-T-T-R	T-T-T-R	L-T-T-R	L-T-R	L-T-R	T-R	L-T-R	
ROBERTS DR (SERVES		NA	N	T-T		T	L-T		T	T		

Cross Street	Type	EXISTING U-Turn @ X-street	Proposed U Turn	Existing				During Construction				
				N Bound[1]	S Bound[1]	E-Bound[1]	W Bound[1]	N Bound[1]	S Bound[1]	E-Bound[1]	W Bound[1]	U-Turns
NBFR TO HEBRON)												
NB FR TO HEBRON CONNECTOR		NA	N	T-R		T	T	T-R		T	T	
Corporate Dr.	Under	NA	N	2 Way Clover Leaf	2 Way Clover Leaf	T-R	T-R	EB Clover Leaf	WB Clover Leaf	R	R	
Business 121	Under	NA	NBSB SBNB	U-T-TR-R	UL-TL-TR	T-T-TR	T-T-TR	T-TR-R	L-T-R	T-TR	T-TR	
Fox Ave.	Over	NA	N	2 WAY CLOVERLEAF	2 WAY CLOVER LEAF	T-R	T-R	2 WAY CLOVER LEAF	2 CLOVER LEAF	TR	TR	
FM 1171 / Main St.	Over	NA	NA	L-TL-R	L-T-R	T-TR-R	T-T-T-R	L-TL-R	L-T-R	T-TR-R	L-T-R	
Valley Ridge Blvd.	Over	NA	NA	2 WAY CLOVE	2 WAY CLOVE	T-TR	T-TR	2 WAY CLOVE	2 WAY CLOVE	T-TR	T-TR	

Cross Street	Type	EXISTING U-Turn @ X-street	Proposed U Turn	Existing				During Construction				
				N Bound[1]	S Bound[1]	E-Bound[1]	W Bound[1]	N Bound[1]	S Bound[1]	E-Bound[1]	W Bound[1]	U-Turns
				R LEAF	R LEAF			R LEAF	R LEAF			
FM 407 / Lake Park Rd.	Under	NA	NBSB SBNB	MODIFIED 2 WAY CLOVER LEAF	MODIFIED 2 WAY CLOVER LEAF	T-R	T-R	T-R	T-R	R	R	
Garden Ridge Blvd.	Under	NA	N	MODIFIED 2 WAY CLOVER LEAF	MODIFIED 2 WAY CLOVER LEAF	L-T	T	NA	R	L	NA	
Highland Village	N/A	NA	NA	NA	T-TR	R	T	NA	T-TR	R	NA	
County Ln. / Denton Dr.	Under	NA	NA	NA	T-TR	R	T	NA	T-TR	R	NA	
Turbeville Rd. / Hundley Dr.	Under	NA	NA	T-TR	T-TR	R	R	T-TR	T-TR	R	NA	

Cross Street	Type	EXISTING U-Turn @ X-street	Proposed U Turn	Existing				During Construction				
				N Bound[1]	S Bound[1]	E-Bound[1]	W Bound[1]	N Bound[1]	S Bound[1]	E-Bound[1]	W Bound[1]	U-Turns
Corinth Pkwy.	Under	NA	NA	TL-TR	TL-TR	T-R	T-R	T-TR	T-TR	TR	TR	
Post Oak	Under	NA	NA	TL-T-R	TL-TR	TR	T-R	TL-TR	TL-TR	TR	TR	
N. Texas Blvd.	Under	NA	NBSB	L-T-R	L-T-TR	TR	T-T-R	TL-R	TL-R	T-TR	TR	
N. Broadway St.	Over	NA	NA	TL-R	TL-R	L-T-T-TR	L-T-T-TR	TL-R	TL-R	TL-T-R	TL-T-R	

Notes:

1. T = thru lane, R = right turn lane, L = left turn lane, TR = combination lanes thru and right, TL = combination lanes thru and left, U = U-turn lane, LU = combination lanes left and u-turn; S = south, N = north, E = east, W = west
2. IH 35E is considered north and south.
3. This table represents the lane configurations for both cross streets and frontage roads at their intersection with the following exceptions: WB Round Grove, WB and EB Corporate Drive, WB and EB Fox Avenue, WB and EB FM 407, WB and EB Garden Ridge Blvd. These cross streets are connected to the frontage roads through complex intersections. Lane configurations for these cross streets represent the main movements provided by the cross street.
4. For cross streets not listed in this table, the minimum number of lanes to be open at all times will be the existing number of lanes.
5. Pedestrian access to be maintained.
6. Subject to Government Entity approval, College Street may be used as a detour for only one direction of traffic in the event that the Belt Line Road configuration cannot be maintained for the same direction during construction as noted above.
7. Full or staged closure of cross streets may be necessary for certain bridge construction activities. Developer shall submit a request for approval to TxDOT and the local Governmental Entity thirty (30) days in advance of any closure and submit a traffic control plan and contingency plan in accordance with Section 8.3.1. Closures will only be permitted for critical bridge placement activities, including but not

limited to demolition, setting beams, or setting deck. Developer shall limit the duration and schedule this work to off-peak or nighttime hours as shown in Table 18-1B, or as otherwise specified by TxDOT and the local Governmental Entity.

Developer shall issue a Lane Closure Notice (LCN) to TxDOT and affected Governmental Entities fourteen (14) Days prior to the publication of any notices or placement of any traffic control devices associated with lane closures, detour routing or other change in traffic control requiring lane closures except lane closures of less than 24-hour duration. The LCN shall contain the estimated date, time, duration, and location of the proposed Work requiring the lane closure.

If an Emergency condition should occur, Developer shall provide a LCN to TxDOT within one Day after the onset of the event. For non-TxDOT controlled facilities, Developer shall immediately notify the controlling Governmental Entity. Developer shall keep TxDOT and affected Governmental Entities informed of any and all changes or cancellations of proposed lane closures prior to the date of their implementation.

~~Lane closures, including Incident or Emergency lane closures caused by any Developer-Related Entity, other than those permitted, will cause Liquidated Damages to be levied against Developer as specified in Exhibit 17 of the DBA. Liquidated Damages shall not be levied if TxDOT determines at its sole discretion that the lane closure is required in connection with an Incident or Emergency not caused by any Developer-Related Entity.~~

If a bridge cannot be demolished safely within these requirements, roads may need to be closed and traffic detoured during the lowest-volume times. Developer shall obtain TxDOT's approval for such traffic closures. If exceptional circumstances exist, ~~additional lanes~~ TxDOT may ~~be closed~~approve, in its sole discretion, a variation of the permitted lane closures during Periods C and D provided in Tables 18-1A and 18-1B ~~with the written permission of TxDOT at its sole discretion~~prior to implementing such variance and upon payment of a fee equivalent to the Liquidated Damages ~~may apply.~~identified in Exhibit 17 of the Agreement that the Developer would incur absent such variation and approval. This fee equivalent is not considered a Liquidated Damage, and therefore shall not be included in the amount shown in Exhibit 17 Section 2(g) of the Agreement. Periods C and D ~~in~~ may be started earlier or extended later with TxDOT approval.

Developer shall obtain prior written approval from TxDOT for any variance from Tables 18-1A, 18-1B, 18-2, 18-3, and 18-4 prior to implementing any such variance.

~~Closure of all *General* Purpose Lanes in one or both directions may only be allowed during 10:00 p.m. and 6:00 a.m. and with the express written approval by TxDOT. Closure of all General Purpose Lanes shall be subject to Liquidated Damages. Any complete roadway closure will require a Traffic Control Plan to be submitted and approved by TxDOT.~~

The detour route for full General Purpose Lane closures shall be limited to usage of the General Purpose Lane on and off ramps and to the greatest extent possible, frontage roads. Any detour utilizing a local street network shall require the prior written approval of the local Governmental Entity and TxDOT.

TxDOT will have the right to lengthen, shorten, or otherwise modify the foregoing restrictions as actual traffic conditions may warrant.

Driveway Closures. Developer shall maintain a minimum of one all-weather driveway per property owner at all times. For properties with multiple driveways, when driveway closure is necessary to progress Work, no driveway may be closed for more than thirty (30) consecutive days or more than forty-five (45) days in a ninety (90) day period without written approval of the property owner.

18.3.1.3Detour Usage

Developer shall use State routes for detour routes, wherever applicable. If State routes are unavailable, Developer shall use local arterials, provided that Developer has conducted the necessary coordination and

obtained the necessary approvals from the Governmental Entity having jurisdiction including but not limited to Emergency Medical Services, fire services, police, school, and post office. Developer shall not use local surface streets for detour routes without the prior written approval by TxDOT. In situations where this occurs, Developer shall perform a video survey and existing conditions report. Developer shall return the detour route back to pre-construction condition.

Developer shall provide motorists with guidance on diverting around the construction, detouring around specific construction sites, and traveling through the construction areas. This shall include the installation and maintenance of temporary regional signs to divert traffic around the Project. Motorist guidance to and along detour routes shall be provided, together with regional guidance.

18.3.2 Restricted Hours

A. Holiday Restrictions

Developer shall provide existing general-purpose-lane capacity, from 12:00 p.m. (noon) of the preceding day to 10:00 pm on the day after the following holiday schedule. No additional lane or ramp closure that restricts or interferes with traffic shall be allowed. TxDOT has the right to lengthen, shorten, or otherwise modify these restrictions as actual traffic conditions may warrant.

a) New Year's Eve and New Year's Day (December 31 through January 1)

b) Easter Holiday Weekend (Friday through Sunday)

c) Memorial Day Weekend (Friday through Monday)

d) Independence Day (July 3 through noon on July 5)

e) Labor Day Weekend (Friday through Monday)

f) Thanksgiving Holiday (Wednesday through Sunday)

g) Christmas Holiday (December 23 through December 26)

B. Event Restrictions

Developer shall provide existing general-purpose-lane capacity for the regional events set forth below. No additional lane or ramp closure that restricts or interferes with traffic shall be allowed. TxDOT has the right to lengthen, shorten, or otherwise modify these restrictions as actual traffic conditions may warrant. TxDOT also has the right to modify the list of major events as they are added, rescheduled or warranted.

a) Any events held within a three (3) mile radius of any point along the length of the corridor with an expected attendance greater than 20,000 (restricted from three (3) hours before the start of the event to three (3) hours after the end of the event).

b) Within 1 mile radius of major retail traffic generators (i.e. malls) (Thanksgiving Day through January 2).

c) NASCAR Nationwide and Sprint Cup Racing Series (3 races total) at Texas Motor Speedway usually held in late March/early April (restricted from 3:00 p.m. of the night preceding the first event until Monday 5:00 a.m. following the event).

d) NASCAR Nationwide and Sprint Cup Racing Series (3 races total) at Texas Motor Speedway usually held in late October/early November (restricted from 3:00 p.m. of the night preceding the first event until Monday 5:00 a.m. following the event).

e) Indy Series Racing and NASCAR Truck Series Racing (2 races) at Texas Motor Speedway usually held in June (restricted from 3:00 p.m. of the night preceding the first event until Monday 5:00 a.m. following the event).

f) University of Texas / University of Oklahoma football game held on a Saturday in September or October (restricted from 3:00 p.m. of the day preceding the event until 12:00 noon the day following the event).

18.4 Construction Requirements

Construction shall be in accordance with Developer's TMP, the manufacturer's directions or recommendations where applicable, and the applicable provisions of the TMUTCD.

18.4.1 Developer Responsibility

If at any time TxDOT determines Developer's traffic control operations do not meet the intent of the TMP or any specific traffic control plan, Developer shall immediately revise or discontinue such operations to correct the deficient conditions.

Developer shall provide TxDOT the names of the traffic control coordinator and support personnel, and the phone number(s) where they can be reached 24 hours per day, seven (7) days per week.

18.4.2 Access

Existing bicycle and pedestrian access and mobility shall be maintained parallel with the frontage roads and across all cross streets. Access to existing transit stop locations shall be maintained during construction or reasonable alternative locations shall be coordinated with and approved by transit operators.

18.4.3 Detours

Developer shall maintain all detours in a safe and traversable condition. A pavement transition, suitable for the posted speed of the section shall be provided at all detour interfaces.

18.4.4 Local Approvals

It shall be the responsibility of the Developer to gain approval from the appropriate Governmental Entity for all traffic control measures on each intersecting street.

18.4.5 Pavement Markings

Developer shall be required to remove existing pavement markings that conflict with temporary or permanent pavement markings. These pavement markings shall be removed by any method that does not materially damage the surface or texture of the pavement. Pavement marking removal by over-painting is prohibited.

18.4.6 Reinstatement of Utility Cuts

After installation of drainage structures, storm sewers, or any other public or private Utility facility by open cut beneath existing pavements carrying traffic during construction, the pavement shall be restored and maintained to a normal satisfactory riding surface equal to or better than the existing surface.

18.4.7 Hauling Equipment

Developer shall keep traveled surfaces used in its hauling operations clear and free of dirt or other debris that would hinder the safe operation of roadway traffic.

Rubber-tired equipment shall be used for moving dirt or other materials along or across paved surfaces.

Where Developer moves any equipment not licensed for operation on public highways on or across any pavement, Developer shall protect the pavement from all damage caused by such movement. Any damage caused by the operation of Developer shall be repaired at the expense of Developer.

All haul routes utilizing any street of an adjacent Governmental Entity shall be coordinated with the appropriate Governmental Entity

18.4.8 Final Clean-Up

Developer shall clear and remove from the site all surplus and discarded materials and debris of every kind and leave the entire Project in a smooth and neat condition, after any construction process.

18.4.9 Stockpiles

Barricades and warning signs are to be placed at stockpiles to adequately warn motorists of a hazard in accordance with TxDOT's Traffic Engineering Standard sheets and the TMUTCD. No material stockpiles shall be located within the clear zone of any traveled lane, unless positive protection is provided.

19 MAINTENANCE

Developer shall maintain the Project in accordance with this Section 19 upon issuance of NTP 2 until Substantial Completion.

19.1 General Requirements

Developer shall maintain the Project in a manner that provides a safe and reliable transportation system for improved mobility.

19.1.1 General Maintenance Obligations

Developer shall take all necessary actions to achieve the following:

a) Minimize delay and inconvenience to Users.

b) Identify and correct all Defects and damages from Incidents

c) Monitor and observe weather and weather forecasts to proactively deploy resources to minimize delays and safety hazards due to heavy rains, snow, ice, or other severe weather events.

d) Remove debris, including litter, graffiti, animals, and abandoned vehicles or equipment from the Project ROW.

e) Minimize the risk of damage, disturbance, or destruction of third-party property during the performance of maintenance activities.

f) Coordinate with and enable TxDOT and others with statutory duties or functions in relation to the Project or Related Transportation Facilities to perform such duties and functions.

g) Perform systematic Project inspections, periodic maintenance, and routine maintenance in accordance with the provisions of Developer's Maintenance Management Plan and Developer's Safety Plan.

Developer is responsible for providing all resources necessary for the performance of all activities in the Maintenance Management Plan.

Developer shall perform the maintenance of the Managed Lanes and the General Purpose Lanes in to the same standard of maintenance.

Developer shall maintain the Elements to achieve the performance requirements set forth in The Performance and Measurement Table Baseline included as Table 19-1.

Table 19-1: Performance and Measurement Table Baseline

~~Performance and Measurement Table Baseline~~									
~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1 Hazard Mitigation~~	~~Cat 1 Permanent Remedy~~	~~Cat 2 Permanent Repair~~			
~~1) ROADWAY~~									
			~~-~~	~~-~~	~~-~~	~~-~~	~~Unless stated otherwise, measurements shall be conducted using procedures, techniques, and measuring equipment consistent with TxDOT's *Pavement Management Information System Rater's Manual.* For the purposes of this Project, pavement performance measurement records relate to 0.1 mile sections.~~		~~-~~
	~~1.1~~	~~Obstructions and debris~~	~~Roadway and clear zone free from obstructions and debris~~	~~2 hrs~~	~~N/A~~	~~N/A~~	~~Visual Inspection~~	~~Number of obstructions and debris~~	~~Nil~~

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1~~ ~~Hazard Mitigation~~	~~Cat 1~~ ~~Permanent Remedy~~	~~Cat 2~~ ~~Permanent Repair~~			
	~~1.2~~	~~Pavement~~	~~All roadways have a smooth surface course (including bridge decks, covers, gratings, frames and boxes) with adequate skid resistance and free from Defects.~~	~~24 hrs~~	~~28 days~~	~~6 months~~	~~**a) Pavement Condition Score**~~ ~~Measurements and inspections necessary to derive Pavement Condition Score~~	~~Pavement Condition Score for 80% of Auditable Sections exceeding:~~ ~~• Mainlanes and ramps – 90~~ ~~• Frontage roads – 80~~ ~~Pavement Condition Score for each Auditable Section exceeding:~~	~~100%~~ ~~100%~~

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1~~ ~~Hazard Mitigation~~	~~Cat 1~~ ~~Permanent Remedy~~	~~Cat 2~~ ~~Permanent Repair~~			
								~~• Mainlanes and ramps – 80~~	~~100%~~
								~~• Frontage roads – 70~~	~~100%~~
	~~1.2 cont~~						~~**b) Ruts – Mainlanes, shoulders & ramps**~~ ~~Depth as measured using an automated device in compliance with TxDOT standards.~~	~~Percentage of wheel path length with ruts greater than ¼" in depth in each Auditable Section~~	
								~~• Mainlanes, shoulders and ramps – 3%~~	~~Nil~~

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1~~ ~~Hazard Mitigation~~	~~Cat 1~~ ~~Permanent Remedy~~	~~Cat 2~~ ~~Permanent Repair~~			
							~~10ft straight edge used to measure rut depth for localized areas.~~	~~• Frontage roads – 10%~~ ~~Depth of rut at any location greater than 0.5”~~	~~Nil~~ ~~Nil~~
							~~**e) Ride quality**~~ ~~Measurement of International Roughness Index (IRI) according to TxDOT standard Tex-1001-S, Operating Inertial Profilers and Evaluating Pavement Profiles~~	~~For 80% of all Auditable Sections measured, IRI throughout 98% of each Auditable Section is less than or equal to:~~ ~~• Mainlanes, ramps – 95" per mile**~~	~~100%~~

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1 Hazard Mitigation~~	~~Cat 1 Permanent Remedy~~	~~Cat 2 Permanent Repair~~			
								~~• Frontage roads – 120" per mile**~~	~~100%~~
	~~1.2 cont~~			~~24 hrs~~	~~28 days~~	~~6 months~~	~~** To allow for measurement bias, an adjustment of -10 (minus ten) is made to IRI measurements for concrete pavements before assessing threshold compliance.~~	~~IRI measured throughout 98% of Auditable Section of less than or equal to:~~ ~~• Mainlanes, ramps 120" per mile**~~ ~~• Frontage roads – 150" per mile**~~	~~100%~~ ~~100%~~

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1~~ ~~Hazard Mitigation~~	~~Cat 1~~ ~~Permanent Remedy~~	~~Cat 2~~ ~~Permanent Repair~~			
							~~(capital asset replacement work and new construction subject to construction quality standards)~~	~~Mainlanes, ramps, 0.1 mile average – 150" per mile**~~	~~100%~~
								~~Frontage roads, 0.1 mile average – 180" per mile**~~	~~100%~~
								~~IRI measured throughout 98% of each lane containing a bridge deck in any Auditable Section , 0.1 mile average – 200" per mile**~~	~~100%~~
							~~10-ft straightedge used to~~	~~Individual discontinuities greater than 0.75"~~	~~Nil~~

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1~~ ~~Hazard Mitigation~~	~~Cat 1~~ ~~Permanent Remedy~~	~~Cat 2~~ ~~Permanent Repair~~			
							~~measure discontinuities~~		
							~~d) Failures~~ ~~Instances of failures exceeding the failure criteria set forth in the TxDOT PMIS Rater's Manual, including potholes, base failures, punchouts and jointed concrete pavement failures~~	~~Occurrence of any failure~~	~~Nil~~

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1 Hazard Mitigation~~	~~Cat 1 Permanent Remedy~~	~~Cat 2 Permanent Repair~~			
	~~1.2 cont~~			~~24 hrs~~	~~28 days~~	~~6 months~~	~~**e) Edge drop-offs**~~ ~~Physical measurement of edge drop-off level compared to adjacent surface~~	~~Instances of edge drop-off greater than 2" (Number)~~	~~Nil~~
							~~**f) Skid resistance**~~ ~~ASTM E274/E274M-11 Standard Test Method for Skid Resistance Testing of Paved Surfaces at 50 MPH using a full scale smooth tire meeting the requirements of ASTM E524-08 .~~	~~• Mainlanes, shoulders and ramps – Number of sections investigated as to potential risk of skidding accident and appropriate remedial action taken where average Skid Number for 0.5-mile section of mainlanes, shoulders and ramps are in excess of 30.~~	~~100%~~

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1 Hazard Mitigation~~	~~Cat 1 Permanent Remedy~~	~~Cat 2 Permanent Repair~~			
								~~• Frontage roads – Number of sections investigated as to potential risk of skidding accident and appropriate remedial action taken where average Skid Number for 0.5-mile section of frontage roads is in excess of 30.~~	~~100%~~

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1 Hazard Mitigation~~	~~Cat 1 Permanent Remedy~~	~~Cat 2 Permanent Repair~~			
	~~1.2 cont~~							~~• When the skid number is below 25 and/or when required by the Wet Weather Accident Reduction Program, areas categorized as high risk, the Developer shall perform a site investigation and perform required corrective action.~~	~~100%~~
			~~Road users warned of potential skidding hazards~~	~~24hrs~~	~~7days~~	~~N/A~~	~~**Skid resistance** (as above)~~	~~Instances where road Users warned of potential skidding hazard where remedial action is identified.~~	~~100%~~

~~Performance and Measurement Table Baseline~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1~~ ~~Hazard Mitigation~~	~~Cat 1~~ ~~Permanent Remedy~~	~~Cat 2~~ ~~Permanent Repair~~			
	~~1.3~~	~~Crossovers and other paved areas~~	~~Crossovers and other paved areas are free of Defects~~	~~24 hrs~~	~~28 days~~	~~6 months~~	~~**a) Potholes**~~ ~~**b) Base failures**~~	~~Potholes of low severity or higher (Number)~~ ~~Base failures of low severity or higher (Number)~~	~~Nil~~ ~~Nil~~
	~~1.4~~	~~Joints in concrete~~	~~Joints in concrete paving are sealed and watertight~~ ~~Longitudinal joint separation~~	~~24 hrs~~	~~28 days~~	~~6 months~~	~~Visual inspection of joints~~ ~~Measurement of joint width and level difference of two sides of joints~~	~~Length unsealed joints greater than ¼"~~ ~~Joint width more than 1" or faulting more than ¼"~~	~~Nil~~ ~~Nil~~

~~Performance and Measurement Table Baseline~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1 Hazard Mitigation~~	~~Cat 1 Permanent Remedy~~	~~Cat 2 Permanent Repair~~			
	~~1.5~~	~~Curbs~~	~~Curbs are free of defects~~	~~24 hrs~~	~~28 days~~	~~6 months~~	~~Visual inspection~~	~~Length out of alignment~~	~~Nil~~
~~2) DRAINAGE~~							-	-	
	~~2.1~~	~~Pipes and channels~~	~~Each Element of the drainage system is maintained in its proper function by cleaning, clearing and/or emptying as appropriate from the point at which water drains from the travel way to the outfall or drainage way.~~	~~24 hrs~~	~~28 days~~	~~6 months~~	~~Visual inspection supplemented by CCTV where required to inspect buried pipe work~~	~~Length with less than 90% of cross section clear (feet)~~	~~Nil~~

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1 Hazard Mitigation~~	~~Cat 1 Permanent Remedy~~	~~Cat 2 Permanent Repair~~			
	~~2.2~~	~~Drainage treatment devices~~	~~Drainage treatment and balancing systems, flow and spillage control devices function correctly and their location and means of operation is recorded adequately to permit their correct operation in Emergency.~~	~~24 hrs~~	~~28 days~~	~~6 months~~	~~Visual inspection~~	~~Devices functioning correctly with means of operation displayed (Number)~~	~~100%~~
	~~2.3~~	~~Travel way~~	~~The travel way is free from water to the extent that such water would represent a hazard by virtue of its position and depth.~~	~~24 hrs~~	~~28 days~~	~~6 months~~	~~Visual inspection of water on surface~~	~~Instances of hazardous water build-up~~	~~Nil~~
	~~2.4~~	~~Discharge systems~~	~~Surface water discharge systems perform their proper function and discharge to groundwater and waterways complies with the relevant~~	~~24 hrs~~	~~28 days~~	~~6 months~~	~~Visual inspection and records~~	~~Non-compliances with legislation~~	~~Nil~~

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1 Hazard Mitigation~~	~~Cat 1 Permanent Remedy~~	~~Cat 2 Permanent Repair~~			
			~~legislation and permits.~~						
	~~2.5~~	~~Protected species~~	~~Named species and habitats are protected.~~	~~24 hrs~~	~~28 days~~	~~6 months~~	~~Visual inspection~~	~~Compliance with the requirement~~	~~100%~~
~~3) STRUCTURES~~				-	-	-		-	-
	~~3.1~~	~~Structures having an opening measured along the center of the roadway of more than 20 feet between undercopings of abutments or springlines of~~	~~Substructures and superstructures are free of:~~ ~~• graffiti~~ ~~• undesirable vegetation~~ ~~• debris and bird droppings~~ ~~• blocked drains, weep pipes manholes and~~	~~24 hrs~~	~~28 days~~	~~6 months~~	~~Inspection and assessment in accordance with the requirements of federal National Bridge Inspection Standards (NBIS) of the Code of Federal Regulations, 23 Highways – Part 650, the TxDOT Bridge inspection Manual, and the Federal Administration's Bridge~~	~~Records as required in the TxDOT Bridge Inspection Manual~~ ~~Occurrences of condition rating below seven for any deck, superstructure or substructure~~	~~Nil~~

~~Performance and Measurement Table Baseline~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1 Hazard Mitigation~~	~~Cat 1 Permanent Remedy~~	~~Cat 2 Permanent Repair~~			
		~~arches or extreme ends of openings or multiple boxes~~	~~chambers~~ ~~• blocked drainage holes in structural components~~ ~~• defects in joint sealants~~ ~~• defects in pedestrian protection measure~~ ~~• scour damage~~ ~~• corrosion of rebar~~ ~~• paint system failures~~ ~~• impact damage~~				~~Inspector's Reference Manual.~~	~~All condition states to be one for all structure components~~	~~100%~~
	~~3.2~~	~~Structure~~	~~i) Expansion joints are free of:~~	~~24 hrs~~	~~28 days~~	~~6~~	~~Inspection and assessment in accordance with the~~	~~Records as required in the TxDOT Bridge Inspection~~	

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1~~ ~~Hazard Mitigation~~	~~Cat 1~~ ~~Permanent Remedy~~	~~Cat 2~~ ~~Permanent Repair~~			
		~~components~~	~~• dirt debris and vegetation~~ ~~• defects in drainage systems~~ ~~• loose nuts and bolts~~ ~~• defects in gaskets~~ ~~ii) The deck drainage system is free of all and operates as intended.~~ ~~iii) Parapets are free of:~~ ~~• loose nuts or bolts~~ ~~• blockages of hollow section drain holes~~ ~~• graffiti~~			~~months~~	~~requirements of federal National Bridge Inspection Standards (NBIS) of the Code of Federal Regulations, 23 Highways – Part 650, the TxDOT Bridge inspection Manual, and the Federal Administration's Bridge Inspector's Reference Manual..~~	~~Manual~~ ~~Occurrences of condition rating below seven for any deck, superstructure or substructure~~ ~~All condition states to be one for all structure components~~	~~Nil~~ ~~100%~~

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1~~ ~~Hazard Mitigation~~	~~Cat 1~~ ~~Permanent Remedy~~	~~Cat 2~~ ~~Permanent Repair~~			
	~~3.2 cont.~~		~~• vegetation~~ ~~• accident damage~~ ~~iv) Bearings and bearing shelves are clean.~~ ~~v) Sliding and roller surfaces are clean and greased to ensure satisfactory performance. Additional advice contained in bearing manufacturers' instructions in the Structure Maintenance Manual is followed.~~ ~~Special finishes are clean and perform to the~~	~~24 hrs~~	~~28 days~~	~~6 months~~			

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1 Hazard Mitigation~~	~~Cat 1 Permanent Remedy~~	~~Cat 2 Permanent Repair~~			
			~~appropriate standards.~~ ~~vii) All non-structural items such as hoists and electrical fixings, operate correctly, are clean and lubricated as appropriate, in accordance with the manufacturer's recommendations and certification of lifting devices are maintained.~~						
	~~3.3~~	~~Non-bridge class culverts~~	~~Non-bridge-class culverts are free of:~~ ~~• vegetation and debris and silt~~ ~~• defects in sealant to~~	~~24 hrs~~	~~28 days~~	~~6 months~~	~~Visual inspection~~	~~Number with vegetation, debris and silt~~ ~~Number with defects in~~	~~Nil~~ ~~Nil~~

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1 Hazard Mitigation~~	~~Cat 1 Permanent Remedy~~	~~Cat 2 Permanent Repair~~			
			~~movement joints~~ ~~• scour damage~~					~~sealant and movement joints~~ ~~Number with scour damage~~	~~Nil~~
	~~3.4~~	~~Gantries and high masts~~	~~Sign signal gantries, high masts are structurally sound and free of:~~ ~~• loose nuts and bolts~~ ~~• defects in surface protection systems~~ ~~• graffiti~~	~~24 hrs~~	~~28 days~~	~~6 months~~	~~Visual inspection~~	~~Number with loose assemblies~~ ~~Number with defects in surface protection~~ ~~Number with graffiti~~	~~Nil~~ ~~Nil~~ ~~Nil~~

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1 Hazard Mitigation~~	~~Cat 1 Permanent Remedy~~	~~Cat 2 Permanent Repair~~			
	~~3.5~~	~~Load ratings~~	~~All structures maintain the design load capacity.~~	~~24 hrs~~	~~28 days~~	~~6 months~~	~~Load rating calculations in accordance with the Manual for Bridge Evaluation and the TxDOT Bridge Inspection Manual.~~ ~~Load restriction requirements as per the TxDOT Bridge Inspection Manual~~	~~Number of load restrictions for Texas legal loads (including legally permitted vehicles)~~	~~Nil~~
	~~3.6~~	~~Access points~~	~~All hatches and points of access have fully operational and lockable entryways.~~	~~24 hrs~~	~~28 days~~	~~6 months~~	~~Visual Inspection~~	~~Number with defects in locks or entryways~~	~~Nil~~
	~~3.7~~	~~Mechanically Stabilized Earth and Retaining~~	~~Mechanically Stabilized Earth and Retaining Walls free of:~~	~~24 hours~~	~~28 days~~	~~6 months~~	~~Inspection and assessment in accordance with the requirements of federal Nations Bridge Inspection~~	~~Records as required in the TxDOT Bridge Inspection Manual~~	~~100%~~

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1~~ ~~Hazard Mitigation~~	~~Cat 1~~ ~~Permanent Remedy~~	~~Cat 2~~ ~~Permanent Repair~~			
		~~Walls~~	~~• blocked weep holes~~ ~~• undesirable vegetation~~ ~~• defects in joint sealants~~ ~~• defects in pedestrian protection~~ ~~• scour damage~~ ~~• corrosion of reinforcing bars~~ ~~• paint system failure~~ ~~• concrete spalling~~ ~~• impact damage~~				~~Standards (NBIS) of the Code of Federal Regulations, 23 Highways – Part 650, the TxDOT Bridge Inspection Manual and the Federal Highway Administration's Bridge Inspector's Reference Manual.~~		

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1~~ ~~Hazard Mitigation~~	~~Cat 1~~ ~~Permanent Remedy~~	~~Cat 2~~ ~~Permanent Repair~~			
			~~Parapets free of:~~ ~~• loose nuts and bolts~~ ~~• blockage of drain holes~~ ~~• undesirable vegetation~~ ~~• impact damage~~ ~~• concrete spalling~~						
~~4) PAVEMENT MARKINGS, OBJECT MARKERS, BARRIER MARKERS AND DELINEATORS~~								-	-

~~Performance and Measurement Table Baseline~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1~~ ~~Hazard Mitigation~~	~~Cat 1~~ ~~Permanent Remedy~~	~~Cat 2~~ ~~Permanent Repair~~			
	~~4.1~~	~~Pavement markings~~	~~Pavement markings are:~~ ~~• clean and visible during the day and at night~~ ~~• whole and complete and of the correct color, type, width and length~~ ~~• placed to meet the TMUTCD and TxDOT's Pavement Marking Standard Sheets~~	~~24 hrs~~	~~28 days~~	~~6 months~~	~~a) Markings – General~~ ~~Portable retroreflectometer, which uses 30 meter geometry meeting the requirements described in ASTM E 1710~~	~~Length meeting the minimum retroreflectivity 175 mcd/sqm/lx for white~~ ~~Length meeting the minimum retroreflectivity 125 mcd/sqm/lx for yellow~~	~~100%~~ ~~100%~~
							~~Physical measurement~~	~~Length with more than 5% loss of area of material at any point~~ ~~Length with spread more than 10% of specified~~	~~Nil~~ ~~Nil~~

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1~~ ~~Hazard Mitigation~~	~~Cat 1~~ ~~Permanent Remedy~~	~~Cat 2~~ ~~Permanent Repair~~			
							~~b) Profile Markings~~ ~~Visual inspection~~	~~dimensions.~~ ~~Length performing its intended function and compliant with relevant regulations~~	~~100%~~
	~~4.2~~	~~Raised reflective markers~~	~~Raised reflective pavement markers, object markers and delineators are:~~ ~~• clean and clearly visible~~ ~~• of the correct color and type~~ ~~• reflective or retroreflective as TxDOT standard~~ ~~• correctly located, aligned~~	~~24 hrs~~	~~28 days~~	~~6 months~~	~~Visual inspection~~	~~Number of markers associated with road markings that are ineffective in any 10 consecutive markers. (Ineffective includes missing, damaged, settled or sunk)~~ ~~[A minimum of four markers should be visible at 80' spacing when viewed~~	~~Nil~~

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1 Hazard Mitigation~~	~~Cat 1 Permanent Remedy~~	~~Cat 2 Permanent Repair~~			
			~~and at the correct level~~ ~~• are firmly fixed~~ ~~• are in a condition that will ensure that they remain at the correct level.~~					~~under low beam headlights]~~ ~~Uniformity (replacement rpms having equivalent physical and performance characteristics to adjacent markers).~~	~~100%~~
	~~4.3~~	~~Delineators & markers~~	~~Object markers, mail box markers and delineators are:~~ ~~• clean and visible~~ ~~• of the correct color and type~~ ~~• legible and reflective~~	~~24 hrs~~	~~28 days~~	~~6 months~~	~~Visual inspection~~	~~Number of object markers or delineators defective or missing~~	~~Nil~~

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1 Hazard Mitigation~~	~~Cat 1 Permanent Remedy~~	~~Cat 2 Permanent Repair~~			
			~~• straight and vertical~~						

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1 Hazard Mitigation~~	~~Cat 1 Permanent Remedy~~	~~Cat 2 Permanent Repair~~			
~~5) GUARDRAILS, SAFETY BARRIERS AND IMPACT ATTENUATORS~~								-	-
	~~5.1~~	~~Guard rails and safety barriers~~	~~All guardrails, safety barriers, concrete barriers, etc... are maintained free of Defects. They are appropriately placed and correctly installed at the correct height and distance from roadway or obstacles. Installation and repairs shall be carried out in accordance with the requirements of NCHRP 350 standards.~~	~~24 hrs~~	~~28 days~~	~~6 months~~	~~Visual inspection~~	~~Length of road restraint systems correctly installed~~ ~~Length free from defects~~ ~~Length at correct height~~ ~~Length at correct distance from roadway and obstacle~~	~~100%~~ ~~100%~~ ~~100%~~ ~~100%~~
	~~5.2~~	~~Impact attenuators~~	~~All impact attenuators are appropriately placed and correctly installed~~	~~24 hrs~~	~~7 days~~	~~6 months~~	~~Visual inspection~~	~~Number correctly placed and installed~~	~~100%~~

~~Performance and Measurement Table Baseline~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1~~ ~~Hazard Mitigation~~	~~Cat 1~~ ~~Permanent Remedy~~	~~Cat 2~~ ~~Permanent Repair~~			
~~6) TRAFFIC SIGNS~~				-	-	-	-	-	-
	~~6.1~~	~~General – All signs~~	~~i) Signs are clean, correctly located, clearly visible, legible, reflective, at the correct height and free from structural and electrical defects~~	~~24 hrs~~	~~28 days~~	~~6 months~~	~~**a) Retroreflectivity**~~ ~~Coefficient of retro reflectivity~~	~~Number of signs with reflectivity below the requirements of TxDOT's TMUTCD~~	~~Nil~~
			~~ii) Identification markers are provided, correctly located, visible, clean and legible~~				~~**b) Face damage**~~ ~~Visual inspection~~	~~Number of signs with face damage greater than 5% of area~~	~~Nil~~
	~~6.1 cont.~~		~~iii) Sign mounting posts are vertical, structurally sound~~				~~**c) Placement**~~	~~Signs are placed in accordance with TxDOT's Sign Crew Field Book~~	~~100%~~

~~Performance and Measurement Table Baseline~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1~~ ~~Hazard Mitigation~~	~~Cat 1~~ ~~Permanent Remedy~~	~~Cat 2~~ ~~Permanent Repair~~			
			~~and rust free~~				~~Visual inspection~~	~~including not twisted or leaning~~	
			~~iv) All break-away sign mounts are clear of silt or other debris that could impede break-away features and shall have correct stub heights~~				~~**d) Obsolete signs**~~ ~~Visual inspection~~	~~Number of obsolete signs~~	~~Nil~~
			~~v) Obsolete and redundant signs are removed or replaced as appropriate~~ ~~vi) Visibility distances meet the stated requirements~~ ~~vii) Sign information is of the correct size, location, type~~				~~**e) Sign Information**~~ ~~Visual inspection~~	~~Sign information is of the correct size, location, type and wording to meet its intended purpose~~	~~100%~~

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1 Hazard Mitigation~~	~~Cat 1 Permanent Remedy~~	~~Cat 2 Permanent Repair~~			
			~~and wording to meet its intended purpose and any statutory requirements~~ ~~viii) All structures and Elements of the signing system are kept clean and free from debris and have clear access provided.~~ ~~ix) All replacement and repair materials and equipment are in accordance with the requirements of the TMUTCD~~ ~~x) Dynamic message signs are in an operational condition~~				~~**f) Dynamic Message Signs**~~ ~~Visual inspection~~	~~Dynamic message signs are fully functioning~~	~~100%~~
	~~6.2~~	~~General - Safety critical signs~~	~~Requirements as 6.1, Plus:~~	~~2hrs~~	~~1 week~~	~~6 months~~	~~Visual inspection~~	~~Number of damaged safety critical signs~~	~~Nil~~

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1~~ ~~Hazard Mitigation~~	~~Cat 1~~ ~~Permanent Remedy~~	~~Cat 2~~ ~~Permanent Repair~~			
			~~"Stop," "Yield," "Do Not Enter," "One Way" and "Wrong Way" signs are clean legible and undamaged.~~						
~~7) TRAFFIC SIGNALS~~				-	-	-	-	-	-
	~~7.1~~	~~General~~	~~i) Traffic Signals and their associated equipment are:~~ ~~• clean and visible~~ ~~• correctly aligned and operational~~ ~~• free from damage caused by accident or vandalism~~ ~~• correctly aligned and~~	~~2 hrs~~	~~24 hrs~~	~~6 months~~	~~**a) General condition**~~ ~~Visual inspection~~ ~~**b) Damage**~~ ~~Visual inspection~~	~~Signals are clean and visible~~ ~~Signals are undamaged~~	~~100%~~ ~~100%~~

~~Performance and Measurement Table Baseline~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1~~ ~~Hazard Mitigation~~	~~Cat 1~~ ~~Permanent Remedy~~	~~Cat 2~~ ~~Permanent Repair~~			
			~~operational~~ ~~ii) Signal timing and operation is correct~~ ~~iii) Contingency plans are in place to rectify Category 1 Defects not immediately repairable to assure alternative traffic control is provided during a period of failure~~				~~**c) Signal timing**~~ ~~Timed measurements~~ ~~**d) Contingency plans**~~ ~~Records review~~	~~Installations have correct signal timings~~ ~~Full contingency plans are in place~~	~~100%~~ ~~-~~ ~~100%~~
	~~7.2~~	~~Soundness~~	~~Traffic signals are structurally and electrically sound~~	~~24 hrs~~	~~28 days~~	~~6 months~~	~~**a) Structural soundness**~~ ~~Visual inspection~~	~~-~~	~~-~~
	~~-~~		~~-~~	~~-~~	~~-~~	~~-~~	~~**b) Electrical soundness**~~ ~~Testing to meet NEC regulations~~	~~Inspection records showing safe installation and maintenance~~	~~100%~~

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1 Hazard Mitigation~~	~~Cat 1 Permanent Remedy~~	~~Cat 2 Permanent Repair~~			
	~~7.3~~	~~Identification marking~~	~~Signals have identification markers and the telephone number for reporting faults are correctly located, clearly visible, clean and legible~~	~~N/A~~	~~28 days~~	~~6 months~~	~~Visual inspection~~	~~Inspection records showing identification markers and other information are easily readable~~	~~100%~~
	~~7.4~~	~~Pedestrian Elements and vehicle detectors~~	~~All pedestrian Elements and vehicle detectors are correctly positioned and fully functional at all times~~	~~24 hrs~~	~~28 days~~	~~6 months~~	~~Visual Inspection~~	~~Inspection records showing compliance~~	~~100%~~
~~8) LIGHTING~~				~~-~~	~~-~~	~~-~~	~~-~~	~~-~~	~~-~~

~~Performance and Measurement Table Baseline~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1~~ ~~Hazard Mitigation~~	~~Cat 1~~ ~~Permanent Remedy~~	~~Cat 2~~ ~~Permanent Repair~~			
	~~8.1~~	~~Roadway lighting – General~~	~~i) All lighting is free from defects and provides acceptable uniform lighting quality~~ ~~ii) Lanterns are clean and correctly positioned~~ ~~iii) Lighting units are free from accidental damage or vandalism~~ ~~iv) Columns are upright, correctly founded, visually acceptable and structurally sound~~	~~24 hrs~~ ~~-~~ ~~-~~	~~28 days~~ ~~-~~ ~~-~~	~~6 months~~ ~~-~~ ~~-~~	~~**a) Mainlane lights operable**~~ ~~Night time inspection or automated logs~~ ~~**b) Mainlane lights out of action**~~ ~~Night time inspection or automated logs~~	~~Number of sections with less than 90% of lights functioning correctly at all times~~ ~~Instances of more than two consecutive lights out of action~~	~~Nil~~ ~~Nil~~

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1 Hazard Mitigation~~	~~Cat 1 Permanent Remedy~~	~~Cat 2 Permanent Repair~~			
	~~8.2~~	~~Sign lighting~~	~~Sign lighting is fully operational~~	~~24 hrs~~	~~28 days~~	~~6 months~~	~~Night time inspection or automated logs~~	~~Instances of more than one bulb per sign not working~~	~~Nil~~
	~~8.3~~	~~Electrical supply~~	~~Electricity supply, feeder pillars, cabinets, switches and fittings are electrically, mechanically and structurally sound and functioning~~	~~24 Hrs~~	~~7 Days~~	~~1 Month~~	~~Testing to meet NEC regulations, visual inspection~~	~~Inspection records showing safe installation and maintenance~~	~~100%~~
	~~8.4~~	~~Access panels~~	~~All access panels in place at all times.~~	~~24 Hrs~~	~~7 Days~~	~~1 Month~~	~~Visual inspection~~	~~Instances of missing access panels~~	~~Nil~~

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1 Hazard Mitigation~~	~~Cat 1 Permanent Remedy~~	~~Cat 2 Permanent Repair~~			
	~~8.5~~	~~High mast lighting~~	~~i) All high mast luminaries functioning on each pole~~ ~~ii) All obstruction lights are present and working (if required)~~ ~~iii) Compartment door is secure with all bolts in place~~ ~~iv) All winch and safety equipment is correctly functioning and maintained without rusting or corrosion~~ ~~(for structural requirements refer to Element Category 3)~~	~~24 hrs~~	~~48 hrs~~	~~1 Month~~	~~Yearly inspection and night time inspections or automated logs~~	~~Instances of two or more lamps not working per high mast pole~~ ~~Identification of other defects~~	~~Nil~~ ~~Nil~~
~~9) FENCES, WALLS AND SOUND ABATEMENT~~				~~-~~	~~-~~	~~-~~		~~-~~	~~-~~

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1 Hazard Mitigation~~	~~Cat 1 Permanent Remedy~~	~~Cat 2 Permanent Repair~~			
	~~9.1~~	~~Design and location~~	~~Fences and walls act as designed and serve the purpose for which they were intended~~	~~24 hrs~~	~~28 days~~	~~6 months~~	~~Visual Inspection~~	~~Inspection records showing compliance~~	~~100%~~
	~~9.2~~	~~Construction~~	~~Integrity and structural condition of the fence is maintained~~	~~24 hrs~~	~~28 days~~	~~6 months~~	~~Structural assessment if visual inspection warrants~~	~~Inspection records showing compliance~~	~~100%~~
~~10) ROADSIDE MANAGEMENT~~				-	-	-		-	-

~~Performance and Measurement Table Baseline~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1~~ ~~Hazard Mitigation~~	~~Cat 1~~ ~~Permanent Remedy~~	~~Cat 2~~ ~~Permanent Repair~~			
	~~10.1~~	~~Vegetated areas – Except landscaped areas – General~~	~~Vegetation is maintained so that:~~ ~~i) Height of grass and weeds is kept within the limits described for urban and rural areas. Mowing begins before vegetation reaches the maximum height.~~ ~~ii) Spot mowing at intersections, ramps or other areas maintains visibility of appurtenances and sight distance.~~	~~24 hrs~~	~~7 days~~	~~28 days~~	~~**a) Urban areas**~~ ~~Physical measurement of height of grass and weeds~~ ~~**b) Rural areas**~~ ~~Physical measurement of height of grass and weeds~~	~~Individual measurement areas to have 95% of height of grass and weeds between 5 in. and 18 in~~ ~~Individual measurement areas to have 95% of height of grass and weeds between 5 in. and 30 in~~	~~100%~~ ~~100%~~

~~Performance and Measurement Table Baseline~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1~~ ~~Hazard Mitigation~~	~~Cat 1~~ ~~Permanent Remedy~~	~~Cat 2~~ ~~Permanent Repair~~			
			~~iii) Grass or vegetation does not encroach into or on paved shoulders, main lanes, sidewalks, islands, riprap, traffic barrier or curbs.~~				~~**c) Encroachment**~~ ~~Visual inspection of instances of encroachment of vegetation~~	~~Occurrences of vegetation encroachment in each auditable section~~	~~Nil~~
	~~10.1 cont.~~		~~iv) A herbicide program is undertaken in accordance with the TxDOT Herbicide Manual to control noxious weeds and to eliminate grass in pavement or concrete.~~	~~24 hrs~~	~~7 days~~	~~28 days~~	~~**d) Wildflowers**~~ ~~Visual Inspection with audit of process.~~	~~Adherence to vegetation management manuals~~	~~100%~~

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1~~ ~~Hazard Mitigation~~	~~Cat 1~~ ~~Permanent Remedy~~	~~Cat 2~~ ~~Permanent Repair~~			
			~~v) A full width mowing cycle is completed after the first frost.~~ ~~vi) Wildflowers are preserved utilizing the guidelines in the mowing specifications and TXDOT *Roadside Vegetation Manual*.~~				~~**e) Sight lines**~~ ~~Visual inspection~~	~~Instances of impairment of sight lines or sight distance to signs~~	~~Nil~~

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1 Hazard Mitigation~~	~~Cat 1 Permanent Remedy~~	~~Cat 2 Permanent Repair~~			
	~~10.2~~	~~Landscaped areas~~	~~i) All landscaped areas are maintained to their originally constructed condition. Landscaped areas are as designated in the plans.~~ ~~ii) Mowing, litter pickup, irrigation system maintenance and operation, plant maintenance, pruning, insect, disease and pest control, fertilization, mulching, bed maintenance, watering is undertaken as per MMP.~~	~~24 hrs~~	~~7 days~~	~~28 days~~	~~Visual inspection~~	~~Inspection records showing compliance~~	~~100%~~

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1~~ ~~Hazard Mitigation~~	~~Cat 1~~ ~~Permanent Remedy~~	~~Cat 2~~ ~~Permanent Repair~~			
	~~10.2~~	~~Landscaped areas~~	~~iii) The height of grass and weeds is kept between 2" and 8". Mowing begins before vegetation reaches 8 in~~ ~~iv) Damaged or dead vegetation is replaced.~~						
	~~10.3~~	~~Fire hazards~~	~~Fire hazards are controlled~~	~~24 hrs~~	~~7 days~~	~~28 days~~	~~Visual inspection~~	~~Instances of dry brush or vegetation forming fire hazard~~	~~Nil~~

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1~~ ~~Hazard Mitigation~~	~~Cat 1~~ ~~Permanent Remedy~~	~~Cat 2~~ ~~Permanent Repair~~			
	~~10.4~~	~~Trees, brush and ornamentals~~	~~i) Trees, brush and ornamentals on the right of way, except in established no mow areas, are trimmed in accordance with TxDOT standards.~~ ~~ii) Trees, brush and ornamentals are trimmed to insure they do not interfere with vehicles or sight distance, or inhibit the visibility of signs.~~ ~~iii) Dead trees, brush, ornamentals and branches are removed. Potentially dangerous trees or limbs are removed.~~	~~24 hrs~~	~~7 days~~	~~28 days~~	~~Visual inspection~~	~~Inspection records showing compliance~~	~~100%~~

~~Performance and Measurement Table Baseline~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1 Hazard Mitigation~~	~~Cat 1 Permanent Remedy~~	~~Cat 2 Permanent Repair~~			
	~~10.4~~	~~Trees, brush and ornamentals~~	~~iv) All undesirable trees and vegetation are removed. Diseased trees or limbs are treated or removed by licensed contractors.~~						
	~~10.5~~	~~Wetlands~~	~~Wetlands are managed in accordance with the permit requirements~~	~~24 hrs~~	~~7 days~~	~~28 days~~	~~Visual inspection, assessment of permit issuers~~	~~Instances of permit requirements not met~~	~~Nil~~

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1 Hazard Mitigation~~	~~Cat 1 Permanent Remedy~~	~~Cat 2 Permanent Repair~~			
~~11) REST AREAS AND PICNIC AREAS~~				-	-	-		-	-
	~~11.1~~	~~Rest areas and picnic areas~~	~~i) Picnic areas are clean and neat in appearance.~~	~~24 hrs~~	~~28 days~~	~~6 months~~	~~Inspection records showing compliance~~	~~Instances where 90% of measured area shall have grass and weeds height between 2 in. and 8 in.~~	~~100%~~
			~~ii) Trash barrels are painted and attached to their supports to prevent stealing.~~					~~Mowing shall begin before vegetation reaches 8 in.~~	~~100%~~

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1~~ ~~Hazard Mitigation~~	~~Cat 1~~ ~~Permanent Remedy~~	~~Cat 2~~ ~~Permanent Repair~~			
			~~iii) Site free of any visible litter, all litter properly disposed. Litter removed from the picnic area grounds and barrels before being allowed to accumulate outside of the barrels.~~	~~24 hrs~~	~~28 days~~	~~6 months~~		~~Number of bare ground areas larger than 5 square feet~~	~~Nil~~
			~~iv) All vehicles used in transporting litter are equipped to prevent the accumulated litter from being strewn along the roadway.~~					~~Number of prohibited, invasive or noxious weeds present.~~	~~Nil~~

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1 Hazard Mitigation~~	~~Cat 1 Permanent Remedy~~	~~Cat 2 Permanent Repair~~			
	~~11.1 cont~~		~~v) Vegetation damaged due to improper or careless mowing and trimming operations or any other reason is replaced.~~					~~Occurrences of encroachment of vegetation or debris for more than two (2) inches onto any curb or sidewalk located throughout each rest area.~~	~~Nil~~
			~~vi) Weeds, grass and other undesirable growth are removed from beds of plants and shrubs as needed. Trees and shrubs are trimmed neatly. All curbs and sidewalks are edged and repaired.~~					~~Occurrences of deviation of soil or mulch above or below the top of the curb.~~	~~Nil~~

~~Performance and Measurement Table Baseline~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1 Hazard Mitigation~~	~~Cat 1 Permanent Remedy~~	~~Cat 2 Permanent Repair~~			
			~~vii) All picnic tables are clean, free of stains and free of any defect.~~					~~Paved surfaces maintained clean and safe with minimal obstruction.~~	~~100%~~
			~~viii) All directional, informational, safety and any other type of signage are properly installed, contains accurate information and is visible from a reasonable distance.~~					~~Occurrences of undermining greater than 2”~~	~~Nil~~
			~~ix) All striping is intact and all parking and travel areas are clearly marked.~~					~~Number of unsealed cracks > ½ inch.~~	~~Nil~~

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1 Hazard Mitigation~~	~~Cat 1 Permanent Remedy~~	~~Cat 2 Permanent Repair~~			
			~~x) All curbs are in place and intact.~~					~~Number of lights fully functional.~~	~~100%~~
~~12) EARTHWORKS, EMBANKMENTS AND CUTTINGS~~				-	-	-		-	-
	~~12.1~~	~~Slope failure~~	~~All structural or natural failures of the embankment and cut slopes of the Facility are repaired~~	~~24 hrs~~	~~28 days~~	~~6 months~~	~~Visual inspection by geotechnical specialist and further tests as recommended by the specialist~~	~~Recorded instances of slope failure~~	~~Nil~~

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1 Hazard Mitigation~~	~~Cat 1 Permanent Remedy~~	~~Cat 2 Permanent Repair~~			
	~~12.2~~	~~Slopes – General~~	~~Slopes are maintained in general conformance to the original graded cross-sections, the replacement of landscaping materials, reseeding and re-vegetation for erosion control purposes and removal and disposal of all eroded materials from the roadway and shoulders~~	~~24 hrs~~	~~28 days~~	~~6 months~~	~~-~~	~~Inspection records showing compliance~~	~~100%~~

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1~~ ~~Hazard Mitigation~~	~~Cat 1~~ ~~Permanent Remedy~~	~~Cat 2~~ ~~Permanent Repair~~			
~~13) ITS and ETCS EQUIPMENT~~				~~-~~	~~-~~	~~-~~		~~-~~	~~-~~
	~~13.1~~	~~ETCS equipment – Maintenance~~	~~All ITS and ETCS equipment is fully functional and housing is functioning and free of defects.~~ ~~i) All equipment and cabinet identification numbers are visible, sites are well drained and access is clear.~~ ~~ii) Steps, handrails and accesses are kept in a good condition.~~ ~~iii) Access to all communication hubs, ground boxes, cabinets and sites is clear~~	~~24 hrs~~	~~14 days~~	~~1 month~~	~~Visual inspection~~	~~Inspection records showing compliance~~	~~100%~~

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1~~ ~~Hazard Mitigation~~	~~Cat 1~~ ~~Permanent Remedy~~	~~Cat 2~~ ~~Permanent Repair~~			
	~~13.1~~	~~ETCS equipment – Maintenance~~	~~All drainage is operational and all external fixtures and fittings are in a satisfactory condition.~~ ~~v) All communications cable markers, cable joint markers and duct markers are visible and missing markers are replaced.~~ ~~Backup power~~ ~~vi) All communications cable markers, cable joint markers and duct markers are visible and missing markers are replaced.~~ ~~vii) Backup power supply system is available at all times~~						

~~Performance and Measurement Table Baseline~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1~~ ~~Hazard Mitigation~~	~~Cat 1~~ ~~Permanent Remedy~~	~~Cat 2~~ ~~Permanent Repair~~			
	~~13.2~~	~~VES equipment – Maintenance~~	~~All VES equipment is kept clean, the identification numbers are visible.~~	~~24 hrs~~	~~14 days~~	~~1 month~~	~~Visual inspection~~	~~Inspection records showing compliance~~	~~100%~~
	~~13.3~~	~~Dynamic message sign equipment~~	~~Dynamic message signs are free from faults such as:~~ ~~i) Any signal displaying an message which is deemed to be a safety hazard~~ ~~ii) Failure of system to clear sign settings when appropriate.~~ ~~iii) 2 or more contiguous sign failures that prevent control office setting strategic diversions~~ ~~iv) Signs displaying an incorrect message.~~	~~2 hrs~~	~~24 hrs~~	~~14 days~~	~~Defect measurement dependent on equipment~~	~~Inspection records showing compliance~~	~~100%~~

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1~~ ~~Hazard Mitigation~~	~~Cat 1~~ ~~Permanent Remedy~~	~~Cat 2~~ ~~Permanent Repair~~			
	~~13.4~~	~~CCTV equipment~~	~~CCTV Systems are free from faults that limit the availability of the operators to monitor the area network, such as:~~ ~~i) Failure of CCTV Systems to provide control offices with access and control of CCTV images~~ ~~ii) Failure of a CCTV camera or its video transmission system.~~ ~~iii) Failure of a pan / tilt unit or its control system.~~ ~~iv) Moisture ingress onto CCTV camera lens~~ ~~v) Faults that result in significant degradation of CCTV images~~	~~2 hrs~~	~~24 hrs~~	~~14 days~~	~~Defect measurement dependent on equipment~~	~~Inspection records showing compliance~~	~~100%~~

~~Performance and Measurement Table Baseline~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1~~ ~~Hazard Mitigation~~	~~Cat 1~~ ~~Permanent Remedy~~	~~Cat 2~~ ~~Permanent Repair~~			
	~~13.5~~	~~Vehicle detection equipment~~	~~All equipment free of defects and operational problems such as;~~ ~~i) Inoperable loops.~~ ~~ii) Malfunctioning camera controllers.~~	~~2 hrs~~	~~24 hrs~~	~~1 month~~	~~Defect measurement dependent on equipment~~ ~~Traffic detector loops:~~ ~~Loop circuit's inductance to be > 50 and < 1,000 micro henries.~~ ~~Insulation resistance to be > 50 meg ohms.~~	~~Inspection records showing compliance~~ ~~Instances of loops out of compliance~~	~~100%~~ ~~Nil~~
~~14) TOLLING Facilities and Buildings (Not Used)~~								-	-

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1 Hazard Mitigation~~	~~Cat 1 Permanent Remedy~~	~~Cat 2 Permanent Repair~~			
~~15) AMENITY~~								-	-
	~~15.1~~	~~Graffiti~~	~~Graffiti is removed in a manner and using materials that restore the surface to a like appearance similar to adjoining surfaces~~	~~24 hrs~~	~~28 days~~	~~6 months~~	~~All graffiti is considered a Category 1 Defect~~	~~Inspection records showing compliance~~	~~100%~~
	~~15.2~~	~~Animals~~	~~All dead or injured animals are removed from the ROW~~	~~2 hrs~~	~~N/A~~	~~N/A~~	~~Visual inspection~~	~~No dead or injured animals are present on ROW~~	
	~~15.3~~	~~Abandoned vehicles and equipment~~	~~All abandoned vehicles and equipment are removed from the ROW.~~	~~1 hr~~	~~24 hrs~~	~~N/A~~	~~Visual inspection~~	~~No abandoned vehicles or equipment present~~	
~~16) SNOW AND ICE CONTROL~~								-	-

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1~~ ~~Hazard Mitigation~~	~~Cat 1~~ ~~Permanent Remedy~~	~~Cat 2~~ ~~Permanent Repair~~			
	~~16.1~~	~~Travel lanes~~	~~Maintain travel way free from snow and ice~~	~~2hrs~~	~~N/A~~	~~N/A~~	~~Maximum 1hr response time to complete manning and loading of spreading vehicles~~ ~~Maximum 2hrs from departure from loading point to complete treatment and return to loading point~~ ~~Maximum 1hr response time for snow and ice clearance vehicles to depart from base~~	~~Inspection records showing compliance~~	~~100%~~
	~~16.2~~	~~Weather forecasting~~	~~weather forecast information is obtained and assessed and appropriate precautionary treatment is carried out to prevent ice forming on the~~	~~2hrs~~	~~N/A~~	~~N/A~~	~~Operations plan details the process and procedures in place and followed~~	~~Inspection records showing compliance~~	~~100%~~

~~Performance and Measurement Table Baseline~~									
~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1 Hazard Mitigation~~	~~Cat 1 Permanent Remedy~~	~~Cat 2 Permanent Repair~~			
			~~travel way~~						
	~~16.3~~	~~Operational plans~~	~~Operate snow and ice clearance plans to maintain traffic flows during and after snowfall and restore the travel way to a clear condition as soon as possible.~~	~~2hrs~~	~~N/A~~	~~N/A~~	~~Operations plan details the process and procedures in place and followed~~	~~Inspection records showing compliance~~	~~100%~~
~~17) INCIDENT RESPONSE~~								-	-
	~~17.1~~	~~General~~	~~Respond to Incidents in accordance with the MMP.~~	~~1 hr~~	~~N/A~~	~~N/A~~	~~Response times met for 98% of Incidents measured on a 1 year rolling basis.~~ ~~No complaints from Emergency Services.~~	~~Inspection records showing compliance~~	~~100%~~
	~~17.2~~	~~Hazardous Materials~~	~~For any Hazardous Materials spills, comply with the~~	~~1 hr~~	~~N/A~~	~~N/A~~	~~MMP details the process and procedures in place and~~	~~Inspection records showing compliance~~	~~100%~~

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1 Hazard Mitigation~~	~~Cat 1 Permanent Remedy~~	~~Cat 2 Permanent Repair~~			
			~~requirements of the MMP.~~				~~followed.~~		
	~~17.3~~	~~Structural assessment~~	~~Evaluate structural damage to structures and liaise with Emergency Services to ensure safe working in clearing the Incident~~	~~1 hr~~	~~N/A~~	~~N/A~~	~~Inspections and surveys as required by Incident~~	~~Incident reports showing compliance~~	~~100%~~
	~~17.4~~	~~Temporary and permanent remedy~~	~~Propose and implement temporary measures or permanent repairs to Defects arising from the Incident.~~ ~~Ensure the structural safety of any structures affected by the Incident~~	~~24 hrs~~	~~28 days~~	~~N/A~~	~~Review and inspection of the Incident site~~	~~Auditable inspection records showing compliance~~	~~100%~~

~~**18) CUSTOMER RESPONSE**~~

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1 Hazard Mitigation~~	~~Cat 1 Permanent Remedy~~	~~Cat 2 Permanent Repair~~			
	~~18.1~~	~~Response to inquiries~~	~~Timely and effective response to customer inquiries and complaints.~~	~~48 hrs~~	~~28 days~~	~~N/A~~	~~Contact the customer within 48 hours following initial customer inquiry.~~	~~Number of responses within specified times~~	~~100%~~
	~~18.1 cont~~			~~48 hrs~~	~~28 days~~	~~N/A~~	~~All work resulting from customer requests is scheduled within 48 hours of customer contact.~~ ~~Follow-up contact with the customer within 72 hours of initial inquiry.~~ ~~All customer concerns/requests are resolved to TxDOT's satisfaction within 2 weeks of the initial inquiry.~~		

~~Performance and Measurement Table Baseline~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1 Hazard Mitigation~~	~~Cat 1 Permanent Remedy~~	~~Cat 2 Permanent Repair~~			
	~~18.2~~	~~Customer contact line~~	~~Telephone line manned during business hours and 24 hour availability of messaging system. Faults to telephone line or message system rectified~~	~~24 hrs~~	~~28 days~~	~~N/A~~	~~Instances of line out of action or unmanned~~	~~Operations records showing non availability including complaints from public.~~	~~nil~~
	~~19.1~~	~~Sweeping~~	~~i) Keep all channels, hard shoulders, gore areas, ramps, intersections, islands and frontage roads swept clean,~~ ~~ii) Clear and remove debris from traffic lanes, hard shoulders, verges and central reservations, footways and cycle ways~~ ~~iii) Remove all sweepings without stockpiling in the right of way and dispose of at approved tip.~~	~~24 hrs~~	~~28 days~~	~~6 months~~	~~Buildup of dirt, ice rock, debris, etc. on roadways and bridges not to accumulate greater than 24" wide or 1/2" deep~~	~~Inspection records showing compliance~~	~~100%~~

~~**Performance and Measurement Table Baseline**~~

~~ELEMENT CATEGORY~~	~~REF~~	~~ELEMENT~~	~~PERFORMANCE REQUIREMENT~~	~~RESPONSE TO DEFECTS~~			~~INSPECTION AND MEASUREMENT METHOD*~~	~~MEASUREMENT RECORD*~~	~~TARGET~~
				~~Cat 1 Hazard Mitigation~~	~~Cat 1 Permanent Remedy~~	~~Cat 2 Permanent Repair~~			
	~~19.2~~	~~Litter~~	~~i) Keep the right of way in a neat condition, remove litter regularly~~ ~~ii) Pick up large litter items before mowing operations.~~ ~~iii) Dispose of all litter and debris collected at an approved solid waste site.~~	~~24 hrs~~	~~28 days~~	~~6 months~~	~~No more than 20 pieces of litter per roadside mile shall be visible when traveling at highway speed.~~	~~Inspection records showing compliance~~	~~100%~~

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
1) ROADWAY									
			-	-	-	-	Unless stated otherwise, measurements shall be conducted using procedures, techniques, and measuring equipment consistent with TxDOT's *Pavement Management Information System Rater's Manual.* For the purposes of this Project, pavement performance measurement records relate to 0.1-mile sections.		-
	1.1	Obstructions and debris	Roadway and clear zone free from obstructions and debris	2 hrs	N/A	N/A	Visual Inspection	Number of obstructions and debris	Nil

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
	1.2	Pavement	All roadways have a smooth surface course (including bridge decks, covers, gratings, frames and boxes) with adequate skid resistance and free from Defects.	24 hrs	28 days	Substantial Completion	**a) Pavement Condition Score** Measurements and inspections necessary to derive Pavement Condition Score	Pavement Condition Score for 80% of Auditable Sections exceeding: • Mainlanes and ramps – 90 • Frontage roads – 80	 100% 100%
								Pavement Condition Score for each Auditable Section exceeding:	

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
								• Mainlanes and ramps – 80 • Frontage roads – 70	100% 100%
	1.2 cont						**b) Ruts – Mainlanes, shoulders & ramps** Depth as measured using an automated device in compliance with TxDOT standards.	Percentage of wheel path length with ruts greater than ¼" in depth in each Auditable Section • Mainlanes, shoulders and ramps – 3%	Nil

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
								• Frontage roads – 10%	Nil
							10ft straight edge used to measure rut depth for localized areas.	Depth of rut at any location greater than 0.5”	Nil
							c) Ride quality Measurement of International Roughness Index (IRI) according to TxDOT standard Tex-1001-S, Operating Inertial Profilers and Evaluating Pavement Profiles	For 80% of all Auditable Sections measured, IRI throughout 98% of each Auditable Section is less than or equal to: • Mainlanes, ramps – 95" per mile** • Frontage roads – 120" per	100% 100%

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
								mile**	
	1.2 cont			24 hrs	28 days	Substantial Completion	** To allow for measurement bias, an adjustment of -10 (minus ten) is made to IRI measurements for concrete pavements before assessing threshold compliance.	IRI measured throughout 98% of Auditable Section of less than or equal to: • Mainlanes, ramps 120" per mile** • Frontage roads – 150" per mile**	100% 100%
							(capital asset replacement work and new construction	Mainlanes, ramps, 0.1 mile	100%

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
							subject to construction quality standards)	average – 150" per mile** Frontage roads, 0.1 mile average – 180" per mile**	100%
							10-ft straightedge used to measure discontinuities	IRI measured throughout 98% of each lane containing a bridge deck in any Auditable Section , 0.1 mile average – 200" per mile** Individual discontinuities greater than 0.75"	100% Nil

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
							d) Failures Instances of failures exceeding the failure criteria set forth in the TxDOT PMIS Rater's Manual, including potholes, base failures, punchouts and jointed concrete pavement failures	Occurrence of any failure	Nil

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
	1.2 cont			24 hrs	28 days	Substantial Completion	**e) Edge drop-offs** Physical measurement of edge drop-off level compared to adjacent surface	Instances of edge drop-off greater than 2" (Number)	Nil

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
							f) Skid resistance ASTM E274/E274M-11 Standard Test Method for Skid Resistance Testing of Paved Surfaces at 50 MPH using a full scale smooth tire meeting the requirements of ASTM E524-08 .	• Mainlanes, shoulders and ramps – Number of sections investigated as to potential risk of skidding accident and appropriate remedial action taken where average Skid Number for 0.5-mile section of mainlanes, shoulders and ramps are in excess of 30.	100%

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
								• Frontage roads –Number of sections investigated as to potential risk of skidding accident and appropriate remedial action taken where average Skid Number for 0.5-mile section of frontage roads is in excess of 30.	100%

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
	1.2 cont							• When the skid number is below 25 and/or when required by the Wet Weather Accident Reduction Program, areas categorized as high risk, the Developer shall perform a site investigation and perform required corrective action.	100%
			Road users warned of potential skidding hazards	24hrs	7days	N/A	**Skid resistance** (as above)	Instances where road Users warned of potential skidding hazard where remedial action is identified.	100%

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
	1.3	Crossovers and other paved areas	Crossovers and other paved areas are free of Defects	24 hrs	28 days	Substantial Completion	**a) Potholes** **b) Base failures**	Potholes of low severity or higher (Number) Base failures of low severity or higher (Number)	Nil Nil
	1.4	Joints in concrete	Joints in concrete paving are sealed and watertight Longitudinal joint separation	24 hrs	28 days	Substantial Completion	Visual inspection of joints Measurement of joint width and level difference of two sides of joints	Length unsealed joints greater than ¼" Joint width more than 1" or faulting more than ¼"	Nil Nil

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
	1.5	Curbs	Curbs are free of defects	24 hrs	28 days	Substantial Completion	Visual inspection	Length out of alignment	Nil
2) DRAINAGE									
	2.1	Pipes and channels	Each Element of the drainage system is maintained in its proper function by cleaning, clearing and/or emptying as appropriate from the point at which water drains from the travel way to the outfall or drainage way.	24 hrs	28 days	Substantial Completion	Visual inspection supplemented by CCTV where required to inspect buried pipe work	Length with less than 90% of cross section clear (feet)	Nil

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
	2.2	Drainage treatment devices	Drainage treatment and balancing systems, flow and spillage control devices function correctly and their location and means of operation is recorded adequately to permit their correct operation in Emergency.	24 hrs	28 days	Substantial Completion	Visual inspection	Devices functioning correctly with means of operation displayed (Number)	100%
	2.3	Travel way	The travel way is free from water to the extent that such water would represent a hazard by virtue of its position and depth.	24 hrs	28 days	Substantial Completion	Visual inspection of water on surface	Instances of hazardous water build-up	Nil
	2.4	Discharge systems	Surface water discharge systems perform their proper function and	24 hrs	28 days	Substantial Completion	Visual inspection and records	Non-compliances with legislation	Nil

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
			discharge to groundwater and waterways complies with the relevant legislation and permits.						
	2.5	Protected species	Named species and habitats are protected.	24 hrs	28 days	6 months	Visual inspection	Compliance with the requirement	100%
3) STRUCTURES									
	3.1	Structures having an opening measured along the center of the roadway of more than 20 feet between undercopings of	Substructures and superstructures are free of: • graffiti • undesirable vegetation	24 hrs	28 days	Substantial Completion	Inspection and assessment in accordance with the requirements of federal National Bridge Inspection Standards (NBIS) of the Code of Federal Regulations, 23 Highways – Part 650, the TxDOT Bridge	Records as required in the TxDOT Bridge Inspection Manual Occurrences of condition rating below seven for any deck, superstructure or	Nil

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
		abutments or springlines of arches or extreme ends of openings or multiple boxes	• debris and bird droppings • blocked drains, weep pipes manholes and chambers • blocked drainage holes in structural components • defects in joint sealants • defects in pedestrian protection measure • scour damage • corrosion of rebar				inspection Manual, and the Federal Administration's Bridge Inspector's Reference Manual.	substructure	

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
			• paint system failures • impact damage						
	3.2	Structure components	i) Expansion joints are free of: • dirt debris and vegetation • defects in drainage systems • loose nuts and bolts • defects in gaskets ii) The deck drainage system is free of all and operates as	24 hrs	28 days	Substantial Completion	Inspection and assessment in accordance with the requirements of federal National Bridge Inspection Standards (NBIS) of the Code of Federal Regulations, 23 Highways – Part 650, the TxDOT Bridge inspection Manual, and the Federal Administration's Bridge Inspector's Reference Manual..	Records as required in the TxDOT Bridge Inspection Manual Occurrences of condition rating below seven for any deck, superstructure or substructure	Nil

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
			intended. iii) Parapets are free of: • loose nuts or bolts • blockages of hollow section drain holes • graffiti						
	3.2 cont.		• vegetation • accident damage iv) Bearings and bearing shelves are clean.	24 hrs	28 days	Substantial Completion			

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
			v) Sliding and roller surfaces are clean and greased to ensure satisfactory performance. Additional advice contained in bearing manufacturers' instructions in the Structure Maintenance Manual is followed. Special finishes are clean and perform to the appropriate standards. vii) All non-structural items such as hoists and electrical fixings, operate correctly, are clean and lubricated						

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
			as appropriate, in accordance with the manufacturer's recommendations and certification of lifting devices are maintained.						
	3.3	Non-bridge class culverts	Non-bridge-class culverts are free of: • vegetation and debris and silt • defects in sealant to movement joints • scour damage	24 hrs	28 days	Substantial Completion	Visual inspection	Number with vegetation, debris and silt Number with defects in sealant and movement joints	Nil Nil Nil

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
								Number with scour damage	
	3.4	Gantries and high masts	Sign signal gantries, high masts are structurally sound and free of: • loose nuts and bolts • defects in surface protection systems • graffiti	24 hrs	28 days	Substantial Completion	Visual inspection	Number with loose assemblies Number with defects in surface protection Number with graffiti	Nil Nil Nil
	3.5	Load ratings	All structures maintain the design load capacity.	24 hrs	28 days	Substantial Completion	Load rating calculations in accordance with the Manual for Bridge Evaluation and the TxDOT Bridge	Number of load restrictions for Texas legal loads (including legally permitted vehicles)	Nil

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
							Inspection Manual. Load restriction requirements as per the TxDOT Bridge Inspection Manual		
	3.6	Access points	All hatches and points of access have fully operational and lockable entryways.	24 hrs	28 days	Substantial Completion	Visual Inspection	Number with defects in locks or entryways	Nil
	3.7	Mechanically Stabilized Earth and Retaining Walls	Mechanically Stabilized Earth and Retaining Walls free of: • blocked weep	24 hours	28 days	Substantial Completion	Inspection and assessment in accordance with the requirements of federal Nations Bridge Inspection Standards (NBIS) of the Code of	Records as required in the TxDOT Bridge Inspection Manual	100%

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
			holes • undesirable vegetation • defects in joint sealants • defects in pedestrian protection • scour damage • corrosion of reinforcing bars • paint system failure				Federal Regulations, 23 Highways - Part 650, the TxDOT Bridge Inspection Manual and the Federal Highway Administration's Bridge Inspector's Reference Manual.		

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
			• concrete spalling • impact damage Parapets free of: • loose nuts and bolts • blockage of drain holes • undesirable vegetation • impact damage • concrete spalling						

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
4) PAVEMENT MARKINGS, OBJECT MARKERS, BARRIER MARKERS AND DELINEATORS									
	4.1	Pavement markings	Pavement markings are: • clean and visible during the day and at night • whole and complete and of the correct color, type, width and length • placed to meet the TMUTCD and TxDOT's Pavement Marking Standard Sheets	24 hrs	28 days	Substantial Completion	a) Markings - General Portable retroreflectometer, which uses 30 meter geometry meeting the requirements described in ASTM E 1710	Length meeting the minimum retroreflectivity 175 mcd/sqm/lx for white Length meeting the minimum retroreflectivity 125 mcd/sqm/lx for yellow	100% 100%

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
							Physical measurement b) Profile Markings Visual inspection	Length with more than 5% loss of area of material at any point Length with spread more than 10% of specified dimensions. Length performing its intended function and compliant with relevant regulations	Nil Nil 100%

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
	4.2	Raised reflective markers	Raised reflective pavement markers, object markers and delineators are: • clean and clearly visible • of the correct color and type • reflective or retroreflective as TxDOT standard • correctly located, aligned and at the correct level • are firmly fixed • are in a condition	24 hrs	28 days	Substantial Completion	Visual inspection	Number of markers associated with road markings that are ineffective in any 10 consecutive markers. (Ineffective includes missing, damaged, settled or sunk) [A minimum of four markers should be visible at 80' spacing when viewed under low beam headlights] Uniformity (replacement rpms having equivalent physical and performance characteristics to adjacent	Nil 100%

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
			that will ensure that they remain at the correct level.					markers).	
	4.3	Delineators & markers	Object markers, mail box markers and delineators are: • clean and visible • of the correct color and type	24 hrs	28 days	Substantial Completion	Visual inspection	Number of object markers or delineators defective or missing	Nil

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
			• legible and reflective • straight and vertical						

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
5) GUARDRAILS, SAFETY BARRIERS AND IMPACT ATTENUATORS									
	5.1	Guard rails and safety barriers	All guardrails, safety barriers, concrete barriers, etc... are maintained free of Defects. They are appropriately placed and correctly installed at the correct height and distance from roadway or obstacles. Installation and repairs shall be carried out in accordance with the requirements of NCHRP 350 standards.	24 hrs	28 days	Substantial Completion	Visual inspection	Length of road restraint systems correctly installed Length free from defects Length at correct height Length at correct distance from roadway and obstacle	100% 100% 100% 100%
	5.2	Impact attenuators	All impact attenuators are appropriately placed and correctly installed	24 hrs	7 days	Substantial Completion	Visual inspection	Number correctly placed and installed	100%

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
6) TRAFFIC SIGNS									
	6.1	General – All signs	i) Signs are clean, correctly located, clearly visible, legible, reflective, at the correct height and free from structural and electrical defects	24 hrs	28 days	Substantial Completion	**a) Retroreflectivity** Coefficient of retro reflectivity	Number of signs with reflectivity below the requirements of TxDOT's TMUTCD	Nil
			ii) Identification markers are provided, correctly located, visible, clean and legible				**b) Face damage** Visual inspection	Number of signs with face damage greater than 5% of area	Nil

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
	6.1 cont.		iii) Sign mounting posts are vertical, structurally sound and rust free				**c) Placement** Visual inspection	Signs are placed in accordance with TxDOT's Sign Crew Field Book including not twisted or leaning	100%
			iv) All break-away sign mounts are clear of silt or other debris that could impede break-away features and shall have correct stub heights				**d) Obsolete signs** Visual inspection	Number of obsolete signs	Nil
			v) Obsolete and redundant signs are removed or replaced as appropriate				**e) Sign Information** Visual inspection	Sign information is of the correct size, location, type and wording to meet its intended purpose	100%

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
			vi) Visibility distances meet the stated requirements vii) Sign information is of the correct size, location, type and wording to meet its intended purpose and any statutory requirements viii) All structures and Elements of the signing system are kept clean and free from debris and have clear access provided. ix) All replacement and repair materials and equipment are in accordance with the				**f) Dynamic Message Signs** Visual inspection	Dynamic message signs are fully functioning	100%

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
			requirements of the TMUTCD x) Dynamic message signs are in an operational condition						
	6.2	General - Safety critical signs	Requirements as 6.1, Plus: "Stop," "Yield," "Do Not Enter," "One Way" and "Wrong Way" signs are clean legible and undamaged.	2hrs	1 week	Substantial Completion	Visual inspection	Number of damaged safety critical signs	Nil
7) TRAFFIC SIGNALS				-	-	-	-	-	-

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
	7.1	General	i) Traffic Signals and their associated equipment are: • clean and visible • correctly aligned and operational • free from damage caused by accident or vandalism • correctly aligned and operational ii) Signal timing and operation is correct iii) Contingency plans are in place to rectify Category 1 Defects	2 hrs	24 hrs	Substantial Completion	**a) General condition** Visual inspection **b) Damage** Visual inspection **c) Signal timing** Timed measurements **d) Contingency plans** Records review	Signals are clean and visible Signals are undamaged Installations have correct signal timings Full contingency plans are in place	100% 100% 100% - 100%

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
			not immediately repairable to assure alternative traffic control is provided during a period of failure						
	7.2 -	Soundness	Traffic signals are structurally and electrically sound -	24 hrs -	28 days -	Substantial Completion -	**a) Structural soundness** Visual inspection **b) Electrical soundness** Testing to meet NEC regulations	Inspection records showing safe installation and maintenance	100%
	7.3	Identification marking	Signals have identification markers and the telephone number for reporting faults are correctly located, clearly visible,	N/A	28 days	Substantial Completion	Visual inspection	Inspection records showing identification markers and other information are easily readable	100%

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
			clean and legible						
	7.4	Pedestrian Elements and vehicle detectors	All pedestrian Elements and vehicle detectors are correctly positioned and fully functional at all times	24 hrs	28 days	Substantial Completion	Visual Inspection	Inspection records showing compliance	100%
8) LIGHTING									

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
	8.1	Roadway lighting – General	i) All lighting is free from defects and provides acceptable uniform lighting quality ii) Lanterns are clean and correctly positioned iii) Lighting units are free from accidental damage or vandalism iv) Columns are upright, correctly founded, visually acceptable and structurally sound	24 hrs - -	28 days - -	Substantial Completion	**a) Mainlane lights operable** Night time inspection or automated logs **b) Mainlane lights out of action** Night time inspection or automated logs	Number of sections with less than 90% of lights functioning correctly at all times Instances of more than two consecutive lights out of action	Nil Nil

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
	8.2	Sign lighting	Sign lighting is fully operational	24 hrs	28 days	Substantial Completion	Night time inspection or automated logs	Instances of more than one bulb per sign not working	Nil
	8.3	Electrical supply	Electricity supply, feeder pillars, cabinets, switches and fittings are electrically, mechanically and structurally sound and functioning	24 Hrs	7 Days	Substantial Completion	Testing to meet NEC regulations, visual inspection	Inspection records showing safe installation and maintenance	100%
	8.4	Access panels	All access panels in place at all times.	24 Hrs	7 Days	Substantial Completion	Visual inspection	Instances of missing access panels	Nil

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
	8.5	High mast lighting	i) All high mast luminaries functioning on each pole ii) All obstruction lights are present and working (if required) iii) Compartment door is secure with all bolts in place iv) All winch and safety equipment is correctly functioning and maintained without rusting or corrosion (for structural requirements refer to Element Category 3)	24 hrs	48 hrs	Substantial Completion	Yearly inspection and night time inspections or automated logs	Instances of two or more lamps not working per high mast pole Identification of other defects	Nil Nil
9) FENCES, WALLS AND SOUND ABATEMENT									

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
	9.1	Design and location	Fences and walls act as designed and serve the purpose for which they were intended	24 hrs	28 days	Substantial Completion	Visual Inspection	Inspection records showing compliance	100%
	9.2	Construction	Integrity and structural condition of the fence is maintained	24 hrs	28 days	Substantial Completion	Structural assessment if visual inspection warrants	Inspection records showing compliance	100%
10) ROADSIDE MANAGEMENT									

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
	10.1	Vegetated areas – Except landscaped areas – General	Vegetation is maintained so that: i) Height of grass and weeds is kept within the limits described for urban and rural areas. Mowing begins before vegetation reaches the maximum height.	24 hrs	7 days	28 days	**a) Urban areas** Physical measurement of height of grass and weeds	Individual measurement areas to have 95% of height of grass and weeds between 5 in. and 18 in	100%
			ii) Spot mowing at intersections, ramps or other areas maintains visibility of appurtenances and sight distance.				**b) Rural areas** Physical measurement of height of grass and weeds	Individual measurement areas to have 95% of height of grass and weeds between 5 in. and 30 in	100%

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
			iii) Grass or vegetation does not encroach into or on paved shoulders, main lanes, sidewalks, islands, riprap, traffic barrier or curbs.				**c) Encroachment** Visual inspection of instances of encroachment of vegetation	Occurrences of vegetation encroachment in each auditable section	Nil
	10.1 cont.		iv) A herbicide program is undertaken in accordance with the TxDOT Herbicide Manual to control noxious weeds and to eliminate grass in pavement or concrete.	24 hrs	7 days	28 days	**d) Wildflowers** Visual Inspection with audit of process.	Adherence to vegetation management manuals	100%

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
			v) A full width mowing cycle is completed after the first frost.				**e) Sight lines** Visual inspection	Instances of impairment of sight lines or sight distance to signs	Nil
			vi) Wildflowers are preserved utilizing the guidelines in the mowing specifications and TXDOT *Roadside Vegetation Manual*.						

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
	10.2	Landscaped areas	i) All landscaped areas are maintained to their originally constructed condition. Landscaped areas are as designated in the plans. ii) Mowing, litter pickup, irrigation system maintenance and operation, plant maintenance, pruning, insect, disease and pest control, fertilization, mulching, bed maintenance, watering is undertaken as per MMP.	24 hrs	7 days	28 days	Visual inspection	Inspection records showing compliance	100%

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
	10.2	Landscaped areas	iii) The height of grass and weeds is kept between 2“ and 8”. Mowing begins before vegetation reaches 8 in iv) Damaged or dead vegetation is replaced.						
	10.3	Fire hazards	Fire hazards are controlled	24 hrs	7 days	28 days	Visual inspection	Instances of dry brush or vegetation forming fire hazard	Nil

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
	10.4	Trees, brush and ornamentals	i) Trees, brush and ornamentals on the right of way, except in established no mow areas, are trimmed in accordance with TxDOT standards. ii) Trees, brush and ornamentals are trimmed to insure they do not interfere with vehicles or sight distance, or inhibit the visibility of signs. iii) Dead trees, brush, ornamentals and branches are removed. Potentially dangerous trees or limbs are removed.	24 hrs	7 days	28 days	Visual inspection	Inspection records showing compliance	100%

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
	10.4	Trees, brush and ornamentals	iv) All undesirable trees and vegetation are removed. Diseased trees or limbs are treated or removed by licensed contractors.						
	10.5	Wetlands	Wetlands are managed in accordance with the permit requirements	24 hrs	7 days	28 days	Visual inspection, assessment of permit issuers	Instances of permit requirements not met	Nil

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
11) REST AREAS AND PICNIC AREAS									
	11.1	Rest areas and picnic areas	i) Picnic areas are clean and neat in appearance.	24 hrs	28 days	6 months	Inspection records showing compliance	Instances where 90% of measured area shall have grass and weeds height between 2 in. and 8 in.	100%
			ii) Trash barrels are painted and attached to their supports to prevent stealing.					Mowing shall begin before vegetation reaches 8 in.	100%

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
			iii) Site free of any visible litter, all litter properly disposed. Litter removed from the picnic area grounds and barrels before being allowed to accumulate outside of the barrels.	24 hrs	28 days	6 months		Number of bare ground areas larger than 5 square feet	Nil
			iv) All vehicles used in transporting litter are equipped to prevent the accumulated litter from being strewn along the roadway.					Number of prohibited, invasive or noxious weeds present.	Nil

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
	11.1 cont		v) Vegetation damaged due to improper or careless mowing and trimming operations or any other reason is replaced.					Occurrences of encroachment of vegetation or debris for more than two (2) inches onto any curb or sidewalk located throughout each rest area.	Nil

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
			vi) Weeds, grass and other undesirable growth are removed from beds of plants and shrubs as needed. Trees and shrubs are trimmed neatly. All curbs and sidewalks are edged and repaired.					Occurrences of deviation of soil or mulch above or below the top of the curb.	Nil
			vii) All picnic tables are clean, free of stains and free of any defect.					Paved surfaces maintained clean and safe with minimal obstruction.	100%

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
			viii) All directional, informational, safety and any other type of signage are properly installed, contains accurate information and is visible from a reasonable distance.					Occurrences of undermining greater than 2”	Nil
			ix) All striping is intact and all parking and travel areas are clearly marked.					Number of unsealed cracks > ½ inch.	Nil
			x) All curbs are in place and intact.					Number of lights fully functional.	100%

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
12) EARTHWORKS, EMBANKMENTS AND CUTTINGS									
	12.1	Slope failure	All structural or natural failures of the embankment and cut slopes of the Facility are repaired	24 hrs	28 days	Substantial Completion	Visual inspection by geotechnical specialist and further tests as recommended by the specialist	Recorded instances of slope failure	Nil

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
	12.2	Slopes - General	Slopes are maintained in general conformance to the original graded cross-sections, the replacement of landscaping materials, reseeding and re-vegetation for erosion control purposes and removal and disposal of all eroded materials from the roadway and shoulders	24 hrs	28 days	Substantial Completion		Inspection records showing compliance	100%

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
13) ITS and ETCS EQUIPMENT									
	13.1	ETCS equipment – Maintenance	All ITS and ETCS equipment is fully functional and housing is functioning and free of defects. i) All equipment and cabinet identification numbers are visible, sites are well drained and access is clear. ii) Steps, handrails and accesses are kept in a good condition. iii) Access to all communication hubs, ground boxes, cabinets and sites is clear	24 hrs	14 days	1 month	Visual inspection	Inspection records showing compliance	100%

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
	13.1	ETCS equipment – Maintenance	All drainage is operational and all external fixtures and fittings are in a satisfactory condition. v) All communications cable markers, cable joint markers and duct markers are visible and missing markers are replaced. Backup power vi) All communications cable markers, cable joint markers and duct markers are visible and missing markers are replaced. vii) Backup power supply system is available at all times						

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
	13.2	VES equipment - Maintenance	All VES equipment is kept clean, the identification numbers are visible.	24 hrs	14 days	1 month	Visual inspection	Inspection records showing compliance	100%

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
	13.3	Dynamic message sign equipment	Dynamic message signs are free from faults such as: i) Any signal displaying an message which is deemed to be a safety hazard ii) Failure of system to clear sign settings when appropriate. iii) 2 or more contiguous sign failures that prevent control office setting strategic diversions iv) Signs displaying an incorrect message.	2 hrs	24 hrs	14 days	Defect measurement dependent on equipment	Inspection records showing compliance	100%

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
	13.4	CCTV equipment	CCTV Systems are free from faults that limit the availability of the operators to monitor the area network, such as: i) Failure of CCTV Systems to provide control offices with access and control of CCTV images ii) Failure of a CCTV camera or its video transmission system. iii) Failure of a pan / tilt unit or its control system. iv) Moisture ingress onto CCTV camera lens v) Faults that result in significant degradation of CCTV images	2 hrs	24 hrs	14 days	Defect measurement dependent on equipment	Inspection records showing compliance	100%

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
	13.5	Vehicle detection equipment	All equipment free of defects and operational problems such as: i) Inoperable loops. ii) Malfunctioning camera controllers.	2 hrs	24 hrs	1 month	Defect measurement dependent on equipment Traffic detector loops: Loop circuit's inductance to be > 50 and < 1,000 micro henries. Insulation resistance to be > 50 meg ohms.	Inspection records showing compliance Instances of loops out of compliance	100% Nil

14) TOLLING Facilities and Buildings (Not Used)

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
15) AMENITY									
	15.1	Graffiti	Graffiti is removed in a manner and using materials that restore the surface to a like appearance similar to adjoining surfaces	24 hrs	28 days	6 months	All graffiti is considered a Category 1 Defect	Inspection records showing compliance	100%
	15.2	Animals	All dead or injured animals are removed from the ROW	2 hrs	N/A	N/A	Visual inspection	No dead or injured animals are present on ROW	
	15.3	Abandoned vehicles and equipment	All abandoned vehicles and equipment are removed from the ROW.	1 hr	24 hrs	N/A	Visual inspection	No abandoned vehicles or equipment present	
16) SNOW AND ICE CONTROL								-	-

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
	16.1	Travel lanes	Maintain travel way free from snow and ice	2hrs	N/A	N/A	Maximum 1hr response time to complete manning and loading of spreading vehicles Maximum 2hrs from departure from loading point to complete treatment and return to loading point Maximum 1hr response time for snow and ice clearance vehicles to depart from base	Inspection records showing compliance	100%
	16.2	Weather forecasting	weather forecast information is obtained and assessed and appropriate precautionary treatment is carried out to	2hrs	N/A	N/A	Operations plan details the process and procedures in place and followed	Inspection records showing compliance	100%

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
			prevent ice forming on the travel way						
	16.3	Operational plans	Operate snow and ice clearance plans to maintain traffic flows during and after snowfall and restore the travel way to a clear condition as soon as possible.	2hrs	N/A	N/A	Operations plan details the process and procedures in place and followed	Inspection records showing compliance	100%
17) INCIDENT RESPONSE									
	17.1	General	Respond to Incidents in accordance with the MMP.	1 hr	N/A	N/A	Response times met for 98% of Incidents measured on a 1 year rolling basis. No complaints from Emergency Services.	Inspection records showing compliance	100%

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
	17.2	Hazardous Materials	For any Hazardous Materials spills, comply with the requirements of the MMP.	1 hr	N/A	N/A	MMP details the process and procedures in place and followed.	Inspection records showing compliance	100%
	17.3	Structural assessment	Evaluate structural damage to structures and liaise with Emergency Services to ensure safe working in clearing the Incident	1 hr	N/A	N/A	Inspections and surveys as required by Incident	Incident reports showing compliance	100%
	17.4	Temporary and permanent remedy	Propose and implement temporary measures or permanent repairs to Defects arising from the Incident. Ensure the structural safety of any structures	24 hrs	28 days	N/A	Review and inspection of the Incident site	Auditable inspection records showing compliance	100%

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
			affected by the Incident						
18) CUSTOMER RESPONSE									
	18.1	Response to inquiries	Timely and effective response to customer inquiries and complaints.	48 hrs	28 days	N/A	Contact the customer within 48 hours following initial customer inquiry.	Number of responses within specified times	100%

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
	18.1 cont			48 hrs	28 days	N/A	All work resulting from customer requests is scheduled within 48 hours of customer contact. Follow-up contact with the customer within 72 hours of initial inquiry. All customer concerns/requests are resolved to TxDOT's satisfaction within 2 weeks of the initial inquiry.		

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
	18.2	Customer contact line	Telephone line manned during business hours and 24 hour availability of messaging system. Faults to telephone line or message system rectified	24 hrs	28 days	N/A	Instances of line out of action or unmanned	Operations records showing non availability including complaints from public.	nil
	19.1	Sweeping	i) Keep all channels, hard shoulders, gore areas, ramps, intersections, islands and frontage roads swept clean, ii) Clear and remove debris from traffic lanes, hard shoulders, verges and central reservations, footways and cycle ways iii) Remove all sweepings	24 hrs	28 days	6 months	Buildup of dirt, ice rock, debris, etc. on roadways and bridges not to accumulate greater than 24" wide or 1/2" deep	Inspection records showing compliance	100%

Performance and Measurement Table Baseline

ELEMENT CATEGORY	REF	ELEMENT	PERFORMANCE REQUIREMENT	RESPONSE TO DEFECTS			INSPECTION AND MEASUREMENT METHOD*	MEASUREMENT RECORD*	TARGET
				Cat 1 Hazard Mitiga-tion	Cat 1 Perma-nent Remedy	Cat 2 Permanent Repair			
			without stockpiling in the right of way and dispose of at approved tip.						
	19.2	Litter	i) Keep the right of way in a neat condition, remove litter regularly ii) Pick up large litter items before mowing operations. iii) Dispose of all litter and debris collected at an approved solid waste site.	24 hrs	28 days	6 months	No more than 20 pieces of litter per roadside mile shall be visible when traveling at highway speed.	Inspection records showing compliance	100%

19.1.2 Developer's Obligation to Remedy and Repair

19.1.2.1 Performance Requirements from NTP2 to Substantial Completion

Developer is responsible for maintenance of all Elements within the limits of the Project in accordance with Book 2, Section 1.2 including the existing Elements. For the avoidance of doubt, "existing" means Elements in place and operating in the IH 35E corridor prior to commencement of construction of the Work.

Developer shall perform an inspection and evaluation of the asset conditions for existing infrastructure and existing improvements in accordance with Table 19-1, Performance and Measurement Table Baseline.

Developer shall prepare and submit to TxDOT for review and comment a Maintenance Management Plan (MMP) that demonstrates how the performance requirements for each Element having an asset condition not meeting the performance requirements specified in Table 19-1 will be fully met and maintained by the Substantial Completion date.

Developer shall ensure that each Element having an asset condition not meeting the Performance Requirements specified in Table 19-1 shall meet such requirements by the Substantial Completion date.

Developer is responsible for maintaining utility availability to adjacent structures. Developer is responsible for maintaining structures/facilities including overpasses, underpasses, utilities, and drainage systems passing directly over or under the Project, as described in Sections 1.1 thru 1.4 of the Technical Provisions, including Elements that are to be reused or rehabilitated. If Developer fails to perform such maintenance within response times as set forth in the MMP, TxDOT reserves the right to perform such work as it deems necessary with its own forces, and/or to enter into special contracts for the maintenance of specific items in accordance with Book 1, Section 16 Default; Remedies. Upon Substantial Completion, TxDOT shall assume the maintenance obligations.

19.1.2.2 Performance Requirements of Temporary Ramps and Diversions

Temporary work for the maintenance of traffic during construction Work and/or Renewal Work are to be maintained in a safe, functional and fair condition meeting the requirements of TxDOT standards and Good Industry Practice.

19.2 Maintenance Management Plan (MMP)

Developer shall prepare a Maintenance Management Plan (MMP) that is consistent with the general maintenance obligations described in Section 19.1 (General Requirements) and defines the process and procedures for the maintenance of the Project for the Term of the Agreement. The MMP shall include performance requirements, measurement procedures, threshold values at which maintenance is required, inspection procedures and frequencies, and subsequent maintenance to address noted deficiencies, for each physical Element of the Project in accordance with Table 19-1, including impacts to Related Transportation Facilities. The MMP shall identify response times to mitigate hazards, permanently remedy, and permanently repair Defects. Response times shall be in accordance with the Performance and Measurement Table Baseline, or better. Developer shall differentiate response times for Defects that require prompt attention due to immediate or imminent damage or deterioration, excluding those items which have no impact on any parties other than Developer, and response times for other Defects. Developer shall update this plan as required, or at least annually.

The MMP shall include procedures for managing records of inspection and maintenance activities, including appropriate measures for providing protected duplication of the records. Inspection and maintenance records shall be kept for the Term of the Agreement and shall be provided to TxDOT at the time the Project is delivered to TxDOT, at either the expiration of the Term or earlier termination of the Agreement.

Developer shall submit the MMP to TxDOT for review and approval at least sixty (60) Days prior to the issuance of NTP2. Approval by TxDOT of the MMP shall be a condition of NTP2.

19.2.1 Municipal Maintenance Agreements for Existing Facility During Work

Developer shall maintain access to any portion of State highways being maintained by the City, outside of the Project limits, as detailed in the municipal maintenance agreement(s) (MMA). The Developer shall maintain portions of the State highways being maintained by the City, in accordance with the Agreement. Upon Substantial Completion, the State highways within the Project limits shall be maintained in accordance with the associated MMA.

The City of Carrollton currently maintains an existing pump station at Beltline Road. Developer shall provide access to the pump station at all times and shall work with the City of Carrollton to ensure any specific needs regarding their maintenance activities are accommodated.

19.2.2 Accident Reduction Program

Developer shall implement an accident monitoring and reduction program in accordance with FHWA requirements and Good Industry Practice.

20 BICYCLE AND PEDESTRIAN FACILITIES

20.1 General Requirements

This Section 20 includes requirements with which Developer shall design and construct all bicycle and pedestrian facilities for the Project. Developer shall ensure the bicycle and pedestrian facilities of this Project support TxDOT's commitment to integrate bicycle and pedestrian travel into Project development. Developer shall coordinate the Elements of this Project with the existing and planned trails and other facilities of local and county administrations for pedestrians and cyclists.

20.2 Administrative Requirements

Developer shall maintain and keep operational all bicycle and pedestrian facilities during construction and throughout the Term of the Agreement.

20.3 Design Requirements

20.3.1 Bicycle Facilities

Developer's facilities shall be consistent with the region's bicycle and pedestrian plan and accommodate existing bicycle paths and crossings, and on-street bicycle facilities. Developer shall coordinate with Governmental Entities to ensure consistency with existing and proposed bicycle facilities.

Developer's facilities shall meet the requirements of the AASHTO Guide for the Development of Bicycle Facilities and shall incorporate the following elements relating to bicycle facilities into the Design:

a) Alignment, profile, cross-section, and materials

b) Points of connection to existing and proposed bicycle facilities

c) Signing, signalization, and pavement markings

d) Separation between bicycle facilities and the nearest travel lane, except where a wide outside lane along frontage roads is planned.

e) Methods of illumination, where applicable

f) Requirements of the Aesthetics and Landscaping Plan

In areas where new frontage roads are constructed as a part of the Work, the outside frontage road lane shall have a width of 16' to serve bicycle users and vehicular traffic.

The Developer shall provide a 14' wide shared use path for bicycles and pedestrians separated from the northbound frontage road over Lake Lewisville.

The Developer shall provide an 8' wide shared use path for bicycles and pedestrians separated from the southbound frontage road over Lake Lewisville.

20.3.2 Pedestrian Facilities

Developer shall design, construct, and maintain sidewalks along the frontage roads and side streets where sidewalks currently exist and where required by State or federal regulations. Sidewalks and pedestrian facilities shall comply with the *Texas Accessibility Standards*. Developer shall install pedestrian signals and curb ramps at all existing and proposed signalized intersections. All pedestrian facilities shall be designed to incorporate ambulatory, visibility, and auditory needs of all users and shall include the following elements relating to pedestrian facilities:

a) Alignment, profile, cross-section, and materials

b) Points of connection to existing and proposed pedestrian facilities

c) Signing, signalization, and pavement markings

d) Separation between pedestrian facilities and the nearest travel lane

e) Methods of illumination, where applicable

f) Requirements of the Aesthetics and Landscaping Plan(s)

Developer shall coordinate with Governmental Entities to ensure consistency with existing and proposed pedestrian facilities.

Prior to construction, Developer shall inventory the Project for areas where no existing sidewalk exists, and there is a visible worn path created by pedestrian and/or bicycle traffic. Where a worn path is visible and there is not an existing sidewalk, Developer shall construct a sidewalk with logical termination points per these Technical Provisions.

Developer is responsible for obtaining Texas Department of Licensing and Regulation (TDLR) reviews and approvals of pedestrian facility design and construction.

21 TOLLING

21.1 General Requirements

TxDOT will enter into a separate contract with~~ the State-wide~~ tolling integrator (hereinafter the "Integrator") to provide the Electronic Toll Collection System ("ETCS") for the Project. ~~The~~ Developer shall support the installation of the ETCS as described herein. ~~Moreover, during the design phase of the Project, the~~ Developer shall coordinate with TxDOT and the Integrator during the design phase to finalize the design of all ETCS~~ civil works~~ -related civil Elements. Developer shall provide access to the Project and coordinate construction activities for the Integrator to construct civil Elements for the Toll Zones concurrent with Developer's Work.

21.2 Administrative Requirements

Not applicable.

21.3 Design Requirements

Developer shall be responsible for designing general roadway work through each tolling zone. This will include ~~design of gantry structures, foundations, glass fiber reinforced polymer rebar (GFRP)~~a special pavement ~~sections, barriers, guard fence, maintenance areas, generators, signing, conduit, electrical, safety lighting~~section with stub ups, in accordance with the details shown in Attachment 21-2, through the Toll Zone meeting the Integrator's specifications. It shall also include general grading, duct banks, and ~~any~~ other typical roadway items included in Developer's Work. Developer shall provide communication fiber, meeting the Integrator's specification, up to the Integrator's designated roadside equipment cabinet in each Toll Zone, and shall provide electric service connections at each Toll Zone. TxDOT will be responsible for civil ~~works related~~ design Elements ~~that will be needed for~~related to the Integrator's ~~systems. The~~work. Developer shall coordinate design work in the Toll Zones with TxDOT and the Integrator to determine design requirements specific to the Toll Zones.

21.3.1 ETCS Infrastructure Requirements

21.3.1.1Mainline Tolling

Mainline Tolling will consist of ETCS generally consistent with the tolling locations indicated in the Draft Interim Schematic.

21.3.1.2Ramp Tolling

Ramp tolling will consist of ETCS generally consistent with the tolling locations indicated in the Draft Interim Schematic.

21.3.1.3 Utility and Personnel Access-way

Developer shall furnish, and install power drops at each toll gantry location. The Developer is responsible for ensuring that the necessary power based upon the Integrator's toll system is provided to each Toll Zone.

21.3.2 ETCS Functional Requirements

21.3.2.1General

Not applicable

21.3.2.2 User Classification Sub-system (UCS)

Not applicable

21.3.2.3 Video Exception Sub-system (VES)

Not applicable

21.3.3 ETCS Performance Requirements

Not applicable

21.4 Construction Requirements

The Developer shall be responsible for all general roadway work through each tolling zone, ~~*e.g.*~~including grading, special paving, ~~grading,~~ striping~~, fabrication, inspection~~ and ~~installation of toll gantries, installation of traffic barriers generators, conduit, electrical, drainage, and any~~ other ~~civil related construction Elements that will be needed for~~ items included in the Developer's work. Pavement placed by Developer in the Toll Zones shall meet the Integrator's ~~systems. The~~specifications and extend seventy-five (75) feet in each direction from the midpoint between two gantries in a reversible Toll Zone or the midpoint of the toll gantry in a bi-directional Toll Zone. Developer shall coordinate construction schedules with TxDOT and the Integrator ~~to determine~~for work taking place within the Toll Zones with specific regard for conduit and grounding under structures and in-pavement loops. Developer shall provide access and coordination for the Integrator to perform construction of toll systems civil Elements.

Pavement in all Toll Zones shall be in accordance with the pavement standard as shown in Attachment 21-2. To allow for the Integrator's testing of the toll systems, Developer shall provide a minimum of 500 feet of pavement at each end of this special pavement section. These 500 foot sections do not have to meet the requirements ~~for the Toll Zones~~of the special pavement standard provided in the attachment.

Developer shall furnish and install safety lighting for the facility including on main lanes, ramps, and at toll gantries. The lighting shall illuminate the Managed Lanes and ingress / egress points to the Managed Lanes such that CCTV cameras can clearly view the Managed Lanes and all gates, vehicle barriers and Toll Zone elements during reversing operations.

~~The~~ Developer shall provide and install all static toll signs and sign support structures except those mounted on the toll gantries. Any signs to be mounted on a toll gantry shall be provided and installed by the Integrator. Developer shall coordinate with TxDOT ~~and~~to obtain graphic design of the current TxTAG logo, NTTA logo, Pay By Mail signs and potentially a 'No ~~Cash signs~~Cash' sign. Developer shall integrate these logos into the design, fabrication, and installation of guide signs and sign support structures in accordance with Texas MUTCD requirements. All advance toll information signs shall be consistent with the adjacent facilities.

Developer shall be responsible for coordinating with the ~~communications and~~ electrical Utility Owners to purchase and install the service on behalf of TxDOT.

~~For clarification, the Developer shall be responsible for the following tasks:~~

~~a. The~~ Developer shall furnish and install ~~all toll gantries, toll gantry foundations, conduits, stub-ups, and maintenance pads. Two gantries will be installed at each Toll Zone.~~

~~b. The Developer shall be responsible for coordinating with the communications and electrical Utility Owners to purchase and install the service on behalf of TxDOT. The Developer shall provide fiber optic cables for communications and~~ power drops at each ~~Toll Zone and shall connect to the Integrator's roadside equipment cabinets. The Developer shall provide and install all conduit,~~ toll gantry location.

Developer shall be responsible for installing power and communication ~~wire and/or cabling, and electrical and communications connections~~lines to the Integrator's designated roadside equipment ~~cabinets~~cabinet.

~~c. The~~ Conduit for electrical service to the roadside equipment cabinets shall be three (3) inches in diameter.

Developer shall provide, install ~~the~~ and test single mode fiber for toll systems communications as described in Section 17.2.1.

Developer shall coordinate with Integrator to ensure that there are no power lines or radio frequency (RF) elements in the Toll Zone that could cause the interference to the toll systems. Additionally, the Developer shall coordinate with Integrator to ensure that the following do not exist in the areas reserved for loop detection systems:

1. Drains or grates placed to interfere with loop placement or within six feet (6') of sensors.
2. Buried drains, water pipes in the area reserved for sensors to a depth of six feet (6').
3. No underground power lines or buried utilities beneath the Toll Zone that could cause interference to the toll systems.
4. No continually reinforced rebar in new pavement. Epoxy coated or fiberglass rebar only.

Integrator will be responsible for design and construction of all toll related civil Elements in the Toll Zone including, fabrication, inspection, and installation of toll gantries, installation of toll gantry traffic barrier, construction of concrete pads for roadside equipment cabinets ~~furnished by the Integrator.~~

~~For clarification, the~~ and generators. Integrator shall be responsible for ~~the following tasks:~~

~~a. The Integrator shall furnish and install an all-electronic toll collection system (ETCS) that generates accurate toll transactions from a transponder or produce a set of video images for toll violation processing for all vehicles traveling through the Toll Zones.~~

~~b. The Integrator shall be responsible for the ETCS hardware and software for operations and maintenance of the toll management system.~~

~~c. The Integrator shall furnish and install all Dynamic Message Signs ("DMS") responsible for displaying toll amounts and not used for general ITS purposes. The Integrator shall also be responsible for installing sign structures, power, and communications for each toll DMS. DMS shall conform to the TxDOT special specification National Transportation Communications for ITS Protocol for Dynamic Message Signs and shall demonstrate compliance before installation of DMS.~~

~~d. The Integrator shall install all toll gantry-mounted static signs.~~

~~e. The Integrator shall provide roadside equipment cabinets for the Developer to install and shall be responsible for providing and~~ installing ~~conduit,~~ power and communication ~~wire and/or cabling, and electrical and communications connections~~lines from the Developer installed fiber duct bank to the Integrator's designated roadside equipment ~~cabinets~~cabinet to the ~~gantry mounted~~ toll systems.

~~f. The~~ A complete listing of Developer/TxDOT/Integrator ~~will provide and install an emergency generator for back-up~~responsibilities is provided in ~~the event of an electrical power outage for each~~Attachment 21-1, Toll ~~Zone~~Systems Responsibilities Matrix.

~~g. The Integrator shall be responsible for furnishing and installing all toll equipment on the gantries.~~