

Attachment 1-7: Deferred Work Components

Deferred Work Component No.	Description
1	Defer (2) 12' Managed Lanes and all shoulders, in each direction from sta 568+26 to sta 591+00. Defer all permanent barrier and associated drainage; existing 9-8x6 MBC will be extended instead of rebuilt.
2	Defer 2 lanes on SB International Parkway (IP) Bridge 1-67 over DART. Bridge 1-67 substructure will be built to 6-lane width; superstructure will accommodate 4 lanes.
3	Defer construction of one lane (12') SBIP from sta 1816+00 to sta 1844+65 and from sta 1788+00 to sta 1807+10. Bridge 1-48 substructure will be built to 4-lane width; superstructure will accommodate 3 lanes.
4	Defer construction of one lane (12') of exit ramp from SBIP to EB 114 from sta 1817+00 to sta 1844+65.
5	Defer construction of one lane (12') of NBIP from sta 1788+00 to sta 1808+00 and from sta 1819+00 to sta 1846+60.
6	Bridge 1-49 substructure will be built to 4-lane width; superstructure will accommodate 3 lanes.
7	Defer construction of one lane (12') of the WB 114 to NB 121 DC from sta 22+00 to sta 38+40.
8	Defer construction of one lane (12') of NB 121 from sta 1835+20 to sta 1846+30.
9	Defer construction of SB 121 from sta 1851+00 to sta 1864+40. Existing conditions will remain in place.
10	Defer the construction of bridge 1-68 leaving existing structure in place.
11	Defer the construction of bridge 1-69 leaving existing structure in place. Defer construction of NB 121 from sta 1851+60 to sta 1865+40. Existing conditions will remain in place.
12	Existing 3-7x5 MBC around sta 1802+50 will be extended instead of rebuilt
13	Defer 2 lanes (24') of WBFR from sta 539+40 to sta 546+65. Defer all lanes, shoulders, and driveways of WBFR from sta 547+50 to sta 558+20, existing drainage and utilities to remain in place. Defer all lanes, shoulders, and driveways of WBFR from sta 571+45 to sta 577+00, existing drainage and utilities to remain in place. Defer right lane (12'), shoulder, and driveways of WBFR from sta 574+00 to sta 585+00, existing drainage and utilities to remain in place.
14	Defer all lanes, shoulders, and driveways of EBFR from sta 608+80 to sta 622+00 and from sta 623+00 to sta 629+00, existing drainage and utilities to remain in place.
15	Defer construction of exit ramp from EB 114 to the DFW International Parkway SBFR from sta 5+96 to sta 21+45 and associated drainage.
16	Defer Mustang to NB 121 entrance ramp construction from sta 3+10 to sta 10+46. Defer construction of bridge 1-29 (sta 8+70 to 22+15) and retaining walls 28LT & 28RT. Defer construction of 121 NBFR from sta 791+66 to sta 810+18 and associated drainage.
17	Defer construction of one lane and shoulders in each direction of 121 GP from sta 1864+40 to sta 1952+10.
18	Defer E-W turn around bridge 1-43 with associated approaches at Texan Trail.
19	Defer E-W turn around bridge 1-5 with associated approaches at Bus 114E.
20	Defer construction and associated ROW acquisition services of FM1709 from sta 448+00 to sta 469+00.
21	Construct only two lanes of 121 SBFR from sta 627+00 to sta 699+85.
22	Defer the construction of bridge 4-65 and exit ramp to Texan Trail from sta 10+85 to sta 26+60 and pavement from bridge 4-65 to WB 114ML from sta 5+15 to sta 19+20.