STATE OF TEXAS
TEXAS DEPARTMENT OF TRANSPORTATION

EXHIBIT OF PROPOSED STATE HIGHWAY IMPROVEMENT

WICHITA FALLS DISTRICT
WICHITA COUNTY
SH 240
BURKBURNETT, TEXAS
SEPTEMBER 2011

SH 240

CSJ: 0903-03-071
COUNTY: WICHITA
LIMITS: FM 369 AT SH 240 TO GRESHAM ROAD AT LOOP 267
SCOPE: CONSTRUCT NEW NON-FREEWAY FACILITY
DESIGN SPEED: 50 MPH
FACILITY TYPE: RURAL
FUNCTIONAL CLASS: 5 (MAJOR COLLECTOR)
EXISTING TRAFFIC VOLUME: 2700 AADT (CURRENT YEAR 2008)
PROPOSED TRAFFIC VOLUME: 3780 AADT (DESIGN YEAR 2028)

LOOP 267

DESIGN SPEED: 40 MPH

RAMP

DESIGN SPEED: 35 MPH

CONSTRUCTION SEQUENCE:

PHASE I:

- CONSTRUCT NEW ROADWAY WHICH DOES NOT CONFLICT WITH EXISTING COUNTY ROAD.
- CONSTRUCT WIDENING PORTION OF NEW ROADWAY ADJACENT TO EXISTING COUNTY ROAD.
- CONTINUE TO MAINTAIN FULL ACCESS AND DESIRABLE TRAVEL CONDITIONS ALONG COUNTY ROAD.

PHASE II:

- TRANSFER TRAFFIC TO NEWLY CONSTRUCTED PORTION OF ROADWAY.
- RECONSTRUCT EXISTING COUNTY ROAD ADJACENT TO WIDENED PORTION OF NEW ROADWAY.
- TRANSFER TRAFFIC TO ULTIMATE ROADWAY OPERATIONS.

NOT A BIDDING DOCUMENT

© 2011 Texas Department of Transportation

THIS DOCUMENT IS RELEASED FOR THE PURPOSE OF INTERIM REVIEW ONLY UNDER THE AUTHORITY OF DARELL E. JOHNSON, P.E. 95730
DATE:____________
IT IS NOT TO BE USED FOR BIDDING, CONSTRUCTION, OR PERMIT PURPOSES.

LEGEND	
PROPOSED SH 240	PROPOSED ℄
	PROPOSED ROW
	PROPOSED SIDEWALK
EXISTING	OVERHEAD POWER
	GAS
	FIBER - AT&T
	SEWER
	FIBER - SANTA ROSA
	WATER
	EXISTING ROAD
	EXISTING ROW
	EXISTING PAVEMENT TO BE REMOVED