FM 157 Realignment Project from 8th Street to South of CR 109

Project Goals

- ✓ Expedite project
- ✓ Enhance safety
- ✓ Improve traffic circulation
- ✓ Congestion relief
- ✓ Provide pedestrian accessibility

Alternatives Analysis - FM 157 Reconstruction Project

FM 157 from US 67 to 8th Street CSJ 0747-05-042
Alternatives Analysis Evaluation Matrix

Criteria		No Build Alternative	Recommended Alternative FM 157 Shifted East	Alternative FM 157 Centered	Alternative FM 157 Shifted West
Item	Unit				
Property Impacts		**0**	**-**	**--**	**--**
Additional Right-of-Way Needed (Acres)	acres	0	1.43	1.30	1.33
Number of Parcels Impacted	# of	0	20	36	20
BNSF Railroad Property Impact	# of	0	1	1	1
Number of Buildings Displaced	# of	0	3	3	8
US Post Office Property Impact	# of	0	0	1	1
City of Venus Fire Station Property Impact	# of	0	0	1	1
City of Venus Water Supply Property Impact	# of	0	0	1	1
Masonic Lodge Impact	# of	0	0	1	1