

# NOTIFICATION OF ADDENDUM

## ADDENDUM NO. 1

**DATED 6/20/2022**

<b>Control</b>	<b>1986-01-067</b>
<b>Project</b>	<b>F 2022(725)</b>
<b>Highway</b>	<b>FM 1314</b>
<b>County</b>	<b>MONTGOMERY</b>

Ladies/Gentlemen:

Attached please find an addendum on the above captioned project. Included in the attachment is an addendum notification which details the changes and the respective proposal pages which were added and/or changed.

Except for new bid insert pages, it is unnecessary to return any of the pages attached.

Bid insert pages must be returned with the bid proposal submitted to the Department, unless your firm is submitting a bid using a computer print out. The computer print out must be changed to reflect the new bid item information.

Contractors and material suppliers, etc. who have previously been furnished informational proposals are not being furnished a copy of the addendum. If you have a subcontractor on the above project, please advise them of this addendum. Acknowledgment of this addendum is not requested if your company has been issued a proposal stamped "This Proposal Issued for Informational Purposes."

You are required to acknowledge receipt of this addendum on the Addendum Acknowledgement form contained in your bid proposal by placing a mark in the box next to the respective addendum.

Failure to Acknowledge receipt of this addendum in your bid proposal will result in your bid not being read.

SUBJECT: PLANS AND PROPOSAL ADDENDUMS

PROJECT: F 2022(725)

CONTROL: 1986-01-067

COUNTY: MONTGOMERY

LETTING: 06/30/2022

REFERENCE NO: 0616

**PROPOSAL ADDENDUMS**

-----

- PROPOSAL COVER
- BID INSERTS (SH. NO.: ALL BID INSERT SHEETS )
- GENERAL NOTES (SH. NO.: I & J (PLAN SHEET 15D) )

- SPEC LIST (SH. NO.: )
- SPECIAL PROVISIONS: )
- ADDED:

DELETED:

- SPECIAL SPECIFICATIONS:
- ADDED:

DELETED:

- OTHER: PLAN SHEETS

DESCRIPTION OF ABOVE CHANGES  
(INCLUDING PLANS SHEET CHANGES)

\*\*\*\*\*BID INSERTS\*\*\*\*\*

DUE TO ADMINISTRATION'S REQUIREMENT FOR THE CONTRACTOR TO SIGN THE FIRST PAGE OF THE BID INSERTS, THERE IS A PAGE SHIFT OF ALL THE BID INSERT PAGES

REVISED THE QUANTITY OF THE FOLLOWING BID ITEMS:

316-6001, 316-6434, 354-6045, 432-6045, 3076-6041.

ADDED THE FOLLOWING BID ITEMS:

134-6001, 3076-6043, 3076-6066.

REMOVED THE FOLLOWING BID ITEMS:

134-6004, 3076-6042.

BID CODE INSERTS SHEETS 1-6, 5-6 AND E&Q SHEETS 16 AND 16A REVISED DUE TO THE ABOVE REVISIONS.

\*\*\*\*\*GENERAL NOTES\*\*\*\*\*

DESCRIPTION OF ABOVE CHANGES  
(INCLUDING PLANS SHEET CHANGES)

(CONTINUED)

SHEET I: ADDED NOTES TO ITEM 7 AND ITEM 316.

SHEET J: PAGE SHIFT DUE TO ABOVE REVISIONS.

\*\*\*\*\*PLAN SHEET REVISIONS\*\*\*\*\*

SHEET 10, 12, 13, AND 14 (PROPOSED TYPICAL SECTIONS): NOTES ADDED FOR CONTRACTOR'S INFORMATION.

SHEET I: ADDED NOTES TO ITEM 7 AND ITEM 316.

SHEET J: PAGE SHIFT DUE TO ABOVE REVISIONS.

\*\*\*\*\*PLAN SHEET REVISIONS\*\*\*\*\*

SHEET 10, 12, 13, AND 14 (PROPOSED TYPICAL SECTIONS): NOTES ADDED FOR CONTRACTOR S INFORMATION.

SHEET 15D (GENERAL NOTES): REVISED DUE TO THE ABOVE REVISIONS.

SHEET 16 & 16A (ESTIMATE & QUANTITY SHEETS): SHEETS REVISED DUE TO REVISIONS STATED ABOVE UNDER BID INSERTS.

SHEETS 17 (ROADWAY SUMMARY): SHEETS REVISED DUE TO REVISIONS STATED ABOVE UNDER BID INSERTS.

\*\*\*\*\*

Printed Name of Authorized Signer: \_\_\_\_\_

Signature of Authorized Signer: \_\_\_\_\_ Date: \_\_\_\_\_

PROJECT F 2022(725)  
 COUNTY MONTGOMERY

Proposal Sheet  
 TxDOT  
 FORM 234-B I-61-5M

ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	104	6054		REMOVING CONCRETE(MOW STRIP) DOLLARS and CENTS	LF	275.000	1
	134	6001		BACKFILL (TY A) DOLLARS and CENTS	STA	79.000	2
	316	6001	002	ASPH (MULTI OPTION) DOLLARS and CENTS	GAL	36,418.000	3
	316	6434	002	AGGR (TY-PB GR-4 OR TY-PL GR-4 ( SAC-B) DOLLARS and CENTS	CY	872.000	4
	351	6011		FLEXIBLE PAVEMENT STRUCTURE REPAIR(18") DOLLARS and CENTS	SY	6,211.000	5
	354	6045		PLANE ASPH CONC PAV (2") DOLLARS and CENTS	SY	128,900.000	6
	432	6045		RIPRAP (MOW STRIP)(4 IN) DOLLARS and CENTS	CY	11.900	7
	500	6001		MOBILIZATION DOLLARS and CENTS	LS	1.000	8
	502	6001	008	BARRICADES, SIGNS AND TRAFFIC HAN- DLING DOLLARS and CENTS	MO	7.000	9
	530	6002		INTERSECTIONS (ACP) DOLLARS and CENTS	SY	1,880.000	10

ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	530	6005		DRIVEWAYS (ACP)  DOLLARS and CENTS	SY	13,219.000	11
	540	6001	001	MTL W-BEAM GD FEN (TIM POST)  DOLLARS and CENTS	LF	62.500	12
	540	6014	001	SHORT RADIUS  DOLLARS and CENTS	LF	62.500	13
	540	6039	001	MTL BM GD FEN TRANS (31"-28")(25')  DOLLARS and CENTS	EA	2.000	14
	542	6001		REMOVE METAL BEAM GUARD FENCE  DOLLARS and CENTS	LF	125.000	15
	544	6001		GUARDRAIL END TREATMENT (INSTALL)  DOLLARS and CENTS	EA	2.000	16
	544	6003		GUARDRAIL END TREATMENT (REMOVE)  DOLLARS and CENTS	EA	2.000	17
	636	6001	001	ALUMINUM SIGNS (TY A)  DOLLARS and CENTS	SF	22.000	18
	644	6001		IN SM RD SN SUP&AM TY10BWG(1)SA(P)  DOLLARS and CENTS	EA	27.000	19
	644	6004		IN SM RD SN SUP&AM TY10BWG(1)SA(T)  DOLLARS and CENTS	EA	18.000	20
	644	6076		REMOVE SM RD SN SUP&AM  DOLLARS and CENTS	EA	42.000	21
	658	6062		INSTL DEL ASSM (D-SW)SZ 1(BRF)GF2(BI)  DOLLARS and CENTS	EA	6.000	22

ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	662	6001		WK ZN PAV MRK NON-REMOV (W)4"(BRK) DOLLARS and CENTS	LF	23,756.000	23
	662	6004		WK ZN PAV MRK NON-REMOV (W)4"(SLD) DOLLARS and CENTS	LF	93,016.000	24
	662	6014		WK ZN PAV MRK NON-REMOV (W)12"(SLD) DOLLARS and CENTS	LF	3,404.000	25
	662	6016		WK ZN PAV MRK NON-REMOV (W)24"(SLD) DOLLARS and CENTS	LF	1,248.000	26
	662	6017		WK ZN PAV MRK NON-REMOV (W)(ARROW) DOLLARS and CENTS	EA	180.000	27
	662	6029		WK ZN PAV MRK NON-REMOV(W)(WORD) DOLLARS and CENTS	EA	76.000	28
	662	6032		WK ZN PAV MRK NON-REMOV (Y)4"(BRK) DOLLARS and CENTS	LF	17,860.000	29
	662	6034		WK ZN PAV MRK NON-REMOV (Y)4"(SLD) DOLLARS and CENTS	LF	97,904.000	30
	666	6030	007	REFL PAV MRK TY I (W)8"(DOT)(100MIL) DOLLARS and CENTS	LF	22.000	31
	666	6036	007	REFL PAV MRK TY I (W)8"(SLD)(100MIL) DOLLARS and CENTS	LF	1,771.000	32
	666	6042	007	REFL PAV MRK TY I (W)12"(SLD)(100MIL) DOLLARS and CENTS	LF	851.000	33
	666	6048	007	REFL PAV MRK TY I (W)24"(SLD)(100MIL) DOLLARS and CENTS	LF	312.000	34

ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	666	6099	007	REF PAV MRK TY I(W)18"(YLD TRI)(100MIL) DOLLARS and CENTS	EA	5.000	35
	666	6162	007	RE PV MRK TY I(BLACK)6"(SHADOW)(100MIL) DOLLARS and CENTS	LF	5,939.000	36
	666	6306	007	RE PM W/RET REQ TY I (W)6"(BRK)(100MIL) DOLLARS and CENTS	LF	5,939.000	37
	666	6309	007	RE PM W/RET REQ TY I (W)6"(SLD)(100MIL) DOLLARS and CENTS	LF	21,483.000	38
	666	6318	007	RE PM W/RET REQ TY I (Y)6"(BRK)(100MIL) DOLLARS and CENTS	LF	4,465.000	39
	666	6321	007	RE PM W/RET REQ TY I (Y)6"(SLD)(100MIL) DOLLARS and CENTS	LF	24,476.000	40
	668	6077		PREFAB PAV MRK TY C (W) (ARROW) DOLLARS and CENTS	EA	45.000	41
	668	6085		PREFAB PAV MRK TY C (W) (WORD) DOLLARS and CENTS	EA	19.000	42
	672	6009		REFL PAV MRKR TY II-A-A DOLLARS and CENTS	EA	736.000	43
	672	6010		REFL PAV MRKR TY II-C-R DOLLARS and CENTS	EA	389.000	44
	678	6002		PAV SURF PREP FOR MRK (6") DOLLARS and CENTS	LF	62,302.000	45
	678	6004		PAV SURF PREP FOR MRK (8") DOLLARS and CENTS	LF	1,793.000	46

ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	678	6006		PAV SURF PREP FOR MRK (12") DOLLARS and CENTS	LF	851.000	47
	678	6008		PAV SURF PREP FOR MRK (24") DOLLARS and CENTS	LF	312.000	48
	678	6009		PAV SURF PREP FOR MRK (ARROW) DOLLARS and CENTS	EA	45.000	49
	678	6016		PAV SURF PREP FOR MRK (WORD) DOLLARS and CENTS	EA	19.000	50
	690	6086		REMOVE VID IMAGE VEH DET SYS (VIVDS) DOLLARS and CENTS	EA	13.000	51
	3076	6041		D-GR HMA TY-D SAC-A PG70-22 DOLLARS and CENTS	TON	11,837.000	52
	3076	6043		D-GR HMA TY-D PG70-22 (LEVEL-UP) DOLLARS and CENTS	TON	6,449.000	53
	3076	6066		TACK COAT DOLLARS and CENTS	GAL	16,036.000	54
	6001	6001		PORTABLE CHANGEABLE MESSAGE SIGN DOLLARS and CENTS	DAY	120.000	55
	6027	6003		CONDUIT (PREPARE) DOLLARS and CENTS	LF	1,105.000	56
	6027	6008		GROUND BOX (PREPARE) DOLLARS and CENTS	EA	13.000	57
	6185	6002	002	TMA (STATIONARY) DOLLARS and CENTS	DAY	59.000	58



ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	6185	6003	002	TMA (MOBILE OPERATION)  DOLLARS and CENTS	HR	96.000	59
	6292	6004		RVDS(PRESENCE DET ONLY)(INSTALL ONLY)  DOLLARS and CENTS	EA	13.000	60

**County:** Montgomery

**Control:** 1986-01-067

**Highway:** FM 1314

**General Notes:**

**General:**

Contractor questions on this project are to be addressed to the following individual(s):

*Abraham M. Guzman, P.E.*

[\*Abe.Guzman@txdot.gov\*](mailto:Abe.Guzman@txdot.gov)

*Matthew M. Connelly, P.E.*

[\*Matthew.Connelly@txdot.gov\*](mailto:Matthew.Connelly@txdot.gov)

Contractor questions will be accepted through email, phone, and in person by the above individual. Contractor questions will be reviewed by the Area Engineer or Assistant Area Engineer. Once a response is developed, it will be posted to TxDOT's Public FTP at the following address:

<https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting%20Responses/>

Questions submitted that generate a response will be posted through this site. The site is organized by District, Project Type (Construction or Maintenance), Letting Date, and CCSJ/Project Name.

If fixed features require, the governing slopes shown may vary between the limits shown and to the extent determined by the Engineer.

Superelevate the curves to match the existing surface.

Notify the Engineer immediately if discrepancies are discovered in the horizontal control or the benchmark data.

References to manufacturer's trade name or catalog numbers are for the purpose of identification only. Similar materials from other manufacturers are permitted if they are of equal quality, comply with the specifications for this project, and are approved, except for roadway illumination, electrical, and traffic signal items.

The cost for materials, labor, and incidentals to provide for traffic across the roadway and for ingress and egress to private property in accordance with Section 7.2.4 of the standard specifications is subsidiary to the various bid items. Restore access roadways to their original condition upon completing construction.

Grade street intersections and median openings for surface drainage.

If a foundation is to be placed where a riprap surface or an asphalt concrete surface presently exists, use caution in breaking out the existing surface for placement. Break out no greater area than is required to place the foundation. After placing the foundation, wrap the periphery with 0.5 in. pre-molded mastic expansion joint. Then replace the remaining portion of the broken out surface with Class A or Class C concrete or cold mix asphalt concrete to the exact slope, pattern,

County: Montgomery

Control: 1986-01-067

Highway: FM 1314

and thickness of the existing riprap or asphalt. Payment for breaking out the existing surface, wrapping the foundation, and replacing the surface is subsidiary to the various bid items.

The lengths of the posts for ground mounted signs and the tower legs for the overhead sign supports are approximate. Verify the lengths before ordering these materials to meet the existing field conditions and to conform to the minimum sign mounting heights shown in the plans.

Furnish aluminum Type A signs instead of plywood signs for signs shown on the Summary of Small Signs sheet.

Stencil the National Bridge Inventory (NBI) number on each existing bridge shown on these plans. The NBI number is shown above the title block for each bridge layout.

Clearly mark or highlight on the shop drawings, the items being furnished for this project. Submit required shop drawings in accordance with the shop drawing distribution list shown in the note for Item 5 for review and distribution.

Procure permits and licenses, which are to be issued by the City, County, or Municipal Utility District.

**General: Roadway Illumination and Electrical**

For roadway illumination and electrical items, use materials from pre-qualified producers as shown on the Construction Division (CST) of the Department's material producers list. Check the latest link on the Department's website for this list. The category/item is "Roadway Illumination and Electrical Supplies." No substitutions will be allowed for materials found on this list.

Perform electrical work in conformance with the National Electrical Code (NEC) and the Department's standard sheets.

**General: Traffic Signals**

For traffic signal items, use materials from the Pre-Qualified Producers List (located at <http://www.dot.state.tx.us/GSD/purchasing/supps.htm>) and the materials pre-qualified for illumination and electrical items (located at <http://ftp.dot.state.tx.us/pub/txdot-info/cmd/mpl/riaes.pdf>) as shown on the Department's Material Producers List and the Roadway Illumination and Electrical Supplies List. Check the latest links on the Department's website for these lists. No substitutions will be allowed for materials found on these lists.

**General: Site Management**

Mow the grass and weeds within the project limits a maximum of 3 times a year as directed. This work is subsidiary to the various bid items.

County: Montgomery

Control: 1986-01-067

Highway: FM 1314

Mark stations every 100 ft. and maintain the markings for the project duration. Remove the station markings at the completion of the project. This work is subsidiary to the various bid items.

Do not mix or store materials, or store or repair equipment, on top of concrete pavement or bridge decks unless authorized by the Engineer. Permission will be granted to store materials on surfaces if no damage or discoloration will result.

Personal vehicles of employees are not permitted to park within the right of way, including sections closed to public traffic. Employees may park on the right of way at the Contractor's office, equipment, and materials storage yard sites.

Assume ownership of debris and dispose of at an approved location. Do not dispose of debris on private property unless approved in writing by the District Engineer.

Control the dust caused by construction operations. For sweeping the base material in preparation for laying asphalt and for sweeping the finished concrete pavement, use one of the following types of sweepers or approved equal:

**Tricycle Type**

Wayne Series 900  
Elgin White Wing  
Elgin Pelican

**Truck Type - 4 Wheel**

M-B Cruiser II  
Wayne Model 945  
Mobile TE-3  
Mobile TE-4  
Murphy 4042

**General: Traffic Control and Construction**

Schedule construction operations such that preparing individual items of work follows in close sequence to constructing storm drains in order to provide as little inconvenience as practical to the businesses and residents along the project.

Schedule work so that the base placement operations follow the subgrade work as closely as practical to reduce the hazard to the traveling public and to prevent undue delay caused by wet weather.

If relocating mailboxes, place them with the post firmly in the ground at nearby locations. Upon completing the project, the Engineer will locate the final mailbox placement. Perform this work in accordance with the requirements of the Item, "Mailbox Assemblies," except for measurement and payment. This work is subsidiary to the various bid items.

If fences cross construction easements shown on the plans and work is required beyond the fences, remove and replace the fences as directed. This work and the materials are subsidiary to the various bid items.

**County:** Montgomery

**Control:** 1986-01-067

**Highway:** FM 1314

When design details are not shown on the plans, provide signs and arrows conforming to the latest "Standard Highway Sign Designs for Texas" manual.

**General: Utilities**

Consider the locations of underground utilities depicted in the plans as approximate and employ responsible care to avoid damaging utility facilities. Depending upon scope and magnitude of planned construction activities, advanced field confirmation by the utility owner or operator may be prudent. Where possible, protect and preserve permanent signs, markers, and designations of underground facilities.

If the Contractor damages or causes damage (breaks, leaks, nicks, dents, gouges, etc.) to the utility, contact the utility facility owner or operator immediately.

Be aware that an operational Computerized Transportation Management System (CTMS) exists within the limits of this project and that the system must remain operational throughout construction. If the Contractor damages or causes damage to this system, repair such damage within 8 hours of occurrence at no cost to the Department. In the event of system damage, notify the Director of Traffic Management Systems at 713-881-3283 within one hour of occurrence. Failure of the Contractor to repair damage to the main fiber optic cable and CCTV cable trunk lines, which convey all corridor information to TranStar, will result in the Contractor being billed for the full cost of emergency repairs.

At least 72 hours before starting work, make arrangements for locating existing Department-owned above ground and underground fiber optic, communications, power, illumination, and traffic signal cabling and conduit. Do this by calling the Department's Houston District Traffic Signal Operations Office at 713-802-5662, or by e-mailing the Department's Houston District Traffic Signal Operations Office at [HOU-LocateRequest@txdot.gov](mailto:HOU-LocateRequest@txdot.gov), to schedule marking of underground lines on the ground. Use caution if working in these areas to avoid damaging or interfering with existing facilities.

Notify the Engineer at least 48 hours before constructing junction boxes at storm drain and utility intersections.

Install or remove poles and luminaires located near overhead or underground electrical lines using established industry and utility safety practices. Consult the appropriate utility company before beginning such work.

If overhead or underground power lines need to be de-energized, contact the electrical service provider to perform this work. Costs associated with de-energizing the power lines or other protective measures required are at no expense to the Department.

If working near power lines, comply with the appropriate sections of Texas State Law and Federal Regulations relating to the type of work involved.

County: Montgomery

Control: 1986-01-067

Highway: FM 1314

Perform electrical work in conformance with the National Electrical Code (NEC) and Department's standard sheets.

Before beginning any underground work, notify the City of Houston's Chief Inspector, Public Works and Engineering, to establish the locations of any existing electrical systems for lighting facilities within the limits of this project.

### Item 5: Control of Work

Submit shop drawings electronically for the fabrication of items as documented in Table 1 below. Information and requirements for electronic submittals can be viewed in the "Guide to Electronic Shop Drawing Submittal" which can be accessed through the following web link, [ftp://ftp.dot.state.tx.us/pub/txdot-info/library/pubs/bus/bridge/e\\_submit\\_guide.pdf](ftp://ftp.dot.state.tx.us/pub/txdot-info/library/pubs/bus/bridge/e_submit_guide.pdf). References to 11 in. x 17 in. sheets in individual specifications for structural items imply electronic CAD sheets.

**Table 1**  
2014 Construction Specification Required Shop/Working Drawing Submittals - TxDOT Generated Plans

Spec Item No.'s	Product	Submittal Required	Approval Required (Y/N)	Contractor/Fabricator P.E. Seal Required	Reviewing Party	Shop or Working Drawing (Note 1)
7.16.1&.2	Construction Load Analyses	Y	Y	Y	B	WD
400	Excavation and Backfill for Structures (cofferdams)	Y	N	Y	A	WD
403	Temporary Special Shoring	Y	N	Y	C	WD
420	Formwork/Falsework	Y	N	Y	A	WD
423	Retaining Walls, (calcs req'd.)	Y	Y	Y	C	SD
425	Optional Design Calculations (Prstrs Bms)	Y	Y	Y	B	SD
425	Prestr Concr Sheet Piling	Y	Y	N	B	SD
425	Prestr Concr Beams	Y	Y	N	B	SD
425	Prestr Concr Bent	Y	Y	N	B	SD
426	Post Tension Details	Y	Y	N	B	SD
434	Elastomeric Bearing Pads (All)	Y	Y	N	B	SD
441	Bridge Protective Assembly	Y	Y	N	B	SD
441	Misc Steel (various steel assemblies)	Y	Y	N	B	SD
441	Steel Pedestals (bridge raising)	Y	Y	N	B	SD
441	Steel Bearings	Y	Y	N	B	SD
441	Steel Bent	Y	Y	N	B	SD
441	Steel Diaphragms	Y	Y	N	B	SD
441	Steel Finger Joint	Y	Y	N	B	SD
441	Steel Plate Girder	Y	Y	N	B	SD
441	Steel Tub-Girders	Y	Y	N	B	SD
441	Erection Plans, including Falsework	Y	N	Y	A	WD
449	Sign Structure Anchor Bolts	Y	Y	N	T	SD
450	Railing	Y	Y	N	A	SD
462	Concrete Box Culvert	Y	Y	N	C	SD
462	Concrete Box Culvert (Alternate	Y	Y	Y	B	SD

County: Montgomery

Control: 1986-01-067

Highway: FM 1314

	Designs Only, calcs req'd.)					
464	Reinforced Concrete Pipe (Jack and Bore only; ONLY when requested)	Y	Y	Y	A	SD
465	Pre-cast Junction Boxes, Grates, and Inlets	Y	Y	N	A	SD
465	Pre-cast Junction Boxes, Grates, and Inlets (Alternate Designs Only, calcs req'd.)	Y	Y	Y	B	SD
466	Pre-cast Headwalls and Wingwalls	Y	Y	N	A	SD
467	Pre-cast Safety End Treatments	Y	Y	N	A	SD
495	Raising Existing Structure (calcs req'd.)	Y	Y	Y	B	SD
610	Roadway Illumination Supports (Non-Standard only, calcs req'd.)	Y	Y	Y	BRG	SD
613	High Mast Illumination Poles (Non-standard only, calcs req'd.)	Y	Y	Y	BRG	SD
627	Treated Timber Poles	Y	Y	N	T	SD
644	Special Non-Standard Supports (Bridge Mounts, Barrier Mounts, Etc.)	Y	Y	Y	T	SD
647	Large Roadside Sign Supports	Y	Y	Y	T	SD
650	Cantilever Sign Structure Supports - Alternate Design Calcs.	Y	Y	Y	T	SD
650	Sign Structures	Y	Y	N	T	SD
680	Installation of Highway Traffic Signals	Y	Y	N	T	SD
682	Vehicle and Pedestrian Signal Heads	Y	Y	N	T	SD
684	Traffic Signal Cables	Y	Y	N	T	SD
685	Roadside Flashing Beacon Assemblies	Y	Y	N	T	SD
686	Traffic Signal Pole Assemblies (Steel) (Non-Standard only)	Y	Y	Y	T	SD
687	Pedestal Pole Assemblies	Y	Y	N	T	SD
688	Detectors	Y	Y	N	A	SD
784	Repairing Steel Bridge Members	Y	Y	Y	B	WD
SS	Prestr Concr Crown Span	Y	Y	N	B	SD
SS	Sound Barrier Walls	Y	Y	Y	A	SD
SS	Camera Poles	Y	Y	Y	TMS	SD
SS	Pedestrian Bridge (Calcs req'd.)	Y	Y	Y	B	SD
SS	Screw-In Type Anchor Foundations	Y	Y	N	T	SD
SS	Fiber Optic/Communication Cable	Y	Y	N	TMS	SD
SS	Spread Spectrum Radios for Signals	Y	Y	N	T	SD
SS	VIVDS System for Signals	Y	Y	N	T	SD
SS	CTMS Equipment	Y	Y	N	TMS	SD

## Notes:

1. Document flow for Working Drawings differs from Shop Drawings in that Working Drawings must be submitted to the Engineer rather than the Engineer of Record and they are for the information of the Engineer only; an approval stamp and distribution to all project offices is not required.

County: Montgomery

Control: 1986-01-067

Highway: FM 1314

**Key to Reviewing Party**

A - Area Office	
Area Office	Email Address
Brazoria Area Office	<a href="mailto:HOU-BRZAShpDrwgs@txdot.gov">HOU-BRZAShpDrwgs@txdot.gov</a>
Fort Bend Area Office	<a href="mailto:HOU-FBAShpDrwgs@txdot.gov">HOU-FBAShpDrwgs@txdot.gov</a>
Galveston Area Office	<a href="mailto:HOU-GALVAShpDrwgs@txdot.gov">HOU-GALVAShpDrwgs@txdot.gov</a>
Montgomery Area Office	<a href="mailto:HOU-MONTAShpDrwgs@txdot.gov">HOU-MONTAShpDrwgs@txdot.gov</a>
North Harris Area Office	<a href="mailto:HOU-NHAShpDrwgs@txdot.gov">HOU-NHAShpDrwgs@txdot.gov</a>
Southeast Area Office	<a href="mailto:HOU-SEHAShpDrwgs@txdot.gov">HOU-SEHAShpDrwgs@txdot.gov</a>
Traffic Systems Construction Office	<a href="mailto:HOU-TSCShpDrwgs@txdot.gov">HOU-TSCShpDrwgs@txdot.gov</a>
West/Central Harris Area Office	<a href="mailto:HOU-WWCHAOShpDrwgs@txdot.gov">HOU-WWCHAOShpDrwgs@txdot.gov</a>
B - Houston Bridge Engineer	
Bridge Design (Houston TxDOT)	<a href="mailto:HOU-BrgShpDrwgs@txdot.gov">HOU-BrgShpDrwgs@txdot.gov</a>
BRG - Austin Bridge Division	
Bridge Design (Austin TxDOT)	<a href="mailto:BRG_ShopPlanReview@txdot.gov">BRG_ShopPlanReview@txdot.gov</a>
C - Construction Office	
Construction	<a href="mailto:HOU-ConstrShpDrwgs@txdot.gov">HOU-ConstrShpDrwgs@txdot.gov</a>
Laboratory	<a href="mailto:HOU-LabShpDrwgs@txdot.gov">HOU-LabShpDrwgs@txdot.gov</a>
T - Traffic Engineer	
Traffic Operations	<a href="mailto:HOU-TrfShpDrwgs@txdot.gov">HOU-TrfShpDrwgs@txdot.gov</a>
TMS – Traffic Management System	
Computerized Traffic Management Systems (CTMS)	<a href="mailto:HOU-CTMSShpDrwgs@txdot.gov">HOU-CTMSShpDrwgs@txdot.gov</a>

“When a precast or cast-in-place concrete element is included in the plans, a precast concrete alternate may be submitted in accordance with “Standard Operating Procedure for Alternate Precast Proposal Submission” found online at <https://www.txdot.gov/inside-txdot/forms-publications/consultants-contractors/publications/bridge.html#design>. Acceptance or denial of an alternate is at the sole discretion of the Engineer. Impacts to the project schedule and any additional costs resulting from the use of alternates are the sole responsibility of the Contractor.”

**Item 7: Legal Relations and Responsibilities**

Do not initiate activities in a Project Specific Location (PSL), associated with a U.S. Army Corps of Engineers (USACE) permit area, that have not been previously evaluated by the USACE as part of the permit review of this project. Such activities include those pertaining to, but are not limited to, haul roads, equipment staging areas, borrow and disposal sites. Associated defined here means materials are delivered to or from the PSL. The permit area includes the waters of the U.S. or associated wetlands affected by activities associated with this project. Special restrictions may be required for such work. Assume responsibility for consultations with the USACE regarding activities, including PSLs that have not been previously evaluated by the USACE. Provide the Department with a copy of consultations or approvals from the USACE before initiating activities.



**County:** Montgomery

**Control:** 1986-01-067

**Highway:** FM 1314

The Contractor may proceed with activities in PSLs that do not affect a USACE permit area if a self-determination has been made that the PSL is non-jurisdictional or if proper USACE clearances have been obtained in jurisdictional areas or have been previously evaluated by the USACE as part of the permit review of this project. The Contractor is solely responsible for documenting any determinations that their activities do not affect a USACE permit area. Maintain copies of their determinations for review by the Department or any regulatory agency.

Document and coordinate with the USACE, if required, before hauling any excavation from or hauling any embankment to a USACE permit area by either 1 or 2 below:

**1. Restricted Use of Materials for the Previously Evaluated Permit Areas.**

Document both the Project Specific Locations (PSL) and their authorization. Maintain copies for review by the Department or any regulatory agency. When an area within the project limits has been evaluated by the USACE as part of the permit process for this project:

- a. Suitable excavation of required material in the areas shown on the plans and cross sections as specified in the Item, "Excavation" is used for permanent or temporary fill (under the Item, "Embankment") within a USACE permit area.
- b. Suitable embankment (under the Item, "Embankment") from within the USACE permit area is used as fill within a USACE evaluated area.
- c. Unsuitable excavation or excess excavation, "Waste" (under the Item, "Excavation"), that is disposed of at a location approved within a USACE evaluated area.

**2. Contractor Materials from Areas Other than Previously Evaluated Areas.**

Provide the Department with a copy of USACE coordination or approvals before initiating any activities for an area within the project limits that has not been evaluated by the USACE or for any off right of way locations used for the following, but not limited to, haul roads, equipment staging areas, borrow and disposal sites:

- a. The Item, "Embankment" used for temporary or permanent fill within a USACE permit area.
- b. Unsuitable excavation or excess excavation, "Waste" (under the Item, "Excavation"), that is disposed of outside a USACE evaluated area.

This project does not require a U.S. Army Corps of Engineers (USACE) Section 404 Permit before letting, but if a permit is needed during construction, assume responsibility for preparing the permit application. Submit the permit application to the Department's District Environmental Section for approval. Once the permit application is approved, the Department will submit it to the USACE. Assume responsibility for the requested revisions, in coordination with the Department's District Environmental Section.

Maintain the roadway slope stability. Maintaining slope stability is subsidiary to the various bid items.

County: Montgomery

Control: 1986-01-067

Highway: FM 1314

If the work is on or in the vicinity of an at-grade railroad crossing, involves incidental work on railroad right of way, or involves construction of a railroad grade separation structure, notify the railroad company’s Division Engineer and the Department’s Project Engineer at least 30 days before performing any work on the railroad right of way and make arrangements for railroad flaggers unless otherwise shown in the contract. Obtain the required Railroad Right of Entry Permit from the railroad company. Payment of applicable permit fees is the responsibility of the Contractor. Acquiring the Railroad Right of Entry Permit is a lengthy process, allow sufficient time for this.

No significant traffic generator events have been identified.

**Item 8: Prosecution and Progress**

The Department will not adjust the number of days for the project and milestones, if any, due to differences in opinion regarding any assumptions made in the preparation of the schedule or for errors, omissions, or discrepancies found in the time determination schedule.

Working days will be computed and charged based on a standard workweek in accordance with Section 8.3.3.2.2.

The maximum number of days the time charges on this contract may be suspended due to contractor mobilization, and material fabrication/accumulation or processing delays is 60 days. The Engineer and the Contractor may mutually agree, in writing, to decrease this maximum number of days.

The Lane Closure Assessment Fee is \$ 500.00. This fee applies to the Contractor for closures or obstructions that overlap into restricted hour traffic for each hour or portion thereof, per lane, regardless of the length of lane closure or obstruction. For Restricted Hours subject to Lane Assessment Fee refer to the Item, “Barricades, Signs, and Traffic Handling.” The time increment for the Lane Closure Assessment fee for this project is one hour.

**Item 316: Seal Coat**

The asphalt application rate shown on the “Basis of Estimate” is an average rate for calculating asphalt quantities. Vary the rate based on the pavement conditions and other factors such as the type and grade of aggregate used, weather, and traffic.

Allowable Asphalt Cements based on Average Daily Traffic (ADT) are shown below:

<u>For ADT greater than 5000</u>	<u>ADT 1000 to 5000</u>	<u>ADT less than 1000</u>
AC-20 XP	AC-15P	AC-10-2TR
AC-20-5TR	AC-20-5TR	AC-10 w/2% SBR
	AC-20-XP	AC-15P
	AC-10-2TR	

County: Montgomery

Control: 1986-01-067

Highway: FM 1314

### **Item 354: Planing and Texturing Pavement**

Stockpile the material at The Department's Maintenance yard located at 901 N FM 3083 East, Conroe, TX 77303, as directed by Abraham M. Guzman, P.E. at (936) 538-3300.

### **Item 502: Barricades, Signs, and Traffic Handling**

Use a traffic control plan for handling traffic through the various phases of construction. Follow the phasing sequence unless otherwise agreed upon by the Area Engineer and the Project Manager. Ensure this plan conforms to the latest "Texas Manual on Uniform Traffic Control Devices" and the latest Barricade and Construction (BC) Standard Sheets. The latest versions of Work Zone Standard Sheets WZ (BTS-1) and WZ (BTS-2) are the traffic control plan for the signal installations.

Submit changes to the traffic control plan to the Area Engineer. Provide a layout showing the construction phasing, signs, striping, and signalizations for changes to the original traffic control plan.

Furnish and maintain the barricades and warning signs, including the necessary temporary and portable traffic control devices, during the various phases of construction. Place and construct these barricades and warning signs in accordance with the latest "Texas Manual on Uniform Traffic Control Devices" for typical construction layouts.

Cover work zone signs when work related to the signs is not in progress, or when any hazard related to the signs no longer exists.

Keep the delineation devices, signs, and pavement markings clean. This work is subsidiary to the Item, "Barricades, Signs, and Traffic Handling."

If a section is not complete before the end of the workday, pull back the base material to the existing pavement edge on a 6H: 1V slope. Edge drop-offs during the hours of darkness are not permitted.

Before detouring traffic onto the mainlane shoulders, remove dirt, debris, vegetation, and other deleterious material from the surface of the shoulders. Appropriately sign the detour in an approved manner. This work is subsidiary to the various bid items.

Cover or remove the permanent signs and construction signs that are incorrect or that do not apply to the current situation for a particular phase.

Do not mount signs on drums or barricades, except those listed in the latest Barricades and Construction standard sheets.

Use traffic cones for daytime work only. Replace the cones with plastic drums during nighttime hours.

Place positive barriers to protect drop-off conditions greater than 2 ft. within the clear zone that remain overnight.

County: Montgomery

Control: 1986-01-067

Highway: FM 1314

Do not reduce the existing number of lanes open to traffic except as shown on the following time schedule:

**One Lane Closure**

Day	Daytime Closure Hours	Nighttime Closure Hours	Restricted Hours Subject to Lane Assessment Fee
Monday	9:00 AM – 3:30 PM	9:00 PM – 5:00 AM	5:00 AM – 9:00 AM 3:30 PM – 9:00 PM
Tuesday	9:00 AM – 3:30 PM	9:00 PM – 5:00 AM	5:00 AM – 9:00 AM 3:30 PM – 9:00 PM
Wednesday	9:00 AM – 3:30 PM	9:00 PM – 5:00 AM	5:00 AM – 9:00 AM 3:30 PM – 9:00 PM
Thursday	9:00 AM – 3:30 PM	9:00 PM – 5:00 AM	5:00 AM – 9:00 AM 3:30 PM – 9:00 PM
Friday	9:00 AM – 3:30 PM	9:00 PM – 5:00 AM	5:00 AM – 9:00 AM 3:30 PM – 9:00 PM
Saturday/ Sunday	No Weekend Closures		

The Area Engineer may The above times are approved for the traffic control conditions listed. The Area Engineer may approve other closure times if traffic counts warrant. The Area Engineer may reduce the above times for special events.

Law enforcement assistance will be required for this project and is expected to be required for major traffic control changes and lane closures. Coordinate with local law enforcement and arrange for law enforcement as directed or agreed by the Engineer. Before payment will be made, complete the “Daily Report on Law Enforcement Force Account Work” (Form 318), provided by the Department and submit daily invoices that agree with this form for any day during the month in which approved services were provided.

Provide full-time, off-duty, uniformed, certified peace officers, as part of traffic control operations. The peace officers must be able to show proof of certification by the Texas Commission on Law Enforcement Officers Standards. The cost of the officers is paid for on a force account basis.

A minimum of 7 days in advance of any total closure, notify the Houston District Public Information Office of which roadways, ramps, intersections, or lanes will be closed, the dates they will remain closed, and when they will be opened again to traffic.

A minimum of 7 days in advance of any total closure, place a portable changeable message (PCM) sign at the location of each total closure which informs the traveling public of the details of the closure. Alternately, if the Traffic Control Plan provides a positive barrier at the location, a non-trailer mounted static message board sign behind the positive barrier may be used in place of a PCM.

**County:** Montgomery

**Control:** 1986-01-067

**Highway:** FM 1314

Use Uneven Lane Signs (CW 8-11) during resurfacing operations for elevation differences between adjacent lanes of greater than 1 in.

The Contractor Force Account “Safety Contingency” that has been established for this project is intended to be utilized for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor’s Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

**Item 506: Temporary Erosion, Sedimentation and Environmental Controls**

The use of hay bales is not permitted as Storm Water Pollution Prevention Plan (SWP3) measures.

The Storm Water Pollution Prevention Plan (SWP3) consists of temporary erosion control measures needed and provided for under this Item. The disturbed area is less than one acre and use of erosion control measures is not anticipated. If physical conditions encountered at the job site require necessary controls, BMP installation, maintenance, and removal will be paid as extra work on a force account basis per Articles 4.4 and 9.7. Since the disturbed area is less than 5 acres, a “Notice of Intent” (NOI) is not required.

Use appropriate measures to prevent, minimize, and control the spill of hazardous materials in the construction staging area. Remove and dispose of materials in compliance with State and Federal laws.

Before starting construction, review with the Engineer the SWP3 used for temporary erosion control as outlined on the plans. Before construction, place the temporary erosion and sedimentation control features as shown on the SWP3.

Schedule the seeding or sodding work as soon as possible. The project schedule provides for a vegetation management plan.

Implement temporary and permanent erosion control measures to comply with the National Pollution Discharge Elimination System (NPDES) general permit under the Clean Water Act.

Before starting grading operations and during the project duration, place the temporary or permanent erosion control measures to prevent sediment from leaving the right of way.

**Item 530: Intersections, Driveways, and Turnouts**

An air-entraining admixture is not required.

For concrete curbs, use Grade 7 aggregate conforming to Section 421.2.6 of the Item, “Hydraulic Cement Concrete.”

**County:** Montgomery

**Control:** 1986-01-067

**Highway:** FM 1314

### **Item 585: Ride Quality for Pavement Surfaces**

To eliminate the need for corrective action due to excessive deviations in the final surface layers, exercise caution to ensure satisfactory profile results in the intermediate paving layers (mixture).

Milling will not be allowed as a corrective action for excessive deviations in the final surface layer of hot-mix asphalt.

For concrete or asphalt curb and gutter sections or frontage roads, use Surface Test Type B and Pay Adjustment Schedule 2 except for the outside lane. Use Surface Test Type B and Pay Adjustment Schedule 3 for the outside lane.

### **Item 618: Conduit**

When backfilling bore pits, ensure that the conduit is not damaged during installation or due to settling backfill material. Compact select backfill in 3 equal lifts to the bottom of the conduit; or if using sand, place it 2 in. above the conduit. Ensure backfill density is equal to that of the existing soil. Prevent material from entering the conduit.

Construct bore pits a minimum of 5 ft. from the edge of the base or pavement. Close the bore pit holes overnight.

Unless otherwise shown on the plans, install underground conduit a minimum of 24 in. deep. Install the conduit in accordance with the latest National Electrical Code (NEC) and applicable Department standard sheets. Place conduit under driveways or roadways a minimum of 24 in. below the pavement surface.

If using casing to place bored conduit, the casing is subsidiary to the conduit.

If placing the conduit under existing pavement to reach the service poles, bore the conduit in place and extend it a minimum distance of 5 ft. beyond the edge of shoulder or the back of curb.

### **Item 620: Electrical Conductors**

Test each wire of each cable or conductor after installation. Incomplete circuits or damage to the wire or the cable are cause for immediate rejection of the entire cable being tested. Remove and replace the entire cable at no expense to the Department. Also test the replacement cable after installation.

When pulling cables or conductors through the conduit, do not exceed the manufacturer's recommended pulling tensions. Lubricate the cables or conductors with a lubricant recommended by the cable manufacturer.

For both transformer and shoe-base type illumination poles, provide double-pole breakaway fuse holders as shown on the Department's Construction Division (CST) material producers list. Check the latest link on the Department's website for this list. The category is "Roadway

**County:** Montgomery

**Control:** 1986-01-067

**Highway:** FM 1314

Illumination and Electrical Supplies.” The fuse holder is shown on the list under Items 610 and 620. Provide 10 Amp time delay fuses.

Ensure that circuits test clear of faults, grounds, and open circuits.

Split bolt connectors are allowed only for splices on the grounding conductors.

For Roadside Flashing Beacon Assemblies (Item 685) and Pedestal Pole Assemblies (Item 687) within the project, provide single-pole breakaway disconnects as shown on the Construction Division (CST) material producers list. Check the latest link on the Department’s website for this list. The category is “Roadway Illumination and Electrical Supplies.” The fuse holder is shown on the list under Item 685. For underground (hot) conductors, install a breakaway connector with a dummy fuse (slug). Provide dummy fuse (slug). For grounded (neutral) conductors, install a breakaway connector with a white colored marking and a permanently installed dummy fuse (slug).

For electrical licensing and electrical certification requirements for this project, see Item 7 of the Standard Specifications and any applicable special provisions to Item 7.

#### **Item 624: Ground Boxes**

The ground box locations are approximate. Alternate ground box locations may be used as directed, to avoid placing in sidewalks or driveways.

Ground metal ground box covers. Bond the ground box cover and ground conductors to a ground rod located in the ground box and to the system ground.

Ground the existing metal ground box covers as shown on the latest standard sheet ED (4)-14.

During construction and until project completion, provide personnel and equipment necessary to remove ground box lids for inspection. Provide this assistance within 24 hours of notification.

Construct concrete aprons in accordance with the latest standard sheet ED (4)-14. Make the depth of the concrete apron the same as the depth of the ground box, except for Type 1 and Type 2 ground boxes. For Type 1 or Type 2 ground boxes, construct the concrete apron in accordance with details shown on the “Ground Box Details Installations” standard.

#### **Item 636: Signs**

Include aluminum route markers, exit only panels, routing signs, and other special panels attached to guide signs in the unit bid price for the parent guide sign material.

Furnish and install signs shown on the traffic signal “Summary of Traffic Signal Materials” sheet. Ensure that the legend on these sign panels is in accordance with the latest “Standard Highway Sign Designs for Texas” manual.

**County:** Montgomery

**Control:** 1986-01-067

**Highway:** FM 1314

The locations of sign panels on overhead structures are approximate. Verify in the field before installing.

For design details not shown on the plans, provide signs and arrows conforming to the latest "Standard Highway Sign Designs for Texas" manual.

**Item 644: Small Roadside Sign Assemblies**

Sign locations shown on the plans are approximate. Before placing them, obtain approval of and then stake the exact locations for these signs.

Use the Texas Universal Triangular Slip Base with the concrete foundation for small ground mounted signs, unless otherwise shown in the plans.

Remove existing street name signs from existing stop signs and re-install them above the new stop signs. Removing and re-installing existing street name signs is subsidiary to the Item, "Small Roadside Sign Assemblies."

When design details are not shown on the plans, provide signs and arrows conforming to the latest "Standard Highway Sign Designs for Texas" manual.

Use Type E Super High Specific Intensity (Fluorescent Prismatic) yellow green reflective sheeting background to fabricate school signs (S1-1, S3-1, S4-3, S5-1, W16-2, SW16-9p, and SW16-7pL(R)).

Assume ownership of the removed existing signs.

Locations of the relocated signs are approximate. Before placing them, obtain approval of and then stake the exact locations for these signs.

Replace existing signs that become damaged during relocation at no expense to the Department.

**Item 662: Work Zone Pavement Markings**

At the end of each workday, mark roadways that remain open to traffic during construction operations with standard pavement markings, in accordance with the latest "Texas Manual on Uniform Traffic Control Devices."

Using raised markers for removable work zone pavement markings on final concrete surfaces is optional.

Do not use raised pavement markers as optional work zone pavement markings on final asphalt surfaces.

For transition lane lines and detour lane lines, use raised pavement markers as shown for solid lines on the latest Barricade and Construction standard sheet for "Work Zone Pavement Marking Details."



County: Montgomery

Control: 1986-01-067

Highway: FM 1314

**Item 662: Work Zone Pavement Markings**

**Item 666: Reflectorized Pavement Markings**

**Item 668: Prefabricated Pavement Markings**

Use Type III glass beads for thermoplastic and multipolymer pavement markings.

Use a 0.100 in. (100 mil) thickness for thermoplastic pavement markings, measured to the top of the thermoplastic, not including the exposed glass beads.

Use a 0.022 in. (22 mil) thickness for multipolymer pavement markings, measured to the top of the multipolymer, not including the exposed glass beads.

For roadways with asphalt surfaces to be striped with work zone or permanent thermoplastic markings, the Contractor has the option to apply paint and beads markings for a maximum 30-day period until placing the thermoplastic markings, or until starting the succeeding phase of work on the striped area. Maintain the paint and beads markings, at no expense to the Department, until placing the thermoplastic markings or starting the succeeding phase of work on the striped area. The work zone markings, whether paint and beads or thermoplastic, are paid under the Item, "Work Zone Pavement Markings" and the markings are paid for only once for the given phase of construction.

If using paint and bead markings as described above, purchase the traffic paint from the open market.

If the Type II markings become dirty and require cleaning by washing, brushing, compressed air, or other approved methods before applying the Type I thermoplastic markings, this additional cleaning is subsidiary to the Item, "Reflectorized Pavement Markings."

Establish the alignment and layout for work zone striping and permanent striping.

Stripe all roadways before opening them to traffic.

Place pavement markings under these items in accordance with details shown on the plans, the latest "Texas Manual on Uniform Traffic Control Devices," or as directed.

When design details are not shown on the plans, provide pavement markings for arrows, words, and symbols conforming to the latest "Standard Highway Sign Designs for Texas" manual.

**Item 672: Raised Pavement Markers**

If other operations are complete on the project and if the curing time period is not yet elapsed, the contract time will be suspended until the curing is done.

Before placing the raised pavement markers on concrete pavement, blast clean the surface using an abrasive-blasting medium. This work is subsidiary to the Item, "Raised Pavement Markers."

**County:** Montgomery

**Control:** 1986-01-067

**Highway:** FM 1314

Provide epoxy adhesive that is machine-mixed or nozzle-mixed and dispensed. Equip the machine or nozzle with a mechanism to ensure positive mix measurement control.

**Item 678: Pavement Surface Preparation for Markings**

Do not blast clean asphalt concrete pavement. Clean asphalt concrete pavement as required under the applicable specifications or as directed.

On new concrete pavement or on existing concrete pavement when placing a new stripe on a new location, remove the curing compounds and contamination from the pavement surface by flail milling or as directed. In addition, air-blast the surface with compressed air just before placing the new stripe.

On existing concrete pavement when placing a new stripe on an existing location, after removing the existing stripe under the Item, "Eliminating Existing Pavement Markings and Markers," air-blast the surface with compressed air just before placing the new stripe.

Do not clean concrete pavement by grinding.

**Item 3076: Dense-Graded Hot Mix Asphalt**

Taper the asphalt concrete pavement at the beginning and ending points.

Use a maximum 6H:1V slope for the asphalt concrete pavement edge.

Where the 6H:1V ACP edge taper extends over onto the unsurfaced shoulders, blade off the loose existing shoulder material to provide a solid base for the outside taper edge. After placing the ACP overlay, blade this material back against the edge taper. This work is subsidiary to the various bid items.

The stockpile will be the point of sampling of coarse aggregate for test method TEX-217-F (Part II, decantation).

Place the asphalt concrete pavement in courses as shown on the typical sections.

Do not use petroleum-based solvents in the beds of hot mix asphalt delivery vehicles.

Dilution of tack coat is not allowed.

Do not use Surface Aggregate Classification (SAC) C for this project.

For determining the Asphalt Content, only ignition ovens will be allowed.

The tack coat rate shown on the "Basis of Estimate" is an average rate for calculating tack coat quantities. Vary the rate based on the pavement conditions and other factors such as manufacturer's recommendations and weather.

County: Montgomery

Control: 1986-01-067

Highway: FM 1314

**Item 6185: Truck Mounted Attenuator (TMA) and Trailer Attenuator (TA)**

A shadow vehicle with Truck Mounted Attenuators (TMAs) or Trailer Attenuators (TAs) is required as shown on the appropriate Traffic Control Plan (TCP) sheets. TMAs/TAs must meet the requirements of the Compliant Work Zone Traffic Control Device List.

Level 3 Compliant TMAs/TAs are required for this project.

In addition to the shadow vehicles with TMAs/TAs that are specified as being required on the TCP layout sheets for this project, provide additional shadow vehicles with TMAs/TAs as shown on the TCP Standard sheets. The Contractor is responsible for determining if one or more of these operations will be ongoing at the same time to determine the total number of TMAs/TAs needed on the project.

County: Montgomery

Control: 1986-01-067

Highway: FM 1314

## Basis of Estimate

Item	Description	Limit and Rate	Unit
134	Backfilling Pavement Edges • Asphalt Emulsion	0.25 Gal. / Sq. Yd.	STA
247	Flexible Base • Crushed Stone	138 Lb. / Cu. Ft.	TON
275	Cement Treatment (Road-Mixed) For materials used as subgrade * • Cement	6 % by weight based on 100 Lb. / Cu. Ft. subgrade	SY TON
292	Asphalt Treatment (Plant-Mixed) • Asphalt • Aggregate	110 Lb. / Sq. Yd.-In. 5 % by weight 95 % by weight	TON
310	Prime Coat	0.25 Gal. / Sq. Yd.	GAL
316	Seal Coat • Asphalt • Aggregate (Gr 4) A-R Binder • Asphalt • Aggregate (Gr 4)	0.32 Gal. / Sq. Yd. 1/130 Cu. Yd. / Sq. Yd. 0.42 Gal. / Sq. Yd. 1/130 Cu. Yd. / Sq. Yd.	GAL CY GAL CY
3076	Dense-Graded Hot Mix Asphalt • Asphalt • Aggregate Tack Coat • Applied on new HMA • Applied on Existing HMA • Applied on Milled HMA	110 Lb. / Sq. Yd.-In. 6 % by weight 94 % by weight 0.06 Gal. / Sq. Yd. 0.09 Gal. / Sq. Yd. 0.11 Gal. / Sq. Yd.	TON

\* If used in existing roadway base, rate will be determined on a case by case basis.