

**SPECIAL SPECIFICATION**

**5434**

**Precast Concrete Wheel Stops**

- 1. Description.** Furnish and install concrete wheel stops.
- 2. Materials.** Wheel stops shall be a minimum of 6 ft. long concrete stops unless otherwise shown on the plans or as approved.
  - A.** For hydraulic concrete provide concrete conforming to Item 421, "Hydraulic Cement Concrete". Minimum concrete strength is equal to Class A concrete.
  - B.** For concrete wheel stops provide reinforcing steel conforming to Item 440, "Reinforcing Steel." Minimum reinforcing shall be two No. 4 or three No. 3 bars placed longitudinally.
  - C.** Submit commercially available wheel stop designs for approval.
- 3. Construction.** Anchoring method and anchor rod type shall be as shown on the plans or by approval.
- 4. Measurement.** This Item will be measured as each wheel stop.
- 5. Payment.** The work performed and materials furnished in accordance with this Item and measured as provided under "Measurement" will be paid for at the unit price bid for "Wheel Stops." This price shall be full compensation for furnishing, preparing, hauling and placing all materials, and for all labor, equipment, tools and incidentals.