

## SPECIAL SPECIFICATION

### 5842

#### Remove and Relay Landscape Pavers

**1. Description.** Remove and relay landscape pavers as shown on the plans and details or as directed.

**2. Materials.** Furnish materials that comply with the details shown in the plans, the requirements of this Item, and the pertinent requirements of the following Items:

- Item 528, “Colored Textured Concrete and Landscape Pavers”
- Item 132, “Embankment”
- Item 247, “Flexible Base”
- Item 421, “Hydraulic Cement Concrete”

**3. Construction Methods.** Exercise care when removing existing pavers, making an effort to remove the pavers with minimal damage. Assure that any removed pavers remain in good reusable condition. Dispose of stained or damaged pavers. Palletize reusable pavers and completely wrap the pavers and pallets with plastic to protect during storage. Safeguard the pavers from theft and/or vandalism while the contract is in progress. Deliver excess pavers to TxDOT property as directed.

When relaying pavers, perform work in accordance with the details shown in the plans, the requirements of this Item, and the pertinent requirements of Item 528, “Colored Textured Concrete and Landscape Pavers.”

**4. Measurement.** This Item will be measured by the square yard of paver area removed.

**5. Payment.** The work performed and materials furnished in accordance with this Item and measured as provided under “Measurement” will be paid for at the unit price bid for “Remove and Relay Landscape Pavers.” This price is full compensation for removing and storing pavers; placing and compacting pavers; bedding and joint-filling sand; and equipment, labor, materials, tools, and incidentals. Paver units damaged during compaction must be removed and replaced. Excavation, embankment, and base required for landscape pavers will not be paid for directly but will be subsidiary to this Item.