

SPECIAL SPECIFICATION**5973****Remove and Relay Landscape Pavers**

- 1. Description.** Remove and relay landscape pavers as shown on the plans. Furnish and lay replacement pavers.
- 2. Materials.** Furnish materials that comply with the details shown in the plans, the requirements of this Item, and the pertinent requirements of the following Items:
 - Item 132, “Embankment”
 - Item 247, “Flexible Base”
 - Item 275, “Cement Treatment (Road Mixed)”
 - Item 401, “Flowable Backfill”
 - Item 421, “Hydraulic Cement Concrete”
 - Item 528, “Colored Textured Concrete and Landscape Pavers”

- 3. Construction Methods.** Exercise care when removing existing pavers, making an effort to remove the pavers with minimal damage. Removal by mechanical means is allowed unless otherwise shown on the plans. Assure that any removed pavers remain in good reusable condition. Dispose of stained or damaged pavers. Palletize reusable pavers and completely wrap the pavers and pallets with plastic to protect during storage. Safeguard the pavers from theft and/or vandalism while the contract is in progress. Deliver salvageable excess pavers to a stockpile location on the project unless otherwise shown on the plans. Dispose of unsalvageable pavers in accordance with federal, state and local regulations. Replace any pavers deemed unusable with new materials as necessary and as directed.

When relaying pavers, perform work in accordance with the details shown in the plans, the requirements of this item, and the pertinent requirements of Item 528, “Colored Textured Concrete and Landscape Pavers.” Paver units damaged during compaction must be removed and replaced with pavers of equivalent size, shape and color.

- 4. Measurement.** Removed pavers to be relayed, salvaged, or disposed will be measured by the square yard in their original position. Replacement pavers will be paid for by the square yard measured in the final position of replacement pavers.
- 5. Payment.** The work performed and materials furnished in accordance with this Item and measured as provided under “Measurement” will be paid for in accordance with 5.A, “Remove and Relay Pavers” and 5.B, “Replacement Pavers.”

A. Remove and Relay Pavers. Removing and relaying pavers will be paid for at the unit price for “Remove and Relay Landscape Pavers.” This price is full compensation for removing and storing pavers; placing and compacting salvaged pavers; preparing bedding; bedding and joint-filling sand; stockpiling salvaged pavers; disposing of pavers; and equipment, labor, materials, tools, and incidentals.

B. Replacement Pavers. Furnishing and placement of replacement pavers will be paid for at the unit price bid for “Replacement Pavers.” This price is full compensation for furnishing replacement pavers; placing and compacting pavers; preparing bedding; bedding and joint-filling sand; and equipment, labor, materials, tools, and incidentals.

Unless otherwise shown on the plans, excavation, embankment, and base required for landscape pavers will not be paid for directly but will be subsidiary to this Item.