
Special Provision to Special Specification 6044

Small Roadside Sign Assemblies



Special Specification 6044 "Small Roadside Sign Assemblies," is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

Section 6044.1., "Description," is voided and replaced by the following:

Replace, remove, relocate, or repair small roadside sign assemblies consisting of sign foundation, sign support, signs, mounting hardware, and applicable appurtenances. For the purposes of this contract, a small sign is defined as any sign with less than 17 square feet of sign face area.

Section 6044.3., "Work Methods," The third paragraph is voided and replaced by the following:

Except for emergency call-outs, complete sign replacement within 14 calendar days of the delivery date of materials. Delivery date of material will be determined by material supplier certification of material availability once the material is available for receipt by the Contract. Supply certification to the Engineer within 2 working days upon request.

Except for emergency call-outs, complete sign repairs within 3 calendar days of the date of the work order, complete removal and relocation of signs within 10 calendar days of the date of the work order, and complete removal of signs within 14 calendar days of the date of the work order.

Complete emergency call-outs within 24 hours of notification from the Department. Emergency callouts will include the following types of signs: Stop, Wrong Way, Yield, Do Not Enter, and One Way.

Section 6044.5.1., "Payment," is voided and replaced by the following:

Replace Small Roadside Sign Support & Assemblies. This price is full compensation for removing existing sign, furnishing and installing new sign; equipment; labor, tools, and incidentals, including signs that are on a normal work order or on an emergency work order.

Section 6044.5.4., "Payment," is voided and replaced by the following:

Repair Small Roadside Sign Support & Assemblies. This price is full compensation for removing existing signs and related materials; installing new signs (when required); modifying existing sign supports; reinstallation of signs and sign assemblies; equipment; labor, tools, and incidentals, including signs that are on a normal work order or on an emergency work order.