

---

# Special Provision to Special Specification 6130

## Underground Cable Vault

---



Special Specification 6130 "Underground Cable Vault," is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

**Section 1 "Description"**. The first paragraph is voided and replaced by the following:

Construct, furnish, install, repair, replace, modify and adjust underground cable vault (UCV), complete in place including cable racks, duct terminators, drain, frame and cover.

**Section 4 "Measurement"**. The first paragraph is voided and replaced by the following:

This Item will be measured as each underground cable vault (UCV) fabricated, installed, repaired, replaced, modified or adjusted with frame, cover, duct terminators, and cable rack as shown on the plans.

**Section 5 "Payment"**. The first paragraph is voided and replaced by the following:

The work performed and materials furnished in accordance with this Item and measured as provided under "Measurement" will be paid for at the unit price bid for "UCV" of the various types, construction methods, and installations, UCV, UCV (Periodic Maintenance), UCV (Remove), UCV (Relocate), UCV (Adjust), UCV (Modify), UCV (Replace) of the various types and sizes shown on the plans. This price is full compensation for furnishing and placing all materials; excavating and backfilling; cable racks; maintenance; disposal of unsalvageable material; and all labor, tools, equipment and incidentals.