

---

# Special Provision to Special Specification 6223

## Large Roadside Sign Assemblies

---



Special Specification 6233 "Large Roadside Sign Assemblies," is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

**Article 6223.1., "Description,"** is voided and replaced by the following:

Replace, remove, relocate or repair large roadside sign assemblies consisting of sign support, signs, mounting hardware, and applicable appurtenances. For the purposes of this contract, a large sign is defined as any sign with equal to 17 up to and equal to 64 sq. ft. of sign face area.

**Article 6223.3., "Work Methods,"** The second paragraph is voided and replaced by the following:

Sign replacement must be completed within 14 calendar days of the delivery date of materials. Delivery date of material will be determined by material supplier certification of material availability once the material is available for receipt by the Contract. This certification will be supplied to the Engineer within two working days upon request.

Sign repairs must be completed within three calendar days of the date of the work order, removal and relocation of signs must be complete within 10 calendar days of the date of the work order, and removal of signs must be completed within 14 calendar days of the date of the work order.