

# Special Provision 000

## Important Notice to Contractors



As of March 6, 2017, utilities within the project limits have not been cleared. The Department anticipates clearance by the dates listed below. Unless otherwise stated, clearance of these obstructions will be performed by their owners. Estimated clearance dates are not anticipated to interfere with the Contractor's operations. In the event the clearance dates are not met, requests for additional compensation or time will be made in accordance with the standard specifications.

The Contractor is invited to review the mapped information of obstructions on file with the Engineer.

UTILITY			
Utility Owner	Approximate Location	Estimated Clearance Date	Effect on Construction
City of Marshall	STA 37+60 – Water line and fire Hydrant at 29' offset	TBD – Coordination with the contractor during construction – the proposed fire hydrant will be at proposed grade on the back side of the new wall	The existing fire hydrant will be in conflict with the proposed retaining wall
City of Marshall	Wastewater line STA 41+50	5/31/17	None
Centerpoint Energy	2" Low pressure gas line near STA 39+25. The gas line is in conflict with the proposed sidewalk. CenterPoint will be rerunning the service to the University at a 5' below gutter flowline	5/31/17	None
AEP	Overhead power line the length of the project (STA 35+00 to STA 42+55) on the west side of FM 1997. The line and poles will be in conflict with construction when the slope is laid back to construct the proposed wall. AEP plans to relocate to the East Side of FM 1997	5/31/17	None
Fidelity Cable	Overhead cable located on AEP's poles on TxDOT ROW on the west side of FM 1997 STA 35+00 to STA 42+55. Fidelity will relocate with AEP	5/31/17	None