
Special Provision to Item 6

Control of Materials



Item 6, "Control of Materials" of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

Article 6.10., "Hazardous Materials," is supplemented by the following between Station #581+00 and Station #585+00 for the storm sewer line EF1:

10.5. Soil and Ground Water Management Plan. Comply with the Soil and Groundwater Management Plan (SGMP) document prepared by TRC Environmental Corporation for this Contract as presented with the FM 664 PS&E.

10.6. Site Health and Safety Plan. The work includes potential exposure to soil and groundwater contaminants. Prepare and follow a Site Health and Safety Plan (SHSP) that has been written in accordance with and in fulfillment of Occupational Safety and Health Administration (OSHA) regulations, and all other applicable laws, ordinances and regulations. The Contractor is solely responsible for their SHSP and compliance with its requirements in performing the work. A copy of the SHSP, including any revisions or changes, and any required documentation will be maintained on site and be available for review by the Engineer. Upon request, the SHSP including any revisions or changes and any required documentation will be provided to the Engineer.

Provide training in the SHSP to the Department as needed.

10.7. Measurement and Payment. Cost associated with the SGMP and SHSP will be paid for in accordance with Article 9.7., "Payment for Extra Work and Force Account Method." Expenses to be paid by force account include but are not limited to: Environmental Specialist, soil and groundwater screening, handling, transportation and disposal.