
Special Provision to Item 6 Control of Materials



For this project, Item 6, "Control of Materials" of the Standard Specifications, is hereby amended with respect to the clauses cited below, and no other clauses or requirements of this Item are waived or changed hereby.

Article 6.10., the second paragraph is voided and replaced by the following:

When the plans specify the removal of an existing paint or coating containing lead or other hazardous materials, the Contractor is responsible to perform the work in accordance with Item 446, "Field Cleaning and Painting Steel" and in accordance with Section 6.10.4., "Asbestos Requirements." When an existing coating containing lead or other hazardous materials needs to be removed to perform work when dismantling steel under Item 496, "Removing Structures," the Contractor is responsible for removing the existing coating.

Section 6.10.1.1., is voided and not replaced.

Section 6.10.3., the first paragraph is voided and replaced by the following:

The plans will indicate locations on elements where asbestos containing materials (ACM) are present. The Contractor is responsible to remove and dispose of asbestos containing materials from members to be demolished to satisfy applicable regulations and rules as listed herein. Notify the Engineer of proposed dates of demolition or removal of structural elements with ACM prior to beginning work.

Section 6.10.3.1., is voided and not replaced.

Section 6.10.4., is voided and not replaced.