

---

## Special Provision to Item 6

### Control of Materials

---



Item 6, "Control of Materials" of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

**Article 6.10., "Hazardous Materials,"** is supplemented by the following for replacement of storm sewers, storm sewer connections, and other utilities on Gessner Road.

**10.5. Soil and Ground Water Management Plan.** Comply with the Soil and Groundwater Management Plan (SGMP) document prepared by RSB Environmental, Inc. for this Contract as presented with the Gessner Road PS&E.

- SGMP Zone A - 1038 Gessner Road - between Stations 8+00 to Station 10+00.
- SGMP Zone B - 1066 Gessner Road - between Stations 12+00 and Station 14+00 and additional 80 ft. east towards Station 15+00.

**10.6. Site Health and Safety Plan.** The work includes potential exposure to soil and groundwater contaminants. Prepare and follow a Site Health and Safety Plan (SHSP) that has been written in accordance with and in fulfillment of Occupational Safety and Health Administration (OSHA) regulations, and all other applicable laws, ordinances and regulations. The Contractor is solely responsible for their SHSP and compliance with its requirements in performing the work. A copy of the SHSP, including any revisions or changes, and any required documentation will be maintained on site and be available for review by the Engineer. Upon request, the SHSP including any revisions or changes and any required documentation will be provided to the Engineer.

Provide training in the SHSP to the Department as needed.