

---

## Special Provision to Item 6

### Control of Materials

---



Item 6, "Control of Materials" of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

**Article 6.10., "Hazardous Materials,"** is supplemented by the following for replacement of storm sewers, storm sewer connections, and other utilities on Memorial Drive:

- SGMP Zone A - 12699 Memorial Drive - between Station 28+22.5 and Station 39+09.5
- SGMP Zone B - 12860 Memorial Drive - between Station 1+95.3 and Station 3+63.7

**10.5. Soil and Ground Water Management Plan.** Comply with the Soil and Groundwater Management Plan (SGMP) document prepared by the Environmental Consultant for this Contract as presented with the Memorial Drive PS&E.

**10.6. Site Health and Safety Plan.** The work includes potential exposure to soil and groundwater contaminants. Prepare and follow a Site Health and Safety Plan (SHSP) that has been written in accordance with and in fulfillment of OSHA regulations, and all other applicable laws, ordinances, and regulations. The Contractor is responsible for their SHSP and compliance with its requirements in performing the work. Maintain a copy of the SHSP, including any revisions or changes, and any required documentation, on site and available for review by the Engineer. Upon request, provide the SHSP, including any revisions or changes and any required documentation, to the Engineer.

Provide training in the SHSP to the Department as needed.

**10.7. Measurement and Payment.** Cost associated with the SGMP and SHSP will be paid for in accordance with Article 9.7., "Payment for Extra Work and Force Account Method." Expenses to be paid by force account include but are not limited to: Environmental Specialist, soil and groundwater screening, handling, transportation, and disposal.