
Special Provision to Item 6

Control of Materials



Item 6, "Control of Materials" of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

Article 6.10., "Hazardous Materials," is supplemented by the following between Station #23+50 and Station #17+00 for the bridge columns, retaining wall foundations, and any excavations into the native soils.

Section 10.5. Soil and Ground Water Management Plan. Comply with the Soil and Groundwater Management Plan (SGMP) document, prepared by LCA Environmental, Inc. for this Contract, as presented with the US 75 at Northaven Trail Phase 1B PS&E.

Section 10.6. Site Health and Safety Plan. The work includes potential exposure to soil and groundwater contaminants. Prepare and follow a Site Health and Safety Plan (SHSP) that has been written in accordance with and in fulfillment of Occupational Safety and Health Administration (OSHA) regulations, and all other applicable laws, ordinances and regulations. Contractor is solely responsible for their SHSP and compliance with its requirements in performing the work. A copy of the SHSP, including any revisions or changes, and any required documentation will be maintained on site and be available for review by the Engineer. Upon request, the SHSP including any revisions or changes and any required documentation must be provided to the Engineer.

Provide training in the SHSP to the Department as needed.

Section 10.7. Measurement and Payment. Cost associated with the SGMP and SHSP will be paid for in accordance with Item 9, Article 7., "Payment for Extra Work and Force Account Method." Expenses to be paid by force account include but are not limited to Environmental Specialist, soil and groundwater screening, handling, transportation, and disposal.