
Special Provision to Item 543

Cable Barrier System



Item 543, "Cable Barrier System" of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

Article 1., "Description" is supplemented by the following:

Remove a cable barrier system and cable barrier terminal sections at the locations shown on the plans.

Article 3., "Construction" The first paragraph is supplemented by the following:

Remove cable barrier system in accordance with the details, dimensions, and requirements shown on the plans and manufacturer's recommendations. Remove cable barrier terminal sections in accordance with the details shown on the plans and manufacturer's recommendations.

Article 4., "Measurement" is amended as follows:

This Item will be measured by the foot of cable barrier system installed or removed and by each cable barrier terminal section installed or removed.

Article 5., "Payment" is supplemented by the following:

The work performed and the materials furnished in accordance with this Item and measured as provided under "Measurement" will be paid for at the unit price bid for "Remove Cable Barrier System," and "Remove Cable Barrier Terminal Section." This price is full compensation for removing cable barrier, removing cable barrier terminal sections, removing concrete, backfill materials, backfilling postholes, hauling, disposal, equipment, labor, tools and incidentals.