
Special Provision to Item 543

Cable Barrier System



Item 543, "Cable Barrier System" of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

Article 543.1., "Description," is supplemented by the following:

Remove a cable barrier system and cable barrier terminal sections at the locations shown on the plans.

Article 543.2., "Materials," is supplemented by the following:

Unless otherwise directed by the Engineer, the cable barrier system and cable barrier terminal sections are to be constructed using salvaged materials removed within the project. All unsalvageable materials and incidentals needed to construct the cable barrier system in accordance with the plans and manufacturer's recommendations are to be furnished by the Contractor.

Article 543.3., "Construction". The first paragraph is supplemented by the following:

Remove cable barrier system in accordance with the details, dimensions, and requirements shown on the plans and manufacturer's recommendations. Remove cable barrier terminal sections in accordance with the details shown on the plans and manufacturer's recommendations. Salvage cable, posts, terminal sections and hardware to be retained by the department or re-used on this project. Concrete foundations and steel post inserts will be unsalvageable material. Do not mar or damage salvageable materials during removal.

Completely remove posts and any concrete surrounding the posts. Furnish backfill material and backfill the hole with the material equal in composition and density to the surrounding soil unless otherwise directed.

Neatly stack salvaged materials to be retained by the Department at designated sites specified by the Engineer. Properly dispose of unsalvageable materials in accordance with federal, state, and local regulations. Repair or replace Contractor-damaged salvageable material at the Contractor's expense.

Article 543.4., "Measurement," is replaced by the following:

This Item will be measured by the foot of cable barrier system installed or removed and by each cable barrier terminal section installed or removed.

Article 543.5., "Payment," is replaced by the following:

The work performed and the materials furnished in accordance with this Item and measured as provided under "Measurement" will be paid for at the unit price bid for "Cable Barrier System" of the test level specified (TL-3, TL-4, etc.), "Cable Barrier System" of the test level specified (TL-3, TL-4, etc.) and post spacing specified, "Cable Barrier Terminal Section" of the test level specified (TL-3, TL-4, etc.), "Install Salvaged Cable Barrier", and "Install Salvaged Cable Barrier Terminal Section". This price is full compensation for placing salvaged material, furnishing unsalvageable parts for re-used cable barrier system, cable barrier terminal section, concrete, delineators, equipment, labor, tools, and incidentals.

The work performed and the materials furnished in accordance with this Item and measured as provided under "Measurement" will be paid for at the unit price bid for "Remove Cable Barrier System", and "Remove Cable Barrier Terminal Section". This price is full compensation for removing cable barrier, removing cable barrier terminal sections, removing concrete, backfill materials, backfilling postholes, hauling, disposal, stockpiled material, equipment, labor, tools and incidentals.

Delineators will not be measured or paid for directly but will be considered subsidiary to this Item.