
Special Provision to Item 680

Highway Traffic Signals



Item 680, "Highway Traffic Signals" of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

Article 680.2., "Materials." The third, fourth, fifth, sixth and seventh paragraphs are voided and not replaced.

Section 680.3.1.1.2., "Conduit." The fourth sentence of the first paragraph is voided and replaced by the following:

Seal the ends of each conduit with approved sealant, after all cables and conductors are installed.

Article 680.5., "Payment." The first paragraph is voided and replaced by the following:

The work performed and materials furnished (with the exception of the traffic signal controller and cabinet) in accordance with this Item and measured as provided under "Measurement" will be paid for at the unit price bid for "Highway Traffic Signals (Department Supplied Controller and Cabinet)" of the type (isolated, system, flashing) specified, or "Removing Traffic Signals."

Section 680.5.1., "Installation." The first paragraph is voided and replaced by the following:

This price is full compensation for furnishing, installing and testing the completed installation, controller foundations, luminaires, signs mounted on signal equipment, damping plates, timber poles, mounting hardware and steel strand; preservation and replacement of damaged sod, shrubbery and trees; removal and replacement of curbs and walks; and materials, equipment, labor, tools, and incidentals. The Department will pay for electrical energy consumed by the traffic signal.