

---

# Special Provision to Item 764

## Pump Stations and Drainage System Cleaning

---



Item 764, "Pump Station and Drainage System Cleaning" of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

**Article 764.1., "Description,"** is voided and replaced by the following:

Perform manual cleaning, hydraulic cleaning, vacuum removal and disposal of debris in drain inlets, pump station wells, basket and inlet pipes, downspouts, sumps, storm sewers and slotted drains. Debris is defined as dirt and other material not part of the drainage system.

**Article 764.3., "Equipment,"** the following paragraph is added at the beginning of this article:

Provide equipment necessary to remove hardened asphalt concrete pavement debris within the drainage system.

**Article 764.4., "Work Methods,"** the following section is added:

764.4.8.           **Drain Inlet (Asphalt Removal).** Remove hardened asphalt concrete pavement debris inside and around the drain inlet.

**Article 764.5., "Measurement,"** the following section is added:

764.5.8.           **Drain Inlet (Asphalt Removal).** By each drain inlet cleaned, as required.

**Article 764.6., "Payment,"** is voided and replaced by the following:

**Payment.** The work performed and materials furnished in accordance with this Item and measured as provided under "Measurement" will be paid for at the unit bid price for "Drain Inlet Cleaning," "Pump Station Well Cleaning," "Basket and Inlet Pipe Cleaning," "Downspout Cleaning," "Sump Cleaning," "Storm Sewer Cleaning," of the type and size specified, "Slotted Drain Cleaning" and "Drain Inlet (Asphalt Removal)." This price is full compensation for cleaning, removing and disposing of debris and wash water, equipment, labor, materials, tools and incidentals.