

Special Specification 1009

Monument Sign and Decorative Rock



1. DESCRIPTION

Remove and relocate existing Monument Sign(s) and Decorative Rock at locations shown on the plans. The workmanship will be as prescribed by these specifications, in conformity with the details shown on the plans or as directed.

2. MATERIALS

After removal of the existing Monument Sign(s) and Decorative Rock has been completed any material deemed not useable for the relocated Monument Sign(s) and Decorative Rock will be replaced with new Monument Sign(s) and Decorative Rock material of the same design and quality as the existing Monument Sign(s) and Decorative Rock. If the Contractor chooses to install new Monument Sign(s) and Decorative Rock, it must be constructed of the same type of material and configuration as the existing Monument Sign(s) and Decorative Rock. A combination of new and existing materials may be used, but only as approved.

3. CONSTRUCTION METHODS

The permanent Monument Sign(s) and Decorative Rock must be equal to or better than the existing Monument Sign(s) and Decorative Rock.

The location of the Monument Sign(s) and Decorative Rock will be as shown on the plans. Removed existing Monument Sign(s) and Decorative Rock will be stored at a designated location until such time as the Monument Sign(s) and Decorative Rock are relocated to the new location.

4. MEASUREMENT

This Item will be measured by one or more of the following methods:

"Removal of Monument Sign and Decorative Rock" will be measured as Lump Sum for the work completed.

"Relocation of Monument Sign and Decorative Rock" will be measured as Lump Sum for the work completed.

5. PAYMENT

The work performed and materials furnished in accordance with this Item and measured as provided under "Measurement" will be paid for by a lump sum for one or more of the following items:

"Removal of Monument Sign and Decorative Rock." This price is full compensation for removing the Monument Sign(s) and Decorative Rock, for furnishing all additional materials that may be required to complete the work which includes but is not limited to: all labor, tools, equipment, excavation, backfilling, disposal of surplus materials and incidentals.

"Relocation of Monument Sign and Decorative Rock." This price is full compensation for relocating the Monument Sign(s) and Decorative Rock, furnishing and installing all materials, for furnishing all additional materials that may be required to complete the work which includes but is not limited to: paint, concrete border, all labor, tools, equipment, excavation, backfilling, disposal of surplus materials and incidentals.