
Special Specification 5008

Precast Concrete Wheel Stops



1. DESCRIPTION

Furnish and install precast concrete wheel stops.

2. MATERIALS

Provide 6 ft. length minimum wheel stops unless otherwise shown on the plans or as approved.

Hydraulic Concrete. Use Class A concrete conforming to Item 421, "Hydraulic Cement Concrete."

Reinforcing Steel. Use reinforcing steel conforming to Item 440, "Reinforcement for Concrete." Minimum reinforcing is two No. 4 or No. 3 bars placed longitudinally.

Precast. Submit commercially available wheel stop designs for approval.

3. CONSTRUCTION

Use an anchoring method and anchor rod type as shown on the plans or as approved.

4. MEASUREMENT

This Item will be measured by each wheel stop.

5. PAYMENT

The work performed and materials furnished in accordance with this Item and measured as provided under "Measurement" will be paid for at the unit price bid for "Precast Concrete Wheel Stops." This price is full compensation for furnishing, preparing, hauling and placing materials, and for labor, tools, equipment, and incidentals.