

# Special Specification 5025

## Relocate Bus Stop Shelters



### 1. DESCRIPTION

Furnish all materials, equipment, labor and incidentals necessary for the relocation of the two existing bus stop shelters as shown on the plans.

### 2. MATERIALS

Furnish materials in accordance with the following:

- Item 400, "Excavation and Backfill for Structures,"
- Item 420, "Concrete Substructures,"
- Item 421, "Hydraulic Cement Concrete,"
- Item 427, "Surface Finishes for Concrete,"
- Item 440, "Reinforcement for Concrete," and
- Item 449, "Anchor Bolts."

2.1. **Concrete.** Furnish Class A concrete as referenced in Item 421 "Hydraulic Cement Concrete."

2.2. **Other Materials.** Use commercial-type hardware as approved.

### 3. CONSTRUCTION

3.1. **General.** Move and reset the two existing bus stop shelters to the locations shown in the plans or as directed.

3.2. **Removal.** Unbolt the anchor bolts and remove the shelters. Store in a secure location if necessary.

3.3. **Transport.** Move the shelters to the locations designated in the plans. Repair any damage and replace any lost parts.

3.4. **Foundation.** Install new concrete foundations and new anchor bolts as detailed on the plans.

3.5. **Install.** Place shelter on foundation and bolt down to new anchor bolts.

### 4. MEASUREMENT

This item will be measured each bus stop shelter relocate.

### 5. PAYMENT

The work performed and materials furnished in accordance with this Item and measured as provided under "Measurement" will be paid for at the unit price bid for "Relocate Bus Stop Shelters." This price is full compensation for furnishing all materials, equipment, labor, and incidentals necessary to complete the work specified, including: removing the two shelters from their foundations, storage, transporting the two shelters to their new locations, foundations, anchor bolts, replacing damaged or lost parts, and installing the shelters on the foundations.