

---

# Special Specification 5027

## Temporary Construction Matting

---



---

### 1. DESCRIPTION

Furnish all necessary labor, equipment, materials and perform all operations necessary for installation of the temporary construction matting in accordance with the details shown on the plans and with the requirements of this specification.

---

### 2. MATERIALS

Provide timber construction materials meeting contractors equipment needs.

---

### 3. CONSTRUCTION

Provide the Engineer with the temporary construction matting details for approval.

Because construction equipment, temporary fills, and gear can retain water or debris, follow clean, drain, and dry procedures for all construction equipment and gear that comes in contact with public waters prior to being used on another site to prevent unintentional spread of aquatic invasive species. All equipment coming into contact with waters must follow Texas Parks and Wildlife Department clean/drain/dry protocol procedures every time equipment and gear leave a waterbody.

Install temporary construction matting on existing ground surface, taking care to minimize soil disturbance.

---

### 4. MEASUREMENT

This Item will be measured by the square yard.

---

### 5. PAYMENT

The work performed and materials furnished in accordance with this Item and measured as provided under "Measurement" will be paid for at the unit price bid for "Temporary Construction Matting." This price shall be full compensation for installing, relocating, removing and all materials, tools, equipment, labor and incidentals necessary to complete the work, including adjustments as needed during operation.