
Special Specification 5045

Map Pedestal



1. DESCRIPTION

This Item will govern for the construction and installation of the map pedestals which will be located in accordance with the plans.

2. MATERIALS

The stone for the pedestals must be Texas Limestone. All drilling, cutting, sawing, grinding, and finishing shall be performed by the stone supplier. The stone must be ready for the contractor to install on the jobsite. The supplier shall patch drill holes as needed.

Concrete must be in accordance with Item 421, "Portland Cement Concrete." Reinforcing steel must be in accordance with Item 440, "Reinforcing Steel." Epoxy must be in accordance with Item 5295, "Epoxy and Adhesives." Concrete grout must be in accordance with Item 4088, "Flowable Backfill."

3. INSTALLATION

Install the map pedestals in strict accordance with the plans and as noted within the General Notes and Specifications.

4. MEASUREMENT

This Item, satisfactorily completed, installed and placed in accordance with the plans and this specification, will be measured by "each" Map Pedestal.

5. PAYMENT

The work performed and materials furnished in accordance with this Item and measured as provided under "Measurement" shall be paid for at the unit price bid for each "Map Pedestal", as specified, complete and in place. This price will be full compensation for furnishing all materials, labor and incidentals necessary to complete the work as shown on the plans. The signs will be paid for under Item 6204, "High Pressure Laminate Trail Map Signs."