
Special Specification 5105

Precast Concrete Fence Installation



1. DESCRIPTION

Install precast concrete fence at locations as shown on the plans.

2. MATERIALS

Precast fence materials of posts and panels to be provided by others as shown on the plans.

3. CONSTRUCTION

Install precast fence per engineered shop drawings to be provided by others as shown on the plans. Manufacturer's shop drawings will include specific details on drilled shaft foundations, mow strip, and special curb. Place materials in accordance with manufacturer's recommendations.

4. MEASUREMENT

This Item will be measured by the foot of precast concrete fence installed, measured along the centerline of the fence from center to center of the end posts.

5. PAYMENT

The work performed in accordance with this Item and measured as provided under "Measurement" will be paid for at the unit price bid for "Precast Fence Installation". The price will be full compensation for hauling, placing materials, equipment, tools, labor, and incidentals. Posts and panels damaged during loading, transport, or installation will be replaced at the Contractor's expense. Drilled shaft foundations, Concrete Curb Special, and Riprap Mow Strip will be measured and paid for in accordance with the pertinent bid items as shown in the plans.