

Special Specification 6039

Overhead Signs



1. DESCRIPTION

Remove and relocate existing overhead sign from current location on overhead sign supports to new or existing overhead sign supports.

2. MATERIALS

Repair damage caused by relocation process to the requirements of this Item, and the pertinent requirements of the following Items:

- Item 445, "Galvanizing"

Reuse undamaged components when relocating an existing overhead sign. If such components are damaged during relocation or if additional components are required, furnish galvanized steel, non-corroding stainless steel, or dichromate-sealed aluminum brackets, clamps, bolts, and other hardware, in accordance with DMS-7120, "Sign Hardware."

3. CONSTRUCTION

- 3.1. **Relocation.** Remove existing overhead sign and relocate to new or existing overhead sign support as shown on the plans. Repair or replace damaged components as directed. Reuse existing components, unless otherwise directed. Accept ownership of unsalvageable materials and dispose of in accordance with federal, state, and local regulations.
- 3.2. **Handling and Storage.** Handle and store existing signs or portions of signs removed so that they are not damaged. Store all signs off the ground and in a vertical position until erected. Prevent any damage to the various sign assembly components. Replace any portion of the sign damaged by the Contractor designated for reuse or salvage, including messages removed. Stockpile all removed sign components that will be reused or that become the property of the Department at designated locations. Accept ownership of unsalvageable materials and dispose of them in accordance with federal, state, and local regulations.
- 3.3. **Cleaning.** After the sign has been installed, wash the entire sign with a biodegradable cleaning solution to remove dirt, grease, oil smears, streaks, finger marks, and other foreign materials. Biodegradable cleaning solution will be acceptable to the sheeting and screen ink manufacturers.
- 3.4. **Inspection.** Signs will be inspected for damage after relocation and installation by both daylight and night visual inspection. Damage to the sign face that is not visible when viewed at a distance of 50 ft. will be acceptable. Replace unacceptable signs.

4. MEASUREMENT

This Item will be measured as each overhead sign relocated.

5. PAYMENT

The work performed and materials furnished in accordance with this Item and measured as provided under "Measurement" will be paid for at the unit price bid for "Relocate Existing Overhead Signs".

This price is full compensation for removing overhead signs; storing the components to be reused or salvaged; disposal of unsalvageable material; reinstalling existing overhead sign on new or existing overhead sign supports; loading and hauling; and equipment, materials, labor, tools, and incidentals.