
Special Specification 6049

Longitudinal Channelizing Mountable Curb System



1. DESCRIPTION

Furnish and install, relocate, or remove longitudinal channelizing mountable curb systems, which includes curb sections and curb system delineator posts.

2. MATERIALS

Provide new longitudinal channelizing mountable curb systems manufactured by one of the approved vendors from the Department's MPL.

Provide longitudinal channelizing mountable curb systems the color as detailed in the plans.

After delivery, a construction site inspection of the longitudinal channelizing curb system and equipment will be made by the Engineer.

If any section of the longitudinal channelizing mountable curb system has been damaged or if, for any reason, the component does not comply with the requirements herein, the Contractor shall repair or replace the longitudinal channelizing mountable curb system at their expense.

Once approved by the Engineer, the longitudinal channelizing mountable curb system shall be installed.

3. CONSTRUCTION

- 3.1. **Install.** Install the longitudinal channelizing mountable curb system in the location as shown on the plans. Follow manufacturer's installation procedures regarding anchoring systems into the various types of roadway surfaces. Only use anchors and hardware provided by the manufacturer. Remove any conflicting pavement markings and raised pavement markers in the locations where the longitudinal channelizing mountable curb system is to be installed.
- 3.2. **Relocate.** Relocate longitudinal channelizing mountable curb system in accordance with the details shown on the plans.
- 3.3. **Removal.** Remove existing longitudinal channelizing mountable curb system as shown on the plans. Deliver the curb system and installation hardware such as mounting anchors to the Department at designated location.

4. MEASUREMENT

Longitudinal channelizing mountable curb systems installed, relocated or removed will be measured by the linear foot of curb system.

5. PAYMENT

The work performed and materials furnished in accordance with this Item and measured as provided under "Measurement" will be paid for at the unit bid price for "Longitudinal Channelizing Mountable Curb System" of the work category (Install, Relocate, or Remove). This price is full compensation for all equipment, labor, tools, materials, and incidentals.

- 5.1. **Furnish and Install.** This price is full compensation for furnishing and installing curb system.
- 5.2. **Relocate.** This price is full compensation for moving the curb system installations on the project from one location to another (including disassembly and reassembly costs).
- 5.3. **Remove.** This price is full compensation for removing curb system and installation hardware from the project and delivering to the Department stockpile as shown on the plans or as directed by the Engineer.