

Special Specification 6053

Shifting or Removing Existing Overhead Signs



1. DESCRIPTION

Shift or remove existing overhead sign panels.

2. MATERIALS

Reuse existing sign panel materials as shown on the plans. When required, provide new materials that comply with the details shown on the plans, the requirements of this Item, and the pertinent requirements of the following:

- Item 636, "Signs"
- Item 654, "Sign Walkways"

3. CONSTRUCTION

Shift or remove signs on structures as shown on the plans or as directed. Remove and store shifted signs as necessary. Prevent damage to sign components. Reuse existing attachment hardware as directed. Cut sign support brackets, if necessary; however, do not extend or lengthen existing brackets. Furnish additional sign attachment hardware, support brackets, etc., as directed. Adjust or add support brackets and appurtenances such as sign lights, walkways, conduit, etc., as shown on the plans.

Handle and store signs to prevent damage to sign corners, edges, and faces. Store signs off the ground and in a vertical position. Store signs 60 in. × 60 in. or smaller in a weatherproof building. Larger signs may be stored outside. Damage to the sign face that is not visible when viewed at a distance of 50 ft., night or day, will be acceptable. Replace unacceptable signs and components.

Stockpile removed sign components for reuse or that become property of the Department at a designated locations. Accept ownership of unsalvageable materials and dispose of in accordance with federal, state, and local regulations.

After installation, wash signs with a biodegradable cleaning solution acceptable to the manufacturers of the sheeting, colored transparent film, and screen ink to remove grease, oil, dirt, smears, streaks, finger marks, and other foreign material.

4. MEASUREMENT

This Item will be measured by each sign panel shifted or removed.

5. PAYMENT

The work performed and materials furnished as accordance with this Item and measured as provided under "Measurement" will be paid for at the unit price bid for "Shift Overhead Sign Panels" or "Remove Overhead Sign Panels." This price is full compensation for shifting, reinstalling, or removing the existing sign panels; furnishing and installing new mounting hardware; furnishing and installing new sign panels, when required; cleaning sign panels; storing of components to be reused or salvaged; disposal of unsalvageable material; and equipment, labor, tools, and incidentals.