

---

# Special Specification 6065

## Large Ground Mounted Signs

---



---

### 1. DESCRIPTION

Collect, transport and install ground mounted sign panels furnished by the Department. Sign supports are provided for under other items.

---

### 2. MATERIALS

Install sign panel materials supplied by the department as shown on the plans or as directed. When required, provide new materials that comply with the details shown on the plans, the requirements of this Item, and the pertinent requirements of the following:

- Item 636, "Aluminum Signs"
- Item 647, "Large Roadside Sign Supports and Assemblies"

---

### 3. CONSTRUCTION

Remove existing signs on sign supports as shown on the plans or as directed. Remove and store existing signs as necessary. Collect, transport and install new signs furnished by the Department. Prevent damage to sign components. Damage to the new sign face that is visible when viewed at a distance of 50 ft. or more, night or day, will be unacceptable. Replace unacceptable signs and components. Reuse existing attachment hardware as directed. Furnish additional sign attachment hardware when required or as directed. Adjust existing sign supports as shown on the plans or as directed.

Handle and store removed signs to prevent damage to sign corners, edges, and faces. Store signs off the ground and in a vertical position. Return removed sign components for recycling to the Department at the district grounds. Accept ownership of unsalvageable or excess materials and dispose of in accordance with federal, state, and local regulations.

After installation, wash signs with a biodegradable cleaning solution acceptable to the manufacturers of the sheeting, colored transparent film, and screen ink to remove grease, oil, dirt, smears, streaks, finger marks, and other foreign material.

---

### 4. MEASUREMENT

This Item will be measured by square foot of new sign panel installed.

---

### 5. PAYMENT

The work performed and materials furnished in accordance with this Item and measured as provided under "Measurement" will be paid for at the unit price bid for "Install State Supplied Ground Mounted Sign Panels." This price is full compensation for replacing large ground mounted sign panels on existing sign supports; installing large ground mounted signs at new locations; furnishing and installing new mounting hardware; cleaning sign panels; storing of components to be reused or salvaged; disposal of unsalvageable material; and equipment, labor, tools, and incidentals. The adjustment of existing sign supports is subsidiary to this bid item.