
Special Specification 6115

Rumble Strips



1. DESCRIPTION

This Item will govern for furnishing all labor, tools, equipment and services necessary to construct or install rumble strips of the type specified, on Portland-Cement-Concrete Trails, complete in place in conformity with the details shown on the plans and as described.

2. CONSTRUCTION METHODS

The rumble strips must be constructed according to the configuration shown on the plans and installed at the locations as indicated on the plans or as directed by the Engineer. Use either a template, a straightedge or other means subject to the approval of the Engineer to provide the proper alignment and configuration of the completed rumble strips.

3. MEASUREMENT

This Item will be measured by unit of each rumble strip location, complete in place.

4. PAYMENT

The work performed under this Item and measured as provided under "Measurement" will be paid for at the unit price bid for "Rumble Strips." This price will be full compensation for all labor, tools, equipment, and incidentals necessary to complete the work.