
Special Specification 6253

Drum Sign Assembly Removal



1. DESCRIPTION

Remove Rotating Drum Sign Assembly.

2. CONSTRUCTION

- 2.1. **Removal.** Disconnect and isolate existing electrical power supplies prior to removal of the assembly. Remove existing sign panel, beacons, pole, and base from existing assembly. Store items to be reused or salvaged without damaging. Store sign panels above the ground in a vertical position at locations shown on the plans or as directed. Accept ownership of unsalvageable materials and dispose of in accordance with federal, state, and local regulations.

Disconnect and remove conductors from abandoned circuits. Remove abandoned conduit and ducts to a point 6 in. below final grade. Destroy existing transformer bases to prevent reuse.

Unless otherwise shown on the plans, remove abandoned foundations, battery ground box and drill shafts, including steel, to 2 ft. below the finished grade. Backfill with material equal in composition and density to the surrounding area, and replace any surfacing, such as asphalt pavement or concrete riprap, with like material to equivalent condition.

3. MEASUREMENT

The item will be measured by each "Rotating Drum Sign Assembly" removed in accordance with these Special Specifications or as directed by the Engineer.

4. PAYMENT

The work performed and materials furnished as prescribed by this Item, and measured as provided under "Measurement", will be paid for at the unit price bid for "Remove Rotating Drum Sign Assembly".

This price is full compensation for removing the various drum sign assembly components; removing the foundations; storing the components to be reused or salvaged; disposal of unsalvageable material; backfilling and surface placement; loading and hauling; and equipment, materials, tools, labor, and incidentals.