

Special Specification 6292

Radar Vehicle Detection System for Signalized Intersection Control



1. DESCRIPTION

Furnish, install, relocate, or remove radar vehicle detection systems (RVDS) of the specified devices at signalized intersections to provide the required zones of detection as shown on the plans, or as directed.

2. MATERIALS

- 2.1. **General.** Except as allowed for relocation of RVDS equipment, ensure all equipment and component parts are new in accordance with Section 1.0 through Section 6.0 of Division Specification [TO-8000](#), "Radar Vehicle Detection System." and in an operable condition at time of delivery and installation.

The Traffic Management Section of the Traffic Operations Division (TRF-TM) maintains the Prequalified Products Master List (QPL) of all RVDS conforming to the requirements of this Specification. New materials appearing on the [QPL for TO-8000](#) require no further sampling and testing before use unless deemed necessary by the Project Engineer or TRF-TM. Provide prequalified RVDSs from the Division's QPL.

Ensure all RVDS serving the same detection purpose within the project are from the same manufacturer. RVDS devices are classified by their functional requirements. The functional requirements are for radar presence detection devices (RPDD) and radar advance detection devices (RADD). The RVDS system classifications are RVDS (RPDD Only), RVDS (RADD Only)" and "RVDS (RPDD and RADD).

Provide each RVDS sensor with a mounting bracket designed to mount directly to a pole, mast-arm, or other structure. Ensure bracket is designed such that the sensor can be tilted both vertically and horizontally for alignment and then locked into place after proper alignment is achieved. All hardware must be designed to support the load of the RVDS sensor and mounting bracket.

- 2.2. **Configuration.** Ensure the RVDS will provide vehicle detection as required on the plans, or as directed.

Ensure the RVDS does not require tuning or recalibration to maintain performance once initial calibration and configuration is complete. RVDS must not require cleaning or adjustment to maintain performance.

RVDS must self-recover from power failure once power is restored.

- 2.3. **Cabling.** Provide appropriate length of all cables necessary to complete the work (of making the RVDS fully operational) at each installation site.

- 2.4. **Software.** Ensure the RVDS manufacturer includes all software required to configure and monitor operation of RVDS field equipment locally and remotely. RVDS software must be a stable production release.

Software must allow the user to configure, operate, exercise, diagnose, and read current status of all RVDS features and functions using a laptop computer.

Software must include the ability to save a local copy of RVDS field device configurations, and load saved configurations to RVDS field devices.

Ensure all licenses required for operation and use of software are included at no additional cost.

Software updates must be provided at no additional cost during the warranty period.

- 2.5. **Electrical.** All conductors supplying the equipment must meet National Electrical Code® (NEC) requirements.

Ensure equipment is designed to protect personnel from exposure to high voltage during installation, operation, and maintenance.

- 2.6. **Mechanical.** Ensure that all parts are fabricated from corrosion resistant materials, such as plastic, stainless steel, aluminum, or brass.

Ensure that all screws, nuts, and locking washers are corrosion resistant. Do not use self-tapping screws.

Ensure equipment is clearly and permanently marked with manufacturer name or trademark, part number, date of manufacture, and serial number.

Ensure RVDS is modular in design for ease of field replacement and maintenance. Provide a sensor that will minimize weight and wind loading when mounted on a traffic signal pole or mast arm.

All printed circuit boards (PCB) must have conformal coating.

- 2.7. **Environmental.** RVDS sensor must be able to withstand the maximum wind load based on the Department's basic wind velocity zone map standard without any damage or loosening from structure.

The RVDS enclosure must conform to criteria set forth in the NEMA 250 Standard for Type 4X enclosures.

The RVDS must meet all NEMA TS2 environmental requirements for temperature, humidity, transients, vibration, and shock.

- 2.8. **Connectors and Harnesses.** Ensure all conductors are properly color coded and identified.

Ensure cable connector design prohibits improper connections. Cable connector pins are plated to improve conductivity and resist corrosion.

Connections for both data and power must be made to the RVDS sensor using waterproof, quick disconnect connectors. Pigtails from the sensor to a waterproof junction box (NEMA 4) or an approved waterproof connector must be allowed for splicing. The pigtails must not be shorter than 3 ft. unless otherwise shown on the plans.

3. CONSTRUCTION

- 3.1. **System Installation.** Install RVDS system devices according to the manufacturer's recommendations to provide properly functioning detection as required. This will include the installation of sensors on signal poles or mast-arms, controller interface modules, power and surge protection panels, cabling and all associated equipment, software, serial and Ethernet communication ports, connectors and hardware required to setup and operate. Ensure that the supplier of the RVDS provides competent on-site support representative during installation to supervise installation and testing of the RVDS. Ensure the radar sensor locations are optimal for system operation and operate as required. Maintain safe construction practices during equipment installation.

Ensure installation and configuration of software on Department computers is included with the RVDS.

Use care to prevent damage to any support structures. Any equipment or structure damaged or lost must be replaced by the Contractor (with items approved by the Engineer) at no cost to the Department.

3.2. **Mechanical Components.** Ensure that all fasteners, including bolts, nuts, and washers with a diameter less than 5/8 in. are Type 316 or 304 stainless steel and meet the requirements of ASTM F593 and ASTM F594 for corrosion resistance. Ensure that all bolts and nuts 5/8 in. and over in diameter are galvanized and meet the requirements of ASTM A307. Separate dissimilar metals with an inert dielectric material.

3.3. **Wiring.** Install all wiring and electrical work supplying power to the equipment in a neat workmanlike manner. Supply and install all wiring necessary to interconnect RVDS sensors to the traffic signal cabinet and incidentals necessary to complete the work. Furnish and install any additional required wiring at no additional cost to the Department.

Wiring must be cut to proper length prior to installation. Provide cable slack for ease of removal and replacement. All cable slack must be neatly laced with lacing or straps in the bottom of the cabinet. Ensure cables are secured with clamps.

3.4. **Grounding.** Ensure all RVDS components, cabinets, and supports are grounded in accordance with the NEC and manufacturer recommendations.

3.5. **Relocation of RVDS Field Equipment.** Perform the relocation in strict conformance with the requirements herein and as shown on the plans. Completion of the work will present a neat, workmanlike, and finished appearance. Maintain safe construction practices during relocation.

Inspect the existing RVDS field equipment with a representative from the Department and document any evidence of damage prior to removal. Conduct a pre-removal test in accordance with the testing requirements contained in this Item to document operational functionality. Remove and deliver equipment that fails inspection to the Department.

Prior to removal of existing RVDS field equipment, disconnect and isolate the power cables from the electric power supply and disconnect all communication cabling from the equipment located inside the cabinet. Coil and store power and communication cabling inside the cabinet until relocation. Remove existing RVDS field equipment as shown on the plans only when authorized by the Engineer.

Use care to prevent damage to any support structures. Any equipment or structure damaged or lost must be replaced by the Contractor (with items approved by the Engineer) at no cost to the Department.

Make all arrangements for connection to the power supply and communication source including any permits required for the work to be done under the Contract. Provide wire for the power connection at least the minimum size indicated on the plans and insulated for 600 V. Meet the requirements of the NEC, latest edition.

3.6. **Removal of RVDS Field Equipment.** Perform the removal in strict conformance with the requirements herein and as shown on the plans. Completion of the work will present a neat, workmanlike, and finished appearance. Maintain safe construction practices during removal.

Disconnect and isolate any existing electrical supply prior to removal of existing field equipment.

Use care to prevent damage to any support structures. Any equipment or structure damaged or lost must be replaced by the Contractor (with items approved by the Engineer) at no cost to the Department.

All materials not designated for reuse or retention by the Department will become the property of the Contractor and be removed from the project site at the Contractor's expense. Deliver items to be retained by the Department to a location shown on the plans or general notes. The Contractor is fully responsible for any removed equipment until released by the Engineer.

3.7. **Documentation.** Provide electronic copy operation and maintenance manuals, along with a copy of all product documentation on electronic media. Include the following documentation:

- Complete and accurate schematic diagrams,

- Complete installation procedures,
- Manufacturer's specifications (functional, electrical, mechanical, and environmental),
- Complete maintenance and trouble-shooting procedures, and
- Explanation of product operation.
- Warranty as specified in Section 3.8.

The RVDS must pass testing to ensure functionality and reliability prior to delivery. These include functional tests for internal subassemblies, a 24 hr. minimum unit level burn-in test, and a unit functionality test. Provide test results and supporting documentation, including serial number tested, must be submitted for each RVDS. If requested, manufacturing data per serial number must be provided for each RVDS.

Unless deemed unnecessary by the Project Engineer or TRF-TM, Provide certification from an independent laboratory demonstrating compliance with NEMA TS2 environmental requirements for temperature, humidity, transients, vibration, and shock.

Unless deemed unnecessary by the Project Engineer or TRF-TM, Provide third party enclosure test results demonstrating the sensor enclosure meets Type 4X criteria.

Unless deemed unnecessary by the Project Engineer or TRF-TM, Provide evidence of RVDS manufacturer's quality assurance program, including proof that the manufacturer of the RVDS is either ISO 9001 certified or other quality management system programs for manufacturing RVDS.

3.8. **Warranty.** Ensure that the detection system has a manufacturer's warranty covering defects for a minimum of 5 years from the date of final acceptance. In addition to the terms required by Article 8 of TO-8000, Ensure the warranty includes providing replacements, within 10 calendar days of notification, for defective parts and equipment during the warranty period at no cost to the Department.

3.9. **Training and Support.** Provide manufacturer approved end user training to the Department and their representatives. Training must include instruction on system configuration, operation, and maintenance. Provide training for a minimum of 10 Department-designated representatives up to 8 hs., including both class and field training.

Ensure that the detection system manufacturer will provide product support for a minimum of 5 years from the date of final acceptance.

4. TESTING

Perform the following tests on equipment and systems unless otherwise shown on the plans. The Department may witness all the tests.

4.1. **Stand-Alone Test.** Conduct a Stand-Alone Test for each unit after installation. The test must exercise all stand-alone (non-network) functional operations and verify that RVDS is placing detector contact closure to assigned detector channels in the traffic signal controller assembly. Notify the Engineer 5 working days before conducting this test.

4.2. **Consequences of Test Failure.** If a unit fails a test, provide a new unit and then repeat the test until successfully completed.

4.3. **Final Acceptance Test.** Conduct a Final Acceptance Test on the complete functional system. Demonstrate all control, monitoring, and communication requirements and operate the system for 30 days. The Engineer will furnish a Letter of Approval stating the first day of the Final Acceptance Test.

4.4. **Consequences of Final Acceptance Test Failure.** If a defect within the system is detected during the Final Acceptance Test, document and correct the source of failure. Once corrective measures are taken, monitor the point of failure until a consecutive 30 day period free of defects is achieved.

4.5. Relocation

- 4.5.1. **Pre-Test.** Provide 5 copies of the test procedures to include tests of the basic functionality of the unit and blank data forms to the Engineer for review and comment as part of material documentation requirements. Functionality tests may include, but are not limited to, physical inspection of the unit and cable assemblies. Include the sequence of the tests in the procedures along with acceptance thresholds. The Engineer will comment, approve, or reject test procedures within 30 days after Contractor submittal of test procedures. Rejected test procedures must be resubmitted within 10 days. Review time is calendar days. Conduct all tests in accordance with the approved test procedures.

Conduct basic functionality testing prior to removal of RVDS field equipment. Test all functional operations of the equipment in the presence of representatives of the Contractor and the Department. Ensure that both representatives sign the test report indicating that the equipment has passed or failed each function. Once removed, the equipment becomes the responsibility of the Contractor until accepted by the Department. Compare test data prior to removal and after installation. The performance test results after relocation must be equal to or better than the test results prior to removal. Repair or replace those components within the system that failed after relocation but passed prior to removal.

- 4.5.2. **Post-Test.** Testing of the RVDS field equipment is to relieve the Contractor of system maintenance. The Contractor will be relieved of the responsibility for system maintenance in accordance with Item 7, "Legal Relations and Responsibilities" after a successful test period. The Contractor will not be required to pay for electrical energy consumed by the system.

After all existing RVDS field equipment has been installed, conduct approved continuity, stand alone, and performance tests. Furnish test data forms containing the sequence of tests including all the data taken as well as quantitative results for all tests. Submit the test data forms to the Engineer at least 30 days prior to the day the tests are to begin. Obtain Engineer's approval of test procedures prior to submission of equipment for tests. Send at least 1 copy of the data forms to the Engineer.

Conduct an approved stand-alone test of the equipment installation at the field sites. At a minimum, exercise all stand-alone (non-network) functional operations of the field equipment with all the equipment installed per the plans as directed by the Engineer. Complete the approved data forms with test results and turn over to the Engineer for review and either acceptance or rejection of equipment. Give at least 30 working days' notice prior to all tests to permit the Engineer or his representative to observe each test.

The Department will conduct approved RVDS field equipment system tests on the field equipment with the central equipment. The tests will, as a minimum, exercise all remote control functions and display the return status codes from the controller.

If any unit fails to pass a test, prepare and deliver a report to the Engineer. Describe the nature of the failure and the corrective action needed. If the failure is the result of improper installation or damage during reinstallation, reinstall or replace the unit and repeat the test until the unit passes successfully, at no additional cost to the Department or extension of the Contract period.

5. MEASUREMENT

New RVDS furnished and installed by the Contractor will be measured by each approach to the signalized intersection.

RVDS furnished by the Department for the Contractor to install only will be measured by each approach to the signalized intersection.

Existing RVDS to be relocated or removed will be measured by each sensor relocated or removed.

6. PAYMENT

- 6.1. **Furnish and Install.** The work performed and materials furnished in accordance with this Item and measured as provided under "Measurement" will be paid for at the unit bid price for "RVDS (Presence Detection Only)", "RVDS (Advance Detection Only)" and "RVDS (Presence and Advance Detection)."

This price is full compensation for furnishing, installing, configuring, integrating, and testing the completed installation including RVDS equipment, voltage converters or injectors, cables, connectors, associated equipment, and mounting hardware; and for all labor, tools, equipment, any required equipment modifications for electrical service, documentation, testing, training, software, warranty and incidentals necessary to complete the work.

- 6.2. **Install Only.** The work performed and materials furnished in accordance with this Item will be paid for at the unit bid price for "RVDS (Presence Detection Only) (Install Only)", "RVDS (Advance Detection Only) (Install Only)" and "RVDS (Presence and Advance Detection) (Install Only)."

This price is full compensation for making fully operational a radar vehicle detection system furnished by the Department; installing, configuring, integrating, and testing the completed installation including RVDS equipment, voltage converters or injectors, cables, connectors, associated equipment, and mounting hardware; and for all labor, tools, equipment, any required equipment modifications for electrical service, documentation, testing, training, software, and incidentals necessary to complete the work.

- 6.3. **Relocate.** The work performed and materials furnished in accordance with this Item will be paid for at the unit bid price for "Relocate RVDS." This price is full compensation for relocating and making fully operational existing RVDS field equipment; furnishing and installing additional cables or connectors; for testing, delivery and storage of components designated for salvage or reuse; and all testing, training, software, equipment, any required equipment modifications for electrical service, labor, materials, tools, and incidentals necessary to complete the work.

- 6.4. **Remove.** The work performed and materials furnished in accordance with this Item will be paid for at the unit bid price for "Remove RVDS." This price is full compensation for removing existing RVDS equipment; removal of cables and connectors; for testing, delivery and storage of components designated for salvage; and all testing training, software, equipment, labor, materials, tools, and incidentals necessary to complete the work.

- 6.5. **Communication Cable.** All communication cables necessary to make the RVDS fully operational will be subsidiary to this Item.