
Special Specification 6352

Vandalism Protection Panels



1. DESCRIPTION

Furnish and install vandal protection panels (VPP) on overhead sign support tower legs as shown on the plans or as directed.

2. MATERIALS

- 2.1 **Galvanized Expanded Metal Panels.** Furnish VPP consisting of Flattened 1 1/2 in. 8 Gauge Galvanized Expanded Metal Panels. Galvanize VPP in accordance with Item 445, "Galvanizing."
- 2.2 **Paint over Galvanizing.** Paint over galvanized surfaces, when required, in accordance with Item 445, "Galvanizing."
- 2.3 **Field Painting.** Provide field paint, as required, in accordance with Item 446, "Field Cleaning and Painting Steel."

3. CONSTRUCTION

- 3.1 **Installation.** Install VPP as shown on the plans or as directed.
- 3.2 **Surface Preparation.** Clean and paint, when required, in accordance with Item 446, "Field Cleaning and Painting Steel."
- 3.3 **Welding.** Weld in accordance with Item 448, "Structural Field Welding." Repair galvanizing damage in accordance with Item 445, "Galvanizing."

4. MEASUREMENT

This Item will be measured by the square foot of surface area covered.

5. PAYMENT

The work performed and materials furnished in accordance with this Item are measured as provided under "Measurement" will be paid for at the unit price bid for "Vandalism Protection Panel."

This price is full compensation for furnishing and installing new materials and hardware; fabrication of VPP, erecting the VPP; preparing and cleaning the materials; and materials, equipment, labor, tools, and incidentals.