
Special Specification 8033

Controller Cabinet Assembly (Materials Only)



1. DESCRIPTION

Furnish and deliver Controller Cabinet Assembly sites specified on the plans.

2. MATERIALS

Provide new materials that comply with the specifications listed below:

- Ensure electrical materials methods conform to the current NEC
 - Provide prequalified controller assemblies from the Department's MPL in accordance with [DMS-11170](#), "Fully Actuated, Solid-State Traffic Signal Controller Assembly"
 - Provide prequalified flasher assemblies from the Department's MPL in accordance with [DMS-11160](#), "Flasher Controller Assembly"
 - Provide prequalified solar power flasher assemblies from the Department's MPL in accordance with [DMS-11150](#), "Solar Power Flasher Controller Assembly"
 - Sampling and testing of traffic signal controller assemblies will be done in accordance with [Tex-1170-T](#)
-

3. MEASUREMENT

This Item will be measured as each controller assembly delivered.

4. PAYMENT

Materials Delivery Materials furnished in accordance with this Item and measured as provided under "Measurement" will be paid for at the unit price bid for "Fully Actuated, Solid-State Traffic Signal Controller Assembly," or "Flasher Controller Assembly," or "Solar Power Flasher Controller Assembly," of the type specified.

This price is full compensation for furnishing materials and delivery of the materials to the stockpile.