



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act." No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




PARTIAL PLANS WITH NO SKEW Showing shear keys on 3'-6" wide caps. 4'-0" caps similar.
PARTIAL PLANS WITH 15° SKEW Showing shear keys on 3'-6" wide caps. 4'-0" caps similar.
PARTIAL PLANS WITH 30° SKEW Showing shear keys on 3'-6" wide caps. 4'-0" caps similar.
PARTIAL PLANS WITH 45° SKEW Showing shear keys on 3'-6" wide caps. 4'-0" caps similar.


- 1 Place shear keys on the upstream side of structure between outside girder and next adjacent girder, unless shown otherwise on plans.
- 2 UHMW polyethylene wear pad. (Typ)
- 3 Leave a 1/4" gap plus or minus between girder and face of wear pad. Cast wear pad with shear key, smooth side facing girder. Care must be taken to keep concrete from flowing under girder. Slope top of shear keys in accordance with Item 420.4.9, "Treatment and Finishing of Horizontal Surfaces."
- 4 Measure at higher bearing seat elevation forward or back. Dimension based on typical bearing pad and bearing seat. Increase as necessary to maintain 5" overlap.
- 5 With No Skew = 1'-8 1/4", measured along C cap.
With Skew = 1'-8 1/4" + Cos Skew, measured along C cap.
- 6 With No Skew = 1'-4 1/4", measured along C cap.
With Skew = 1'-4 1/4" + Cos Skew, measured along C cap.
- 7 Face of UHMW polyethylene wear pad. Smooth side of pad facing girder.
- 8 Abutments = 1/2 Cap width.
Interior bents = Cap width.
- 9 Abutments = 1/2 Cap width + Cos Skew.
Interior bents = Cap width + Cos Skew.



PARTIAL ELEVATION OF ABUTMENT OR INTERIOR BENT CAP
 Showing shear key with girder Type TX46. Other I-Girder types similar.




ELEVATION




PART SECTION


ULTRA HIGH MOLECULAR WEIGHT (UHMW) POLYETHYLENE WEAR PAD DETAILS



BARS M (#5)



BARS Na (#5) (For abutments)



BARS Nb (#5) (For interior bents)

MATERIAL NOTES:
 Provide Class "C" concrete ($f_c = 3,600$ psi). Provide Class "C" (HPC) if shown elsewhere on the plans.
 Provide Grade 60 reinforcing steel.
 Provide epoxy coated reinforcing steel for shear key if abutment or interior bent reinforcing steel is epoxy coated.
 Provide Ultra High Molecular Weight (UHMW) polyethylene wear pads in accordance with ASTM D6712.

GENERAL NOTES:
 Designed according to AASHTO LRFD Bridge Design Specifications. Details showing skew are drawn showing right forward skew. See Bridge Layout for actual skew direction.
 These details are limited to bridges skewed 45 degrees and less. This standard is only applicable for I-Girders.
 Modify details for bearing conditions, and girder spacing not shown on this standard. Details do not account for sole plate or pedestal bearing seat.
 Include shear key concrete in abutment or bent concrete for payment.
 UHMW polyethylene wear pads are subsidiary to Class "C" concrete.

Cover dimensions are clear dimensions, unless noted otherwise. Reinforcing bar dimensions shown are out-to-out of bar.

		Bridge Division Standard	
SHEAR KEY DETAILS PRESTRESSED CONCRETE I-GIRDERS			
IGSK			
FILE: IG-IGSK-17.dgn	DN: TxDOT	CK: TxDOT	DW: JTR
©TxDOT August 2017	CONT	SECT	JOB
REVISIONS	COUNTY		SHEET NO.

DATE: FILE: