



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: FILE:




**EARWALL ELEVATION DETAIL**  
(Slope top of earwall away from beams.)

- ① Top of cap elevations are based on section depths shown on span details.
- ② 1'-8" for 7DS20 beams, 1'-11" for 7DS23 beams.
- ③ With pile foundations, replace Bar A, located at bottom centerline of cap with 4 ~ #11 x 5'-3" bars placed between piles. Deduct 67 Lbs from reinforcing steel total.
- ④ 1/2" preformed bituminous fiber material between beam stem and earwall. Bond to beam with an approved adhesive. Cast inside face of earwall with face of beam stem.
- ⑤ Surface finish top of cap with a textured, wood float. Level surface in the direction of the centerline of beams. Provide bearings surface clean and free of all loose material before placing bearing pads.
- ⑥ 2 spaced at 12" Max.
- ⑦ Do not cast earwalls until beams are erected in their final position.
- ⑧ Top of backwall elevation is equal to top of beam elevation.

TABLE OF FOUNDATION LOADS		
Average Span Length	Drilled Shaft Loads	Vertical Pile Loads
Ft	Tons/DS	Tons/Pile
30	48	29
35	52	31
40	56	34
45	60	36
50	64	39
55	68	41
60	72	43




**HALF ELEVATION ~ DRILLED SHAFT ABUTMENT**



**HALF ELEVATION ~ PILE ABUTMENT**

(Showing 16" piles ~ for piles larger than 16", adjust Bars S spacing as required to avoid piling.)



**SECTION A-A**

**MATERIAL NOTES:**  
Provide Class C concrete ( $f'_c = 3,600$  psi).  
Provide Class C (HPC) concrete if shown elsewhere in the plans.  
Provide Grade 60 reinforcing steel.

**GENERAL NOTES:**  
Designed according to AASHTO LRFD Bridge Design Specifications.  
Designed for normal embankment header slope of 3:1 or 2:1.  
See Bridge Layout for header slope, beam type, and foundation type, size and length.  
See Common Foundation Details (FD) standard sheet for all foundation details and notes.  
See Concrete Riprap (CRR) standard sheet or Stone Riprap (SRR) standard sheet for riprap attachment details, if applicable.  
See applicable rail details for rail anchorage in wingwalls.  
Details are drawn showing right forward skew. See Bridge Layout for actual skew direction.  
This abutment does not accommodate an approach slab. These abutment details may be used with standard SDSB-28-30 only.

Cover dimensions are clear dimensions, unless noted otherwise.  
Reinforcing bar dimensions shown are out-to-out of bar.

HL93 LOADING SHEET 1 OF 2

		<b>Bridge Division Standard</b>	
<b>ABUTMENTS</b> <b>PRESTRESSED CONCRETE</b> <b>DECKED SLAB BEAMS</b> <b>28' ROADWAY 30° SKEW</b> <b>ADSB-28-30</b>			
FILE: dsbste18-20.dgn	DN: JLR	CK: SDC	DW: JTR
©TxDOT August 2020	CONT	SECT	JOB
REVISIONS	DIST		COUNTY
			SHEET NO.

