



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:




**ROADWAY ELEVATION OF TRAFFIC RAIL ON MOMENT SLAB (TRF-MS)**  
 (Showing SSTR rail other rails are similar. Reinforcing not shown for clarity.)




**ROADWAY ELEVATION OF TRAFFIC RAIL ON GRADE BEAM (TRF-GB)**  
 (Showing SSTR rail other rails are similar. Reinforcing not shown for clarity.)

- ① See applicable bridge rail standard.
- ② MA(#5) space longitudinally along moment slab at 12" Max. (Spaced 2 1/2" longitudinally from outside edge of moment slab).
- ③ Approximate moment slab concrete = 0.19 CY/LF and reinforcement = 22.4 LB/LF.
- ④ S1(#4) or S2(#4) spaced longitudinally along grade beam at 8" Max. (Spaced 2 1/2" longitudinally from outside edge of grade beam).
- ⑤ Use bar S1(#4) with 1'-4" grade beam width and bridge rail types: All rails except for T224, C412, T66, C66, T80HT and T80SS. Approximate grade beam concrete = 0.14 CY/LF and reinforcement = 13.8 LB/LF. Use bar S2(#4) with 1'-7" grade beam width and bridge rail types: T66 and C66. Approximate grade beam concrete = 0.16 CY/LF and reinforcement = 14.2 LB/LF.
- ⑥ 1'-6" for bridge rail types: All rails except for T224, C412, T66, C66, T80HT and T80SS. 1'-9" bridge rail types: T66 and C66.
- ⑦ Modify reinforcing on standard bridge rail anchorage if necessary by extending rail anchorage 12" Min, vertically into traffic rail



BARS S1(#4)




BARS S2(#4)

**CONSTRUCTION NOTES:**  
 Align moment slab (TRF-MS) or grade beam (TRF-GB) open joints with rail open joints maintaining no less than minimum rail length. Provide moment slab (TRF-MS) or grade beam (TRF-GB) with open joints at no greater than 100' spacing unless otherwise shown on the plans or approved by the Engineer.


**MATERIAL NOTES:**  
 Provide Class "C" concrete. Provide Class "C" (HPC) if required elsewhere.  
 Provide Grade 60 reinforcing steel.  
 Epoxy coat or galvanize all reinforcing steel if required elsewhere.  
 Deformed Welded Wire Reinforcement (WWR) (ASTM A1064) of equal size and spacing may be substituted for bars S1(#4), S2(#4) and H(#5) unless noted otherwise. Provide the same laps as required for reinforcing bars.  
 Provide bar laps, where required, as follows:  
 Uncoated or galvanized ~ #5 = 2'-4"  
 Epoxy coated ~ #5 = 3'-6"

**GENERAL NOTES:**  
 Use of these details will result in a moment slab (TRF-MS) or grade beam (TRF-GB) foundation that is acceptable for traffic rails which are MASH TL-2, TL-3, or TL-4 compliant.  
 See elsewhere in the plans for selected options between moment slab (TRF-MS) and/or grade beam (TRF-GB).  
 The foundation design resistance is based on the current AASHTO bridge railing requirements with the assumption of fair to good soil support conditions. Poor soil conditions will require suitably deeper and/or wider foundations.  
 See appropriate rail standard for details and notes not shown. This detail is intended for use as a guide to unusual railing anchorage situations but may be included in the plans, modified as necessary to apply to specific installations required on the project.  
 Payment for moment slab (TRF-MS) and/or grade beam (TRF-GB) will be by Class "C" concrete or Class "C" (HPC) concrete for rail foundations.  
 The associated bridge railing will be paid for by the linear foot which includes the concrete and reinforcement.  
 Excavation will be subsidiary to other items.

Cover dimensions are clear dimensions, unless noted otherwise. Reinforcing bar dimensions shown are out-to-out of bar.



**SECTION OF TRAFFIC RAIL ON MOMENT SLAB (TRF-MS)**  
 (Showing SSTR rail other rails are similar.)



**SECTION OF TRAFFIC RAIL ON GRADE BEAM (TRF-GB)**  
 (Showing SSTR rail other rails are similar.)

		<b>Bridge Division Standard</b>	
<b>TRAFFIC RAIL FOUNDATIONS FOR MASH TL-2, TL-3 &amp; TL-4 BRIDGE RAILS</b>			
<b>TRF</b>			
FILE: r1Std027-20.dgn	DN: TxDOT	CK: TAR	DW: JTR
©TxDOT September 2019	CONV	SECT	JOB
REVISIONS		HIGHWAY	
07-20: Added moment slab with rail foundation lengths.	DIST	COUNTY	SHEET NO.