



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

GENERAL NOTES


- FOR TECHNICAL AND APPLICATION SUPPORT PLEASE CONTACT HILL & SMITH INC. AT 614-340-6294.
- ZONEGUARD HAS BEEN ACCEPTED BY FHWA AS A MASH TL-3 LONGITUDINAL BARRIER.
- STANDARD INSTALLATIONS REQUIRE ANCHORING AT EACH END OF THE RUN. MINIMUM DEFLECTION INSTALLATIONS REQUIRE ANCHORING AT 33'-4" CENTERS. NO MODIFICATIONS ARE NECESSARY OTHER THAN INCREASED ANCHORING.
- 50'-0" UNITS CAN BE USED TO ACHIEVE DOWN TO AN 800' RADIUS CURVE. 16'-8" UNITS CAN BE USED TO ACHIEVE CURVES DOWN TO 250' RADIUS. SPECIAL SHORT UNITS (SHOWN) IN 2.5 DEGREE INCREMENTS CAN BE USED TO ACHIEVE DIRECTION CHANGES OR AT A FIXED RADIUS OF 47'-0".
- HILL & SMITH OFFERS AN EXPANSION UNIT THAT CAN BE USED ACROSS A BRIDGE EXPANSION JOINT OR TO ACCOMMODATE THERMAL EXPANSION. THE UNIT IS ANCHORED IN THE MIDDLE, AND ADJUSTED ACCORDING TO THE TEMPERATURE AT THE TIME OF INSTALLATION. THE EXPANSION JOINT CAN BE USED WITH ENGINEER APPROVAL. THE EXPANSION UNIT HAS NOT BEEN ASSESSED TO MASH CRITERIA.
- ANCHOR PINS ARE 1 1/4" DIAMETER. LENGTH IS 1'-8" FOR ASPHALT AND 1'-0" FOR CONCRETE. SEE ANCHORING TABLE FOR ADDITIONAL DETAILS.




PLAN VIEW




ELEVATION VIEW
ZONEGUARD STANDARD UNIT x 50'-0"




PLAN VIEW




PLAN VIEW




ELEVATION VIEW
ZONEGUARD STANDARD UNIT x 33'-4"



ELEVATION VIEW
ZONEGUARD STANDARD UNIT x 16'-8"



PLAN VIEW



ELEVATION VIEW
ZONEGUARD EXPANSION UNIT x 46'-5 1/2"
(SEE GENERAL NOTE 5)


	STANDARD INSTALLATION	MINIMUM DEFLECTION INSTALLATION CONCRETE	MINIMUM DEFLECTION INSTALLATION ASPHALT
	FOUR ANCHORS AT END OF THE RUN	TWO ANCHORS (ONE EACH SIDE) EVERY 33'-4"	TWO ANCHORS (ONE EACH SIDE) EVERY 33'-4"
MASH TL-3 DEFLECTION (2270 KG TRUCK @ 25° & 100 KM/HR)	6'-10"	5"	2'-0"

EXPECTED DEFLECTION TABLE


DESCRIPTION	ASPHALT	CONCRETE
1 1/4" PIN ANCHOR	1'-8" LONG, MINIMUM ASPHALT COVER OF 3"	1'-0" LONG, MINIMUM CONCRETE COVER OF 6"
1 1/4" ALL THREAD ANCHOR	-	1'-0" LONG, MINIMUM EMBEDMENT OF 6"

ANCHORING TABLE

ALTERNATE ANCHORING METHODS CERTIFIED BY HILL & SMITH, INC. ARE AVAILABLE PER FHWA APPROVAL LETTER.



ZONEGUARD RADIUS UNITS



ZONEGUARD TYPICAL SECTION

		Design Division Standard	
ZONEGUARD SYSTEM STEEL BARRIER MASH TL-3 ZONEGUARD-19			
FILE: zoneguard19	DN: TxDOT	CK: KM	DW: VP
© TxDOT: JULY 2019	CON	SECT	JOB
REVISIONS	DIST	COUNTY	SHEET NO.

DATE:
FILE: