PLANT SPECIFICATIONS (PLANT MATERIAL MUST CONFORM TO ALL SPECIFICATIONS)

Botanical Name	Common Name	Color	Quantity	MINIMUM SPECIFICATIONS				
				Root Condition	Caliper	Height	Spread	Remarks
TREES								
PALM TREES								
SHRUBS								
VINE/GROUND COVER								

PLANT SPECIFICATION NOTES:

1. Reference Item 192 of the Texas Standard Specifications for Construction of Highways, Streets and Bridges 2014 for specifications, dimensions, volumes and measurements that are not shown.
2. All plants must be nursery grown in containers unless otherwise shown on plans.
3. Provide photographs of plant material when requested by engineer and landscape architect.
4. Properly handle and maintain plants during delivery, handling, storage, and planting. The engineer and landscape architect may inspect any phase of work and may reject any plant material improperly handled and/or maintained.
5. DELIVERY NOTICE. Reference Item 192.3.2 plant delivery. Provide 48 hour notice of proposed plant material delivery prior to arrival at project or storage area.
6. DELIVERY TICKETS. For each plant material shipment, provide invoice showing the number, size, and name (common and botanical) of each of the species of plant material.
7. WATERING PLAN(S). Prior to arrival at project or storage area, provide watering plan(s) of plants to be installed or stored. Watering plan(s) must be approved by engineer and landscape architect prior to delivery to project or storage area.

© 2014

Texas Department of Transportation

HOUSTON DISTRICT

PLANTING AND ESTABLISHMENT
SHEET 3 of 8

PLANT SPECIFICATIONS

FILE:	FED DIV	STATE	PROJECT NUMBER				SHEET
	6	TEXAS					
REVISIONS: FEB 2015 for 2014 specs	DIST	COUNTY	CONTROL	SECT	JOB		HIGHWAY
	12						